JULY 1944
50 CENTS PER COPY

AVIATION

The Oldest American Aeronautical Magazine

IN THIS ISSUE

BLITZKRIEG GOES TO SEA
— Adm. McCain's own story of our most potent sea weapon and what it can do in the future.

★

RUSSIA'S WOMEN FIGHTER PILOTS
— They now fight the Nazis — but they first had to fight for a place in the Red Air Force.

★

NORTH AMERICAN "MUSTANG"
— A top-notch frontline fighter added to Aviation's incomparable design analysis series.

★

CABIN PRESSURIZATION?
— Bridging that gap between sales and engineering is really tough.

★

REBUILDING THE "CLIPPERS"
— An experience handbook for big-plane maintenance crews.

★

FRANKLIN OVERHAUL
— "Performance insurance" for the small plane owner, today and tomorrow.

★

BOOMERANGING CONTRACTS
— How to avoid "a minor matter that's NOT a minor matter."

★

HOW ARE THE PROFITS?
— Our annual survey sums them up and looks into the future.

McGRAW-HILL
PUBLISHING COMPANY, INC.

More Thunder for the Thunderbolt

The thunder of 2,000 horsepower packed into a single Pratt & Whitney engine is already familiar music to Army P-47 pilots.


Now being built around the even more powerful R2800-C engine, the Republic Thunderbolt in the words of men who know is "a new airplane with even greater performance."

PRATT & WHITNEY AIRCRAFT
EAST HARTFORD, CONNECTICUT
ONE OF THE FOUR DIVISIONS OF UNITED AIRCRAFT CORPORATION

Look at the Speed Nuts

SPRING-TENSION LOCKING ACTION!





An arched spring lock and an inward thread lock are basic features found only in Speed Nuts. The ingenious design that sets up these two forces accomplishes more than you'd realize unless you checked into it more closely.

Spring steel Speed Nuts have a base which is well arched, and arched prongs that are formed to follow the helical pitch of standard screw threads. As the screw is tightened, the arch is reduced, forcing the prongs deeper into the root of the screw threads. This provides a double spring-tension lock that prevents vibration loosening.

Speed Nuts eliminate the use of lock washers and are 50% to 75% lighter in weight than other self-locking nuts. They are faster to apply and drastically reduce assembly costs. Double your use of Speed Nuts and you will double your assembly savings. Write for literature.

TINNERMAN PRODUCTS, INC.
207D FULTON ROAD • CLEVELAND 13, OHIO
In Canada—Wallace Barnes Co., Ltd., Hamilton, Ontario
In England . . . Simmonds Aerocessories, Ltd., London

The lightest weight self-locking nuts ever produced!



AVIATION

CONTENTS FOR JULY, 1944

Volume 43 • Number 7

Briefing for July		5
Down the Years in Aviation's Log		5
Editorial: The Invasion Spotlighted Our Need: To Stay Armed		109
Boeing B-29 "Superfortress"	*Herb Powell*	110
Quality Plus Quantity Made D-day Possible		111
The Blitzkrieg Goes to Sea	*Vice Adm. John S. McCain*	112
How Women Fliers Fight Russia's Air War	*Madelin Blitzstein*	116
Here Are Your Markets, III	*John Foster, Jr.*	118
Aviation Research—Engineering—Production		
Design Analysis No. 7, The North American P-51 *Mustang*	*William R. Nelson*	127
Fan Cooling "Ups" Engine Performance	*Kenneth Campbell*	148
Tooling Dock Technique Saves Time, Speeds Accuracy, I	*Leland A. Bryant*	152
So You're Going To Pressurize?	*Charles W. Morris*	155
Hole Piercing Proves Faster—And Cheaper	*Herbert Chase*	161
Load Characteristics of Cellulose Acetate Plastic, II	*William N. Findley*	164
Methods for Forming Sheet Aluminum, III		166
Electronics Smooth Supercharging		168
Aviation's Sketch Book of Design Detail		203
Aviation's Engineering Data Book		209
Review of Patents	*A. Henry Crowell*	212
New Products and Practices		242
Aviation Maintenance		
How to Get Top Efficiency From Your Vacuum Pumps		171
Rebuilding the *Clippers*		175
Inspection and Top Overhaul on the Franklin	*F. B. Chadwick*	178
"On and Off" Speed is Aeroprop Feature		180
Service Steps for the Eisemann Magneto	*E. J. Goggans*	183
Aviation's Maintenance Notebook		185
Air Transport		
Three International Policies—Which Will We Have?	*A. A. Hartsinck*	190
Civil Operations and Training		
Contracts With Minors Can Boomerang	*Leslie Childs*	192
Southwest Airways Flies 1,000,000 Training Hours		195
Finance		
Industry's Sales Soar . . . But Not Profits	*Raymond L. Headley*	197
Flying Equipment		
New Auxiliary Engine Gives More Power Per Pound		199
Book Reviews		210
Side Slips		235
The Aviation News		
National Aviation	213	
War Communique No. 31	217	
Washington Windsock	219	
Aviation Manufacturing	221	
Transport Aviation	225	
Aviation Abroad	228	
Financial Notes	231	
Aviation People	233	

George W. Pfeil, *Publisher* — Leslie E. Neville, *Editor*

John Foster Jr., *Managing Editor*
Herb Powell, *Associate Editor*
E. E. Thelp, *Assistant Editor*
Raymond Handley, *Financial Editor*
Wm. R. Nelson, *West Coast Editor*
Blaine Stubblefield, *Washington Editor*
Dallas Mallard, *Art Editor*
Paul Wooton, *Chief of Washington Bureau*

★ ★ ★

On Leave of Absence With Government Services


Carl Norcross, *Colonel, Air Forces*
Charles F. McReynolds, *Major, Air Forces*
Jay P. AuWerter, *Captain, Air Forces*
Randolph Hawthorne, *Captain, Air Forces*
Kenneth D. Reynolds, *Lieut., Infantry*
David Baker, *Private, Air Forces*
E. Eugene Miller, *Special Assignment*
Dan Fink, *Special Assignment*

★ ★ ★

Andrew B. Martin, *Sales Manager*

District Managers: Boston, Hunter Sweet; New York, Robert F. Siegel; Philadelphia, C. M. Edler and E. M. Schallenger; Cleveland, A. H. Bertsch and E. O. Wayne; Detroit, C. W. Evans; Chicago, A. E. Means; St. Louis, W. E. Dennell; Los Angeles, E. W. Pfeffer; San Francisco, John Otterson

McGRAW-HILL PUBLISHING CO., INC. Publication office, 99-129 North Broadway, Albany, N. Y. Return postage guaranteed. Editorial and executive offices, 330 West 42nd Street, New York, 18, N. Y. Branch offices: Chicago, 520 North Michigan Ave.; San Francisco, 68 Post Street; Aldwych House, Aldwych, London, W.C. 2; National Press Bldg., Washington; 18 South Broad St., Philadelphia; Hanna Bldg., Cleveland; 844 General Motors Bldg., Detroit; Paul Brown Bldg., St. Louis; 1427 Statler Bldg., Boston; Rhodes-Haverty Bldg., Atlanta; 601 W. 5th St., Los Angeles; 736 Oliver Bldg., Pittsburgh. JAMES H. McGRAW, Founder and Honorary Chairman; JAMES H. McGRAW, Jr., President; HOWARD EHRLICH, Executive Vice President for Business Operations; JOHN ABBINK, Executive Vice President for Editorial Operations; CURTIS W. McGRAW, Vice President and Treasurer; JOSEPH A. GERARDI, Secretary; J. E. BLACKBURN, Jr., Director of Circulation. Aviation, 330 W. 42nd Street, New York. Published monthly; price 25c a copy; $3 in Canada. Allow at least ten days for change of address. All communications about subscriptions should be addressed to Director of Circulation, 330 West 42nd Street, New York. Subscription rates—United States, Mexico and Central American Countries, $3.00 a year; $4.00 for two years; $5.00 for three years. Canada, $3.50 for one year; $5.00 for two years; $7.00 for three years, payable in Canadian currency at par. Great Britain and British Possessions 30 shillings per year; 50 shillings for three years. All other countries, $3.50 a year; $5.00 for three years. Entered as second-class matter September 7, 1928, at the Post Office, Albany, New York, under the Act of March 3, 1879. Volume 43, Number 7. Printed in U. S. A. Cable Address: "Mcgraw-hill New York." Member A.B.C. Copyright 1944 by McGraw-Hill Publishing Company, Inc. 330 West 42nd Street, New York, N. Y. The contents of this issue are copyrighted and may not be reproduced without the permission of the copyright owners. The following publication is combined with AVIATION: AERONAUTICAL ENGINEERING AIRCRAFT JOURNAL. All rights to this name are reserved by the McGraw-Hill Publishing Co. Aviation is indexed in Guide to Periodical Literature and in Industrial Arts Index.



This is the field of battle in the sky ..the stable field of a rotating magnet heart of a Bendix-Scintilla* Aircraft Magneto Into the making of this vital part go superlative steel and precise engineering ..for on the strength and stability of its magnetic force depends the generation of sparks to fire the engines of our fighting aircraft

Bendix-Scintilla engineers have contributed notably to the advancement of Aircraft Ignition Their inventiveness and practical experience, now wholly devoted to the prosecution of the war, will one day again be applied to the pursuits of peace.



THE WORLD'S FINEST AIRCRAFT IGNITION

Bendix Scintilla Aircraft Magnetos, Harnesses and Switches, vital members of The Invisible Crew, are standard equipment for the major aircraft engine manufacturers, including:

Allison • Jacobs • Continental • Lycoming • Lawrance • Wright Aero Corp. • Pratt & Whitney • Warner • Packard • Ranger • Ford • Nash • Chrysler • Kinner

SCINTILLA MAGNETO DIVISION
SIDNEY, NEW YORK

THE INVISIBLE CREW
Precision Equipment by
Bendix Aviation Corporation

*TRADE MARK OF BENDIX AVIATION CORPORATION

Briefing for July





KENNETH CAMPBELL (left), Wright Aero Senior Project Engineer gives full details—backed up with our Aviation sketches—of the development of aircraft engine fan cooling (page 148) And LELAND M. BRYANT (right), presents the know-how for assembling and checking jigs and fixtures through an exposition of the tool dock he developed for Convair at San Diego (page 152)

If anyone ever doubts that 'the best defense is a good offense" refer him to Vice Adm John McCain's story on page 112 Here's the development of Jap-whipping strategy and tactics in our carrier-based aviation that actually converted liabilities into assets And the look-see Adm McCain gives us as to what's going to happen makes even better reading

A lot of Nazi pilots wish that Joe Stalin believed the old adage that ' woman's place is in the home " For if Joe believed that, Goering's 'supermen" wouldn't face the embarrassing prospect of being shot out of the sky by the so called weaker sex. How Russian women fought for a place in the Red Air Force as combat pilots so they could battle Goering's boys is told dramatically in the story beginning on page 116.

Read anyone's list of best" airplanes and you'll find the North American P-51 *Mustang* right up in the top flight You'll understand why when you read the story on page 127—No. 7 in our unmatched Design Analysis series—a bang-up job by AVIATION's West Coast Editor Bill Nelson.

Here Are Your Markets —right on a two-page map which you can cut out and mark up to your heart's content (page 118) This month we conclude Managing Editor John Foster's important series presenting the nationwide distribution framework. A reprint of the whole series is yours for the asking

Prescorning cobine for high altitude operation is really a two way headache For the Sales Department wants one thing—while Engineering wants to build something quite different. Charles W. Norris of AiResearch tackles the basic problems necessary to eliminate the headache (page 155).

Tomorrow's planes —pressurized or not —will mean bigger and tougher problems for maintenance men. Pan American's Atlantic Division is writing an invaluable handbook for these men as it replaces structural members in the faithful Boeing 314 *Clippers* Details of this huge, completely pre-engineered task are given on page 175

The personal flyer's and fixed base operator's maintenance field is covered, too. On page 178 for example, F. B. Chadwick, Aircooled Motors Service Manager, gives all the dope on 10, 25, and 100-hr inspections and top overhaul Then, on page 183, E. J. Goggins gives the simple routine for keeping the new Eisemann 4- and 6-cylinder magnetos operating right up at 100 percent efficiency

There'll come a day, sooner than many think, when the aviation companies' customer is going to change—from Mister Whiskers to Joe Public and Joe Junior And if you're thinking of making contracts with a lot of Joe Juniors, for your balance sheet's sake read "Contracts with Minors Can Boomerang" by Leslie Childs It's on page 192.

And speaking of profits (as who doesn't like to?) Financial Editor Ray Hoadley this month presents his annual exclusive roundup of the aircraft industry's financial standing You'll find his table an excellent reference piece, and the survey itself is quite hopeful for the investor Turn to page 199

Before the great new Boeing B-29 *Superfortresses* blasted the Japs in their own front yards, Associate Editor Herb Powell had been to Wichita to study them —crawling from stem to stern and flying in one In his first-hand story beginning on page 110, he tells you not only everything that can be told about the ship itself within the bounds of security but gives the fascinating background information bound up with a truly great manufacturing achievement.

Down the Years in AVIATION'S Log

25 Yr. Ago (1919)—London *Daily Express* offers $50,000 prize for commercial flight to India and Africa carrying ton payload. American Handley-Page Co incorporated as airline operator at Ogdensburg, N. Y.

15 Yr. Ago (1929)—Frank Hawks flies twice across continent in 36 hr 49 min elapsed time TAT inaugurates 48-hr coast-to-coast air-rail service. Detroit Chicago air service commences North American Aviation buys Pitcairn Bendix acquires Pioneer Instrument. Amelia Earhart appointed ass't traffic mgr. of TAT Knott and Klingensberg of Germany open glider school at Cape Cod Phoebe Omlie of Memphis Tenn, breaks women's altitude record at 25 400 ft. Curtiss-Wright Corp merger announced *Saturday Evening Post* buys Ford plane for business purposes.

10 Yr. Ago (1934)—Black - McKellar Act passed making temporary airmail contracts permanent. Cleveland Airport handles 11 887 passengers in month USS aircraft carrier *Ranger* commissioned. Naval Affairs Committee appropriates $5 363 000 for Pensacola Naval Air Station. James R Wedell killed while giving flight instruction Turkish Army sends six officers here to study aviation Richard C duPont soars 155 mi from Elmira, N Y, to Somerset, N J UAL orders de-icers for 30 Boeings from Goodrich DeHavilland obtains sole British Empire Mig rights for Hamilton Propellers, except for Canada. Admiral Reeves, former *Langley* commander, becomes first pilot admiral. Hisso produces 1 120-hp 14-cyl radial engine New England Lobster Co buys Keystone *Commuter* to contact fishing fleet.



THE INSTANT STARTING and reversal characteristics of the Kollsman Drag Cup Motor make it possible for this device to perform a vital function in the aircraft direction finder—keeping the loop antenna always pointing to the receiving station despite all movements of the airplane. Developed by Kollsman engineers specifically to meet the requirements of this unusual application, the Drag Cup Motor has been refined and modified to perform many other varied tasks. It is one of a new line of highly successful Kollsman miniature motors that give further evidence of the versatility of Kollsman precision engineering.

KOLLSMAN AIRCRAFT INSTRUMENTS

PRODUCT OF

SQUARE D COMPANY

ELMHURST, NEW YORK GLENDALE, CALIFORNIA

IS *Your* TOWN READY TO FLY?



Inexpensive "T" Landing Strip on Edge of Town, Illustrated



To take full advantage of the coming air age, your town must be ready to fly the minute Victory is won! It must follow the lead of thousands of other progressive towns and plan landing facilities now

An inexpensive landing strip or airport will offer you and your fellow-townsmen the new pleasure and convenience of private flying, and afford connection with main airlines In addition, it will make your town more progressive, increase business opportunities and swell civic activity

The new booklet, "What Your Town Needs for the Coming Air Age", will help you and your town officials in laying practical plans It gives the why, where and how of building landing facilities Write for your free copy now Piper Aircraft Corporation Dept, A74W, Lock Haven, Penna.



GET YOUR AVIATION BOOKLET—"Piper Cub In War and In Peace" Full color 32 pages. Covers history of flight plans. Piper Cub planes coming air age—how to fly Enclose 10c in stamps or coin for postage-handling. Write Piper Aircraft Corporation—Department A74 Lock Haven Pennsylvania

16mm SOUND FILM—"The Construction of a Light Airplane." For distribution points write Supervisor Audio-Visual Aids- Extension Services, Pennsylvania State College State College Pennsylvania

PIPER *Cub*

Points the Way to Wings for All Americans

Trail Blazing in the Skies

HOW GOODYEAR AIRCRAFT CORPORATION SERVES THE AIRCRAFT INDUSTRY


1. *By constructing subassemblies to manufacturers' specifications.*
2. *By designing parts for all types of airplanes.*
3. *By re-engineering parts for quantity production.*
4. *By building complete airplanes and airships.*
5. *By extending the facilities of Goodyear Research to aid the solution of any design or engineering problem.*

PIONEERING NEW METHODS



SAVING HOURS IN METAL FORMING OPERATIONS — Another recent development speeding production at Goodyear Aircraft Corporation is a new universal chuck for gripping materials in metal working equipment. Conventional chucks require two to three hours for dismounting and fitting with different, expensive machined jaws every time a different shaped part is to be inserted *The new Goodyear chuck requires only a few minutes for this change-over — and uses jaws cast from an inexpensive material.* Thus the productive time of these important metal forming machines is increased by several hours a day, and time-consuming jaw machining operations are practically eliminated. This new, fast-action chuck is, therefore, an important contribution to America's aircraft program. It's one more example of Goodyear pioneering and leadership.

BUILDING PROVEN AIRCRAFT



1,000 CORSAIRS IN RECORD TIME — In little more than a year after completing its first Corsair, Goodyear Aircraft Corporation had produced a full thousand of these crack fighters. This production of a new type of ship was achieved in a completely new plant, and the battle-front record of the Goodyear-built Corsairs used by the U. S. Marines shows how well the job was done. The ability to attain volume production so quickly and so competently stems from Goodyear's thirty years' experience in aeronautical engineering — a background starred with many notable developments in aircraft design and fabrication that make Goodyear one of America's foremost names in aeronautics.


BUY WAR BONDS BUY FOR KEEPS



GOODYEAR AIRCRAFT

WHY THE GIANT CONSTELLATION" RELIES ON GOODYEAR

Tires Tubes Wheels Brakes



BIGGEST and fastest transports in operational duty today are TWA's fleet of giant Lockheed-built Constellations, now going into military service with the Army Air Forces. Like so many other big ships, these 40-ton goliaths have 100% Goodyear equipment on their main landing gear. The stalwart dual tires are 17.00-20 Goodyear Grooved All-Weather Intermediates with Goodyear tubes. The double brakes are time-proved Goodyear Hydraulic Disc Brakes, famed for velvet-smooth, non-fading action—mounted in Goodyear cast magnesium-alloy wheels. *Long experience proves this all-star line-up guarantees utmost efficiency, dependability and safety in landing-gear operation!* Pioneer builder of airplane tires since 1909, Goodyear today produces the most complete, modern line of tires, tubes, wheels and brakes for every type of aircraft—from helicopters and light trainers to the greatest leviathans of the air, now in service or in prospect.

All Weather—A registered T. M. of The Goodyear Tire & Rubber Company

BUY WAR BONDS — BUY FOR KEEPS

GOODYEAR
THE GREATEST NAME IN RUBBER

THERE'S A GOODYEAR TIRE FOR EVERY NEED

SMOOTH CONTOUR
HIGH PRESSURE
LOW PRESSURE
AIRWHEEL
(extra low pressure)
LOW PROFILE
ICE-GRIP
HELICOPTER
AUXILIARY WHEEL
BEACHING GEAR

Most types available with choice of smooth tread, channel tread or the famous Goodyear All-Weather non-skid tread.



PERFECTING TOMORROW'S TIRES—TODAY!

Looking toward the future, Goodyear operates the largest privately owned airplane tire and brake testing machine in the United States. Capable of exerting 50,600,000 foot-pounds of energy, it is used in developing equipment for tomorrow's super aircraft.



BRING YOUR PROBLEMS TO HEADQUARTERS

Backed by the resources of the finest research laboratory in the industry, and more than 30 years' experience in developing airplane tires, tubes, wheels, brakes and other accessories, Goodyear engineers are ready to help you in working out any application. Address Goodyear, Aeronautics Dept., Akron 16, Ohio or Los Angeles 54, California.

AERONAUTICAL RUBBER GOODS • TIRES • TUBES WHEELS • BRAKES



© 1944 The Studebaker Corporation

"Those engines sure have the power!"

THE brother of a waist gunner on a Boeing Flying Fortress wrote Studebaker quoting him as saying:

"Those Wright Cyclone engines that Studebaker builds are really dependable and sure have the power."

Comments like that are fully appreciated, of course But Studebaker men and women know that what count most are the accomplishments of the stout-hearted air crews and rugged ground crews of our country's warplanes and the achievements of our fighting forces everywhere

In fact, whatever amount of satisfaction the Studebaker organization may derive from the extent and consequence of its war work is always tempered by the realization that Studebaker is only one unit in a vast American fighting and producing team where everyone's effort is important.

Studebaker takes pride in its assignments on that team. Huge quantities of Wright Cyclone engines for the Boeing Flying Fortress—big multiple-drive military trucks—and other units of vital war matériel continue to stream forth from the five great Studebaker factories




UNSUNG HERO OF OUR NAVY

Aerial radio gunner in a Navy dive bomber! One of the toughest jobs of all! Let's show him we're for him and

★ BUY MORE BONDS ★

Studebaker BUILDS WRIGHT CYCLONE ENGINES FOR THE BOEING FLYING FORTRESS



DOUBLE-ACTION DRAWING OPERATIONS ON MECHANICAL AND HYDRAULIC PRESSES

LEFT Both Hydraulic and Mechanical Double-Action Presses are used in this shop for drawing stainless steelware RIGHT A large Single-Crank Toggle Drawing Press recently installed in an aircraft plant to produce deep drawn stampings

THE MANY INSTALLATIONS of both types of press design in industry today attest to the fact that there is a definite place for both the mechanical and hydraulic principles for double-action drawing operations.

The Toggle press operates at high fixed speeds with increasing pressure as the bottom of the stroke is reached, making it suitable for a wide variety of drawn work with heavy pressure available for first draws and bottom stamping, and lighter pressure for the long draws using the mid-stroke capacity of the press The speed of production is the same independent of long or short draw.

The Hydro-Dynamic Press has a uniform maximum pressure capacity throughout its stroke with a constant draw speed Shorter draws can be made at an increased production rate as compared with long draws. This press is suitable for extremely long draws and for heavy work and can be obtained in speeds comparable to the mechanical press.

Your nearest Bliss Sales Representative will be glad to assist you in selecting the proper press for your particular drawing problems. As a builder of both types of presses you can be certain of unbiased recommendations.

BLISS · TOLEDO · CONSOLIDATED · MARQUETTE · BLISS BUILT

E. W. BLISS COMPANY


53rd Street and 2nd Avenue, Brooklyn 32, New York

TOLEDO, OHIO • CLEVELAND, OHIO • SALEM, OHIO • HASTINGS, MICHIGAN • DETROIT, MICHIGAN
CHICAGO, ILL. • ROCHESTER, N. Y. • NEW HAVEN, CONN • PHILADELPHIA, PA. • BOSTON, MASS.


E. W. BLISS COMPANY OF CANADA, LTD., TORONTO, ONTARIO, CANADA

Agents: Moore Machinery Company, Los Angeles and San Francisco, California


What happens in the "Stratolab"



Designed for specialized study of high altitude flying, the AiResearch "Stratolab" offers the most complete research facilities in this field. In this three-sectional vacuum chamber several tests can be carried on simultaneously—under controls so accurate that performance of equipment can be predicted within 2% before it goes into actual service.



Weather is "created"—duplicating that of any part of the globe and thousands of feet above it. Here, where temperatures can be brought below *minus 90° F*, reactions of crew and equipment can be accurately determined before they leave the home ground.



Stratosphere brought to earth. In this chamber, pressure can be lowered to that at 65,000 feet . . . air made ten times thinner than at sea level! Here are developed AiResearch pressure and temperature controls for better aircraft performance and crew comfort at high altitudes.

WITH VICTORY, the AiResearch "Stratolab" will return to peacetime projects . . . to developing air control equipment for swifter, safer, more economical transport . . . and to creating AiResearch "comfort-protection" for high altitude commercial flying.

"Where Controlled Air Does The Job"
Automatic Exit Flap Control Systems • Engine Air Intercooling Systems • Temperature Control Systems • Supercharger Aftercooling Systems • Engine Oil Cooling Systems

AiResearch
MANUFACTURING COMPANY
LOS ANGELES • TORRANCE
DIVISION OF THE GARRETT CORPORATION



SPOTTING JAPS IN THE "WILLIWAWS"

ON May 11, 1943, an American Task Force landed on Attu in the Aleutians to drive out the invading Japs. Drive them out they did after prolonged and bitter action in which bullets and arctic weather took heavy toll. This epic action provided one of the early instances of the effective support of ground troops by carrier based Naval planes.

The heroic men of Attu will not forget the curse of Aleutian climate. Bitter cold. Dense fog. Snow and rain 250 days in the year. A pilot may take off in perfect weather yet 10 minutes later may be unable to land because fog has blanketed his carrier or his landing field.

The Japs used this natural phenomenon to clever advantage. They placed their men and guns right on the fog line. Result—they could see the attackers but the attackers could not see them. And the wily Japs would shift up and down the mountainous coasts, always keeping under cover of the fog. It's pretty hard to kill a foe you can't even see.

The Japs and the fogs weren't the only foes around Attu. Sleet storms, sudden squalls, freezing clouds that load the wings of a bomber with a ton of ice in less than a minute. And the "williwaws" that can drop a plane 3000 feet in a few seconds.

But the Japs had to be routed from U. S. soil in a hurry . . . dead or alive, preferably dead. That called for bombing in weather as treacherous as the foe.

The Navy knew the Kingfisher was the bird to turn the trick . . . to spot targets and guide our bombing planes where they could drop their deadly eggs in the midst of the foe's strong holds. Because they are Edo Float-equipped, Kingfishers (OS2Us) are known as the planes with "sea-going legs"—because they are able to land on rough water and get off again.

Up went the Kingfishers to serve as spotting planes for the carrier launched planes assigned to carry out bombing missions. Targets designated by ground units were reported to flights of OS2Us based in the area and relayed through them to the bombing planes. Revetted positions and fox-holes of the enemy came under deadly and accurate strafing and bombing attack. A goodly number of confirmed hits were reported on the designated target areas as well as many "probables".

There aren't any Japs on Attu now. Edo equipped Kingfishers could climb higher than the Rising Sun. And with the Kuriles only 650 miles away, the gallant crews of the scout planes with the "sea going legs" can be counted upon to point the way direct to the heart of Japan.

EDO FLOAT GEAR
Serves the United Nations
EDO AIRCRAFT CORPORATION
402 SECOND STREET
COLLEGE POINT, L.I., N.Y.

New landing light lenses molded of "LUCITE"

Du Pont "Lucite" reduces weight and breakage, provides weather resistance and dimensional stability. Lens design boosts candlepower.



BEFORE AND AFTER the introduction of "Lucite" . . . a marker lens part of the field lighting equipment. This is an ellipsoidal Fresnel lens, providing concentrated high candlepower beam at certain angles. Old lens weighed 39 ounces, new "Lucite" lens weighs about 3 ounces. High finish of mold surfaces makes the most of the high degree of light transmission of "Lucite." Because of high wattage and temperature of bulb, Heat-Resistant "Lucite" is used for these lenses . . . is injection-molded from top center sprue. Molder of all the lenses illustrated on this page is Stinson A'G'A Plastics.

News of another demonstration of the many advantages of Du Pont "Lucite" methyl methacrylate resin comes with the armed forces' release of the description of field lighting equipment in which this versatile plastic plays a major part.

The armed forces wanted this equipment to have light weight and resistance to breakage. It was necessary at the same time to improve the optical accuracy while maintaining good dimensional stability and weather resistance.

"Lucite" met all these requirements and made possible, in addition, a design which almost tripled candlepower from the same light sources.

Do you have problems involving similar needs? "Lucite" may be the answer. Du Pont plastics technicians will lend you the help of their experience in solving plastics problems on war and development work. Address inquiries to: E. I. du Pont de Nemours & Co. (Inc.), Plastics Department, Arlington, N. J., or 5801 So. Broadway, Los Angeles 3, California. In Canada: Canadian Industries, Ltd., Box 10, Montreal.



ANOTHER IMPORTANT weight reduction is effected by use of Heat-Resistant "Lucite" for the obstacle lens. Old lens weighed 26 ounces; lens of "Lucite" only 3 ounces. Note three-color lens below.

AVAILABLE: *Special story on Heat-Resistant "Lucite" molding powder. Write on your business letterhead for your copy.*



INTERESTING DEMONSTRATION of the workability of "Lucite" is this tri-color lens, the application of which is still restricted. Three flat molded strips of general purpose "Lucite"—yellow, green, and red—are welded into a single homogeneous optical lens unit, an extremely accurate job in which skillful workmanship and good material combine to produce a superior product.

DU PONT PLASTICS

DU PONT — BETTER THINGS FOR BETTER LIVING . . . THROUGH CHEMISTRY

Outstandingly Successful for Many Jobs in These Fields:

Cylindrical Grinding

Centerless Grinding

Internal Grinding

Surface Grinding

Tool Grinding

Snagging

57 ALUNDUM ABRASIVE


. . . Another Norton Abrasive to Help You Meet Your Grinding Jobs More Exactly.

Thoroughly tested—and never have field tests of a new grinding wheel been more successful in a half century of Norton experience.

Its use up to now has been restricted to critical war jobs, because of limited production facilities. Now, it is available for general use. Ask the Norton abrasive engineer about 57 Alundum, the latest of the Norton abrasives for grinding wheels.


Norton Co., Worcester 6, Mass.

Behr-Manning, Troy, N. Y., is a Norton Division



NORTON ABRASIVES


AROUND THE WORLD



Everywhere around the world, - - wherever airplanes are produced or serviced, - - (Axis countries excepted) you'll find them being produced or serviced better and faster with HALL Valve Seat Grinders and wet type Valve Refacers . . . And the engines of those planes are giving superior performance more hours between valve overhauls because of the finer precision and finish obtainable with HALL equipment . . . Write for complete information on the HALL grinding equipment to meet your particular production or service requirments

THE HALL MANUFACTURING CO., Toledo 7, Ohio

HALL



ONE CAPACITOR INSTALLATION *that did 2 jobs . . .*

Power-factor correction pays . . . now and postwar

PERMANENT AS WELL AS TEMPORARY BENEFITS Capacitors not only relieve war-crowded power lines of wattless current now, but offer permanent savings in power costs.

CONTROLLABLE TO MEET FLUCTUATING CONDITIONS. Automatic control can be used to apply correction only when required

CAPACITORS EASILY RELOCATED Whether installed indoors or out, capacitors can be easily relocated when low power-factor conditions on the system change.

Westinghouse application engineers will be glad to help you check on possible benefits from capacitors. Investigate today. Send for D. D. 49 210, "Automatic Switching of Capacitors". Westinghouse Electric & Mfg Co., East Pittsburgh, Pa.

Automatic control corrects voltage swings as well as power-factor for Buffalo war plant

A Buffalo war plant was faced with the problem of providing added system capacity with least possible modification of existing electrical equipment. It also had a problem of extremely poor voltage regulation due to a recent changeover from 25 to 60-cycle power using, in some cases, the same transformers

Capacitors solved both problems A total capacity of 3400 kv-a was installed, effectually correcting both conditions. It was found that during periods of light loads, excessive voltage rises would occur on some of the feeders Westinghouse application engineers solved this problem by providing voltage-controlled automatic switching of the capacitors. When voltage is low, the capacitors are connected; when voltage rises, their corrective effect is cut off. Voltage, as a result, is now held to a minimum variation, regardless of load conditions. J 60554

Westinghouse
PLANTS IN 25 CITIES OFFICES EVERYWHERE

CAPACITORS


Makin' the Grade... A LYCOMING FEATURE



WHEN, ON YOUR FIRST SOLO CROSS-COUNTRY FLIGHT, YOU HIT IT "ON THE NOSE!"

Sketched from life by Clayton Knight

BUY MORE WAR BONDS



Lycoming Model R-235, four-cylinder opposed 100 h.p. engine used in the HE-1 Navy ambulance plane.

It was exciting, sure. But the point was you'd gone a long way towards being the pilot you'd like to be . . . with skill you and your buddies could depend on! An engine, like a pilot, must be depended on, too. That's why every Lycoming part is tested thoroughly. All these precision-tested parts add up to an engine known for dependability — Lycoming!

AN Avco PRODUCT

LYCOMING
AIRCRAFT ENGINES

LYCOMING DIVISION — THE AVIATION CORPORATION, WILLIAMSPORT, PA.

Originated — BY ACCO ENGINEERS...
PROVED — BY LABORATORY AND FIELD TEST...
APPROVED — FOR ARMY AND NAVY AIRCRAFT



Improved

— — — THAT, IN SHORT, IS THE STORY OF

TRU-LOC

SWAGED TERMINALS AND FITTINGS

Yes, these swaged terminals and fittings were originated and patented by American Chain & Cable Company, Inc. Moreover, developments and improvements keep pace with—even anticipate—demands of advancing aircraft design.

By devising new methods of manufacture—by constant experimentation and rigid testing procedure—ACCO maintains leadership in the making of these vital aircraft parts.

There can be no compromise in the selection of aircraft terminals and fittings, they have to be right the first time. In specifying TRU-LOC, terminals and fittings, you have the plus assurance offered by the manufacturer with the greatest experience in this field.

If your data file on TRU-LOC terminals and fittings is not up to date, write our Detroit office

AUTOMOTIVE AND AIRCRAFT DIVISION
6-235 GENERAL MOTORS BUILDING, DETROIT 2, MICHIGAN
AMERICAN CHAIN & CABLE COMPANY, Inc., BRIDGEPORT, CONNECTICUT

ESSENTIAL PRODUCTS... TRU-LAY Aircraft, Automotive, and Industrial Controls, TRU LOC Aircraft Terminals, AMERICAN CABLE Wire Rope, TRU STOP Brakes, AMERICAN Chain, WEED Tire Chains ACCO Malleable Castings, CAMPBELL Cutting Machines FORD Hoists, Trolleys, HAZARD Wire Rope MANLEY Auto Service Equipment MARYLAND Bolts and Nuts, OWEN Springs, PAGE Fence, Shaped Wire, Welding Wire READING PRATT & CADY Valves READING Steel Castings WRIGHT Hoists-Cranes — *In Business for Your Safety*

They don't write headlines about fittings

★ There's big news in the headlines these days . . . *big* news that millions of *little* things have helped to create. Things like the fuse for a bomb, the sight for a machine gun, the fittings for a plane. Things that, assembled and in the hands of our fighting men, are blasting forever the hopes of the Axis nations.

Here at AFCO, the fact that we make some of the smallest parts for fighting aircraft has been an added inspiration to make these fittings even more precisely than called for by specifications. Here, workers set their goals not alone on the number of pieces produced, but on the quantity completed *without rejects*. Threads are channeled with perfection that would do justice to a diamond cutter. Holes are reamed with an exactness that challenges the micrometer. Inspection is a rite instead of a routine. Then, each part is individually paper capped so that every fitting may arrive at its destination in faultless condition.

We never expect to see airplane parts make Page One in the war news. They don't write headlines about fittings. But, we do believe that aircraft fittings bearing the AFCO trade-mark are *good enough* to help put the *good news* in bigger type—*and sooner*.



AFCO Fittings

NEW "AN" TUBE, PIPE AND HOSE FITTINGS

FITTINGS OF QUALITY FOR PLANES OF WAR AND PEACE

The Aircraft Fitting Company • 1400 East 30th Street • Cleveland 14, Ohio

MECHANICAL SWEAT GLANDS




SWEAT GLANDS are nature's temperature control. So accurate is nature's method that the body is held within a fraction of one degree variation, regardless of room or weather temperatures.

Aircraft engines need temperature control too. They must take off on short notice, in all kinds of weather, soar to the freezing cold of high altitudes and then dive thousands of feet with open throttles. No lubricating oil or engine cooling system could ever successfully cope with such conditions without the aid of sensitive temperature control instruments.

Sylphon Aircraft Controls provide engines with *mechanical sweat glands* . . . instruments responsive to the slightest temperature change. Simple, rugged and self-powered, they convert the temperature changes themselves into controlled mechanical movement, to adjust the flow of engine coolant so that constant engine temperatures are always maintained.

Write for Bulletin NA-822, which describes the latest developments in Sylphon Aircraft Controls.



Liquid Cooled Engine Thermostat, for controlling the amount of cooling medium circulated through the heat exchanger. Designed so that the valve position is entirely unaffected by static pressures in the cooling system, by varying pressure drops across the heat exchanger or control valves, or by changes in altitude

FULTON SYLPHON



Acme Photo



Hurtling cross-country at an average speed of 355 m.p.h., TWA's sleek new Lockheed Constellation arrives at the Washington airport with a new record of 6 hours and 59 minutes. This largest transport plane in the world has been turned over to the Army for whom it can carry 100 soldiers with full equipment.

RECORD-SMASHER

—the shape of things to come!

Our hats are off to TWA and Lockheed. Their magnificent Constellation which recently shattered all coast-to-coast records, is more than a superb example of American designing and engineering genius. It is a glimpse into the future . . . a concrete prophecy of finer, swifter air transportation in the days to come.

It is only natural that we at CECO feel a glow of pride that CECO CARBURETORS have been chosen for this newest giant of the skies. And in the future as in the past, our combined efforts will be concentrated on building finer and still finer products for the "record-smashers" of the years ahead.

CECO


CARBURETORS
FUEL PUMPS
PROTEK-PLUGS

Wingspread on this streamlined beauty is 123 feet—longer than the first flight of the Wright Brothers at Kittyhawk



CHANDLER-EVANS CORPORATION SOUTH MERIDEN CONNECTICUT, U. S. A.

★ ★ THE CHOICE FOR CRITICAL FLYING ★ ★



FROM the days of "flying crates," Wolf's Head Oil has been a continuous favorite in aviation. By cooperating closely with aviation designers and engineers, Wolf's Head technicians have made valuable contributions to the progress of all flying . . . and Wolf's Head today is the choice of both fleet maintenance men and leading airplane engine makers—many of whom select Wolf's Head exclusively for their critical test and breaking-in runs.

As tomorrow's advanced engines come off the production lines, Wolf's Head will have anticipated their needs . . . will have ready for them the exact qualities they require in oil engineered from "the Finest of the Fine" Pennsylvania crudes.


Wolf's Head Oil Refining Company, Inc., Oil City, Penna., and New York 10, New York

WOLF'S HEAD

100% PENNSYLVANIA
AVIATION OIL

P.G.C.O.A. Permit No. 6

R-301 *the Aluminum Alloy that is* STRONG, CORROSION-RESISTANT, WORKABLE



PLANE DESIGNERS wanted a higher strength aluminum alloy for increased performance. Aircraft shopmen wanted an aluminum alloy of good workability in order to reduce production time. Users of aircraft wanted an aluminum alloy with good corrosion resistance, to withstand *any* atmosphere and climate.


Reynolds' Metallurgists, reading these needs, created R-301.

R-301 is a high-strength aluminum alloy core, integrally bonded with a corrosion-resistant, medium-strength aluminum alloy cladding. The core and cladding alloys respond to the same heat treatment—resulting in a final product possessing high strength.

R-301 in the solution heat treated temper is stable and more workable than any other high-strength aluminum alloy in the corresponding temper—thereby eliminating costly post-forming heat treatment and consequent distortion of aircraft parts.

R-301 is being produced in three tempers, suitable for a wide range of applications. Inquiries are invited. Reynolds Metals Co., Aluminum and Parts Div., Louisville, Ky.

* * *





(*Upper right*) Heavy, bending rolls, forming an armor hood for the pilot's compartment. R-301 can be cold-rolled to shape.

(*Lower right*) R-301 drills and routs to sharp, accurate contour. The hard surface cladding reduces the hazard of accidental scratching.

The superior workability of R-301 offers a major advantage in forming [illegible] flanged parts

REYNOLDS METAL

REYNOLDS ALUMINUM

The Great New Source of

EXTRUSIONS WIRE

A Pioneer in Making Air Serve the Aviation Industry



AN EXPERT IN Sweeping Air

Exhausting many objectionable by-products of daily operations from shop working areas

● DeVilbiss not only pioneered in using air to *produce* many operating advantages but also to *remove* many working handicaps—by sweeping the air clear of objectionable—and often hazardous—dust, fumes, odors and spray vapors in shop areas.

Our exhaust engineering experience started more than 30 years ago with the development of the first paint spray booth That small, wood panel model led to a broad line of DeVilbiss Exhaust Equipment—from wall fans for small shop areas to huge waterwash booths that accommodate complete bombers.

Besides, DeVilbiss air experience includes years of research and engineering effort in developing and producing equipment for compressing, cleaning, regulating, conveying and using air.

This DeVilbiss Equipment has a long record of fast, efficient and economical performance in aircraft work—for touchup painting, applying insignia, caulking seams, wing doping, clearing fuel lines, greasing engine cylinders, cleaning engine parts and supplying air for tools.

In 56 years, DeVilbiss has accumulated a vast reservoir of knowledge on how air can serve you best A DeVilbiss engineer will gladly apply it to your operations.

THE DEVILBISS COMPANY, Toledo 1, Ohio
Canadian Plant: WINDSOR, ONTARIO

DE VILBISS
Spray Systems

SPRAY EQUIPMENT • EXHAUST SYSTEMS • AIR COMPRESSORS • HOSE & CONNECTIONS





FIGHTERS AND BOMBERS MUST HAVE GUNS

and Guns must have HEAT

● The world's best fighters and bombers—Flying Fortresses, Lightnings, Mustangs, Wildcats, Thunderbolts, to name only some . . . keep their guns blazing in sub-zero altitudes with H. & A. Electric Contact Heat Units . . . almost universally specified by the U. S. Army and Navy as standard aircraft armament equipment.

Made in every conceivable shape, size and contour to fit pipes, valves, cylinders and containers to maintain exact temperatures of free-flowing or viscous liquids, H. & A. heater units are now being adapted to numerous industrial uses.

● Ask us to solve your control heating problems Write H & A. Engineering Department . . . 92 Lacey Avenue Buffalo 14, New York



H & A
Manufacturing Co. Inc.
PLANTS IN BINGHAMTON AND BUFFALO, N. Y.



AMERICA'S FIGHTING PLANES



U. S. ARMY AIR FORCES AND U. S. NAVY PHOTOS

How many of these planes do you know? Would you like a 24x37" poster illustrating them as here and giving a brief description of each one, what it does and the battles it has fought? Write on company letterhead to Koppers Company, American Hammered Piston Ring Division, Baltimore (3), Md.





The only Army-Navy "E" awarded for piston ring production

Dow Corning ANNOUNCES first commercial production of SILICONES

Long sought goal reached through two great manufacturing organizations

Now industry can benefit by the unique properties found in a totally new group of products derived from silicon. For the first time, successful commercial production of such products has been attained. It has been reached by uniting, in Dow Corning Corporation, the technological resources of two great organizations—The Dow Chemical Company and Corning Glass Works.

Dow Corning Silicones are now available to industry in the forms of resins, fluids, and greases. Many other products are under development for high temperature or low temperature use Detailed information and technical assistance are available on request.

- **Dow Corning Insulating Resins—**

  Heat curing, high temperature stable insulating varnish for use with Fiberglas, mica and asbestos insulating materials to make possible higher operating temperatures for electrical equipment.

- **Dow Corning Fluids—**

  Inert liquids, with viscosity little affected by temperature changes; excellent dielectrics; chemically resistant, high temperature stable, operate down to very low temperatures.

- **Dow Corning Greases—**

  Plug cock grease for lubricating industrial plug cocks and valves—Stopcock grease for glass, ceramic and plastic fittings.

DOW CORNING CORPORATION
BOX 592, MIDLAND, MICHIGAN



Look Listen Learn

ALL ABOUT


CHERRY RIVETS

Actual size pictures for quick comparison and identification

Cherry visual aids, manuals and handbooks tell nearly everything there is to know about these remarkable blind rivets.

For faster, better blind riveting refer to the Cherry Rivet Chart. It should have a prominent place on the wall of every aircraft manufacturing plant and service department. To learn the what, how, which and why of blind riveting listen to a Cherry Rivet "Pointer" Talk—mighty instructive to beginners and old timers alike.

And remember Cherry Rivets are true blind rivets—work from one side of the job only. They are headed up with a pull instead of a pound and so they are efficient fasteners for plastics and soft, pliable or brittle materials of all sorts, also for all blind riveting in metal.



As part of your training program have a Cherry Rivet Field Service Engineer give this "Pointer" Talk in your plant

Get this manual into the hands of every riveter in your shop. It is distributed to every Cherry Rivet "Pointer" Talk audience and may be had by others on request. Address Department A-110, Cherry Rivet Company, 231 Winston St., Los Angeles 13, California.

CHERRY RIVETS THEIR MANUFACTURE AND APPLICATION ARE COVERED BY U. S. PATENTS ISSUED AND PENDING

Cherry Rivet Company

LOS ANGELES, CALIFORNIA



Channel crossing time... 2½ minutes flat!

It's 21 miles from the white cliffs of Dover to the beach at Calais. Yet jet propelled fighter planes of types currently under development for the United Nations, can cover that distance in about 2½ minutes flat.

For jet propelled planes are capable of speeds *in excess of 500 miles per hour*—more than ¼ as fast as a machine gun bullet.


In addition to its great speed in level flight and its excellent performance in rate of climb, the jet propelled plane possesses other advantages which its further development may be expected to demonstrate.

At McDonnell—after Victory—we expect to further the progress of jet propelled aircraft through comprehensive research and development work. *Right now*, our all-important job is making planes, parts and plastics for war... and a quicker Victory.

McDONNELL *Aircraft Corporation*

Manufacturers of PLANES · PARTS · PLASTICS ★ SAINT LOUIS-MEMPHIS ★

Ingersoll-Rand
Comes to "Close Quarters" with the aid of





RBC NEEDLE BEARINGS

Ingersoll-Rand Close-Quarter Drills are exceptionally powerful machines, in which all rotating parts are supported by anti-friction bearings. Among these, an important part of the load is borne by RBC precision Needle Bearings.


The "Multi-Vane" Close-Quarter Drill shown here is equipped with RBC 20th CENTURY Bearings, designed as a self-contained unit, incorporating a full complement of small diameter rollers in a hardened and ground outer race. This application makes use of a solid hardened and ground inner race.

Much of the reputation for low maintenance cost enjoyed by these "Multi-Vane" Drills is due to these precision anti-friction bearings designed for minimum overall dimensions and maximum carrying capacity.





Showing Location of RBC 20th CENTURY Bearings in "Multi-Vane" Close-Quarter Drill



There's an RBC Bearing in This Picture, Too!

Even though they are out of sight, the RBC 20th CENTURY Needle Bearings located at strategic points within this "Multi-Vane" flue rolling machine are doing a most important job, insuring smooth and continuous operation of rotating parts. Actual use demonstrates that these bearings may be operated advantageously at high speed ranges. Perhaps YOUR equipment would benefit through use of RBC BEARINGS. Our engineers are ready to assist you.

ROLLER BEARING CO. of AMERICA
TRENTON . . . . NEW JERSEY



Highways of the Skies

People will fly!

And a lot of fast express will take to the air tomorrow.

To guide this vast new air traffic safely from ground to ground will require new conceptions of instrument landing, ranging and marking equipment.

Federal has had long experience in making aerial navigation equipment. Now, at the great Federal laboratories, still newer and better means of three dimensional traffic control are being developed and perfected.

Here is the logical place to start your plans for tomorrow—*one* design-and-manufacturing organization ready to plan ahead with you. Get acquainted with Federal now!



Federal designs that extra margin of performance into its radio communication equipment—built in a great variety of frequency ranges and power sizes for aeronautical, point-to-point, radio telephone and telegraph, marine and mobile applications.

BUY MORE BONDS


Federal Telephone and Radio Corporation

An IT&T Associate

Newark 1, N. J.

Increase production with the *right* cutting oil!

Nowadays, with time the essential factor in production, cutting speeds have been increased to keep step with the tremendous demands of wartime manufacturing. Higher speeds mean greater vibration and heating and a new emphasis has



been placed on cutting oils that will prevent welding and seizure of chip and tool.


Recognizing these war demands, Union Oil Company has placed on the market an improved line of cutting oils, designed to meet every need of the machining world.

Whether you turn the softest magnesium or ream the toughest steels, there is a Union Cutting Oil which will help speed up your production. Their high film strength and extreme pressure characteristics permit faster cutting speeds and give longer tool life.

Union Cutting Oils are noncorrosive and completely sterile. They maintain excellent wetting conditions with good penetrating properties, allowing a cooler job and better surface finishing.



If you want cutting oils that are designed to do the toughest war job—and if you like to buy from a single source—phone a Union Oil Resident Manager in any of the five Western states, or write Union Oil Company, 617 W. 7th Street, Los Angeles 14, California.



Union Oil Company—maker of 492 quality products—is the largest independent oil company in the West.

UNION CUTTING OILS

Another **UNION OIL** Success-Tested Product



That's right . . . take a hair, magnify it 62.5 times . . . result — a husky rod. This is just what Jones & Lamson Optical Comparators do to those tiny dimensions that are difficult, or even impossible, to measure by any other means.

If you are a manufacturer of parts that must be right — to a hair — it will pay to investigate Jones & Lamson Comparators. These machines are designed for use in the shop (they don't have to be babied), and they can be used as easily as a mechanic's scale.

Jones & Lamson inspection engineers are at your service to study your particular measurement and inspection problems. Call on them today!

MEASUREMENT AND INSPECTION—BEYOND A SHADOW OF A DOUBT!

This book, "Beyond a Shadow of a Doubt" will be sent to executives asking for it on their firm letterhead

JONES & LAMSON MACHINE COMPANY


OPTICAL COMPARATORS Springfield, Vermont, U.S.A.

Manufacturers of: Universal Turret Lathes • Fay Automatic Lathes • Automatic Double-End Milling and Centering Machines • Automatic Thread Grinders • Optical Comparators • Automatic Opening Threading Dies and Chasers.



NOW! A PROVEN

Made Even Better!



Entirely independent of the engine, South Wind model 906-A-1 is ram-air operated with rated output of 50,000 Btu/hr. It is 7 inches in diameter and 17⅜ inches long—with weight of approximately 17 pounds, including filter and valves.



Designed especially for fan operation, the South Wind Model 906-E weighs only 15 pounds, less fan. With the fan shown, weighing 7 pounds, the heat output is approximately 45,000 Btu/hr.

SOUTH WIND HEATER

Simpler! Surer! Hotter!

ALREADY a record-holder for dependability and long life, Stewart-Warner's never-ending development work has made this remarkably compact, light-weight South Wind model 906 an even finer unit than before.

In life tests—still uncompleted—two of these South Winds have already passed the 1900-hour mark in excellent operating condition.

In the improved version . . . 906-A-1 . . . the shut-off and restriction valves and filter are combined into a single, simpler unit, eliminating numerous fittings and connections and greatly reducing the chance of foreign matter getting into the system. In addition, the new valves have synthetic rubber instead of metal seats, making them relatively immune to leakage due to foreign material lodging on the seats. All terminals are now enclosed.


Starting characteristics have been further improved. In tests at −70° F., the heaters started consistently at 29,000 feet with 87-octane gasoline, and at 30,000 to 31,000 feet with 91-octane fuel.

Although rated at 50,000 Btu/hr. output, substantially greater output is possible under certain conditions. When total inlet air pressure of 10 inches of water is available, output of 80,000 Btu/hr. has been attained *with no increase of maximum metal temperatures above those at normal rated output.*

ACCESSORY CONTROLS MAKE OPERATION FULLY AUTOMATIC



Stewart-Warner South Wind Therme-Switch and Duct Pressure Switch are light weight controls, quickly adjustable to desired settings, with special design and operating advantages developed by South Wind engineers. They are engineered to operate as a team with the 906-A-1 heater, and provide fully automatic regulation of fuel and ignition, so heater operation can be controlled from a single switch.



NEW! Model 911 South Wind—ram-air operated—10 inches in diameter and weighing but 23 pounds — gives up to 250,000 Btu/hr. output . . . more heat per pound and cubic inch than ever attained before!

Another Product of STEWART WARNER

South Wind Heaters

ARE U. S. PAT. OFF.

ARMY NAVY

HEATER DIVISION, STEWART-WARNER CORPORATION, CHICAGO 14, ILLINOIS
West Coast Office, Stewart-Warner Aircraft Heater Engineering and Service,
1273 Westwood Blvd., West Los Angeles, California

A Report to the Owners of

MORE THAN

42,665,000* Vehicles

EQUIPPED WITH

STANDARD TIRE VALVES

A SERIOUS TIRE SITUATION. Because of the critical rubber shortage, the present tires on your vehicles may be all you'll have for the duration. Because of this serious situation, they must be made to last by keeping them free from abuse and properly inflated at all times. It's a fact that a tire underinflated 6 lbs. loses up to 30% of its potential mileage.

Since Pearl Harbor new car, tire and tube production has been limited principally to military and essential war-time needs. Inner tubes equipped with Standard Tire Valves in civilian service today are, on the average, over 5 years old—with millions 10 to 15 years old. Five years and more of constant use with no apparent relief to sight means but one thing—even more wear and tear.


HERE'S GOOD NEWS ABOUT YOUR VALVES! Tire Valves are built with standardized replaceable parts—for your convenience. This standardization that began 46 years ago, is widespread throughout the world today, due to the foresight and progressiveness of the tire and automotive industry. One size valve cap and valve core will fit every one of the more than 189,000,000 standard valves in use in the United States alone. Standard caps and cores may be obtained wherever gas or tires are sold or flats repaired.

WHAT YOU CAN DO TO MAKE YOUR TIRES LAST See that every tire valve is air-tight. 1. Inspect the core to see if it is damaged and replace only if necessary. 2. Be sure that a Standard Valve Cap is on every tire valve, for if a core is damaged and you cannot get another one immediately, the cap screwed down finger-tight absolutely guarantees an air-tight valve seal. 3. If your tire still loses air excessively . . . *after* you have inflated it to the correct war-time pressure and sealed the valve with a Standard Air-tight Valve Cap . . . you know the leak is in the tube. Have the tube fixed immediately, for underinflation ruins a tire, breaks down the side walls and, as a result, the tire cannot be recapped.

To conserve vital rubber, every man, woman and child should see that a Standard Tire Valve Cap is on every valve. You can tell at a glance when one is needed. Next time you get gas—get air—get air-tight Schrader Caps.

*1943 Registration Figures

Reprints of this advertisement are available for Bulletin Boards



A SCHRADER'S SON, *Division of Scovill Manufacturing Company, Incorporated,* BROOKLYN, NEW YORK



A teletype clicks in code into Patterson Field, Ohio — — — Rush thirty B-25 main landing gear struts to China-Burma-India Headquarters Stop Emergency." Four days later the landing gear struts have finished their 14,000 mile Global Express ride! It's an emergency order but this speed of delivery is now standard practice on the India run. Come hell or headwinds—it's four days out and four days back!

To maintain that schedule, wire and cable must do its job — — engines, precision instruments, lights and radio communication must not fail! Information on Auto-Lite's low-cost dependable aircraft wire and cable should be in your files. Form No. C-503 describes Steelductor, the high-tension wire famous for better economy and performance. Form No. 838 describes Auto-Lite's low-tension, abrasion-resistant aircraft wire and cable. Write for your copies of these Bulletins today.



THE ELECTRIC AUTO-LITE COMPANY

Wire Division

SARNIA ONTARIA PORT HURON, MICH

BACK THE ATTACK—BUY MORE THAN BEFORE

AUTO-LITE AIRCRAFT WIRE and CABLE

TUNE IN AUTO LITE'S GREAT RADIO SHOW "EVERYTHING FOR THE BOYS"—EVERY TUESDAY NIGHT—NBC NETWORK



Air Transport CANNONBALL

Delivering high priority passengers and war cargo half way across the world so fast that the military affectionately dubbed it the "Cannonball Express," Douglas C-54 Transports connect Florida and India. Operated by the Army's Air Transport Command, the "Cannonball" has flown more than 14,500,000 miles and made better than 2,800 South Atlantic crossings.

Thus war wings are blazing airtrails for your world-wide travels after Victory!



DOUGLAS EQUIPPED AIRLINES: American Airlines — Newallas Airlines Ltd — Braniff Airways — Chicago & Southern Air Lines — Colonial Airlines — Delta Air Lines — Eastern Air Lines — Western Air Lines — Northeast Airlines — Northwest Airlines — Pan American Airways — Pennsylvania Central Airlines — TWA — United Air Lines — China National Airways — Pan American-Grace Airways — Avianca (Aerovias Nacionales de Colombia) — Cia. Mexicana de Aviacion — Panair Do Brazil — Cia. Nacional Cubana de Aviacion, S.A. — Urabe Medellin and Central Airways — Cruzeiro do Sul (Brazil) — Primeras Lineas Uruguayas de Navegacion Aerea S. A. — Aerovias de Guatemala, S. A. — Canadian Pacific Airlines — Australian National Airlines — Royal Dutch Airlines (K.L.M.) — Royal Netherlands Indies Airways (K.N.I.L.M.) — Sabena (Belgian Congo) — Swissair (Switzerland) — A.B. Aerotransport (Sweden) — Indian National Airways — L. A. P. E. (Spain) — Aer Lingus (Ireland) — Americas Airlines of Mexico — British Overseas Airways (BOAC) (England).



Now! AN ALUMINUM ALLOY CLAMP THAT COMBINES HIGH STRENGTH WITH LIGHT WEIGHT



*MARMAN 3087-D-(61-ST) 500-2
ALUMINUM ALLOY CLAMP—actual size

CHARACTERISTICS OF ALL MARMAN CLAMPS

CIRCUMFERENTIAL LOADING
Tension is uniform around any convex surface. No bulging, pinching or distortion.

QUICKLY INSTALLED
QUICKLY REMOVED
Marman C'amps may be opened and wrapped around any member, they be installed and removed conveniently without disturbing lines.

A SIZE AND SHAPE FOR EVERY JOB
Circular, oval, square, oblong and irregular shapes are all easily handled with Marman Clamps.

Marman Aluminum Alloy Clamps save weight . . . in many instances more than 50% compared with steel clamps of equivalent strength. The patented Marman design requires no severe forming, and clamping action develops no stress concentrations anywhere in the clamp assembly. These clamps are particularly suited for Aircraft ventilation, carburetor intake, supercharger, intercooler and similar installations where medium or large sizes are required.

COMPARISON DATA!


*Type: D(61-ST)	Type C B (AN-S-11)
Size: 5½" I. D.	Size: 5½" I. D.
Width: .6875"	Width: .6875"
Band Thickness: .032"	Band Thickness: .031"
Weight: 1 oz.	Weight: 2⅛ oz.
Min. Yld.: 800 lbs.	Min. Yield: 600 lbs.

MARMAN clamps

MARMAN PRODUCTS CO. Inc.
940 WEST REDONDO BOULEVARD
INGLEWOOD, CALIFORNIA

THE LARGER THE CLAMP THE GREATER THE WEIGHT SAVING!

Design of Needle Bearings Eliminates Stress Concentrations



FULL COMPLEMENT OF NEEDLE ROLLERS PROVIDES MANY LINEAR INCHES OF CONTACT; DISTRIBUTES LOAD OVER LARGER AREA

Elimination of stress concentrations is one of the outstanding features of all Torrington Needle Bearings which stems from their basic design principle —the use of *a full complement* of small diameter needle rollers.

In operation, this means that the load on the Needle Bearing is widely distributed over a comparatively large number of rollers, and each in turn provides 'line' contact with inner and outer race. As illustrated in the accompanying diagram, a large number of needle rollers are always within the "load zone" as the rollers revolve around the shaft. Thus the load is *evenly* distributed and the full capacity* of the bearing may be utilized without fear of concentration of stresses at any given point or on any single component of the bearing. As long as the design load is within the rated capacity of the bearing, the dangers of rapid or uneven wear, of stress fatigue, or of brinelling bearing parts are virtually eliminated.

This feature, coupled with the efficient lubrication of rollers, made possible by the design of the outer raceway which serves to hold the lubricant within the bearing, insures maintenance-free operation and long service life.

For All Design Requirements

From the several types of Torrington Needle Bearings available, the design engineer may select the one best suited to the requirements of a particular application. Load, speed, service conditions, design limitations and cost considerations can be met with full confidence that the right Torrington Needle Bearing, properly installed, will provide long bearing life and freedom from service attention. Let our engineering department work with you in selecting the correct type Needle Bearing for your application. Experience in layout and design of hundreds of different applications will enable our engineers to give practical assistance in meeting your design requirements. More information on the types and sizes of Torrington Needle Bearings together with a more complete description of the advantages of these compact, anti-friction units, will be found in our Catalog No. 30-A available on request. Send for your copy.

**Utilization of full or theoretical capacity of Needle Bearings is dependent upon proper shaft hardness, correct installation and other factors. See Torrington Needle Bearing Catalog for more complete information.*

THE TORRINGTON COMPANY
Established 1866 • Torrington, Conn. • South Bend 21, Ind.
"Makers of Needle Bearings and Needle Bearing Rollers"

New York	Boston	Philadelphia
Detroit	Cleveland	Seattle
San Francisco	Chicago	Los Angeles
Toronto		London, England

TORRINGTON
NEEDLE BEARINGS




The war won't wait for sunny weather or dry landing strips. Every plane surface must be highly weather-proof. That's why many of the most famous allied fighters and bombers are protected with Berryloid Aircraft Finishes. In thirty years there have been no finer finishes made—none so durable, none so weather-resistant. Peacetime manufacturers will likewise benefit by this dependable quality.

BERRY BROTHERS
Aircraft Dopes · Lacquers · Primers
Detroit 7, Mich. — Walkerville, Ont.

BOSTON · JERSEY CITY · CINCINNATI · CHICAGO · ST. LOUIS · INGLEWOOD, CALIF.
MONTREAL · WINNIPEG · TORONTO


BERRYLOID
AIRCRAFT FINISHES



American aircraft have it and are demonstrating that fact on a day after day, round the clock schedule because small aircraft ports as well as large are built on a top quality basis.

Flex-O-Tube hose assemblies, with which the Pan-American Atlantic Clipper is equipped, are a typical example of this. Each of these Flex-O-Tubes is engineered, manufactured and tested for a specific application. They are important small parts.

The same Flex-O-Tube quality needed on long range airliners is one of the reasons for the INTESTINAL FORTITUDE of our fighting aircraft around the globe.




THE **Flex-O-Tube** COMPANY

LAFAYETTE at 14th AVE., DETROIT 16, MICHIGAN
Offices: CHICAGO · FORT WORTH
LOS ANGELES · NEW YORK
SEATTLE · TORONTO, ONT.



FROM OUR CATALOG OF **1875**

This quaint wood cut was reproduced from the pages of the 1875 catalog of the Wiley & Russell Manufacturing Company, one of the parent companies of the Greenfield Tap & Die Corporation. It shows the "finest threading tools" of that time and the copy modestly states "it is warranted to do five times the work that can be done in the old way"




Now GREENFIELD'S NEWEST CATALOG

Here is a valuable new addition to the library of all who are concerned with the purchase or use of Taps, Dies, Gages, and other small tools. The pages of Greenfield's new Catalog No. 44 include complete and up-to-date listings of sizes and styles, plus a wealth of technical data that will help the engineering and production staffs of every metal-working industry as they work on war and post-war products.

The new catalog has been most carefully indexed and arranged for quick reference. Copies are available from your local "Greenfield" Distributor.

GTD **GREENFIELD**
GREENFIELD TAP & DIE CORPORATION
GREENFIELD, MASSACHUSETTS, U. S. A.



The Decisive Factor In This Argument May Be the Last Word In CONTACT ALLOYS

SKILL and nerve are important in combat—but they're not enough without good equipment. A defective wing strut can defeat the bravest pilot. And a little thing like an electrical contact can mean the difference between life and death.

Knowing this, an aircraft company, about to get rolling on a new type of medium bomber, called for the finest contacts that could be made for the job. The contacts were needed for a power-driven gun turret, and so they turned to Mallory.


Fortunately, the Mallory policy of continuous development had already produced the needed material, Elkonite* G-12, as well as a superior manufacturing process to give these contacts added life. They had demonstrated consistently a very low contact resistance, and sufficient hardness to wear very slowly. Installed in the relay circuit, Elkonite G-12 passed all short circuit tests—demonstrating, in addition, a remarkably low voltage drop over a long period of operation, avoiding dangerous temperature rise of the contact mechanism and permitting it to run cool and safely under the most severe conditions.

This experience, far from unusual, is another illustration of Mallory foresight combined with technique. How about sharing Mallory "Know how" with you? How about doing it now—while designs are still in the blue print stage?


P. R. MALLORY & CO., Inc., INDIANAPOLIS 6, INDIANA

The Harder They Fight, the More They Need—Buy War Bonds

*Elkonite is the registered trademark of P. R. Mallory & Co., Inc., for refractory metal compositions



WALDES TRU-ARC RETAINING RING




For thrust-load fixing, and shaft and housing applications, Waldes Truarc provides distinct advantages over nuts and bolts or wedges and washers . . . it reduces dimension and weight . . . saves material . . . cuts manufacturing time . . . simplifies assembly and dis-assembly.

On request, we will gladly furnish samples and full data for your tests.

Waldes Truarc presents a significant advance in retaining rings.

It spreads or contracts without distortion; always retaining its perfectly fitting circular contour.





U. S. Pat. Re. 18,144
Sole Manufacturers in U. S. A.

WALDES KOH-I-NOOR INC. ★ LONG ISLAND CITY, N. Y.

Canadian Representatives: **FRENCO PROGRESSIVE & ENGINEERING CO., LTD.,** 72-74 Stafford St., Toronto



IN THE

Aircraft Industries

SOUTH BEND LATHES have long been popular for precision manufacturing operations and fine tool work in the aircraft industry. Today, in the greatest plane production schedule in history, these modern lathes are more than keeping their traditions for dependable precision and exacting tolerances. Providing lathes to most of the aircraft industry is one of our many important war assignments.

TRAINING HELPS

South Bend training helps—books, sound films, wall charts, and booklets on the care and operation of engine lathes and toolroom lathes—are available for facilitating the training of new lathe operators. Write for a copy of Bulletin 21-C.

BUY WAR BONDS NOW . . . SAVE FOR LATHES

SOUTH BEND LATHE WORKS

LATHE BUILDERS FOR 37 YEARS • SOUTH BEND 22, INDIANA



This cab no longer waits at 3 A.M...

A certain type of Westinghouse Electronic Tube was urgently needed in England. Every night, as the last lot came off the test rack at our Bloomfield Plant, we had a cab waiting, ready to rush it to the airport for bomber ferry across the Atlantic. Today, things are different. Engineering ingenuity and a vast program of plant expansion have multiplied Westinghouse Electronic Tube production 30 times. We've trained 28 new workers for each one formerly employed, expanded floor space 20 times. And now we're not only meeting time and quality musts on all Government contracts—we're also continuing to supply the heavy demands of war industry. Your nearest Westinghouse Office or Distributor will be glad to receive your inquiries for Westinghouse Tubes. Westinghouse Electric & Manufacturing Company, Bloomfield, N. J.

AVAILABLE [illegible]

WL-195	Pliotron	WL-672	Thyratron
WL-196	Pliotron	KU-676	Thyratron
WL-463	Pliotron	WL-677	Thyratron
KU-610	Thyratron	WL-681/686	Ignitron
KU-627	Thyratron	WL-710	Ballast Tube
KU-628	Thyratron	WL-788	Ballast Tube
KU-629	Thyratron	WL-8578	Phanotron
WL-631A	Thyratron	WL-892	Pliotron
WL-651/656	Ignitron	WL-895	Pliotron
WL-652/657	Ignitron	WL-896	Ballast Tube
WL-655/658	Ignitron		



Westinghouse

PLANTS IN 25 CITIES OFFICES EVERYWHERE

Quality Controlled ELECTRONIC TUBES

INTERIOR OF VELON* MEANS

bright colors are practical!

maintenance is virtually zero!



THOUSANDS of plane, bus, train, car and cab seats upholstered in colorful woven *Velon* have now been in use for nearly three years—*with not one sign of wear yet visible!* They are as fresh and new looking as the day they were installed.

That's because *Velon* is virtually indestructible, and easy to keep clean. Practically 100% non-absorbent, it can be wiped clean and fresh as new in a few seconds, with water or cleaning fluid. *Velon* is stainless, non-inflammable, highly resistant to grease, acids, alkalis and solvents. It never cracks, never loses its original shape

No wonder "Interior of Velon" will be a feature of postwar transportation! Then *Velon* will be available in upholstery fabrics, in draperies, window shades and screens, wall coverings, panelings. Every color and combination will be *practical*—because even the most delicate shades will last forever.

Watch for *Velon's* release for civilian use. It will mean a new high in eye-appeal—a new low in maintenance cost.

P.S. For *completely* modern seating, make the cushioning FOAMEX.

ANOTHER CONTRIBUTION TO A BETTER WAY OF LIFE by

Firestone

*Trademark pronounced VEL-LÓN



A tail light blinks and one hundred bombardiers unleash death and destruction on the enemy below Only a little light—this E A. Tail Light—but on its split-second signal hangs the success of the bombing mission.


With skilled craftsmanship, developed through years of service to industry, and refined by the inexorable demands of war, E A Laboratories engineer and build many kinds of highly precisioned equipment for aircraft

After victory, lessons culled from the cauldron of battle, translated into new, finer products for peace, will advance E A Laboratories leadership in the many industries it serves.




E. A. LABORATORIES, INC., BROOKLYN, N. Y.

MAKERS OF AUTOMOTIVE, AVIATION, BICYCLE AND MARINE APPLIANCES



SIOUX AIRCRAFT

WET VALVE SEAT GRINDING MACHINE
for INLINE and RADIAL motors




Write for details and delivery dates

STANDARD THE WORLD OVER

ALBERTSON & CO., INC. SIOUX CITY, IOWA, U. S. A.



HOW WE DETECT STEEL FLAWS IN ARMATURE SHAFTS . . .
for Precision-Built Aircraft Motors



EMERSON-ELECTRIC AIRCRAFT MOTORS are made for gun turret drives, hydraulic units, fuel pumps, actuators, winterizing units, communication systems—also with built-in gear and magnetic brake.

Specifications for many types of aircraft motors require exacting tests of raw materials, and at every stage of production. Magnaflux testing of the steel in armature shafts is one of these requirements.

The shaft is first magnetized and then sprayed with a special mixture of iron powder and oil. The shape of any surface flaw is plainly indicated by the pattern of the iron powder which adheres to the shaft directly over the imperfection.

Rigorous inspection operations of this type have had much to do with the success of Emerson-Electric Aircraft Motors in meeting specifications and the severe service requirements on combat aircraft.

THE EMERSON ELECTRIC MANUFACTURING CO., ST. LOUIS 3, MO.

Branches: New York • Chicago • Detroit • Los Angeles • Davenport

399

EMERSON ELECTRIC

MOTORS · FANS — APPLIANCES

The CONE AUTOMATIC MACHINE COMPANY



sees many

GOOD THINGS AHEAD

It is reported that:

The world's most powerful electric motor has recently been completed. Developing 7,000 horsepower at only 25 r.p.m., it is said to be capable of lifting an entire four stack destroyer at the rate of 200 feet per minute.

Get ready with CONE for tomorrow

A new resin dip for small metal parts feels like rubber, protects the part, strips easily by hand and may be re-used.

Get ready with CONE for tomorrow

A new invention consists of a panel that hangs over a bed and is a source of radiant energy. Properly adjusted to the sleeper's metabolism and length of slumber, it is expected to give him the equivalent of a full night's sleep in as little as two hours.

Get ready with CONE for tomorrow

The rare metal, indium, is being used as a tarnish-proof plating for gold and silver and is being used as an alloy in bearing metal and solder.

Get ready with CONE for tomorrow

A new chemical does most of the work of the dangerous hydrofluoric acid without danger to the human skin.

Get ready with CONE for tomorrow

The new plastic-coated fabrics will be water-proof and abrasion-resistant and may be flexed for a long time before cracking. They will be useful materials for baby carriages, auto tops, furniture, bus seats, shoe tips, raincoats, luggage, shower curtains and handbags.

Get ready with CONE for tomorrow

Even the high-pressure cylinders used to hold compressed gases are now being made by stamping and drawing.

Get ready with CONE for tomorrow

A colored surface .0001 inch thick, applied to the surfaces of gages does not affect their accuracy, but warns of wear by a change in color.

A national producer's council hopes to reduce the cost of home building by 20% by promoting more modern building codes and labor regulations.

Get ready with CONE for tomorrow

The by-products of sawdust have become so valuable that some sawmills are using coal for fuel.

Get ready with CONE for tomorrow

A prominent scientist states that it may take twenty years to utilize fully the scientific discoveries made since Pearl Harbor.

Get ready with CONE for tomorrow

A synthetic shellac made from corn is expected to permanently replace the natural product which is made from the secretions of an insect found in India.

A large manufacturer of farm machinery proposes to enter the peace-time farm market with a line of refrigerators and cold storage lockers.

Get ready with CONE for tomorrow

A new low-temperature grease permits aerial cameras to operate at temperatures as low as 100 degrees below zero.

Get ready with CONE for tomorrow

A French automobile manufacturer expects to make a small, economical car for the American post-war market.

Get ready with CONE for tomorrow

A maker of paper parachutes, for dropping supplies to troops, expects to continue their manufacture after the war for use in the air delivery of mail and light-weight express.

Get ready with CONE for tomorrow

The world's shortest firing range, only twenty-two feet long, duplicates the air pressure and temperature of the stratosphere.




Here is performance that is definitely AHEAD

This part calls for extreme accuracy and yet requires wide forming cuts on a variety of diameters. In one position an attachment taps an inside thread 5/16"-18 while, at the same time, a die cuts an outside thread 5/8"-27. Produced on the 6 Spindle Conomatic at the rate of 12.5 seconds per part.




CONE

AUTOMATIC MACHINE CO., INC. ★ WINDSOR, VERMONT, U.S.A.



RIGHT ON THE BUTTON!



YOU'RE RIGHT when you buy the socket wrench with the button—and only Blackhawk Wrenches have it.

Only Blackhawk gives you "Thumb-Release Lock-On"—and the "button" on the socket is the earmark of this important feature. A spring-backed plunger on the drive pushes into a sidewall hole in the socket—assuring a positive lock. Hell and high water can't make the Blackhawk Socket Wrench combination fall apart.

BUT—press the Thumb-Release Button (which floats nearly in that socket sidewall hole)—and your wrench assembly pulls apart with magical ease!

Insist on the Blackhawk Button for Speed with Safety

The Blackhawk Socket is never left on the nut when you pull away from your work. No fishing in tight spots for fallen sockets. You work *faster and more safely* with dependable world-famous Blackhawk Socket Wrenches!

These slim, trim, sturdy wrenches are the pride of top mechanics everywhere. You, too, will be the "King of the Shop" when you own Blackhawk Wrenches.

See your jobber or take a minute now to mail the coupon for catalog of Blackhawk Wartime Wrenches and the "Mechlin" booklet that tells all about wrenches and how to use them! Every mechanic should have these two books.



A Product of BLACKHAWK MFG. CO., Dept. W2174, Milwaukee 1, Wis.

BLACKHAWK

ONLY Blackhawk Gives You "Lock-On" in 3/8"—7/16"—1/2"—3/4" and 1" Square Drives

BLACKHAWK MFG. CO.
Dept W2174, Milwaukee 1, Wisconsin

Please rush Blackhawk Wartime Wrench Booklets

Name_____

Address_____

City_____ State_____

SHEFFIELD

DIAL INDICATOR SNAP GAGE

FOR INSPECTION AND CLASSIFICATION

1 Gage may be used with dial either at the bottom or the top, whichever is more convenient.

2 Dial is adjustable radially and can be swung through 360° to facilitate reading.

3 Scale has a range of .005"—each graduation .0001".


4 Movable anvil is spring urged for constant gaging pressure, but spring has no effect on indicator. Special spring pressures available.

5 Movable anvil bearing is long enough to preserve alignment with the fixed anvil.

6 Fixed anvil is adjustable to a maximum of one inch.

7 Adjustable backstop has a cylindrical face for accurate line contact

8 Comfortable handle with plastic grip to insulate gage from heat of inspector's hand.





Work may be gaged to the accuracy of o one "tenth" indicator without removing it from the machine

THE SHEFFIELD CORPORATION

Dayton 1, Ohio, U.S.A.

MACHINE TOOLS • GAGES • MEASURING INSTRUMENTS • CONTRACT SERVICES



Dry run Susie

Around the big training hangar at Lockheed's Service School they call it "Dry Run Susie"—an accurate replica of the P-38 cockpit, with instruments, gauges and controls all in their proper places. A working textbook to show military student mechanics the operating and maintenance characteristics of America's most versatile fighting plane.

Cockpit Without Wings

This cockpit without wings never leaves the ground, but in its operation it exemplifies the kind of practical training taught by Lockheed instructors at the factory school. Each future ground crew man spends time in the pilot's seat learning the instruments of flight. This is but part of the fundamental training he gets. When this 30-day postgraduate course is completed he is an expert P-38 mechanic—ready to follow warplanes into action, wherever they may fight.

A Place in the Future

Lockheed will produce military planes and train the men to maintain them as long as there is a need. Victory must be won before the "air age" of peace can begin. But when it comes, Lockheed will be part of it—building planes, getting them ready to fly and keeping them ready to fly.

LOOK TO *Lockheed* FOR LEADERSHIP

LOCKHEED AIRCRAFT CORPORATION, BURBANK, CALIFORNIA

What's Up, Boys!

HEINEMANN
is planning
a new
AIRCRAFT
BREAKER



We are developing
a small, single pole

MAGNETIC AIRCRAFT CIRCUIT BREAKER

for 400 cycle service

ARE YOU INTERESTED?

If so, just clip the coupon
shown here and mail it to

HEINEMANN CIRCUIT BREAKER CO.

Subsidiary of Heinemann Electric Co.

Estab. 1868

115 PLUM STREET — TRENTON, N. J.


HEINEMANN CIRCUIT BREAKER CO
115 Plum St — Trenton, N. J.

I am interested in your idea for a MAGNETIC AIRCRAFT CIRCUIT BREAKER

Name

Company

Address



Now a complete line "MX" WHEELS, MOUNTED WHEELS AND STICKS

On a great many jobs which call for finishing and polishing there are always many out-of-the way places—grooves, curves, angles and flat surfaces not readily accessible. To reach such places the "MX" Mounted Wheels, used on portable type machines, are proving to be the solution of this some times vexing problem.

"MX" Mounted Wheels have the same finishing and polishing action and the same characteristics as the straight "MX" Wheels. "MX" Wheels, both straight and mounted, are being used on such typical jobs as polishing out tool marks and scratches, cleaning out the channels of connecting rods, polishing and finishing the hard to-get-at parts. For burring and polishing any complicated metal shapes, parts and castings. For finishing flutes between the cutting edges of broachers and reamers. For breaking down corners on miscellaneous parts.

NOTE "MX" *Mounted* Wheels are made only in the straight shapes but they can be readily shaped or formed by the user to meet his finishing or polishing conditions. It is a simple matter to point, groove or round the wheels using a fine grit Carborundum Brand Silicon Carbide Stick as a dressing tool.

"MX" Sticks are particularly useful for breaking down edges and finishing work that can be turned in a lathe. They are also used with success for hand finishing molds and other such small, irregular surfaces.

"MX" Tools can save you time and improve the finish of your product. Send for "MX" Booklet which shows typical, successful, time-saving applications.

The Carborundum Company, Niagara Falls, N. Y.



CARBORUNDUM
ABRASIVE PRODUCTS

"MX" Products by CARBORUNDUM

TRADE MARK — TRADE MARK

Sales Offices and Warehouses in New York, Chicago, Philadelphia, Detroit, Cleveland, Boston, Pittsburgh, Cincinnati, Grand Rapids

(Carborundum and "MX" are registered trade marks of and indicate manufacture by The Carborundum Company)



...THE END OF THE LINE

When our enemies look frantically aloft at the screaming Douglas Dive Bombers descending upon them with a lethal load of destruction, they know it is the end of the line for them.

Back in sunny California at the El Segundo plant, these newly assembled Douglas SBD's are pulled to the end of the line by a compact, powerful, air-motor hoist. Then another I-R air-powered hoist with a capacity of 10,000 pounds lifts the plane from its dolly car.

These are but two of many applications of compressed air and air-operated machinery that help speed the planes to our men on the war fronts.

Ingersoll-Rand Industrial Air Motor Hoists are built in twelve sizes with capacities ranging from 300 to 20,000 pounds. They feature — automatic brake — graduated reversing valve — positive lubrication and automatic up-and-down stop for safety.

Our Engineers are available to help you make a selection.

Ingersoll-Rand

11 BROADWAY, NEW YORK 4, N. Y.

B 456



Get this new aid

THAT HELPS IDENTIFY WELDING TROUBLES

New trainees learn to spot faulty welding procedures faster..."old hands" can increase their efficiency ... with the help of this new 24-page book. By stressing accurate visual inspection, it helps boost both weld quality and quantity.

Each of the 14 most common welding troubles is illustrated with a typical "good" and "bad" example; causes are analyzed; and specific suggestions for cure are outlined.

The book is pocket-size—ideal for plant distribution. Welders can take it home to read or keep it handy on the job.


It's a helpful trouble shooter for problems like splatter, corrosion, undercutting and brittle joints. Order a copy of this booklet for each of your welders today.

This same information is also made available by Westinghouse in chart form for wall mounting. Write for free copies of booklet B-3326 and chart DC-250 on your company letterhead. Please atate exact quantities required. Westinghouse Electric & Manufacturing Company, East Pittsburgh, Pa., Dept. 7-N. J-90497-3

Westinghouse

PLANTS IN 25 CITIES... OFFICES EVERYWHERE

AIRCRAFT WELDING EQUIPMENT


REPLACE "SLOW-DOWNERS"
with Snap-ons
On any operation an inefficient or poorly adapted tool is a time killing "slow-downer" — a wasteful drag on the speed and skill of even the best machanic. Snap-on tools help speed up the toughest jobs in production, assembly and maintenance . . . in hundreds of foremost plants they are "standard equipment", the choice of better mechanics throughout industry. Snap-on direct-to-user tool service is available through 37 factory branches located in key production centers throughout the United States and Canada
SNAP-ON TOOLS CORPORATION
8020-G 28th Avenue Kenosha, Wisconsin
Snap-on Tools
THE CHOICE OF BETTER MECHANICS


Two Bags of Twenty
Piloting Corsairs, two Marine fliers—Lieut. Kenneth A. Walsh and Capt. Donald N. Aldrich—have each brought down twenty Japanese planes. In addressing production workers at Goodyear Aircraft, Walsh said:
"Give us enough Corsairs, and we'll drive the Japonese back to Tokyo—the Jap Zero is highly moneuverable, but frogile. The Corsair, on the other hand, is tough. Words connot express how much the sturdiness, strength and fine workmanship of a Corsair meon to you when you have a Jap on your toil. They are built to get you back safely."
Tha Corsair typifies the ability of Americen menufacturers to undertake the building of anything needed for the war effort, and coma up with something better than tha enemy can turn out. Prominant among the factors of superiority in American planes is the ruggedness provided by the broader use of tough drop forgings for the parts which must withstand tha tarrific strasses of flight and combat.
Super-tough drop forgings in endless volume — for the Corsair and many other history-making planes — are being delivered on time by our lerge modern plent, which is devoted to the mass production of airframe and landing gear drop forgings exclusively.
Member at the A.C.C.A.
Kropp Forge Aviation Co.
5301 W. ROOSEVELT ROAD CHICAGO
Engineering Repreeentetives in Principei Cities

TODAY... AND IN THE DAYS TO COME





Out of the war's testing cauldron has come no finer life saving device than the Switlik, American-designed and thoroughly proven **SAFE-T-CHUTE.** ☆ ☆ ☆ ☆ Born of the many years of practical experience to Stanley Switlik and developed to its present high standards through the genius of Switlik Engineers, there can be no better testimony to the efficiency of **SAFE-T-CHUTE** than the praise of the famous Caterpillars, that group of airmen who have bailed out but who go back "upstairs" with confidence, because of their faith in their **SAFE-T-CHUTE.** ☆ And when the war is won, rest assured that Switlik resources will be ready for other needs. Just as our output today goes to meet War's demands so will the Switlik Safety Products tomorrow play an important part in keeping the peace ☆ ☆ ☆ Wear a **SAFE-T-CHUTE** whenever you take to the air. It is truly the "Lifeline of the Skies." ☆ ☆ ☆ ☆ ☆ ☆ ☆

NEW educational air-safety film available for colleges—training schools—high schools. ☆ ☆

ALSO write for the informative Switlik Parachute Chart and new manual. All free for the asking.

SWITLIK
SAFE-T-CHUTES

THE MORE BONDS YOU BUY
THE MORE HOURS THEY FLY

SWITLIK PARACHUTE COMPANY
Dept A7 TRENTON 7, NEW JERSEY

One million hours closer to Victory.

Copyright 1944, Switlik Parachute Co

HOW TO SOLVE *Lubrication Problems*


The First All-Purpose Grease for Plain Bearings!

COMBINES BEST FEATURES OF BOTH LIME AND SODA BASE GREASES...
NEW, UNIQUE, PATENTED PRODUCT

STANDS TEMPS. FROM FREEZING TO 350° F.!



STANDS LIGHT TO HEAVY PRESSURES!



STANDS WASHING EVEN BY BOILING WATER!



ALL METHODS OF APPLICATION!




HERE'S THE ALL-PURPOSE GREASE you've been looking for, if you're operating a plant where it's to your advantage to use just one grease.

This great Socony Vacuum development meets the needs of all plain bearing lubrication as indicated above. It's also suitable for numerous ball and roller bearing applications.

The reason: Gargoyle Grease Sovarex combines the advantages of both lime and soda base greases. It is resistant to both water and heat and stands up under boiling water. It also resists dilute alkali and acid solutions. It sticks on the job when other greases fail.

See your Socony-Vacuum representative for details on Gargoyle Grease Sovarex.

WHERE PLANTS BENEFIT BY USING ONE GREASE!




GARGOYLE Lubricants

SOCONY-VACUUM OIL CO., INC. • Standard Oil of N.Y. Div. • White Star Div. • Lubrite Div. • Chicago Div. • White Eagle Div. • Wadhams Div. • Magnolia Petroleum Co. • General Petroleum Corp. of California.

GARGOYLE GREASE SOVAREX

$90,000,000 BABY_

"Flying Horsepower"



First FCC Unit Now in Operation at Beaumont Texas

Represents World's Largest Catalytic Cracking Program...19 Huge Socony-Vacuum Refining Units Produce Finest Aviation Gasoline

"NINETY-MILLION-DOLLAR BABY" is right! "Flying Horsepower" is a ninety-million-dollar investment in Victory and America's future.

Socony-Vacuum has already spent this vast sum on new refining facilities and equipment to produce base stock for the new super aviation fuels.

Nineteen big Catalytic Cracking refining units strategically scattered across the country, are "on stream" now, turning out "Flying Horsepower" in volume. Others are scheduled to start producing soon.

This represents the greatest Catalytic Cracking Program in the world. It's the result of 11 years' research in this field and multiple new developments, such as a magic bead catalyst.

Now every drop of "Flying Horsepower" is consigned to military needs—to boost the speeds, maneuverability, pay-loads and range of U. S. warplanes. But when Victory is won, this same great fuel power will be available for commercial and private planes.

After Victory, look for "Flying Horsepower" in Mobilgas.

SOCONY-VACUUM OIL COMPANY, INC.
26 Broadway, N.Y.C., and Affiliates: Magnolia Petroleum Co., General Petroleum Corporation of California



FOR AMERICAN WARPLANES TODAY...

Today, "Flying Horsepower," incorporated in the new super aviation fuels, is boosting the performance of U. S. warplanes. It's adding speed and maneuverability to fighters, and increasing the loads, range and ceilings of bombers.



FOR COMMERCIAL FLYING TOMORROW—

After Victory, this extra fuel power will be translated into terms of peacetime flying. It will open up new possibilities for designers, help pave the way to speedier air transports and freighters carrying heavier pay-loads on longer flights.

New Mobiloil to Match It . . .

Along with "Flying Horsepower" for extra fuel power, Socony Vacuum has developed a great new Mobiloil Aero for extra engine protection. The new oil already proved in operational flights, provides exceptional resistance to engine deposits.



Get the Facts about **Mobilgas—Mobiloil Aero**

Mobilgas
SOCONY-VACUUM

FACTS ABOUT MOBILGREASE AERO EP LO-HI

New Extreme Pressure Grease Stands Up From –70° F. to +250° F.

HERE is a new aviation grease to meet today's exacting demands. It is an extreme pressure grease—designed to protect aircraft gears and other mechanisms from the high unit loads now employed. In addition, this grease remains a dependable lubricant under extreme temperature change —from 70° F. below zero to plus 250° F. Thus, it assures you ease of starting at sub-zero temperatures and continued Correct Lubrication with high operating temperatures. Get full details from your Socony-Vacuum representative.

Mobilgrease Aero EP Lo-Hi Used In:

- Wing Flap Motor Gear Cases
- Landing Wheel Motor Gear Cases
- Bomb Bay Door Motor Gear Cases
- Plane Control Mechanisms
- And other points requiring extreme pressure grease

SOCONY-VACUUM OFFERS A COMPLETE LINE OF:

Aviation Greases

Specially designed greases for high temperatures, low temperatures, and extreme pressure conditions.

Aviation "Specialty" Oils

Special oils and fluids for instruments, low-temperature oils, hydraulic oils, general lubricating oils.


SOCONY-VACUUM OIL CO., INC.

and Affiliates: Magnolia Petroleum Company, General Petroleum Corporation of California

AVIATION DIVISION
26 Broadway
New York 4, N. Y.

Aviation Products

Socony-Vacuum is backed by 78 years of Lubrication Experience!



BE SURE YOU HAVE THE RIGHT RELAY

The *right* relay, of course, is the one which will exactly fit your needs, and give you the longest, most dependable service at lowest cost. Here's how you can get it:

1. Write for the Automatic Electric catalog. It lists over forty basic types of relays, providing every combination needed for modern electrical control. All technical facts are clearly tabulated for your guidance.

2. If you want help in applying this information to your problem, call in our field engineer. He will be glad to put his experience to work for you.

Send today for your copy of the catalog—or simply ask our field engineer to bring one over.


Relays
AND OTHER CONTROL DEVICES
by AUTOMATIC ELECTRIC

AUTOMATIC ELECTRIC SALES CORPORATION
1033 West Van Buren St., Chicago 7, Ill.

In Canada:
Automatic Electric (Canada) Limited, Toronto

Are we sowing a crop of peacetime

FOX MINES IN AMERICA?



In a rocky ravine somewhere on the invasion front, an American soldier lies dead . . . victim of an enemy fox mine . . . the supreme price of war. But peace, too, can have its booby traps, if we aren't careful now.

Are we sowing a crop of "fox mines" for our fighting men to come home to — the slow explosionless defeat of unemployment, hunger and hopelessness, the breadline and the bonus army?

Not if we think straight . . . not if we plan ahead now.

If you are a manufacturer, there is one thing that you can do at once. Have your production men and planners consult now with the engineers of the basic machine tool producers. They can help you in planning ahead for the difficult task of reconverting your own skills and machinery to an all-out peacetime production.

One of these engineers is a Bryant man. We urge you to call him today. For his specialized knowledge of internal grinding machinery is important to the manufacture of literally *everything* that will make this country a finer place: this is victory, a victory that it will be safe for our boys to come home to.

BRYANT CHUCKING GRINDER COMPANY SPRINGFIELD VERMONT, U.S.A.

GEARED TO THE GRIND OF MODERN WAR

by LAND, SEA and AIR

In global war, wind, rain, sleet, grit and shock all wage a campaign of their own. Therefore, Bolton Radio Shielded Ignition Assemblies for warcraft engines are designed not only to minimize radio interference, but also to offset the extreme wear and tear incident to modern combat.

Durable material and construction are as much a Bolton responsibility as correct electrical design; hence they are very definitely a part of every piece of equipment supplied the armed forces.



BOLTON SHIELDED IGNITION HARNESS

BOLTON MANUFACTURING CORPORATION

then he said to himself

"I hope they don't ask me HOW!"



Pierre Laval, on being handed the mouthpiece by Adolf, promptly broadcast to the French people:

"In the New Europe, it is socialism that will be installed . . . In the New Cities, labor will be protected, honored and magnified, as well as those spiritual and moral values that may blossom there."

Just like that he solved France's problems of postwar.

Of course, we all smile derisively as we think how promptly after that, labor was pushed into railway cars and whisked into forced production in other lands.

And we smirk as we contemplate the "spiritual and moral values" that have blossomed since.

But here at home, we accept as gospel the glorious promises of our social planners for oodles of streamlined super-products the people will get for a song.

Rarely do we ask, "BUT HOW!!"

"Protected, Honored and Magnified"—*he says*

Look, Pierre, under your own or any *new social order,* a small group of soft-handed *theorists* like yourself could never give a *practical* answer to the challenge "BUT HOW?" Yet under an old American *free enterprise* system . . . where protection, honor and magnification are in every man's grasp—*workmen* down in most metal working plants can themselves answer: *HERE'S HOW!!* (How to get MORE products. — How to get BETTER products. — How to get products AT A LOWER COST —so that more people can *afford* to buy).

HOW TO PRODUCE BETTER AIRCRAFT AT LOWER COST



RECOURSE to Arc Welding leads to advancement in aircraft design and construction . . . assures maximum strength of members . . . makes possible *real mass production* for minimum costs

The New Lincoln "Shield-Arc Jr." Aircraft Welder contributes this.

Current settings as low as 10 amperes can be obtained, making possible a new high standard of welding thin-gauge aircraft metals and alloys. Its output can be adjusted in extremely fine increments of both current and voltage.

Teamed up with the new "Plane-weld" Electrodes and the Lincontrol (foot-operated control), the New "Shield-Arc Jr." steps up speed and quality of aircraft fabrication

Full details in Bulletin 338 . . . free on request.

THE LINCOLN ELECTRIC COMPANY • CLEVELAND 1, OHIO

America's greatest natural **recourse**

ARC WELDING



Hey, Guy... He's goin' to land in the cow pasture!

One of these days...when peaceful products start to supplant the weapons of war...a new form of transportation will be available to rural America. It will be the kind of transportation that can make use of cow pastures and that will carry convertible loads of freight or passengers—profitably. Right now our entire production here at Fletcher Aviation is devoted to war, but we are also crystallizing our plans for peace...with an airplane to be known as the Fletcher Feedliner.

Fletcher Aviation Corp.
PASADENA CALIFORNIA

MANUFACTURERS OF AN INCREASING SUPPLY OF WAR GOODS UNDER THE MANAGEMENT OF THE FLETCHER BROTHERS



INSTRUCTIONS issued by the headquarters of a large company called for use of conventional ovens to dry paint on aircraft instruments. Drying time was six hours—two hours per coat.

Production man in one of the company's plants decided to use a drying tunnel with General Electric Drying Lamps. He reduced drying time to 27 minutes—nine minutes per coat!

Exceptional? No! Radiant energy from G-E Drying Lamps is speeding production, cutting costs and saving manpower in hundreds of plants. For further information, get in touch with your nearest G-E Lamp Office or write General Electric, Div., 166AV-G Nela Park, Cleveland, Ohio.


WHAT PART OF THE SUN DO YOU WANT?

"MOVING THE SUN INDOORS" is the constant aim of G-E Lamp Research. G-E lamps bring industry the benefits of the sun, from the infra-red lamps for heat, through filament, mercury and fluorescent lamps for light, to ultra-violet lamps for health.

Keep Buying War Bonds—Keep the War Bonds You Buy

Hear the General Electric radio programs: "The G-E All-Girl Orchestra", Sunday 10 p.m. EWT, NBC; "The World Today" news, every weekday 6.45 p.m. EWT, CBS


G-E LAMPS
GENERAL ELECTRIC



For complete details of all P & N Junction Boxes please send for Catalog No. 43-JB.



Box sizes range from 1⅞" x 1⅞" up to 23" x 15". Material Thickness from .032" to .064" in 2S0 or 350 Aluminum. Covers to fit in 3S½H Aluminum. Fasteners: Boxes can be equipped with conventional nut and screw type fasteners. (Other types of fasteners on request). Delivery: 30 days or less.




POULSEN & NARDON, INC.
Terminal Box 2398
LOS ANGELES 54, CALIF



Consider the fuse in an
airplane's electrical system...
small part, isn't it? But how important
it is to the operation of that plane!

Piston rings are
relatively small, too. But not
small in importance to aircraft
engine manufacturers.



The world's finest piston rings are standard equipment for these
world-famous aircraft engines—Allison • Wright • Packard-built
Rolls-Royce • Franklin • Warner

The Perfect Circle Companies

Hagerstown, Indiana • Richmond, Indiana • Newcastle, Indiana • Tipton, Indiana • Toronto, Ontario, Canada

Faster Finishing



SEVERANCE MIDGET MILLING CUTTERS TAKE DEEP SHARP BITES

On metal, wood or plastic parts, castings or patterns Severance cutters take deep sharp bites instead of merely burnishing They throw off clean chips instead of dust

For every type of finishing and deburring, Severance cutters do a quicker, faster job than ordinary rotary tools, rasps or burrs Equally efficient with portable power tool, with stationery set-up or by hand

Severance cutters can be successfully reground scores of times without losing their effective cutting qualities. If you are having difficulty in finishing any manufactured parts, send us samples and our engineers will design cutters to solve your problems

Severance "Carbide" Midget Milling Cutters are available in a wide variety of shapes and sizes.



SEVERANCE MIDGET MILLING CUTTERS • PRECISION RE GRINDING Severance Tool Industries Inc. Saginaw, Mich • Plants in Long Island City 1, N Y.; Detroit 2, Mich.; Fort Wayne 8, Ind.; Chicago 6; and Los Angeles 21 In Canada: 60 Front Street West Toronto Ontario

Severance

Our hat is in the ring!



IT'S election year here in America The political campaign is on. But to the manufacturer, 1944 is important for more than political reasons.

The campaign plans for postwar business that you make now—the kind of product you decide to manufacture—will vitally affect your ability to meet competition, to keep your workers busy—yes, even to stay in business

When it comes to the selection of the materials for your after-the-war product, there will be many worthy candidates competing for your vote—glass, plastics, wood, aluminum, magnesium, and new steels

The choice will be difficult. It should go to that material, or combination of materials, which will offer to your customers the most for their money, in efficiency, durability and beauty

U·S·S Steels, whose sphere of application has been vastly increased by the impetus of war research, offer inherent advantages none of these other materials can equal.

Their record is unexcelled for structural strength per unit volume, for toughness, resistance to shock and fatigue, and for versatility of application No manufacturer concerned about the future can afford to overlook their golden possibilities.

Steels that meet the challenge of today and tomorrow

U·S·S CARILLOY ALLOY STEELS—S A E. and Aircraft Quality Steels for the special jobs of industry

U·S·S HIGH STRENGTH STEELS to carry high unit stresses and to reduce weight to a minimum at low cost

U·S·S ABRASION-RESISTING STEELS to combat wear and to stand

U·S·S COPPER STEEL to give twice the atmospheric corrosion resistance of regular steel at little additional cost

U·S·S HOT-ROLLED AND COLD-ROLLED STSELS to provide the basic advantages of steel plus maximum economy.

U·S·S STAINLESS AND HEAT-RESISTING STEELS to endure temperatures disastrous to other metals—to resist highly corrosive environments.

USS ONLY STEEL CAN DO SO MANY JOBS SO WELL


CARNEGIE-ILLINOIS STEEL CORPORATION

Pittsburgh and Chicago

Columbia Steel Company, San Francisco, *Pacific Coast Distributors*
United States Steel Export Company, New York

UNITED STATES STEEL

POINTERS ON ENGINES . . . . . *No. 7 of a Series*



Ranger Gets the "Inside Story"

These patterns tell the inside story of metals.

They are "pictures" taken of the physical and chemical properties of the raw materials which make up parts of the Ranger Sixes and Twelves.

Ranger technicians employ them constantly in their control of quality—assiduously in their daily research into new possibilities.

Under the white arc of the spectrograph, the basic elements in a sample of aluminum are revealed—copper, manganese, silicon—and the proportions in which they occur. The X-ray diffraction camera supplements this information. From the sunburst pattern of its pictures can be determined the *chemical form* in which the elements in a given sample are present.

By using another X-ray technique, Ranger technicians can examine the chemical bond between aluminum fins and the steel cores of Ranger cylinders. In the metallurgical laboratories, technicians have found an efficient engine sealing compound; determined standards for synthetic rubbers used in engine construction; unearthed the "whyfors" of metal fatigue.

All this adds up to knowledge. This knowledge, plus the ingenuity of design and dynamic balance, has created in Ranger engines a sleek, efficient source of aircraft power. The kind of power that lends the "touch of tomorrow in the planes of today."

BUY U. S. WAR BONDS AND STAMPS

RANGER AIRCRAFT ENGINES

Division of Fairchild Engine and Airplane Corporation • Farmingdale, Long Island

OK for Fighting Vought F4U "CORSAIRS"





KLIXON "PUSH-PULL" BREAKER. TYPE 8673J

Ratings from 5-50 amps. "Pull" feature permits opening the circuit manually at the breaker for deenergizing the circuit for servicing work. Both trip-free and non trip-free types in production, with specially designed "shunting" switch by passing the thermal element to give non trip free" action



KLIXON PUSH BREAKERS

PM type ratings from 5-30 amps. PLM type ratings from 35-150 amps



KLIXON PSM PUSH BREAKER

Same mounting dimensions as standard AN mechanical toggle switches. Ratings up to 75 amps.



KLIXON SWITCH BREAKERS


C-6363 ratings from 5-35 amps. D-6364 ratings from 35-120 amps



KLIXON REMOTE-CONTROL BREAKER

Available in three frame sizes with ratings from 35-200 amps. for circuits up to 30 volts D C





KLIXON

Aircraft Circuit Breakers

A few final touches and another "batch" of fast fighting, high altitude, hard-hitting Chance Vought "Corsairs" get the O. K. to join the Navy for active duty.

O. K., too . . . are the Klixon Aircraft Circuit breakers that go into these deadly Navy fighters. The reason . . . because like the plane, they're able to take it under the fightingest conditions—always protecting the electrical circuits from serious damage through shorts or overloads. Harmless momentary transients do not cause nuisance trip-outs.

Klixon Aircraft Circuit breakers contain no fussy, complicated parts. Their simple Spencer snap-acting disc thermal elements are sensitive to ambients and amperes but they are plenty rugged when it comes to withstanding shock, motion, altitude or vibration.

Bulletins, containing sizes, dimensions, ratings and performance characteristics give the whole story. Send for your copies.

ARMY-NAVY E AWARD

KLIXON

SPENCER THERMOSTAT COMPANY, ATTLEBORO, MASS.


GREATER ACCURACY—MORE PRODUCTION ON PARTS LIKE THESE with the SUNNEN PRECISION HONING MACHINE




Stainless Steel Lead Compensator Valve Seat Hole is honed to .0002" limit.



Roller Bearing Outer Race Finish improved from 12 micro inches to 2 micro inches.



Inner Bearing Ring "Accurately removes last tenth" of stock."



Saved time in producing a smooth accurate finish on this bronze remote control valve body



Cones for Wheel Balancing Machine "Accurately align hones two interrupted surfaces."



Hydraulic Two-Way Control Valve Hole is honed to eliminate leakage



Automobile Distributor Shaft Gears. Taper removed at a rate of 60-90 per hour



Diesel Engine Fuel Injector Cylinder. So accurate that a piston can be fit within .00005 inch.




Aircraft Valve Guide. Valve tappet roller pin hole honed to 6 micro inch finish.




Bronze Valve. The Sunnen method of honing is used to secure a high finish and accuracy



Aircraft Hydraulic Brake Cylinder. Honing 3 times faster than lapping — and gave a straighter hole.



Aircraft Piston Pin. Sunnen honing is twice as fast and gives a cleaner, better looking pin.



Now you can get even greater accuracy and more production per hour than ever before with the improved Sunnen Precision Honing Machine. This machine is now furnished with a larger base containing a coolant pump, which provides a constant flow of honing fluid to the part being honed. The fluid acts both as a coolant and a lubricant, giving better honing properties to the abrasive. You get a smoother finish, more accurate work in less time.

Consider These Advantages, Too

- Hones and finishes internal cylindrical surfaces from .185" to 2.625"
- Can be used in any metal or plastic except lead or babbitt
- Does not require skilled labor
- Accuracy guaranteed within .0001"
- No jigs or fixtures needed
- Economical to operate
- Quickly and easily set up



The coveted Army-Navy "E" waves over the Sunnen plant—evidence of the important part Sunnen equipment is playing in the war effort

Why not write today — asking a Sunnen engineer to show you how it can be used on your jobs — or ask for a bulletin giving complete information?

SUNNEN

SUNNEN PRODUCTS COMPANY, 7942 Manchester Ave., St. Louis 17, Missouri

Canadian Factory: Chatham, Ontario



THEY TAKE OFF — THEY FLY — ON BOWER ROLLER BEARINGS

On the runway landing wheel bearings carry the rolling load. The instant the engine turns over, other bearings go vigorously into action — in propeller shaft, reduction gears, generator, supercharger, instruments. Planes fly on Bower Roller Bearings as well as on wings.



NAVAL AVIATION

WHERE PERFORMANCE REALLY COUNTS...



... COUNT ON DEPENDABLE
CHAMPION SPARK PLUGS

Full throttle, the jarring, explosive push of the giant catapult, and a Navy scout plane is airborne to search the seas ahead for lurking submarine or other enemy craft. In the few seconds after launching, the plane actually drops slightly, then the full power of the engine takes hold. This is no place for spark plug failure. Dependable Champion Spark Plugs, true to their more than thirty-year-old heritage, are designed to meet extreme as well as normal service. The records of our armed forces in the air, on the land and on the sea provide dramatic daily evidence that where performance really counts, you can count on dependable Champion Spark Plugs. Champion Spark Plug Company, Toledo 1, Ohio; Windsor, Canada; Feltham, England

C-26—Unshielded



BUY WAR BONDS MORE THAN BEFORE

5th WAR LOAN

INSTALL CHAMPIONS AND FLY WITH CONFIDENCE



Interstate

BUILDS HYDRAULIC ACTUATING Cylinders

FOR EVERY PURPOSE


Interstate knows its cylinders. It designs each for a specific job — and knows in advance it will do that job. For Interstate has a wealth of skill and experience on which to draw. Not only in the making of aircraft precision units generally — but hydraulic actuating mechanisms particularly. Put your cylinder-problems up to Interstate! Address Sales Department —

INTERSTATE AIRCRAFT AND ENGINEERING CORPORATION • EL SEGUNDO, CALIFORNIA



The landing gear on this Douglas Havoc is operated by an Interstate Hydraulic Actuating Cylinder...





PRESSTITE *Extruded Seam Sealing Tape Seals Fuselage Joints of Lockheed's Giant "Constellation"*

Built to fly faster, farther, and with bigger loads than any other land transport now in production, Lockheed's giant 4-engined 8,800 horsepower craft recently broke the transcontinental record from Burbank to Washington. The fuselage seams of this great carrier are safely sealed against weather and pressure with Presstite Extruded Seam Sealing Tape.

Thus another famous American airplane joins the ranks that include the "Flying Fortresses," "Commandos" and many others in which Presstite Sealing Compounds are used.

Your own sealing problems may not be as complex as those in the aircraft field where extremes in temperatures and pressures, plus constant strains and flexings, are encountered. But it is Presstite's wide experience in developing sealers for industry that has made such wartime achievements possible.

Presstite's engineers are *sealing specialists*—continually developing sealing compounds to meet specific requirements of industry and the Armed Forces. We'll gladly work with you, too, on your present and postwar sealing problems.

A Partial List of Industries for Which Presstite has Successfully Developed Special Sealing Compounds:

For the Aircraft Industry:
Sealers for—
Integral Fuel Tanks
Fuselage Seams
Drop-off- Expendable Fuel Tanks
Gun Turrets
Synthetic Glass
Instruments
Intercoolers
Air Ducts
Insulating Dissimilar Metals
Seaplane Floats

For the Refrigeration Industry:
Sealers for Domestic and Commercial Refrigerators
Bonding and Sealing Low Temperature Insulation in Refrigerated Rooms

For the Railroads:
Sealers for Insulating, Soundproofing and Weatherproofing of Railway Cars—Sealing Car Windows and Spot Welded Seams

For the Building Industry:
Roof Coatings, Caulking, and Waterproofing Compounds

For the Shipbuilding Industry:
Insulation Adhesive and Sealers—Rust Preventive Compounds

For the Automotive Industry:
Special Adhesives and Sealers

For the Construction Industry:
Sealers for Jointing Sewer Pipes
Sealers for Waterproofing Excavation Work

Miscellaneous:
For Glazing Greenhouse Windows
Extruded Caulking Compounds
Ammunition Paints
Plus Many Special Products for the Army and Navy

Our Engineering, Technical, and Laboratory facilities are at the service of any industry with a sealing problem.

PRESSTITE SEALING COMPOUNDS

PRESSTITE ENGINEERING CO.
3910 Chouteau Ave., St. Louis 10, Missouri
Sales Offices: Los Angeles 21, Calif., 2145 Bay St., Detroit 2, Mich., 6432 Cass Ave.

FIRST OF THE U. H. F. CABLES
Offered in 1937 by AMPHENOL



First Today—

Is Amphenol Polyethylene, Solid Dielectric, Low-Loss, High-Frequency, Coaxial Cable

Clean, smooth, properly centered polyethylene covered wire is extruded by this machine.

Our ultra-high-frequency cable was a polystyrene bead cable—born of much study and endless laboratory work. It took the place of ceramic and fibre insulated lines. Thus, Amphenol became the pioneer in low-loss cable manufacture—a logical development of leadership in quality radio equipment—firmly established with radio experimenters and "ham" operators long before war developments required the mass production of U. H. F. cable.

Since that first polystyrene bead cable Amphenol has worked shoulder-to-shoulder with the designers and developers of equipment for radio, frequency modulation, television—since 1941 at the right hand of Army and Navy engineering officers playing an important part in wartime electronic developments.

Today, Amphenol's RG Polyethylene standard—Army-Navy type—cables feature quality materials, Amphenol workmanship in every inch . . . product of Amphenol's latest type extruding equipment, skilled personnel, seasoned staff and second-to-none laboratory. Write for the catalog of AMPHENOL RG Cables.




By a dozen different scorching tests Amphenol RG Cable is proved before it is shipped.



STRIKING POWER

More than 50,000 Allison engines have been built for the use of Allied fighting pilots around the globe. ★ These skilled pilots using fighting planes powered by these engines have established a lopsided "box score" in our favor. ★ That is testimony to the striking power of good men armed with good American fighting equipment. ★ It is also an indication of aircraft engine performance you will be glad to have in the planes you use after final victory.



POWERED BY ALLISON

P-38—Lightning
P-39—Airacobra
P-40—Warhawk
A-36 and P-51—Mustang

The more-than-50,000 Allison engines built for the U. S. Army Air Forces power the above planes.

KEEP AMERICA STRONG
BUY MORE WAR BONDS

LIQUID-COOLED AIRCRAFT ENGINES

Allison

DIVISION OF
Indianapolis, Indiana

GM
GENERAL MOTORS

Every Sunday Afternoon—GENERAL MOTORS SYMPHONY OF THE AIR—*NBC Network*

FIRST ON THE NORMANDY COAST

The Army's SCR-299's went ashore with the wave of Allied assault troops that split the 2nd front wide open. These mobile radio units rolled up on the beachhead early in the battle to serve as vitally important front line communications weapons to coordinate and direct the striking power of the land, sea and air forces . . . In truck or duck, the Hallicrafters-built SCR 299's go anywhere and are sturdy enough to withstand front line action. Highly dependable and powerful, they "get the message through."

hallicrafters RADIO

THE HALLICRAFTERS CO., MANUFACTURERS OF RADIO AND ELECTRONIC EQUIPMENT, CHICAGO 16, U. S. A.




BUY A WAR BOND TODAY!

Phillips - - -
one of the nation's
five
largest producers
of combat
aviation gasoline

Phillips
AVIATION GASOLINE

MPANY BARTL OMA
s to the Army, Navy, for s

I PREDICT . . .
By Egmont Arens
Leading Industrial Designer



I predict quantity production, right after the war, of unsinkable boats with continuous skins, tougher and lighter than wood, hull and top sides molded in one piece of Co-Ro-Lite, a new molding material consisting of plastic bonded rope fibres. Scale models of such boats are now being tested under a variety of conditions, and hulls of similar construction up to 32' have already been successfully molded. Light weight, speed and low cost will be overall outstanding features. The skin-stressed monocoque construction produces a light weight hull and top. An aluminum aircraft-type engine, housed out of the way in a small space under the aft deck, will provide speed and low operating expenses. Production by molding assures low initial cost, and a one-piece hull, eliminating yearly overhaul and caulking, means low upkeep. Thus motor-boating will be a pleasure everyone can buy with their War Bonds when Peace is restored.

* * *

Note: The Weatherhead Company, one of the oldest and most important manufacturers of parts for the aviation, marine, automotive and other key industries, looks forward to the day when its four plants will be contributing to peacetime needs.

Look Ahead with

Weatherhead

THE WEATHERHEAD COMPANY, CLEVELAND, OHIO
Manufacturers of vital parts for the automotive, aviation, refrigeration and other key industries.
Plants: Cleveland, Columbia City, Ind., Los Angeles
Canada—St Thomas, Ontario



FREE: *Write on company letterhead for "Seeds Of Industry"—a history of The Weatherhead Company its many facilities and diversified products.*

VERSATILE HANSEN COUPLINGS...

HANSEN COUPLINGS are versatile, in that they are made for a wide range of uses, such as for air, oil, grease, oxygen, gasoline and acetylene. Designed, engineered and built to handle air, liquids and gases in the most efficient manner with absolutely no losses whatever due to leakage. Hansen couplings will safely handle pressures from 2 ounces to over 10,000 pounds.

Extremely easy to operate, merely push plug into socket, it is locked absolutely tight, slight pull on sleeve, it is unlocked and detached. When plug is inserted in the air, oxygen, or acetylene couplings, it automatically opens the valve and automatically closes it when plug is ejected . . . No twisting, turning or locking, complete swivel action eliminates kinking of hose line.

Large illustration at left shows Push-Tite coupling which handles air, oil, and grease while couplings illustrated below handle gas, acetylene and oxygen.

Send for Free Catalog

HANSEN

MANUFACTURING COMPANY
1786 EAST 27th STREET
CLEVELAND, OHIO







PORTRAIT OF A HERO
...handle with care!

Many a wounded hero will come home well and strong again, thanks to a thin sheet of film...

Thanks to the miracle of the X-Ray . . .

And thanks to air conditioning and refrigeration which help make the miracle possible! *Air conditioning* supplies clean, filtered air—with accurate regulation of both temperature and humidity—in plants where X-Ray film is made, in army hospitals where it is used. *Refrigeration* cools the solutions used in processing the film.

Out of such wartime applications, General Electric is evolving new techniques, finer equipment for conditioning temperature and humidity. When equipment again is available for peacetime commercial and industrial uses, it will be vastly improved—more compact, more efficient, more flexible than ever before!

Now . . . we'll be glad to put your name down for *earliest available* data on postwar air conditioning and refrigeration equipment. Write: *General Electric Co., Air Conditioning and Commercial Refrigeration Divisions, Section 426, Bloomfield, N. J.*

☆ BUY WAR BONDS ☆


Air Conditioning by

GENERAL ELECTRIC

Hear the General Electric Radio Program: The G E ALL GIRL ORCHESTRA Sundays 10 P M EWT NBC — THE WORLD TODAY News Every Weekday 6:45 P M EWT CBS

Machining Magnesium?

Here's how to assure maximum production



Magnesium alloys have excellent machinability. They can be cut at high speeds and feeds, taking a fine finish, while maintaining close tolerances. Tools used with other metals usually perform satisfactorily on magnesium, but best results can be obtained if these rules are followed:

1. Cutting edges must be kept sharp. Tool faces should be polished to insure free cutting action and reduce the tendency for magnesium particles to adhere to the tool tip. Clearances for chips should be large.

2. Magnesium is generally machined dry. In special cases, however, a cutting fluid is used. Do not use oil-water emulsions.

3. Taps and reamers should be slightly oversize, compared to such tools for other metals, magnesium cuts close to size.

4. Because of a lower modulus of elasticity, magnesium parts must be firmly but carefully clamped, to insure accuracy and prevent deformation.

These are just the high spots of "Do's and Don'ts" learned in our more than twenty years of producing magnesium products. For Mazlo Magnesium literature on this subject, write Aluminum Company of America, Sales Agent for Mazlo Magnesium Products, 1713 Gulf Building, Pittsburgh 19, Pennsylvania.

MAGNESIUM MAZLO PRODUCTS

AMERICAN MAGNESIUM CORPORATION

SUBSIDIARY OF ALUMINUM COMPANY OF AMERICA



What will this wartime development do for you?

Alcoa special rolled shapes having cross sections as large as thirty square inches, and weighing 1,200 pounds per piece, have saved many a man-hour in the assembly of America's bombing planes. Actual designs are a military secret, but they approximate what you see here.

Rolled structural shapes have the distinct advantage of long lengths. This means that fewer joints are required, resulting in less dead weight and faster assembly.

This development, coming out of the war, opens up entirely new realms of design. As in our airplanes, builders of railroad cars, buses, boats and construction equipment can employ such rolled shapes. Aluminum gives lightness, sturdiness, corrosion resistance and easy fabrication. Shapes are tailored to suit stresses and other requirements.

Perhaps those wartime projects now on your drawing board can employ Alcoa Aluminum rolled structural shapes to save man power and materials. And how about your postwar designs? Alcoa engineers will gladly help you determine the facts. ALUMINUM COMPANY OF AMERICA, 2182 Gulf Building, Pittsburgh 19, Pennsylvania.

ALCOA ALUMINUM

New Combustion Process Utilized in Fluid Heat's Complete Line of Aircraft Heaters



Fluid Heat's New Model SRH-100 Heater

THIS heater has a maximum output of 100,000 BTU per hour in flight, yet weighs only 24 pounds, including all controls and accessories. Overall dimensions are 8½ inches diameter, 27 inches in length. Model SRH-50, not shown because it is identical in design, delivers 50,000 BTU per hour. It is 6½ inches in diameter, 20 inches long, weighs only 15 lbs 4 oz. Both models are available with blower for ground operation. Transfer between flight and ground operation is controlled by a ram switch.

FLUID HEAT Aircraft Heaters use a new combustion process of special advantage in aircraft heating. Proved by severe frontline service on Navy patrol bombers and on the Mars, largest flying boat in the world, they are now available for any type or size of aircraft being built or considered.


NEW COMBUSTION PROCESS

Fluid Heat Aircraft Heaters employ a vapor entraining process utilizing pre heated combustion air. This process accomplishes combustion with an unusually low pressure drop permitting operation at low ram pressures. It produces a completely suspended fire and therefore gives freedom from lead oxide formation. Flame retention is so positive that flame characteristics are the same from sea level to ceiling. All heaters are barometrically compensated for constant combustion efficiency at all altitudes.


DEVELOPMENT BACKGROUND

Fluid Heat has, for sixteen years, pioneered in the development and manufacture of automatic combustion and heat transfer equipment. Those years of heat engineering know-how are built into each light, compact, efficient Fluid Heat Aircraft Heater. You will want Fluid Heat Aircraft Heaters on the planes you design, build, or equip. Write for full information on this new and proved heating achievement.


FLUID HEAT DIVISION
Anchor Post Fence Co.
6740 Eastern Ave., Baltimore 24, Md.



Fluid Heat's Model STH-15—Proportionately light weight and compact, this model delivers 15,000 BTU per hour. It de-ices windshields and heats fighter-plane cockpits. With all controls and accessories, the weight is but 7 pounds. Size is 3 "x 5" x 18".



Fluid Heat's Model STH-15A—This is the same as Model STH 15, except that it is equipped with a blower for ground operation. Transfer between flight and ground operation is automatically controlled.



Fluid Heat's Model SGE-1—Designed primarily for the special conditions involved in the operation of Navy patrol bombers, this light and compact model delivers 90,000 BTU per hour. It performs four vital functions: heats cabins in flight, on the ground or water; defrosts windshields; and pre-heats engines. Transfer between ground and flight phases is automatic.

fluid heat
AIRCRAFT HEATERS



NICKEL AIDS THE COMMUNICATIONS INDUSTRY

to KEEP 'EM IN TOUCH!

In the tradition of Morse and Bell and Marconi, the communications engineer carries on today.

His work, always valuable, now is vital.

No military campaign proceeds without it. The close teamwork between air, ground, and sea arms is possible only through instruments and equipment that keep them in touch though scattered throughout the four quarters of the globe.

And the vastly increased pace of modern war production brings with it increased use of every home-front circuit, line and wave-length.

All branches of the communications industry — telephone, telegraph, radio — are *meeting* the tremendous demand for their products. In war, communication engineers are taking advantage of their long peacetime experience with metals and alloys.

Time and time again this experience has shown them that a little Nickel goes a long way in improving other metals.

So now, when the dependability of what this industry makes is of supreme importance to the Nation, it favors more than ever the use of Nickel.

In repeaters, relays, magnetos, loading coils, transformers, loud-speakers and modern cables — even in the molds that form plastic radio parts — they call upon Nickel and its alloys for several unique advantages.

When other metals lack toughness, Nickel often supplies it. When they lack strength and fatigue resistance or corrode too easily, adding Nickel provides the needed qualities. Under abrasion, wear, shock and stress metals perform better *with* Nickel than *without*.

In the communications industry, as in many another, the knowledge, experience and cooperation of our staff has been at the disposal of technical men. Whatever your industry may be . . . if you want help in the selection, fabrication, and heat treatment of alloys . . . similar counsel and data are at your service.



Catalog "C" makes it easy for you to get Nickel literature. It gives you capsule synopses of booklets and bulletins on a wide variety of subjects — from industrial applications to metal lurgical data and working instructions. Why not send for your copy of Catalog C today?

* *Nickel* *

THE INTERNATIONAL NICKEL COMPANY, INC., *67 Wall St., New York 5, N. Y.*

AMERICAN *Phillips* SCREWS

are faster . . . and cost less to use . . . because they're



Fumble-Proof

The American Phillips *Recessed Head* fits firmly onto the 4-winged driver which can't slip out or twist out in any direction. So the faster methods of driving (spiral and power) are safe to use. No fumbling, no dropping of screws. *Time is saved.*

Self-Aligning

The American Phillips Screw and Driver form a angle unit that is automatically self aligning. No fussing around to get a straight start, no fatiguing nerve strain which leads to poor work that must be done over. Here again — *time is saved.*

Straight-Driving

The American Phillips Screw and Driver *stay in alignment* under the stress of the driving operation. So the screw can't be driven any way but straight. No burred heads, no scarred work. Screw head is set up tight and flush *every time. Total time savings* UP TO 50% — not to mention savings of screws and materials.

ONLY PHILLIPS SCREWS HAVE THE ENGINEERED TAPERED RECESS

AMERICAN SCREW COMPANY


PROVIDENCE 1, RHODE ISLAND

Chicago 11: 589 E. Illinois St. · *Detroit 2:* 502 Stephenson Building

Put the Screws on the enemy . . . BUY BONDS!



Stromberg Injection Carburetion carries the fight to the enemy



FOR TOP-FLIGHT PERFORMANCE

The Stromberg Injection Carburetor has considerably increased the *ceiling* as well as the range of fighting and bombing planes. And Bendix—with the finest research facilities in its field—continues to make improvements. Watch Bendix for the latest advancements in Injection Carburetion.

Sorties into the heart of Europe and beyond are commonplace today—*and one basic reason is Stromberg Injection Carburetion*. By automatically assuring the most economical mixture of fuel and air under all conditions of altitude, speed, position and temperature, these precision-built carburetors extract many extra miles from every gallon of gas. Standard equipment on the finest, fastest Allied fighters and bombers today, these products of Bendix Creative Engineering hold great promise for the commercial airlines of tomorrow.

Bendix PRODUCTS DIVISION

Bendix Aviation Corporation • South Bend, Indiana

FREE ENTERPRISE

The Obligation of Management and Labor to Cooperate...in War...in Peace

The Invasion is on! We have unleashed our full might for military victory. We have confidence that our great strength will bring success. We are strong because we have achieved unity in mobilization and in combat.

Though victory appears assured, we cannot rest until we have done everything in our power to speed the day when death and destruction are halted.

The home front is an important factor in this time element, for the fighting power of our Armed Forces depends upon their weapons. Napoleon's army fought "on its stomach"—man against man. Eisenhower's men fight on their tonnage—tanks, artillery, machine guns, heavy bombers.

As never before in the long succession of wars, the legends of heroic deeds on the battlefronts in this world conflict will be paralleled in history by the great accomplishments on the production fronts. Along with these heroic achievements of our Armed Forces, the world will long remember the record of our production accomplishments which have made us the stongest military power in the world, as well as the arsenal of democracy.

As the conflict reaches its climax, as battles grow fiercer and more destructive, our responsibility becomes greater and more critical. We must coordinate our productive efforts with the same ingenuity and the same precision with which our Armed Forces have coordinated theirs. We dare not waste the productivity of a single man or machine in these critical days.

As our landing craft are discharging our fighting men on the beaches of Europe and the Pacific, they must not want for equipment. No interference with war production for any reason can be justified. There must be no picket lines in America!

The landing of American troops in France virtually has stopped all strikes in the United States. This is important and encouraging news because the prelude to Invasion, unfortunately, has been an epidemic of strikes. Time lost through strikes, during the first four months of 1944, was double that lost during the same period last year. April saw more strikes than any other month since Pearl Harbor, and in May the record again was broken. Here is what happened within two weeks in May:

> Nine thousand men in six Chrysler plants in Detroit were out when a jurisdictional dispute in a "soda pop" war between the American Federation of Labor teamsters and the Congress of Industrial Organizations fired their discontent.
>
> A three day sit-down strike occurred among 950 employees in the B-H Aircraft plant over the refusal of the company to discharge a superintendent unsatisfactory to the union.
>
> Thirteen hundred men in the Chevrolet transmission and axle plant at Saginaw struck over a no smoking rule and a change in shift starting time.
>
> Two thousand employees at the Browne and Sharpe Manufacturing Company walked out when a woman was hired to fill a job long held by a man.
>
> Production of penicillin, blood plasma, and other medical supplies was halted at two Detroit plants of the Parke Davis Company as 1900 employees struck for a ten-cent raise.
>
> Over 25,000 lumber workers in the Pacific Northwest struck because the War Labor Board denied their demand for a wage increase.

At the end of the third week of May, 70,000 workers in 26 plants in Detroit were idle because of strikes.

Strikes in Detroit alone reduced production as much as a moderately successful German air raid would have done. Far more important than their effect on output is the effect of strikes upon national unity and morale. To our home front and to our Armed Forces, strikes belie our pledge to back the attack with all the power at our command. Hence, strikes limit our all-out war effort.

Prompt and decisive action is needed to keep America free from strikes for the remainder of the war. Stoppages of work on the production lines cannot be condoned while lives are being lost in fighting the enemy.

Most union leaders realize this need and are preparing to impose discipline upon their members who violate the no strike pledge. The Warehouse Division of the International Longshoremen's and Warehousemen's Union (C.I.O.) recently declared: "Strikes in this time of war are treason against the nation and betrayal of the interests of labor." A message sent by William Green to all heads of American Federation of Labor unions stated:

> "D-day is here. From now on until Hitler is finally crushed, every worker enrolled in the army of production must consider himself a part of the invasion forces of the United States and conduct himself accordingly. I call on you in the name of the American boys who are risking their lives under enemy fire to maintain uninterrupted production under any and all circumstances. Until victory is won every worker must give the same all out service that our Armed Forces are giving on the field of battle."

Strongest of all was the appeal of R. J. Thomas, president of the United Automobile Workers, to members of his union:

> "Our union cannot survive if the nation and our soldiers believe that we are obstructing the war effort . . . there can be no such thing as legitimate picket lines . . . I appeal to our membership. If you value your union, if you want to live and serve after the war, we must restrain ourselves and our hot headed brothers today. If we do not, there will be no union after the war."

Union officers are entitled to vigorous support from management and government in their efforts to prevent strikes. Behind many a strike is an accumulation of unsettled grievances. Managements are overworked, and many union shop stewards are new and inexperienced and do not always do their part in turning down cases which lack merit. Both of these conditions make it easy for large backlogs of unsettled grievances to pile up. A special drive to clean up unsettled cases and to prevent new accumulations of them is one way by which managements and local union officials can help shorten the war.

The government too has a contribution to make to the prevention of strikes—both through the prompt disposal of disputes and through firm action against the leaders of strikes. The National War Labor Board and the Regional Boards are disposing of over five thousand cases a month and have made an excellent record in reducing their backlogs. Nevertheless, the boards still have many old cases; and about one out of four strikes has been an effort to get action from one of the labor boards. The boards are entitled to cooperation from employers and unions in keeping down their docket. In instance after instance, cases are dumped in the lap of the board before the union and employer have made a real effort to get a meeting of minds and to work out settlements.

In the present emergency, strikes are an expression of the lack of adequate understanding and team work between unions and management. Any future great upsurge in industrial strife likewise will be due to misunderstanding. After this war this country must not go through another "1919" when the time lost from strikes reached an all time high. With 13 million workers, or almost half of the non-salaried employees of the country, in trade unions, the power and prestige of unions is greater than ever. ***The long-run prosperity of the country requires that business and labor learn how to cooperate in supporting the policies which produce the largest possible profits and the largest possible payrolls.***


Although business is primarily interested in the largest possible profits, and labor is primarily interested in the largest possible payrolls, both objectives call for the same basic conditions. Payrolls depend upon the prospects for profits. If bad relations between business and labor or unwise public policies cause employers to take a pessimistic view of the outlook for profits, both employment and payrolls will be depressed.

Individual unions and individual employers always will have differences over wages and hours and the status of labor in particular plants or in particular occupations. Some disputes on such issues are inevitable, but resort to arbitration and calm intelligence can help greatly in avoiding strikes in the long run. Cooperation between labor and management is an economic necessity. In our kind of economy, payrolls and profits ***both depend upon the willingness and the ability of business and labor to work together in creating the conditions under which enterprise flourishes.***

The foundation for intelligent and effective cooperation must be accomplished by skillful and imaginative managers in plants throughout the country who are willing to help unions with their problems, and who are able to interest union leaders and their members in the problems of business. Union members and their leaders are keenly interested as a rule in the efforts of management to win new markets. They know that jobs depend upon the success of managements in improving the product, adding new items to the line, and, less frequently, cutting costs and prices. Employees like to be kept informed about what management is doing, what problems it is meeting, and what success it is having. Most of all, they like to have an opportunity to contribute their ideas and suggestions.

The recent epidemic of strikes should not blind us to the fact that even today there are more plants where managements and unions are on good terms than ever before in the country's history. Consider, on the one hand, the extensive and constantly growing efforts of unions to train and develop shop stewards and, on the other hand, the efforts of employers to teach foremen how to carry out the new responsibilities imposed upon them by union agreements. Unions and managements together are learning how to operate together such technical devices as time study and job evaluation. Managements which, several years ago, opposed the provision of umpires to interpret union agreements and to settle deadlocked cases today are taking the lead in suggesting such arrangements.

The war is reaching a crisis, and all groups in the country must be aware as never before of their common interests. This presents an opportunity which should be seized to lay the permanent foundations for more effective team work in American industry. Let history record that the days when Europe was being liberated also were the days when unions and employers were making unprecedented progress in preparing American industry for the return of the service men by developing policies of cooperation between business and unions. Such cooperation will help achieve a peace worthy of our efforts and our sacrifices.



President, McGraw-Hill Publishing Company, Inc.

Invasion Has Spotlighted Our Need: *TO STAY ARMED*

IN HIS CLASSIC WORK *On War,* Clausewitz, the father of German military strategy, describes the turning of the tide of battle as the "flashing sword of retribution". No words more eloquent could be found to herald the fast approaching twilight of the Nazi gods.

As the impact of invasion strikes the hearts of home-front workers, the purpose of their tireless efforts of the past three years becomes distinct. The piano manufacturers who fabricated strange pieces for countless gliders, the assemblers who dreamed of endless lines of C-47's, the builders of the *Thunderbolts, Mustangs,* and many other aircraft, now see the goal they have been striving for. Their objective has been more than victory. It has been victory at the lowest possible cost in lives.

It is too early to estimate the number of casualties spared by our surface forces as a direct result of relentless pre-invasion bombing plus the magnificent air support furnished by the 11,000 allied airplanes which took part in the invasion. But it is only necessary to glance back at our tragic losses in the first raid on Dieppe to evaluate the contribution of air power to the economy in expenditure of life in waging war. The elements of surprise and of initial superiority of force undoubtedly contributed. But without air power the results would have been appalling.

This is the humane side of aerial warfare. Terrible as air bombardment appears to any normal human being, it reduces the time and lives required to convince an enemy that he must yield to the conqueror's will.

OUR PRESENT OPERATIONS indicate that our military leaders have been quick to learn all the tricks that Herr Hitler taught. They have been able to add quite a few new ones and to perform all of them better and on a scale far beyond his fondest dreams. Behind our military might, industrial management and labor have demonstrated the overwhelming superiority of their efforts as compared with those of any or all of the enemy nations. But there is yet another lesson for our citizens and our statesmen to learn from Hitler before we return to peaceful ways of life. It is found in a single sentence on page 1 of *The Art of Modern Warfare,* by Col. Herman Foertsch, a brilliant strategist of the German General Staff. The translation carries out the typical Teutonic bluntness. It reads:

"To believe that it is only necessary to disarm oneself, in order to have others follow suit, is foolishness."

These words of wisdom are followed immediately by a quotation from the writings of the German Commander Moltke:

"Eternal peace is a dream and not even a good dream, for war is a part of God's world ordinance."


For those readers who might feel that this philosophy belongs to German thought alone, Col. Foertsch offers another direct quotation conveying the same idea from a great lover of peace—John Ruskin.

UNHAPPILY human progress has not reached the stage where war will disappear. Even the millennium is restricted to one thousand years. But if we cannot prevent wars we can and must strive to extend the time between future conflicts.

It is not mere coincidence that the attack on Pearl Harbor came as our aircraft production curve crossed that of the Axis powers. Enemy strategists knew full well that they must strike then, or not for a long time to come. History will show that they waited too long, underestimating our ability to accelerate production to unforeseeable heights.

But from these obvious facts comes an uncomfortable but inescapable conclusion: If our airpower had been stronger, sooner, they would not have dared to attack us at all.

We have tried the disarmament route, and it has led us to the very brink of defeat. We must enhance our future security by turning the words of our enemies against them. No matter how eloquent the prattle of pacifists may seem, we must never relax in the preservation of our military might again.



EDITOR


BOEING B-29 "SUPERFORTRESS"





THESE B-29 SHOTS

graphically reveal structural and design details of Boeing's great bomber. Flight photo (top) indicates fine speed lines. This model has teardrop astrodome forward. Note Goodrich de-icer boot installation on vertical stabilizer. Left: Flight photo of B-17G "Flying Fortress" alongside B-29 affords pointed comparisons. Latter built again as large, has longer nose, and high aspect ratio of its wing is marked. Empennage view shows compact, multi-windowed tail gunner's office (gun hinsting tailtip had not yet been fitted). Below: Sweeping lines of huge "Superfortress" are accentuated by sharp contrast with tiny Culver 'Cadet'. Seen is B-29's retractable tail-skid for protection of tail in landing. Side blisters of this ship have metal-grille covers. For security reasons external armament is not shown in these photos.



Specifications and Performance

Span	141.2 ft
Length	98 ft
Height, at tail	27 ft
Wing section	Boeing 117
Maximum chord	204 in
Fuselage	Semi-monocoque, 9 ft dia cabin pressurized
Landing gear	Tricycle (steerable, three sets dual wheels)
Armament	Multiple installations of 50 cal guns in streamlined, low protrusion power turrets; also a 20 mm cannon
Speed	Over 380 mph
Ceiling	Well over 30,000 ft
Power plants	Four 2,200 hp Wright "Cyclones"



Biggest, Fastest, Highest Flying Bomber Carries Largest Bomb Load Greatest Range

By **HERB POWELL,** *Associate Editor, "Aviation*

Pressurized cabin is feature of superbomber . . . Simplicity of plane's construction demonstrates maker's mastery of maeutacture

TRIUMPH of putting the mightiest of bombers—Boeing's great B-29 *Superfortress*—into the air against our enemies is, above all, the triumph of the vision, ingenuity, effort, and courage of the American aircraft industry.

With the initial bombing of Japan by this most-powerful airplane, radio and press carried word to every man-in-the-street of this huge craft's tremendous capacities—for unequaled speed, range, bomb loads, and ceiling.

But it was the unequaled capacity of our industry which made it possible. That was the primary impression taken away by those of us who have observed the production lines in the Boeing Airplane Co. at Wichita and learned the detailed story of the superbomber from its makers.

Briefly, the B-29 (illustrated and also described in a table on the opposite page) is an all-metal, mid-wing monoplane with single-tail and retractable dual-wheel tricycle landing gear. Power, greater than that of any other bomber, is supplied by four, 18-cyl. Wright *Cyclone* engines of 2,200 hp. each, for a total of 8,800 hp. Through reduction gears these engines turn the largest propellers in use today, four-blade Hamilton Standard airscrews of 16 ft. 6 in. dia. Fitted to each engine are twin exhaust-driven turbosuperchargers, a dual installation necessitated by the fact that no single supercharger available was large enough for the high horsepower engines. Armor is built into the plane's fuselage, but it does not carry a load.

A prime feature of the B-29 is its pressurized cabin. Maintained via ducts leading from the superchargers on the two inboard engines, the pressurization is held fairly static to an initial high altitude, then falls slightly at subsequent higher altitudes with the increased rarity of the outside air. Oxygen masks are supplementary at extreme heights. Supercharging on one engine will supply the pressure, hence that on the other affords a 100 per cent reserve.

(*Turn to page 278*)



QUALITY PLUS QUANTITY MADE D-DAY AIR POWER POSSIBLE

Greatest air operation ever undertaken featured Allies' long-awaited push onto European continent, and stellar role was taken by 9th Troop Carrier Command and its old reliables, the Douglas C-47's, which not only delivered paratroopers, but towed unnumbered Waco CG-4A gliders with airborne infantry and supplies to hold initiative for more than five hours before actual landings on shoreline. (Press Association photo.)

"Ten-tenths" air cover which featured great land-sea operatioe against Fortress Eerape gives final proof of American manufacturers' farmidable smosh-the-Axis doctrine.

D-DAY WAS A DAY OF PROOF—bitter proof to the enemy—that our American aircraft production concepts were right.

It was a day of culmination for those who designed and built quality, multiplied it into Axis-smashing quantity, and got it to the front—largely on its own wings—with all the maintenance ingredients to keep it punching at a victory-insuring pace. Only D-day could bring us the ultimate proof, and now that it has come and gone the veil can be partially lifted and more of the magnificent record written.

Outstanding affirmative answer given was on the value and importance of airborne operations, with the 9th Troop Carrier Command emerging in a stellar role. Hitler, once the teacher,

(*Turn to page 277*)

THE BLITZKRIEG GOES TO SEA

By VICE ADM. JOHN S. McCAIN, USN

Deputy Chief of Naval Operations for Air

Here, by one of the leaders who helped build it, is a dramatic yet realistic appraisal of our newest weapon—carrier-based aviation. What it can be expected to do in the future makes "must" reading.



"LIGHTNING WAR!" screamed headlines in 1939 as Germany unveiled the fastest, most completely mobile army of history. "Blitzkrieg" crashed into the world's vocabulary.

The catch-phrase captured public fancy, but significance of Nazi tactics apparently was ignored. France continued with what the world now knows was a dismal military mistake. She prepared to combat shifting, flexible, mobile power with a supposedly impregnable Maginot line of fixed fortresses—a line which possessed neither the length to prevent flanking nor the depth to forestall encirclement. Wehrmacht "Lightning" turned the Maginot line in 1940 and crushed the resistance of a mighty nation in 30 days.

Japan, as Capt. Michael H. Kernodle* recently pointed out in addressing a Washington meeting of the Military Order of the World War, made the same mistake. Just as the French in 1939-40 pinned their defense to a chain of fixed fortresses, so the Japanese in 1942-43 tied their hopes to a "Maginot line" of bases in the Pacific Ocean. They placed themselves on the defensive in a fixed position, sacrificing their only chance to take the offensive and bid for a victory. That Japan was forced to rely on the stationary line because her mobile power was destroyed in the Coral Sea and at Midway is immaterial now. Important at this point in World War II is the fact that, just as France's Maginot Line failed to stand against a mobile enemy in 1940 so Japan's fixed defenses in the Pacific are crumbling before repeated blows from the most highly mobile and overwhelming striking arm the world has ever seen.



That striking arm is the United States Naval Task Force, a seagoing blitzkrieg. Its backbone is the weapon that saved America from invasion—the United States Navy aircraft carrier.

"Lightning war" isn't entirely new. It wasn't an innovation in 1939. Concentration of power, linked with mobility and surprise, has figured in battle tactics for centuries. Probably Hannibal and his elephants were waging "lightning war" when they crossed the Alps. Germany simply interpreted the combination of mobility and power in terms of greater speed, greater surprise, and greater resulting devastation than ever had been attempted before.

It remained for the United States Navy and its aircraft carriers to lift this modern "lightning war" from its wheels and fixed airports, to develop the principle of concentrated mobile power into a truly worldwide striking force, unhampered by terrain, unfettered by coastlines. Aboard carriers, "lightning war" went to sea.

Many military experts are not fully aware, even yet, of the tremendous striking power of the individual aircraft carrier. The limits of the effective power which may be available when carriers are used in greater and greater numbers only can be imagined now. One newspaper correspondent hinted at it recently when he wrote:

"The United States Navy today can duplicate from the decks of carriers—in numbers of planes, at least—the 'thousand-plane raids' that caused so much excitement in Europe a few months ago. And to do this over Jap targets the Navy need concentrate only about half of its 'announced' carrier strength."

Can you imagine being able to place 20, 50, or even 100 airports, complete with runways, hangars, repair shops, and warplanes, within range of any single Japanese fortress we choose? Compared with this type of battle magic, the wizardry of Aladdin's genii was a shoestring operation. How many of the Japs' so-called "non-sinkable basis" do you suppose they can move into the battle area to combat such a force? The answer is none, no more than France could move its Maginot line fortresses to meet Germany's mobile attacks.

Candidly, we may as well confess that necessity fathered the tactics which developed the aircraft carrier into the commanding weapon of World War II. The mobile task force might never have evolved, despite that necessity, had the United States Navy not been steeped in the tradition that the best defense is a vigorous offense. And had it not been for earlier foresight, determination, and unswerving belief in Naval Aviation the required striking power and superior mobility might never have been available when the necessity for such task forces arose from the ashes at Pearl Harbor.

Japan's attack on Dec. 7, 1941, was political treachery, but it was also a great military victory which left the United States facing the most difficult situation ever encountered by a naval power. With a Pacific battle line of four major combat units against Japan's twelve, the Navy was expected to stop the enemy advance, to save Australia and the Hawaiian Islands, and to maintain the extended supply lines to Sydney.

In addition to superior battle line strength, Japan had greater numbers of aircraft available for action. Its communication lines were shorter. Its convoy routes likewise were shorter and were protected. And it held the initiative. The once-powerful United States Navy was in a desperate defensive position with its battle-line strength so curtailed that any attempt to risk a fleet engagement would have been brazen foolhardiness bordering on national suicide.

The Navy might have defended the United States by blocking harbor entrances and waiting for Japanese forces to show up and start shooting but at best such a course, completely foreign to the sound United States naval doctrine of aggressiveness, could scarcely have achieved more than a compromise or a stalemate—not victory. The Navy determined to meet the complex situation audaciously. From that determination sprang "lightning war" on the high seas.

Strategically the Navy was forced to remain on the defensive until the European situation had been stabilized and until its Pacific strength had been regained, but that did not necessarily require a tactical defense. "The law and tradition of the United States Navy," its officers learn, "is to take the initiative and strike." Schooled in that tradition, the Navy had no alternative. Although strategically in a defensive position, the Navy doctrine called for tactical offensive with the forces that remained.

Those forces consisted of five aircraft carriers in the Pacific, enough fast hard-hitting cruisers and destroyers to accompany them, and a small band of the most competent airmen in the world. The Navy shelved battle line tactics, switched to a war of speed and mobility. With the aircraft carrier and its flyers to furnish long range striking power while cruisers and destroyers provided a defensive screen and short range strength, the flexible, mobile, almost independent United States Carrier Task Force took shape, fashioned to strike hard and fast.


Less than two months later, on Feb. 1, 1942, while daring air squadrons from the carrier *Enterprise* blasted Japanese bases at Roi, Kwajalein, Taroa and Wotje in the Marshall Islands, equally daring airmen from the *Yorktown* struck Jaluit, Makin, and Mili in the Gilberts. Twin task force thrusts smashed carefully constructed threats to American supply lines. The seagoing blitzkrieg was born.

These earlier carrier task forces were small, usually including only one, or perhaps two, carriers with a few protecting cruisers and destroyers. They roved the Pacific, raking the Jap's installations at every crucial point, blasting his supply lines, disrupting his reinforcement routes, knocking his plans and progress completely askew. They raided Wake then Marcus. Airfields and seaplane bases which the Jap laboriously built and manned as so-called "unsinkable carriers" were decommissioned in whole or in part just as surely as though they had been ships at anchor in the Pacific lagoons. The "unsinkable carriers" were the easiest sort of targets for the mobile United States carrier task forces—"sitting ducks," if you please. Uncle Sam's aircraft and big guns simply pounded them to ruins, then steamed majestically on their way to blast other installations.


Shattered along with those Jap installations were the remnants of the persistent theory that carrier aircraft were of value only as elevated platforms from which the enemy could be scouted and observed. Carrier planes demonstrated

*Capt. Kernodle was Air Officer aboard the *Wasp* when that carrier relieved Malta early in the war and Executive Officer when this carrier supplied air coverage for the invasion of the Solomon Islands. After the sinking of the *Wasp*, Capt. Kernodle was assigned to the staff of Gen. Vandegrift, Marine commander on Guadalcanal, with additional duty as commander of the Advanced Naval Air Base there.

As Deputy Chief of Naval Operations for Air, Vice Adm. John S. McCain has been a vital factor in taking lightning war to sea—in the aircraft carrier and deeper and deeper into the enemy's territory. (Official U. S. Navy photo.)



Much of the success of today's carrier-task force operations is due to Navy tradition of always taking the offensive, plus foresight, as exemplified by this photo of early American carrier development, showing takeoff from the first real carrier, the Langley.



Added versatility has been given already-versatile carrier aviation by "ugly ducklings" such as one shown here. These escort carriers first proved worth in North African and Attu campaigns. More recently during Marshall invasions, they literally "went ashore" with leading vessels to provide most effective spot air support yet developed. (Official U. S. Navy photo-British Combine.)

the striking power to stop the Jap they became the Navy's Sunday punch.

The battles of the Coral Sea and Midway, in which destruction of her carrier strength doomed Japan's ocean mobility, further erased the battleline conception of naval tactics and clinched the carrier's place as backbone of the fleet. Opposing forces fought solely by means of air power without ever being within gun range of each other or close to it.

As the battleship force regained its pre-Pearl Harbor strength, new and remodeled men-of-war joined the task forces, increasing the potency of each carrier by adding spectacular surface and anti-aircraft protection, bolstering task-force striking power by hammering Jap-held shore fortifications under umbrellas of friendly aircraft. Meanwhile, more and more aircraft carriers slid off the ways and joined the already potent mobile forces until task forces that included from 5 to 20 carriers and scores of supporting vessels dared the Jap to show his fighting fleet.

Early this year, the late Frank Knox, Secretary of the Navy, announced that more than 42 aircraft carriers of all types were in service. The launching of many, many more has been announced since that time. These range from the 33,000-ton fleet carriers, more than 800 ft. long and carrying more than 80 planes each, through the 10,000 ton converted carriers of the *Independence* class, down to the "ugly duckling" escort carriers. The last group by sheer fury of attack in anti-submarine warfare and in the North African and Attu invasions, has earned an essential role in combat operations. The bold little escorts moved right in with amphibious forces in the recent Marshall Islands invasion to provide the most effective spot air-support yet developed.

As these various carriers joined the Pacific fleet, the rapier-like task forces developed into clubbing juggernauts that now rove hundreds of miles from the nearest friendly base and strike with impunity deep in enemy territory.

Consider the naval-air operations made possible by such forces as revealed during early February. The month opened with one gigantic carrier task force spearheading the conquest of the Marshall Islands, more than 500 mi. from the nearest friendly base. On Feb. 16 and 17, while many carrier planes still were helping the Marshall mop-up in the Kwajalein area, a carrier task force bombed and shelled Truk, one-time bastion of the Jap naval strength more than a thousand miles past Japan's "unsinkable carrier" front line. Meanwhile, another carrier task force attacked Eniwetok Atoll, leading an invasion which was completed Feb. 21. While that operation progressed, the Truk attacking force steamed northward to the Mariana Islands between Truk and the Japanese mainland where on Feb. 22, its carrier-based planes pounded bases on Saipan and Tinian.

These were not just stabs. They were crushing blows. Japs based on the Marshalls and Eniwetok were beaten into submission and the territory occupied. At supposedly untouchable Truk at least 23 Japanese vessels were sunk and more than 200 aircraft downed. These operations included none of the naval activity farther south in the Pacific area nor any of the many supplementary forays by army and navy long range bombers. And the world thought it was seeing "lightning war" in 1939!

Despite present success as task forces focus mighty military power at key points, the United States must continue to plan on the basis of a long war against resourceful and determined opponents. Under-estimating the enemy is a luxury that even a powerful nation such as ours can ill afford. No one can foretell now whether the United States still will be at war in late 1945 or 1946 when the new 45,000-ton super-carriers (for which contracts recently were announced) become available much less predict what effect they may have on naval operations.

It is difficult to imagine how super-carriers could enable United States forces to traverse wartime seas with any more security than is now being achieved. Present forces have dared Jap sea power again and again. The United States Naval Air Force, minus super-carriers, has without a single exception proved superior to any opposing aircraft, whether based on land or sea. The myth of carrier vulnerability to land-based air opposition already has been disproved. Super-carriers simply are expected to increase the United States Naval Air Force's present superiority. How much, no one now knows.

Greater armor protection and so-called super-decks should give super-carriers increased immunity to bomb damage. Greater compartmentation should nullify the torpedo threat. Wide flight decks and heavier arresting gear are expected to make routine the use of twin-engine bombers possible in regular carrier procedure, thus extending carrier aircraft range and adding to destructive fire power of task forces.

The net value of such improvements cannot be accurately determined on the basis of present enemy equipment and tactics. Recent bomb and torpedo attacks aimed at present United States carriers have been utter failures. At Rabaul, Japan lost 64 of 70 planes when it attempted such an attack. Carriers afloat today have proved that their compartmentation is adequate to permit them to take torpedoes and continue in combat. Present task forces are not finding the additional range and power of twin-engine aircraft necessary in order to shatter crucial bases of the Japanese defense system in surprise attacks.

However having felt the devastating power of lightning war at sea, the nation's enemies undoubtedly are making every effort to adjust their defenses to meet it. By the time the super-carriers are ready for the fleet, it may be that their additional power, speed, and air range will be required. Construction of the super-carriers can best be termed insurance—insurance of continued victory. In the Pacific—for they will mean increased carrier effectiveness, and victory in the Pacific most certainly hinges on the mobile warfare waged by aircraft carriers.

"Hinges" does not imply carrier self-sufficiency. The carrier alone is no more a self-sufficient combat unit than an isolated battleship; no more invulnerable, nor vulnerable, than any isolated advanced base. The fleet carrier is simply a mobile flying field which can stay at sea for weeks with its 2,000 or more officers and men and can fuel and supply other ships as well as its air complements. It has its own hangar, its own weather bureau, its own repair shops and replacements, but it still requires support. Tactically it oc-

(Turn to page 257)

Today, using less than half its "announced" carrier strength, U. S. Navy can throw thousand plane raids from carrier decks against Japs' supposedly "unsinkable carriers"—string of fatally immobile land bases. Such raids says Adm. McCain, can easily be dwarfed by action of our forthcoming super carriers. (Official U. S. Navy photo.)





Celebrated Soviet women flyers—Marina Raskova (left), Paulina Ossipenko (center), and Valentina Grizodubova. Latter, now USSR's Chief of Aeronautical Authority, Foreign Division, is sole survivor of this record-breaking trio. Maj Raskova met death in air combat last year, while Capt. Ossipenko was killed while testing a new aircraft prior to the Nazi invasion. (Sovfoto.)

HOW WOMEN FLYERS FIGHT RUSSIA'S AIR WAR

By MADELIN BLITZSTEIN

Many hurdles—of education and of opportunity—have faced the women who have contended for places in Soviet aviation. But those places definitely have been won, first in record flights and now in actual front-line sky fighting.

DESPITE THE FACT that the Russian government officially discourages their participation in combat flying, many Soviet women have, nevertheless, joined the air fight against the Nazis. And they have rung up an outstanding record in shooting the enemy from the skies, as well as in bombing many key Nazi objectives—thus in addition to their excellent job of essential flying behind the front.

The striking bravery and skill of Maj Marina Raskova, pilot and Red Air Force Regiment Commander, is exemplary. Killed in air action last year, her ashes were laid, with full military honors, in the Kremlin wall not far from those of her co-flyer, Capt. Paulina Ossipenko, who met her death while testing a new plane some months before the Nazi invasion. The Raskova rites comprised the first state funeral held in the Soviet Union during the present war.

Today, other women pilots are constantly in training to take the place of those who, like Raskova and Ossipenko, fall in active duty.

Now holding the important USSR post of Chief of Aeronautical Authority, Foreign Division, is Valentina Grizodubova, sole survivor of the courageous Raskova-Ossipenko-Grizodubova trio. Valentina was awarded the coveted title of Hero of the Soviet Union because, together with her two comrade flyers, she made not only national but international aviation history.

While these three Russian women pilots established new records, both as individuals and in concert, it is the biography of Valentina Grizodubova which is most closely connected with the historical development of aviation in the Soviet Union.

Before the October Revolution, Valentina's father, Stepan Grizodubov, an industrial scientist, evinced ability in both aircraft construction and flying. In 1910, he completed the design of his first aircraft—one of the initial Russian airplane designs. Like the Wrights, Grizodubov personally built the plane he had visualized, with certain aid from interested fellow workers. Meanwhile, not having a son, he saw nothing unusual about taking his daughter up into the air with him. Thus Valentina was introduced to the air at an early age.

It was in 1928 that Valentina received her pilot's license, but she was not yet satisfied with her knowledge of aeronautics. She continued her studies and, in a few years, was made an instructor in a flying school. Later, she was named pilot of the Gorky propaganda air squad.

By 1937, Pilot Grizodubova held no less than five international women's flying records. These were awarded for flying a single-seat sport plane 100 kilometers (63 mi.) at an average speed of 137 mph., for flying a single-seat light seaplane the same distance at a speed of 118 mph.; for flying a two-place seaplane this distance at an average speed of 124 mph.; for bettering the current international altitude record for women by making a flight to a height of 1.98 mi.; and for breaking the non-stop flight record for women by flying from Moscow to Aktubinsk in Asiatic Russia, a distance of 901.5 mi.

For these and other achievements, Pilot Valentina received the Red Banner of Labor and the Order of the Red Star. Moreover, in December 1937 she was elected a deputy to the Supreme Soviet, for she was then—as she is now—interested in governmental matters.

In 1938 she joined hands with Marina Raskova and Paulina Ossipenko. Each of the latter had had an individual aviation history totally different from hers.

Perhaps the most interesting life story is that of Paulina Ossipenko, born in 1907 in the Dnepropetrovsk Region. There were twelve children in Paulina's peasant household, her mother was illiterate and her father could read and write only with great difficulty.

When Paulina reached school age, her family was unable to buy her shoes, clothes, or books, hence school was ruled out; instead the little girl went into service, first as a nurse, then as a farmhand and finally, at 17, she was working as a charwomen in a grain elevator.

When farm collectivization was introduced, Paulina got a chance to show her capabilities; she was shifted to work on a poultry run, and she served there long hours, with noteworthy conscientiousness. Due to her labors, the health of her poultry was exemplary and as a reward the villagers elected Paulina Ossipenko to their local Soviet in 1927.

This office brought Paulina another opportunity to increase her knowledge; she went to the village school and studied grammar and mathematics. And soon she was transferred to the city of Kiev to delve into poultry science. It is to be noted that those days were doubly difficult for her because most of her fellow pupils had much more previous schooling than she. Paulina had to spend nights cramming her lessons, and she often had to have extra help from the other students. Nevertheless, she was graduated with honors and certified back to her native village as an instructor in poultry-raising.

Farm life filled this girl's time and thoughts—until one day two training planes visited the village. Immediately Paulina made up her mind to become a pilot. And in spite of the open derision from the local farmers—who were certain that a chicken raiser was not fit to be an airplane pilot—Paulina, after great insistence, gained permission to enroll in an aviation school near Sevastopol. The mysteries of physics, electrical engineering, and aerodynamics accordingly were unveiled for her, and Paulina Ossipenko was graduated in 1932 with exceptional grades. When she returned to her native village dressed in flying kit, her family was rightly proud and the villagers incredulous.

Because of the ability she had displayed, Paulina was sent to serve with the air unit of the Kharkov garrison. Only two years later, she was made a flight commander, her special field becoming altitude flights. She flew to a height of 4.7 mi. without oxygen, then broke all existing women's records for altitude flying by hitting the mark of 5.5 mi. In addition to these records, Paulina established (in three successive days, May 22–24, 1937) three international women's records. One for altitude without a payload, a second with half-ton payload, and the third with a one-ton payload.

Now ranked as a lieutenant, she was quickly to win additional honors. There came her election as a delegate to the All-Army Conference of Commanders' Wives in Moscow in 1936 — — at the Kremlin, she delivered a speech concerning the participation of women in national defense — — and the people's Commissar of Defense granted her permission to attempt a non-stop cross-continent flight from Sevastopol to Archangel.

In July of 1938, she completed this flight, with Vera Lomako and Marina Raskova as her co-pilots. For this success, Paulina Ossipenko was made a captain and awarded the Order of Lenin.

This Sevastopol-Archangel flight was Paulina's first with Marina Raskova. Let

(*Turn of page 255*)



Jr. Lt. Lilya Litvak was awarded Order of the Red Star following service at Stalingrad, where she accounted for three enemy planes in single-combat and helped down two in group-combat. In a later action, she was attacked by four Messerschmitts, and despite a serious leg wound she destroyed two of them and eluded the others. She was, however, killed at the Battle of Kharkov in 1943. (Sovfoto.)




Once an air club instructor and engineer at Moscow's Frunze plant, Lt Valeria Khomyakova is now a fighter pilot. She is credited with downing a Ju-88. (Sovfoto.)

HERE ARE YOUR MARKETS

PART III — MOUNTAIN AND PACIFIC REGIONS AND CONCLUSION

By **JOHN FOSTER, JR.** *Managing Editor, "Aviation"*

Concluding AVIATION'S detailed presentation of nation-wide merchandising data, the Mountain and Pacific regions are analyzed. And finally, the broad distribution framework is ranged, with logical locations named for setting up a national aviation-product sales and service network.



Sparse is word for family populations in eight states making up Mountain region, for Colorado is only one to top 300,000. Nation's smallest state-family population —33,291—is in Nevada. Nevertheless, complete network of aviation product distribution outlets will include Mountain region, and profitably so. Three Pacific states cover many ranges, with California measuring out as Class A market in this—as well as every other—category.

COMPARED WITH THE "LUSH" MARKETS of the Middle Atlantic and Pacific regions, and the consistently fertile fields provided by the East and West North Central areas, the eight states comprising the Mountain region at first appear to present formidable obstacles to aircraft sales and service. True, the distributors and dealers—like the cities themselves—will be farther apart, but there must be both sales and service in any complete distribution organization.

Although the Mountain region is eighth in importance among the nine regions, according to the measurable data shown in Table VIII, analysis of Montana, Idaho, Wyoming, Colorado, New Mexico, Arizona, Utah, and Nevada as individual states shows aircraft and accessory manufacturers can find profitable outlets for their products in the region.

Montana, with 159,963 families has but 0.6 percent of the U. S. total, with .37 percent of the buying income and .42 percent of the retail sales. It should be noted, however, that the 129,758 passenger cars owned means that four out of every five families has this type of transportation. Pilots outnumber private planes by a bit over 7 to 1, for the last available date (as of Oct. 1, 1941) showed there were 786 non-airline pilots registered, compared with 163 planes, or 0.7 percent of the country's total. A total of 69 airports give the state .47 improved landing facilities for every 1,000 sq. mi. On a weighted basis Montana measures out in 35th place among the 48 states.

Idaho's 141,727 family population is just 0.5 percent of the nation's total, and the state's buying income and retail sales percentages stand at .30 and .37, respectively. Here again, the automobile ownership is high, the total standing at 116,972, or .83 per hundred families. Here again, also, the pilots outnumber the planes owned by over 7 to 1, the figures being 748 and 106. The 42 airports—well distributed geographically—give the state .51 ports per 1,000 sq. mi. The combined factors put Idaho in 38th place among the states.

Conforming closely to the Mountain region pattern, Wyoming's 69,374 families comprise but 0.2 percent of the nation's total but automobile ownership continues at nearly one for every family—61,423. Buying income and retail sales stand at .17 and .21 percent of the national total, respectively.

Although the state is the home of famed Yellowstone National Park, little has been done to encourage flying in this unusual summer resort area, for the state has only 35 airports—35 per 1,000 sq. mi. This lack of facilities may account for the fact that the state had but 471 non-airline pilots and recorded ownership of but 86 aircraft, factors which weigh the state at 44th place on a state-by-state rating.

In 31st place on a weighted state basis, Colorado is one of the five mountain region states in the Class D bracket. Family population of 316,000—largest in the region—is 1.2 percent of the national total, buying income is .71 percent and retail sales are .82. Typical of the region, though, is automobile ownership, the total standing at 279,849, an average of .89 for every hundred families. Registration of aircraft is also highest in the region, the 222 planes making up 0.9 percent of the national total. Pilots not engaged by airlines total 1,339, a ratio of more than 6 to 1. Airport facilities here, too, are hardly commensurate with the scenic attractions of the state, for with 47 ports, landing facilities measure out to .45 per 1,000 sq. mi.

New Mexico and Arizona appear to offer greater potentialities than actualities, for their family populations of 129,475 and 131,133 together make up only 0.7 percent of the national total, while buying incomes are .21 and .30 percent each and retail sales amount to .26 and .35 percent respectively. Automobile ownership, however, is greater in Arizona, the average standing at .79 per hundred families compared with .62 in New Mexico.

In straight aviation criteria, too, Arizona leads its neighbor state, except for aircraft owned; New Mexico has 143 and Arizona 1 less. Pilots registered totaled 657 in Arizona and 542 in New Mexico, and in airports the Sunshine State again led, 70 to 60. Individual state ratings put Arizona in 36th place, New Mexico in 37th.

Utah at 40th place among the states, also conforms to the Mountain pattern of sparse family population, the 139,487 total being just 0.5 percent of the national total, and automobile ownership holding up to a good cars-per-hundred-family ratio of 79, with a total of 110,033. Again Utah conforms on aviation criteria, non-airline pilots totaling 860 and aircraft owned standing at 112, or 0.4 percent. The total of 29 airports is smallest for the eight states, but at .36 per 1,000 sq. mi., it is a bit ahead of Nevada.


Although Nevada has the smallest family population of any state—33,291 or 0.1

Table VIII—Mountain Region

	Montana	Idaho	Wyoming	Colorado	New Mexico	Arizona	Utah	Nevada	Total
1. Family pop.	159,963	141,727	69,374	316,000	129,475	131,133	139,487	33,291	1,120,450
2 Percent nat'l pop.	.6	.5	.2	1.2	.5	.4	.5	.1	3.8
3 Percent U. S. buying income	.37	.30	.17	.71	.21	.30	.32	.11	2.49
4 Percent U. S. retail sales	.42	.37	.21	.82	.26	.35	.38	.14	2.95
5 No. passenger cars	129,758	116,972	61,423	279,849	80,046	103,545	110,033	30,126	911,752
6 No. cars per 100 families	81	83	88	89	62	79	79	91	
7 No. aircraft registered	163	106	86	222	143	142	112	60	1,040
8 Percent aircraft registered	.7	.5	.4	.9	.6	.6	.4	.3	4.4
9 No. pilots registered	788	748	471	1,339	542	657	860	249	5,652
10 No. airports	49	42	35	47	60	70	29	34	386
11 Airports per 1,000 sq. mi.	.47	.51	.35	.45	.48	.61	.36	.31	
12 Percent airports	2.4	1.5	1.3	1.7	2.1	2.5	1.0	1.2	13.7
13 State market rating	D	D	E	D	D	D	E	E	
14. Region market rating									.8



Buying income index of Mountain region states correlates exactly with family population as shown by comparison with illustration on opposite page. Correlation between the two indices is exact in California also, but in both Washington and Oregon ratings for buying income is one range higher than population, a healthy sign for both manufacturers and sales organizations now making aggressive merchandising plans.



Sparse population and low buying income keep retail sales at low levels in Mountain region correlation between the three indices being exact for every state except Colorado, where sales index drops one range below population and income. In Pacific states, retail sales correlate very closely with population and again California hits top range.

percent—the state should not be over looked for at least dealership possibilities, if for no other reason than the prospects among its many "six-weeks" residents. Even the 'native" population make up good transportation prospects, for automobile ownership stands at 30,126, or 91 per hundred families, the highest in the region. Ratio of plane ownership to pilots is tops in the Mountain region, for the state had 66 aircraft registered and 249 non-airline pilots. A total of 34 airports or .31 per 1,000 sq mi—smallest percentage in the region—would not appear to back up the consistent sponsorship provided by aviation's long-time friend Sen Pat McCarran, for Nevada stands 46th among the 48 states.

While the Mountain Region is far and away the largest, geographically, it has the smallest family population in the country, a total of 1,120,450 or 3 8 percent of the U. S aggregate. This alone would seem to indicate it would be the worst market, but the contrary can be made the case by aggressive selling. The very fact that distances are so great gives the airplane a distinct advantage. That the people of the region are ready prospects for good transportation facilities is shown by automobile registrations of 911,752, or 81 for every hundred families. This means that between 78 and 85 cars are owned per 100 families, second highest rating in the whole United States.

Registrations of 1 040 private planes exceeds that of the East South Central region, whose population is more than twice as great, and the total of 5,652 of non-airline pilots registered is above both the East South Central and New England regions.

Adequate facilities appear to be one of the greatest deterrents to broader acceptance of private flying, for although the 386 landing fields comprise 13 7 percent of those throughout the country, the average of 45 per 1,000 sq mi leaves much to be desired. That private flying can have unusual utility in this region is shown by consistently good weather, for this area is the most fog-free in the whole country. Practically the entire region has, according to Weather Bureau maps, less than five days fog per year, with only small sections of the northwest and east-central portions having between five and ten days per year.

Pacific Region

California not only produces airplanes—its people very definitely own and fly them. Measurable data, as shown in Table IX, rank the state as a Class A market, second only to New York in importance for the country as a whole.

The 10,657 non-airline pilots registered give the state a total of more than twice that of any other, most conclusive indication that private flying has long been accepted in a large way. Its ownership of 2,292 planes (9 8 percent of the national total) is exceeded only in Pennsylvania, where registrations on the last available date were 2,372 or 10 2 percent. The correlation between available landing facilities and the growth of private flying is forcibly shown here, for California, with 227 airports tops the nation even though other states may have more per 1,000 sq mi. And, unlike some of the southern states, military installations for training purposes appear now to have much better locations for possible postwar civilian use, since they are closer to population centers.

On non aviation criteria California stacks up well also. Its 2 138 343 family population make up 6 2 percent of the national total, but buying income percentage

(*Turn to page 123*)

Table IX—Pacific Region

	Washington	Oregon	California	Total
1 Family pop	637,237	337 492	2 138,343	3,010,172
2 Percent pat'l pop	1 0	9	6 2	8.7
3. Percent U. S. buying income	2.03	1 11	8.54	11.68
4. Percent U. S. retail sales	2.20	1.30	9.37	11.87
5 No. passenger cars	441,234	300,840	2,261,928	3 009 712
6 No. cars per 100 families	82	01	100	
7. No. aircraft registered	400	010	3,210	3,006
8. Percent aircraft registered	1 7	1.4	9.8	12.9
9 No pilots registered	2,420	1,421	10,657	14,498
10 No. airports	01	40	227	334
11. Airports per 1,000 sq mi	01	47	1.45	
12. Percent airports	2.2	1.8	7.0	11.0
13 State market rating	B	C	A	
14 Region market rating				.3



HERE ARE YOUR MARKETS

AVIATION'S distribution framework for aircraft, parts, and accessories, a framework in which any dealer any place in the United States would be within 3½ hr—at 100 mph cruising speed—of his distributor. Established on the basis of today's airports (some 3,000 potential dealer locations) it is presented as the basis upon which the aircraft industry can—with aggressive merchandising—more than double the number of major outlets.



Table X—Temperature and Precipitation Averages

(With high and low marks for Dec 1943 as an additional guide to winter weather conditions prevailing in the marketing regions.)

State	Temperature High	Temperature Low	Temperature Ave.	Precipitation High	Precipitation Low	Precipitation Ave.
Alabama	83	9	47.3	5 72	1 11	3 50
Arizona	80	—8	42 6	4 14	.33	1.50
Arkansas	82	—5	40 7	5 56	1 88	3 43
California	83	—8	46 2	12.86	.33	3 30
Colorado	65	—25	26.8	2.96	.02	.77
Florida	89	14	59 4	6 43	.00	1 62
Georgia	87	2	47.4	6 30	2.36	3 80
Idaho	65	—35	27.6	7 93	.12	1 15
Illinois	69	—12	29.3	2 92	T	1.27
Indiana	67	—10	30.0	2 65	.09	1.16
Iowa	65	—13	26 2	1.38	T	52
Kansas	68	—21	30 6	3 65	T	1.50
Kentucky	68	—1	35.2	3 79	1.07	2.20
Louisiana	66	10	51.5	6 37	1.46	5.22
Maryland-Delaware	69	—15	34.5	2 50	11	1.41
Michigan	52	—25	24.3	5 07	04	.82
Minnesota	52	—28	18.9	.44	00	07
Mississippi	82	9	47.5	7 00	2 02	3 91
Missouri	72	—20	31.3	3 93	.76	2.10
Montana	69	—29	25.9	2.61	T	42
Nebraska	86	—20	29.3	1 95	00	16
Nevada	70	—16	33 6	2 57	00	86
New England	59	—37	21.7	2 33	.40	99
New Jersey	62	—10	31.1	2 81	.22	1 41
New Mexico	74	—29	31.8	5 08	.00	1.42
New York	59	—34	23 3	2 25	.06	1 11
North Carolina	82	—5	41 8	5 89	1 08	3 36
North Dakota	65	—22	21.5	.41	T	.12
Ohio	63	—10	29 4	2 28	.24	1 03
Oklahoma	78	—6	36 2	5 22	1 06	3 10
Oregon	70	—10	33 6	12 32	.16	1 68
Pennsylvania	63	—23	26 4	3.23	.45	1.12
South Carolina	84	7	46 0	5 32	1 39	3 94
South Dakota	69	—23	26 5	.95	00	.11
Tennessee	72	—2	39 0	5.19	2.00	3 21
Texas	88	—2	46.5	7 53	.50	2 83
Utah	64	—20	29 6	2.56	01	96
Virginia	79	—3	37.1	4 16	90	2 17
Washington	72	—6	33 0	22 67	04	3 22
West Virginia	66	—15	32.1	4 20	45	1 96
Wisconsin	57	—21	22 7	1.08	.00	.27
Wyoming	69	—26	24 6	2.69	04	.52


is higher—8 54 percent—as is the figure for retail sales, which stands at 8 37. On the measure of transportation needs, automobile ownership of 2,261 938 shows up at more than one per family, at a ratio even slightly higher than that in Michigan, heart of the country's auto industry.

Oregon, much smaller geographically, measures out as a Class C market for aviation products in 27th place on a nationwide basis. Its 337,492 family population comprises 0 9 percent of the nation's total, but its buying income stands at 1 11 percent and the state does 1 30 percent of the country's retail sales. That Oregonians are good transportation prospects is shown by passenger car registrations of 306,540, almost one per family.

In the ratio of aircraft ownership to family population, Oregon is above average for the country, with 310 planes registered, or 1 4 percent of the national total, as it also is in the number of non-airline pilots, which totals 1,421. Both these figures would undoubtedly be raised with an increase from the present total of 46 airports, or 47 per 1,000 sq mi.

Consistent with the ratios of the Pacific region's other two states, Washington's 1 6 percent of the family population has 2 03 percent of the buying income and does 2 20 percent of the national retail sales. Four of every five of the families own a passenger automobile, for the total stands at 441,234.

There are approximately six pilots to every plane, the respective totals being 2,420 and 404, the latter comprising 1 7 percent of the national registration. These




Passenger car registrations, as guide to transportation habits, also follows pattern set by other indices for both Mountain and Pacific regions, with California showing highest ratio with 2,261,938 cars for 2,138,343 families.

two figures might easily be materially increased with more landing facilities, since the state's airports number 61, or .91 per 1,000 sq mi. On a weighted basis of presently measurable data, Washington ranks in 15th place among the states.

Boosted in every category by California's impressive figures, the Pacific region makes up the third ranking aviation product marketing area in the country. The 3,013,172 families make up 8 7 percent of the national family population, they have 11 68 percent of the country's buying income and have accounted for 11 87 percent of the retail sales. The total of 3,009,712 passenger car registrations gives the highest ratio of cars to families in the country.

The 14,498 non airline pilots make up the second largest regional total, topped only by the 15,160 in the East North Central region, while the 3,006 private planes —12 9 percent—make up the third highest total, trailing the Middle Atlantic's 4,703 and the East North Central's 4,658. The total of 334 airports gives the Pacific region fifth place among the country's nine regions in this category.

Southern California chambers of commerce to the contrary, there *are* areas with better year-round flying conditions, for Weather Bureau maps show that the annual average number of days with dense fog in that section ranges from 20 to 40, dropping to 10–20 in the central coastal region and increasing to over 50 along the



In aircraft registrations—one of best clues to past acceptance of aviation—California again has highest rating of any state in Pacific or Mountain regions; in fact its total of 2,292 is outranked only by Pennsylvania's 2,372.

northern coast of the Pacific region. On the whole, however, weather will be much less of a limiting factor in marketing aircraft and aircraft products in this region than in some others, especially in view of the past record hung up by the far western states.

The Distribution Framework

With the various aviation marketing data compiled and analyzed by individual states and regions, the final step is to correlate them on a nation-wide basis as a guide for establishing distributor and dealer areas.

Exact locations for each will of course vary with each company's policy, the price of its products, perhaps the present distributor-dealer set-up, and other factors. In a study such as this, presenting basic data for the use of both producers and distributors, it would be unwise today to arbitrarily state that "a distributor should be located here, and dealers located there or there." It is, in fact, impossible for even an individual at this time to say "we will put a distributor here and a dealer there;" somebody else may get that distributor or dealer first in which case an alternate must be selected.

There are, however, certain basic factors that will apply in every case, so that an over-all framework can be set up, a framework within which each individual manufacturer or potential distributor or dealer can establish his own pattern.

In suggesting the various distribution areas one fundamental premise has always been kept in mind. That is, in any organization that is to be able to guarantee one-day delivery to any dealer, the network of distributors must be so complete that every dealer in any particular distribution area will be no more than a 7-hr. round-trip flying time from his distributor. On the basis of 100 mph. cruising speed, this would mean that distribution areas would have a radius of not more than about 350 mi.; in most cases it would probably be less.

Such a network would call a minimum of some 20 distribution points, but it is obvious that population and wealth concentrations, high aircraft registrations, and large numbers of airports would indicate support—in fact the need—for more distribution units than this bare minimum.

We have, therefore, selected 37 areas including 46 possible locations which not only meet the geographic qualification, but provide the framework within which a distributing organization could be set up, with each organization making its own choice of final locations that would best cover the territory for that particular company.

The Distribution Centers

In the country's No. 1 marketing region—the Middle Atlantic States—it is obvious that the metropolitan New York City area provides a very important distribution point, a point which would call for locations either on Long Island, in Westchester County, nearby New Jersey, or perhaps in all three. Since the Middle Atlantic region embraces 7,278,911 families with 25.21 percent of the country's buying income, 4,703 aircraft and 344 airports, additional sales and service facilities might easily be necessary. Spreading them out, then, would suggest these additional possible locations: Buffalo, N. Y., and Philadelphia and Pittsburgh, Pa. It should be noted that possible distribution points only have been suggested, dealer locations are outside the scope of this study.

Despite the fact that all, or at least part of Connecticut, could best be served by the New York distribution center, Boston is the logical point from which to cover the remainder of the New England region which with part of Connecticut, would embrace approximately 2,000,000 families and some 125 airports. If an additional outlet proves necessary, Portland, Me., appears the most logical, especially in view of its location on the coast for amphibious or water-based craft.

The eight South Atlantic states, stretching from Delaware to Florida and making up the fourth most important region, run smack into the overlapping of territories noted earlier in the series. Under the straight geographical formula for example, distributors at either Philadelphia or Pittsburgh would extend well into the South Atlantic region. However, it must be remembered that both population and wealth are concentraded in this section of the country. Therefore it is apparent that a distributorship might well be established in either Baltimore or Washington, to cover the territory from, say, the Pennsylvania line southward, including Maryland, Delaware, Virginia, and West Virginia. As the population and wealth become more sparse toward the south, the next distributing point would logically appear to be Atlanta, to cover North and South Carolina, Georgia, and northern Florida as part of its territory. The southern half of Florida and, possibly, the Bahamas and Cuba, could be serviced by a distributing center located in Miami.

Due to many similarities in terrain, weather, and economics, the lower half of the East South Central region—the states of Alabama and Mississippi—might well be served from the Atlanta distributorship. However, if the region, also including Kentucky and Tennessee, appears to require separate coverage, a distributing point located at Nashville would nearly meet the requirements of having the most remote dealer no more than 350 mi. away from his distributor.

Midwest Sales-Service Centers

While the five states of the East North Central region constitute a much smaller geographic area, it must be remembered that they comprise the nation's second most important marketing region and therefore will require greater concentration of sales and service facilities.

It would appear that the two most obvious spots would be Chicago and/or Detroit. Additional locations (if more coverage proves necessary) which would give a good geographic distribution throughout the territory would include Cleveland, Columbus, and Cincinnati, Ohio, the latter probably overlapping into Kentucky. Indianapolis appears logical for the southern portion of the Hoosier state. Perhaps not all these would be distributor points, at least they would be pertinent for large dealerships.

Moving now into the seven West North Central states—making up the fifth most important region—the northernmost territory would best be served from a distributorship in the Twin Cities, Minneapolis or St. Paul, a point which could cover the eastern portions of both North and South Dakota. Omaha could serve all or most of Nebraska and western Iowa. Although some organizations might choose Des Moines for its central Iowa location, the state could also be served from a unit located in Davenport or in Moline, Ill., both of which are in an almost direct line from Chicago.

Eastern Kansas would naturally come in the market sphere of Kansas City, which could also handle the western part of Missouri. The eastern part of Missouri falls into the sphere of St. Louis, which would overlap into southern Illinois.

Unless the products are in a price range where very complete coverage is essential the state of Arkansas could probably be served from St. Louis or a distribution center located in the West South Central region in either Tulsa or Oklahoma City. If, however, the products are in the bracket suggested, a distributor might logically be established in Little Rock. Note that the suggested location is "either Tulsa or Oklahoma City," both are wide awake aviation cities, hence the choice between them is something each sales manager will have to decide for himself.

In Kansas, by far the leading aviation center is Wichita, home of three major league aircraft builders of which at least two can be counted on as important factors in the personal plane production field. It would be natural to assume that each would represent a distribution point, and it would be up to each individual manufacturer, distributor, or dealer to determine for himself if he wanted to attempt an invasion right in these companies' own "front yard."

This point of "front yard invasion" will come up in several areas, particularly along the East and West Coasts (as shown by the complete list of a aircraft manufacturers given in Aviation's 11th Annual Directory Issue, published last February). It is an important factor, for such matters as delivery price and service facilities must be considered.

In Texas there is again the matter of choosing between two leading aviation cities—Dallas and Fort Worth. And again the selection must be made by each individual distribution head. Although the Dallas-Fort Worth location would cover most of the state, with the 350-mi. radius qualification, the need for more distribution facilities would logically lead to such additional establishment in Houston or San Antonio.

If the 350-mi. network is to be maintained, it will be necessary to establish a distributor at El Paso to cover west Texas and New Mexico. Keeping this chain unbroken would also call for at least one distributor in Arizona, where the logical location would be either Phoenix or Tucson, both of which have long been good flying centers. All three of these locations, it should be remembered are adjacent to or near northern Mexico.

Denver shows up as the number one choice in Colorado, also possibly covering part of Western Kansas and southern Wyoming, while Salt Lake City could serve all of Utah plus portions of Wyoming and Idaho.

If manufacturers intend to see that no part of the country is more than about 350 mi. from a distributor, one or possibly two, should be set up in Montana. One at Billings would serve eastern Montana and Western North Dakota, ranging over to the territory serviced from the Minneapolis-St. Paul area, the other at Great Falls, Missoula, or Butte, would cover the western part of the state, as well as part of Idaho.

Center of the northwest sphere of the Pacific region is Seattle from which the 350-mi. radius would cover all the state of Washington and most of Oregon. However, concentration of distribution facilities might call for setting up a distributor in Portland in which case there would be no "uncovered" territory along the Pacific Coast near the California-Oregon boundary for establishment of a major distribution unit in the San Francisco area would cover not only all of northern California but also part of Nevada. And last but far from least, Los Angeles would be the logical headquarters for distribution throughout the southern California area.

THINGS TO WATCH

- **Factors effecting marketing conditions will very from time to time and location to location, they must be under constant, close study so that full advantage or counteracting measures can be taken of the changes they bring. Prominent among such factors are these:**
- ***Population shifts.*** **The war has brought marked increases to some areas. It has tended to drain others, the figures should be reviewed at frequent intervals to make sure required number of prospects are available within a given territory.**
- ***Regulations.*** **Many states, possibly even counties or cities, may be expected to enact additional legislation effecting flying and, consequently, the aviation product distributor's means of livelihood.**
- ***Taxation trends.*** **Often closely allied with regulatory legislation and a factor which can easily make the difference between black or red ink on the books, taxation trends should be carefully calculated.**
- ***Landing facilities.*** **Progressive states and communities can speed the growth of personal flying by providing necessary landing facilities. Chambers of Commerce and state aviation commissions can give good clues as to progress likely to be made in this respect.**

The Sales Foundation

Here then is a distribution "framework" of some 38 economic-geographic centers giving a choice of some 47 cities within which to establish an individual distribution organization. While there will undoubtedly be variants the measurable data presented indicates that more than one company will have representation in many of the same cities with more than a good chance that all will not only be able to find profitable outlets for their products but also to insure profitable business for their distributors, and the latter, in tuen, can be assured of sound, money-making dealers in the surrounding territory.

The suggested distribution points, it should be remembered have not been presented as the final word, they are the natural result of measurable data compiled and presented to offer the utmost value to both manufacturers and distributors—actual as well as potential—in the hope that aviation merchandising will progress to the point where the 37 distribution areas will quickly become known as merely the early foundation of a much more complete network.

Helping a new star ☆



Set a new record


Lockheed built it and called it the Constellation and it broke the Los Angeles-to-Washington speed record by 3 hours and 24 minutes. It develops more than 8,000 hp., cruising at high, over-weather altitudes, and does it faster than many fast pursuit ships.

Normally, the Constellation can accommodate 57 passengers in its roomy air-conditioned cabin. But right now, it is working for Uncle Sam, accommodating as many as 100 fully-equipped men.

Many compact, friction-free Timken Bearings are giving the Constellation the all-important qualities of lighter weight, smoothness of operation, conservation of power, endurance and economical maintenance — as well as maximum radial and thrust load-carrying capacity. If these indispensable aircraft bearing features can help meet your requirements, why not write us. We'll be glad to make recommendations. The Timken Roller Bearing Company, Canton 6, Ohio.

TIMKEN

TAPERED ROLLER BEARINGS



DESIGN ANALYSIS NO. 7

The North American P-51 "Mustang"

By **WILLIAM R. NELSON**, *West Coast Editor, "Aviation*

AVIATION'S graphic and thoroughly detailed engineering dissection of NAA's great fighter—initially completed less than four months after design inception, then fourfoldly hailed for low-altitude cooperation, dive-bombing versatility, high-altitude fighting speed, and long-range prowess.


Prior to World War II it was generally agreed among aeronautical engineers and military aviation authorities that it was impracticable, if not impossible, to design an airplane capable of accomplishing more than one type of military operation.

The record of North American's P-51 *Mustang* fighter proves, however, that it is both possible and practical to create a single basic design that can be modified, as military needs dictate, to keep abreast of requirements. Among single-seat, single engine fighters, the *Mustang* has been credited as the best low-altitude cooperational craft, the most versatile dive bomber, the fastest high-altitude fighter, and the plane with the greatest range.

All this has been achieved by a plane whose basic design and most of its original specifications remained unchanged. New models incorporated equipment and design refinements but retained the desirable advantages of preceding versions.

The original *Mustang*, designed and built for the British in less than 120 days, was intended for low and medium altitude work. It was a low-wing all-metal monoplane powered by a 12-cyl., V-type Allison engine of 1,150 hp., and it was credited with close to 400 mph speed. RAF pilots said it was highly maneuverable, had no "cranky" characteristics, and, for those early war days, it was heavily armed, with 50-cal. guns, one on each side of the engine, and one .50 and two 30-cal. guns in each wing. A gun camera was mounted in the left wing.

In its P-51 version for the USAAF, the *Mustang*—retaining its high maneuverability with somewhat increased speed—quickly acquired fame as a "train buster" by virtue of its two 20-mm. cannon in each wing. Stripped




Tabulated weights of principal assemblies.

of guns and with a K-24 camera it became a widely used scouting and reconnaissance plane.

The invasion of Sicily was highlighted by reports of a phenomenal, new "secret" fighter-dive bomber. This craft—which combat men quickly dubbed the *Invader*—was the A-36 version of the *Mustang*. Retaining the characteristics of its fighter and level-bomber forebears, the A-36 was equipped with dive brakes, two 500-lb. bombs, and six .50-cal machine guns.

Next revision retained the basic design and uses of previous models, but increased the speed with a 1,465-hp Allison engine with single-stage, single-speed supercharger. Auxiliary fuel tanks gave considerably greater range. Carried were wing bomb racks and four .50-cal guns, two in each wing, maintaining striking effectiveness against ground targets.


Another revision introduced the 1,500-hp Packard-built, Rolls-Royce *Merlin* engine with two-speed two-stage supercharger. Also added were removable bomb racks, depth charges, chemical tanks, and auxiliary fuel tanks. Armament was four .50 cal guns. Speed and ceiling both went up, whereupon the *Mustang* was officially credited with the highest ceiling ("over 40,000 ft.") and the greatest speed ("over 425 mph") of any fighter in existence. Soon the *Mustang* was accompanying our heavy bombers on their longest missions, since it possessed the longest range of any single-engine fighter in the war.



Packard built Rolls-Royce "Merlin" 1,500 hp engine used in "Mustang".


These achievements are, from an engineering standpoint, remarkable—because they were accomplished by a plane that does not to any extent embody previously unknown engineering features, but rather employed refinements of known accepted practices.

Such performance is attained by close attention to aerodynamic cleanness of design, employing an efficient, low-drag, laminar-flow airfoil, a modification of an NACA design. Second-



Exploded view of "Mustang", with nomenclature.

1 Radiator forward air scoop
2 Radiator forward air duct
3 Coolant radiator assembly
4 Oil radiator cover
5 Oil radiator
6 Oil cooler air inlet door
7 Spinner Assembly
8 Engine mount front frame assembly
9 Engine mount assembly
10 Engine top cowling RH
11 Engine top cowling LH
12 Wing nose assembly
13 Wing panel RH
14 Wing tip RH
15 Aileron RH
16 Aileron trim tab
17 Windshield
18 Cockpit exit hatch
19 Cockpit exit hatch panel LH
20 Cockpit exit hatch panel RH
21 Radio access window RH
22 Radio access window LH
23 Oxygen access door
24 Oxygen rear door
25 Fillet
26 Fillet
27 Fillet
28 Elevator
29 Elevator trim tab
30 Vertical stabilizer
31 Vertical stabilizer tip
32 Rudder trim tab
33 Rudder
34 Elevator trim tab
35 Elevator
36 Horizontal stabilizer
37 Fillet
38 Tail wheel unit assembly
39 Tail wheel door LH
40 Tail wheel door RH
41 Radiator aft air scoop
42 Cover
43 Fuselage forward section
44 Coolant radiator access cover
45 Wing flap
46 Wing center rib
47 Wing to fuselage fillet
48 Wing to fuselage fillet
49 Gun bay door
50 Ammunition bay door
51 Bomb rack
52 Aileron trim tab LH
53 Aileron LH
54 Wing tip LH
55 Wing panel LH
56 Landing light
57 Landing light cover
58 Landing gear fairing
59 27" smooth contour wheel
60 Main landing gear shock strut
61 Wing to fuselage fairing
62 Wing nose assembly
63 Main landing gear access cover
64 Intermediate rear engine cowling
65 Wing center bulkhead
66 Exhaust stack fairing
67 Firewall assembly
68 Main gear fairing door
69 Fuel tank door
70 Fuel tank
71 Engine lower aft cowling
72 Engine lower intermediate cowling
73 Engine lower forward cowling
74 Engine intermediate cowling LH
75 Engine intermediate cowling RH



Three view drawing of P-51 Mustang with leading dimensions

Dimensions and Loading Particulars

GENERAL

Span	37.03 ft
Length (over all)	32 ft 2⅜ in
Length (tail wheel on ground)	30 ft 8 in
Height (tail wheel on ground, propeller blade vertical at top)	12 ft 6 in

WINGS

Airfoil section	NAA NAA low [illegible]
Chord at root	8 ft 8 in
Chord near tip (215 in. from fuselage centerline)	4 ft 2 in
Incidence (variable)	Approx. 1 deg
Sweepback	3 deg 35 min 32 sec
Dihedral (at 25% line)	5 deg

STABILIZER

Span	13 ft 2⅛ in
Maximum chord	2 ft. 6 in
Incidence	2 deg
Dihedral	(none)

FUSELAGE

Width (max.)	2 ft 11 in
Height (max.)	6 ft 7 1/16 in
Length (without engine mount, front oil heat exchanger to tip of tail	24 ft 2⅜ in
Length (with engine mount tip of propeller shaft to tip of tail)	30 ft. 9 11

AREAS

Wings (less ailerons)	220.55 sq. ft
Ailerons (total)	12.64 sq. ft
Flaps (total)	32.6 sq. ft
Stabilizer (including elevators)	27.85 sq. ft
Elevators (including tabs)	13.05 sq. ft
Elevator Trim Tabs (total)	2.00 sq. ft
Vertical Stabilizer	8.84 sq. ft.
Rudder (including tabs)	10.25 sq. ft
Rudder trim tabs (total)	82 sq. in.

SETTINGS & RANGE OF MOVEMENT OF CONTROL SURFACES

Stabilizer fixed	2 deg	
Vertical stabilizer fixed offset (from fuselage centerline)	1 deg	
	Deg	In at Max. Chord
Ailerons wing Up travel (from neutral)	10 deg 12 deg. or 15 deg	2.2=2.7 3.3
Down travel (from neutral)	10 deg 12 deg or 15 deg	2.2=2.7 3.3
Elevators Up travel	30 deg	8.63
Down travel	20 deg	5.9
Rudder Right	30 deg	13.5
Left	30 deg	13.5
Flaps	50 deg	20.5
Trim tabs		
Elevator Up	10 deg	
Down	25 deg	
Rudder, Right	10 deg	
Left	10 deg	
Aileron, Up	10 deg.	
Down	10 deg	
Tolerance on control surfaces Movements	Approx. ± ½ deg	

LANDING GEAR

Type	Hydraul. retract. oleo ventional 3 wheel
Tread	11 ft. 10 in
Shock struts	Air-Oil Combination
Wheels (magnesium alloy construction) dia	27 in
Tires (all weather tread)	27 in
Brakes	Disk hydraulic
Oleo travel	8 in

TAIL GEAR

Type	Hydraul., retract. steerable
Shock strut	Air-oil combination
Wheel dia.	12.5 x 4.5 in
Tire (channel tread)	12.5 x 4.5 in
Oleo travel	7.50 in.


ENGINE

Type	Packard built Rolls-Royce
Designation	V-1650-3
Number of cylinders	12
Gear ratio	21 44
Coolant (70% water and 30% ethylene glycol by volume)	Type D-Spec AN-E-2

PROPELLER

Type	Hamilton Standard Hydromatic
Dia	11 ft. 2 in
Blades	4 paddle type
Pitch setting (hydraulic controlled) Low	24 deg
High	65 deg


1 ENGINE SECTION
2 COCKPIT ENCLOSURE
3 RADIATOR AIR SCOOP
4 MAIN FUSELAGE SECTION
5 REAR FUSELAGE SECTION




Five main sections of P-51




Exploded drawing of engine cowling and framework



Engine controls (1) Engine throttle control; (2) throttle stop release, (3) throttle name plate, (4) adjustable throttle stop, (5) quadrant to bellcrank flexible control; (6),-(11), (12), (15), (16) (25) fairleads, (7) flexible control; (8) propeller control bracket; (9) propeller control bellcrank; (10) emergency boost control handle, (13), (14), (17), & (18) control rods to jackshaft; (19) carburetor air control, (20) flexible air control, (21) air control support (22) jackshaft, hot air control, (23) hot air door actuating rod, (24) air shut-off control rod and (25) shut-off rod support.



Exhaust system and vent lines. (1) Exhaust shroud to keep heat from sparkplugs (2) gasket, with lockplate (3) and nut (4) which hold jet exhaust stacks (5) in place in fairing (6), (7) drain from mixture boost (8) (9) (10) & (11) blast tubes for cooling sparkplugs situated on exhaust side of cylinders and (12) & (13) parts forming generator blast system for cooling purposes.



Main air scoop, situated beneath fuselage, is fitted with adjustable discharge flaps or scoops to regulate airflow through both oil and engine coolers.

degree curves, calculated as mathematical expressions, are employed for external lines of fuselage, fillets, ducting, and air scoop.

The air scoop is located below and just aft of the center of fuselage, where it was found by wind tunnel tests to create less drag, while operating efficiently. Both oil and coolant radiators are contained in the air scoop.

An identifying feature of the *Mustang* is the square wing and tail surface tips, which tended to prevent stalling and to maintain excellent aileron control.


The fuselage, of semi-monocoque construction, is divided into three main sections. Engine mount, main, and rear section, all joined with bolts. With exception of cockpit armor fore and aft, fuselage is entirely Alclad and aluminum alloy extrusions.

Engine mount is a box beam of Alclad sheet and extruded parts, designed so that the engine can be removed as a unit. Mount is attached at the firewall with four bolts.


Main fuselage section is constructed around four 24ST extruded longerons, intermediate frames, Alclad covering, and stringers. Stainless steel sheet and armor plate firewall form forward bulkhead. A turnover truss of 24ST extrusions and formed sheet protect the pilot. Upper longerons are extruded H-sections which extend aft from firewall, tapering to T section and terminating near rear section. Lower longeron, H-beam and U-channel, extends full length of section.

Eight riveted and bolted assemblies which comprise main fuselage section may be removed and replaced as units. They are: Firewall, turn-over truss, upper deck, left and right side panel subassemblies, radio shelf, web assembly, and lower section with air scoop.

Comfort and safety are given consideration in the design of the cockpit seat, which accommodates the seat-type parachute and has a kapok back-cushion life preserver, provisions for heating and cooling, and protecting armor plate at the firewall and seat.





Fuel system. (1) Fuel strainer, (2) Parker primer pump, (3) engine driven fuel pump; (4) selector valve with handle; (5) booster pumps on tanks, (6) fuel gages. Outer streamlined tanks, used for ferrying or long distance flights, are droppable via the bomb release. Primer, operated manually, draws fuel from strainer and injects it directly into engine.





Engine mount. Detail A is Lord shear rubber bushing; B, front Lord mounts; C, carburetor air inlet casting.

Engine coolant system. Here (1) is coolant header tank vented at 2 which connects through pipe 3 to radiator 4 returning liquid by pipe 5 to pump 6. Supercharger center is supplied by 7 and 8. System is filled at plug 9











Air ram scoop for carburetor. By operating shutter at left and blast gate at right, pilot can regulate both temperature and pressure of air going into carburetor. Detail (upper left) shows construction of vibration-absorbing connection to base of carburetor



Oil system showing hopper tank at center with dilution solenoid above and radiator at rear. Oil leaves engine by upper of two pipes (lower left), going directly to radiator, thence to top of tank through hopper in tank and back to engine oil pump through large pipe from bottom of tank. Small pipe leading into delivery pipe at lower left is for oil dilution



Wing panel is built up on 19 pressed ribs and two spars of 24ST Alclad. Insert shows proportion of wing surface taken up by flap and aileron. Wing tip has single spar and pressed end. Details are fore-


ings. Detail A is front spar-to-fuselage connecting bracket, B is pilot's foot rest and seat bracket and C is rear spar-to-fuselage connecting bracket. Others are aileron and flap hinge brackets.

The combination armor-plate firewall protects the pilot both against projectiles from line of level flight to approximately 20 deg. below it, also against fire from engine. Firewall is face-hardened steel armor, except a section at center of stainless steel to provide room for oil tank. Aft protection is provided by two plates of face-hardened steel behind the seat.

Protection and visibility are afforded by windshield, rear window, and cockpit enclosure. Forward flat section of windshield is bullet-proof, 5-ply laminated glass, 1½ in. thick, slanted 31 deg. from vertical, being the best compromise for visibility, protection, and aerodynamic contouring. Side and upper panels of windshield are of ¼-in. safety plate and transparent plastic. Windshield cowling extends from lower forward end of glass to firewall and down to upper longeron.

Over instrument panel a shroud, integral with windshield, extends aft with a circular rubber extrusion to protect pilot. This shroud supports windshield defroster, optical gun sight, and handholds, and it also eliminates instrument glare in windshield glass.

Flaps are made of 24ST with Alclad skin. Stiffness is provided by 15 main ribs and 13 nose ribs.



Cockpit enclosure consists of upper and side plastic panels, each in two sections, forward one forming a sliding window with locking handle. Right upper panel hinges upward; left panel hinges downward against fuselage. Both have locks controlled from inside and outside. Hood is attached by four hinges on upper longerons. An emergency release permits enclosure to be removed or jettisoned in emergency.

Aft windows of molded Lucite fit fuselage contour and are removable for access to radio behind pilot. Aft of radio, plywood bulkhead prevents draft and keeps objects from rolling aft and fouling controls. Nut plates at center of bulkhead secure oxygen bottles.

The rear fuselage section consists of two 24ST longerons, a shelf and five formers of 24ST, three solid bulkheads, and Alclad skin.


Wing is cantilever stressed-skin design in two sections, bolted at center. Each consists of main panel, removable tip, aileron, and full trailing edge flap. Wing has angle of incidence of approximately 1 deg. at root and dihedral of 5 deg. along 25 percent chord line, to give stability.

The 25 percent chord line is perpendicular to longitudinal axis of airplane. Wing area, including ailerons, is 233.19 sq. ft., with span of 36 ft. ⅞ in. and a taper ratio of .499.


Main wing panel consists of a main spar, rear spar, pressed ribs, and extruded stringers covered with alloy sheet. Space is provided at inboard end for self-sealing fuel cell, part of which is located in fuselage. A gun bay is in each wing panel to accommodate guns, ammunition containers, and chutes. Main landing gear retracts into wheel bay in the inboard leading edge.

Main structural member of wing is forward or main spar, of two sections of 24ST sheet spliced together. Inboard spar section is fabricated of .129-in. thick 24ST, with angle flanges along both upper and lower edges for spar caps. A .25-in. thick 24ST bar is riveted to inner side of upper cap between stations 0 and 85.5.

Rear spar is formed of two sheets of 24ST spliced at station 128.6. Upper cap is reinforced by a .091 24SO angle.



Ailerons are built of 24ST with plastic tab. A metal diaphragm retains aerodynamic smoothness at joint with wing.



Main fuselage with firewall, front and rear wing attachment fittings, and air scoop underneath. Details A and B are forged fittings through which pass bolts holding engine mount and firewall. Fuselage wing fittings are forgings carrying bolts for attachment of wings

between stations 0 and 92.5. Ribs and formers are approximately 12.5 in. apart and are of 24SO, heat-treated after forming to 24ST. At leading edge, wing has sweepback of 3 deg., 35 min., 32 sec. Aspect ratio is 5.815.

Each aileron has two spars and twelve flanged ribs covered with 24ST Alclad, and ribs are 24SO heat-treated to 24 ST. The forward spar is U-shaped 24ST to 24 ST. Trailing edge is 24ST sheet reinforced with aluminum supports and plastic ribs. Three aileron hinge brackets bolted to the forward spar provide bearing attachment points.

Ailerons are dynamically and statically balanced. Internal aerodynamic balance is obtained by a diaphragm attached to forward edge of aileron and sealed to the rear spar by fabric strip.


Phenol-fiber trim tabs are mounted in each aileron by three hinge bearings. A metal horn tab provides attachment for actuating rod. Left tab, adjustable in flight, is operated by knob on control pedestal. Angular travel, 10 deg. up and 10 deg. down, is limited by stops on cables.

Ailerons are conventionally controlled by the stick, and to meet variations in specifications they can be connected for angular travel of 10, 12, or 15 deg.

Structure of the 24ST Alclad-covered wing flaps is two Alclad spars, 13 nose ribs of 24SO heat-treated after forming to 24ST, 15 main ribs, and a series of rolled-section stringers, all of 24 ST. The flap trailing edge is formed from a single 24ST sheet reinforced with 27 tapered hat-section supports. The flaps are hinged on three sealed ball bearings, and are hydraulically controlled by a lever on the control pedestal. Position of lever selects and holds any corresponding position of the flaps.

Stabilizer is full cantilever, non-adjustable, with detachable tips, and is fixed at a positive 2-deg. angle of incidence relative to the longitudinal axis of the airplane. Forward and aft spars are of 24ST Alclad. Flanged ribs are formed of 24 SO Alclad heat-treated to 24ST, as are six extruded stringers. Dual stringers are on the lower covering. Stabilizer tips are of 52S, ½H stock on two ribs. Area is approximately 28 sq. ft., and span is 13 ft. 2½ in.

Main fuselage is built on four extruded 24ST longerons with heavy frames and a few light stringers. Turnover truss is built of 24ST extrusions and sheet for pilot protection. Web assembly is shown at bottom



Elevator incorporates 18 flanged ribs, front spar, trailing edge, and a short intercostal beam, all 24ST Alclad. Covering is fabric with Alclad leading edge extending to main spar, except for that portion cut out for elevator hinge fitting. Right and left elevators are interchangeable, fastened to stabilizer with five sealed ball bearing hinges, and are statically and dynamically balanced. Static balance is by a 13½-lb. lead weight attached to outboard end of leading edge. Total elevator area is approximately 13 sq. ft., and angular movement by the control stick is 30 deg. up and 20 deg. down. Each elevator has an adjustable trim tab approximately 4¾ in. by 32¼ in.

Fin is composed of front and rear spars of 24ST Alclad and ribs covered with 24ST Alclad sheet. Tip is on two ribs, and skin is stiffened spanwise by light rolled stringers. Area of fin is 9.61 sq. ft., and it is set 1 deg. to the left of center line of rear beam.


Rudder consists of spar, 20 flanged Alclad ribs, V trailing edge, and a short beam in front of trim tab which is covered with fabric, and 24ST sheet covers leading edge back to main spar, except cut-out for rudder hinge fitting. The rudder is hinged to fin with three sealed ball bearings and is dynamically balanced by means of 16.6-lb. lead at top. An additional balance weight at bottom of leading edge reduces static unbalance. Area is 10.4 sq. ft., and angular movement is 30 deg. each side of neutral. Operation is by pedals through cables.

Phenol-fiber trim tabs on elevators and rudder are hinged by three sealed needle bearings. Rudder tab is controllable from cockpit, and angular travel is 10 deg. each side of center. Elevator tabs, operated by a control wheel on left of cockpit, have angular travel 10 deg. up and 25 deg. down, limited by stops on cable.


Landing gear is three-point, with two 27-in. main wheels and full-swiveling, steerable 12.5 in. tail wheel, hydraulically retractable. Main wheels retract into wing wells and tail wheel into fuselage, all fully enclosed.


Except for hydraulic main gear down-lock pin, landing gear locks are actuated from the control handle bellcrank. Cables from bellcrank actuate tail gear up-latch and down-lock pin. A push-pull rod from the lower end of the control handle works lock system in main wheel bay.

Main landing gear magnesium support casting is bolted to front spar at the outboard end of the wheel well. Hydraulic struts on the front spar re-



Cockpit inclosure with floating back cushion and armored seat back. Heavily framed center glass (top left) is bullet proof.





Fuselage rear frame with diagram giving positions of elevator and rudder control frames and fin attachment forging.

tract the gear inboard. A spring-loaded, hydraulically controlled pin locks main gear down.


Tail gear is mounted on a magnesium casting bolted to lower longerons. Shock strut assembly includes cylinder, piston, torque tube, and post housing which supports axle. Gear is steered by cables from rudder bellcrank. Fairing doors are hinged at side, and a link pulls them up as gear is retracted. Tail wheel is unlocked with stick in the forward position during taxiing and parking.


Emergency lowering of landing gear is accomplished by pushing down control handle at left of seat, also relieving hydraulic pressure in retracting struts with emergency knob in cockpit, which causes gear to drop of its own weight. Pilot then yaws plane until gears engage downlocks.

Cylinder, connected to brake by aluminum alloy tubing, furnishes pressure for the Goodyear multiple disk brake, via separate hydraulic system controlled by pedals. This pressure is relieved by a spring when pedal is released. Parking brake is controlled by depressing brake pedals and pulling knob below instrument panel. Pressure is retained until released by depressing both brake pedals.


Latest model of P-51 is powered by a 12-cyl. Packard-built Rolls-Royce 1,500 hp V-1650 liquid-cooled engine having an after-cooler to reduce charge temperature.

Induction system employs a two-speed, two-stage supercharger with low-gear ratio of 6.391:1 and high-gear ratio of 8.095:1. Pilot may select cold rammed air, cold, unrammed filtered air or unrammed hot air, as necessary. The Bendix-Stromberg double-throat-







Left: Rudder is fabric-covered 24ST leading edge under fabric. Plastic tab is carried on three hinges. Rudder-operating horn is a forging (shown at bottom of rudder, both views). Right: Two views of fin. This is built of 24ST with rolled stringers and is covered with Alclad sheet.



Elevator is built of 24ST frame with fabric covering. Leading edge is 24ST under fabric. Trim tab, made of plywood, is operated by horn near center. Balance weights are concealed in stabilizer. Elevator control is through 3-bolt coupling at inside end.




Stabilizer is full cantilever type with Alclad frame and covering. Hall hard 52S is used for the tips built on two ribs.




P-51 Cockpit Layout

1 Cockpit fluorescent light
2 Crash pad
3 Fluorescent light
4 Gun sight
5 Throttle
6 Compass
7 Clock
8 Suction gage
9 Manifold pressure gage
10 Remote contactor
11 Altimeter
12 Directional gyro
13 Flight indicator
14 Tachometer
15 Oxygen flow blinker
16 Mixture control
17 Propeller control
18 Coast control
19 Landing gear indicator
20 Airspeed indicator
21 Rate-of turn indicator
22 Rate-of climb indicator
23 Coolant temperature indicator
24 Oil temperature and fuel and oil gage
25 Oxygen regulator
26 Enclosure for emergency release handle
27 Engine instruction plate
28 Control stick grip
29 Gun and bomb control panel
30 Parking brake control handle
31 Parking brake instructions plate
32 Engine primer
33 Oxygen pressure gage
34 Oxygen system warning lamp
35 Bomb control handle
36 Landing gear controls
37 Booster pump switches
38 Supercharger control
39 Supercharger warning light
40 Starter switch
41 Oil dilution switch



42 Ignition switch
43 Compass light control
44 Gun sight light control
45 Left hand fluorescent light control
46 Fuel valve control
47 Hydraulic pressure gage
48 Emergency furing door control
48 Hydraulic hand pump
50 Airplane restriction plate (top)
51 Cockpit enclosure handle
52 Generator disconnect switch
53 Battery-disconnect switch
54 Pitot heater switch
55 Landing light switch
56 Position light switches
57 Ammeter
58 RH fluorescent light control
59 Circuit breaker buttons
60 SCR 522 radio control box
61 Cockpit light
62 SCR 535 radio control box
63 Map case
64 (Restricted)
65 Right fuel tank gage
66 Hot air control
67 Pilot's relief tube
68 Sliding window lock handle (below)
69 Carburetor mixture control
70 Signal pistol discharge tube
71 Coolant radiator scoop control
72 Oil radiator scoop control
73 Quadrant friction control
74 Flap control handle
75 Carburetor air control
76 Rudder trim tab control
77 Aileron trim tab control
78 Elevator trim tab control
79 Bomb control anti-salvo guard
80 Left fuel tank gage
81 Defroster control




Rudder controls with rear wheel steering mechanism at A and wheel lock at B. C is heavy rear bracket for carrying rear steering stresses.

ed, injection type, updraft carburetor is fitted with a double-diaphragm acceleration pump, automatic mixture control, fuel pressure regulator, fuel control unit, and throttle.

Automatic manifold pressure regulator limits maximum boost when below full throttle and maintains predetermined pressure for any given position of throttle lever.

Ignition is provided by two magnetos of the rotating magnet type, the right hand one being connected to booster coil which supplies high tension current when starting.

Engine mount consists of two V-shaped 24ST box beams stiffened by built-up cross members of 24ST Alclad. Forward frame incorporates leading



Guns and armor. (1) & (2) Ring sights, (3) & (5) ammunition boxes; (4) machine guns, (6) & (7) ammunition chutes, (8), (9), (11) & (13) armor plate, (10) bullet-proof windshield; (12) optical gun sight; (14) detachable Plexiglas side panels.


edge, and front duct section of carburetor air scoop and aft frame attaches to the two beams near the center. Engine is supported on rubber mountings between side beams. Mount is attached to firewall by four bolts.

Cowling, providing maximum accessibility to both engine and accessories, consists of 24ST Alclad formers and seven removable panels.

With adoption of Rolls-Royce engine, the *Mustang* was equipped with 11 ft 2 in. four-blade Hamilton Standard Hydromatic propeller, controlled by a governor which maintains selected propeller speed. Spinner is a streamlined spun-shell of aluminum alloy.

Fuel is supplied from self-sealing cells, one in each wing, and from auxiliary tanks when fitted. Fuel flows from tanks through a submerged booster pump to dual check valve, then through selector valve and strainer to engine-driven fuel pump and carburetor. When auxiliary tanks are used, fuel passes through the selector valve to main fuel line. The booster pumps which boost fuel to engine pump at high altitudes operate as emergency pumps in event of engine-pump failure. Only one booster pump is operated at a time.

Fuel strainer and hand-operated engine priming pump are provided, and entire system is suitable for aromatic fuels. Droppable ferrying or combat



Fuselage electrical installation, showing control above oil scoop for automatic regulation of oil and coolant temperatures, storage batteries, navigation light (upper right) and (detail A) methods of making connections.

tanks may be installed on bomb racks when bombs are not being carried, fuel being withdrawn by engine-driven pump. Pressure is supplied to ferrying tanks by connecting them to vacuum pump exhaust.

Oil flows from bottom of 12.3-gal oil tank (forward of firewall) to oil pump which delivers through Cuno filter to moving parts of engine. Scavenger pump in sump delivers it to oil tank, either directly through a thermostatic control valve, having a by-pass, or to radiator and then back to tank, depending upon oil temperature.


Self-thawing oil radiator is forward of coolant radiator inside scoop. Airflow through scoop is regulated by outlet flap, thermostatically controlled. Flap can be controlled from the cockpit for emergency operation, and a surge valve, integral with thermostatic valve, permits cold oil at excessive pressure to by-pass radiator completely and return to tank.

Three systems—engine oil, engine coolant, and aftercooler—cool the *Mustang's* Rolls-Royce engine.

Engine cooling system utilizes a centrifugal pump which delivers cool-



Left landing wheel of 'Mustang'. (1) Shock strut; (2) fairing; (3) wheel with dust cap, and (4) 27-in. tire.



Control stick. Center connection operates elevators while rocker with forked ends moves ailerons.

high speed, jet action from the heated air compensates to a large degree for internal air drag. Flame dampening exhaust stacks on either side contribute to speed by exerting a jet-propulsion effect of approximately 200 hp.

The *Mustang's* electrical system is 24-v d.c., single wire, grounded type; most of the wiring open, supported by clips. Engine wiring, because of possible radio interference and vibrational stress, is shielded and supported by conduit.


Current is supplied by a 34 amp.-hr. battery, aft of seat, charged by engine-driven generator. Connection with electrical system is through solenoid switch. A 100-amp high speed generator supplies current through a relay, which serves as generator cutout. A voltage regulator maintains potential at 28.

Radio equipment consists of sets for communication with other aircraft or ground. Antenna is a fore-and-aft.


ant into jacket on lower exhaust side of each cylinder block, whence it passes to cylinder head through transfer tubes and out through manifolds on intake side of head, discharging into header on front of engine, from which it flows through radiator.

Secondary after-cooling system which reduces temperature of supercharged fuel-air mixture, consists of expansion tank, heat exchanger and coolant pump. Coolant flows from expansion tank to pump, through radiator and supercharger case, and through a jacket between supercharger impellers, cooling air before it passes into second stage impeller chamber. Coolant then passes into heat exchanger and cools air from the second stage before returning to expansion tank.

Scoop with thermostatic exit flaps provides air for oil, engine, and after-coolant radiators and is located beneath fuselage aft of cockpit, where it causes less drag than if farther forward. At



Elevator and elevator tab controls are by cable from cockpit. Tab rear controls are detailed at A. Cable to tabs is operated by handwheel, to which is connected an indicator driven by small gears, as shown in detail B.



Aileron and trim tab controls. Detail A shows operating mechanism of left hand tab, controlled from cockpit by turning knob. Travel of cables is restricted by stops and adjustments are made by means of turnbuckles. B is detail of right aileron tab adjustment, set on ground and shows method of attaching and actuating aileron cables by link from stick attachment.

vertical mast type. Receivers and transmitters are aft of seat.

Gunnery equipment consists of four fixed 50-cal. guns in pairs in wings, in canted position, rotated 60 deg. to prevent protuberances. They are adjusted to converge fire with center line of airplane at 300 yd. Lateral adjustment of ½ deg. is provided on either side, and guns are quickly removable through doors in upper wing surface. Ammunition is fed to top sides of guns through stainless steel chutes. Cases and links are ejected through metal chutes in lower wing skin. All four guns fire simultaneously, control being by switch on control stick. Sighting is through optical gun sight or auxiliary ring-and-bead sight. Electric heaters are attached to each gun, permitting them to function at temperatures as low as —70 deg.

A removable streamlined bomb rack is provided on each outer wing panel for bombs up to 500 lb., depth charges, chemical, or auxiliary fuel tanks. Fusing of bombs is electrically controlled from cockpit, and bombs can be dropped in a dive, level flight or 30 deg. climb. Sway braces are integral with racks.

FAN COOLING "UPS" ENGINE PERFORMANCE*

PART I

By **KENNETH CAMPBELL**, *Senior Project Engineer, Wright Aeronautical Corp.*

A pointed and thorough discussion of theory and experimentation leading to noteworthy savings in brake horsepower through employment of fan devices to force cooling air past the engine in high-altitude flight.




Fig. 1. Diagram of cooling airflow mechanism with no fan

COOLING FANS comprise only one component of performance improvement through cooling development. Table I shows the place that cooling fans occupy in cooling improvement opportunities. But, unlike the other components of Table I, they offer much greater and more immediate returns than any of the others. Worth-while improvements in rate of climb, top speed at high altitude, ceiling, useful load, or cruising economy, are to be had from fan application.

Objective I (Table I) is strictly an engine-development matter. Much research has been done on methods "a" and "b" in the past ten years, but important gains are forthcoming from current work. Particularly beneficial is the redesign of fins to recognize the rise of air temperature along the path. It has been asked: why not reduce volume instead of baffle pressure drop. Reducing volume requires disproportionately increased baffle pressure drop or, with fins redesigned to avoid this, it causes severe temperature rise in cooling passages defeating the objective of cooling the hotter rear portion of cylinder.

Regarding method "c," an increase of 50 deg. F. in allowable head temperature reduces baffle pressure drop required almost one half for given cylinder and baffle design. The designer is aware of this from a drag cost standpoint; the engine (if we may personify it) does not always agree when asked to endure satisfactorily 150 type-test hours. If the pilot wishes to raise temperature limits for combat periods he may—and, we know, he does and comes home.

As for method "d," fuel injection into the cylinders appears to offer the best solution. Uniform mixture strength distribution on carburetor engines is most difficult due to the air-stream's making a 70 deg. to 90 deg. bend approaching the supercharger impeller entrance. The greater the aerodynamic perfection achieved in this passage the greater is the deviation of the fuel streams from uniformity.

Objective II (Table I) has been promoted most from extensive fundamental analysis long since completed and published by the NACA. In spite of this, the number of installations which place a high premium on method "a" are markedly few. These losses are usually tolerated in the interest of space saving or center-of-gravity compromises costing (under marginal cooling regimes with large engines) several hundred thrust horsepower per nacelle, if this can be called a "compromise." As will be seen shortly, the subject happens to be intimately bound up with cooling fans.

Energizing the cooling airstream from within (method "b") gives performance gains due to cooling drag reduction which are startling to the unmitated, bringing increase in performance in nearly all useful regimes. This can include cruising, according to flight test data on one of our recent applications.

A straightforward and simple principle




Fig. 2. Approximation of pump efficiency for cooling fan evaluation.

* Paper presented at National Aeronautic Meeting SAE, Apr. 5, 1944

TABLE I—Development Opportunity for Reducing Thrust Horsepower Consumed in Air Cooling of Engines

(Exclusive of Internal Contents)

Objective I

To reduce the baffle pressure differential across engine by—

a. Better heat transfer design of internal cylinder structure, fins, and baffles, particularly in region of highest temperatures or stresses.

b. Reducing restrictions to external air flow across engine in series with fin passages.

c. Developing metallurgical, structural, and combustion chamber design to permit generally higher head temperatures.

d. Improving uniformity of mixture strength and charge distribution among cylinders, reducing somewhat hottest temperatures.

Objective II

Given a required pressure differential across engine to reduce large additional losses in rest of system used to obtain it by—

a. Reducing pressure drops entering and leaving cowl or duct system and approaching and leaving engine.

b. Adding energy to cooling airstream within system, discharging it rearwardly more nearly at flight velocity, either by a cooling fan (as here outlined) or by exhause stack ejector action.




Fig. 3. Diagram of cooling airflow mechanism with fan

of vital importance to airplane performance has been confused for years with all its many influencing variables and mathematical meetics. Rigorous and elegant expositions have perhaps left some responsible designers unappreciative of the real performance dividends to be gained by applying this simple principle to engine installations. This we believe, has been the cause of many serious deficiencies in performance from the expected, even on recent important designs (meantime, our apologies to those steeped in the subject to whom the above remarks do not apply).

The analysis which follows is open to criticism from the meticulous on many counts, but its purpose is simplicity—to promote important performance improvement which can still be had for the asking.

The simplest and best physical conception of the cost of cooling air flow is the over all measure of thp consumed. The free air at zero absolute velocity is first picked up by the advancing entrance opening and is accelerated to absolute flight speed in front of the engine. Then, after using a little or a lot of the pressure energy thus created to overcome the several required pressure drops built into the cowling passages including the engine proper, the remainder of the pressure is used to accelerate—a lot or a little, respectively—the air out in a rearward direction.

But since the relative exit velocity from the system ordinarily does not equal the speed of flight (because it is generated by a pressure less than the initial flight dynamic pressure q), the exhausted air still retains a forward component of absolute velocity after it is discharged (forget the heat effect for the present). This exit velocity deficiency, or forward component of absolute velocity, times the mass flow per second is an mV value, or thrust. That is, the airplane has been subjected to a net rearward thrust, or drag, in order to put forward velocity energy into the discharged cooling air which originally was at zero velocity.

This thrust, acting on the plane at flight velocity, results in a certain thp consumption, all chargeable to cooling. It is always greater—much of the time is several times greater—than the power required merely to force the cooling air through the engine baffle passages. It can in several ways be reduced.

Referring to the nomenclature of Fig.




Fig. 4. Contribution of cooling fan to rate of climb





Fig. 5. Cooling fan on Focke-Wulf 190

Fig 6. Propeller-speed fan of 1936



1 (which diagrams the situation just discussed, the velocities being in ft/sec.) this is represented by the following expression

$$\text{Cooling thp} = (V_3 - V_0)\, m\, V_0/550 \quad (1)$$

Let us next examine the thp. losses within the cowling itself. In Fig. 1, Δp is the baffle pressure drop across the engine (in psf.) required for the cooling for the atmospheric and engine conditions prevailing. This Δp value across a given engine model in turn meters a definite volume Q in cu.ft./sec. determined in the engine manufacturer's laboratory and corrected for density. The power required to force the air through the engine is then

$$\text{Engine cooling thp} = Q\,\Delta p/550$$

Per our Objective 1 (Table 1) considerations, the engine manufacturer is devoted to reducing the Δp required and thereby the component of cooling thp. for the engine passages alone. But this opportunity for improvement is only the beginning. It is ΔP, not Δp, which determines the internal thp. consumed, that is, the drop in total pressure, ΔP, or $(q - P_4)$ in Fig. 1, across the entire internal cooling system. Thus the engine Δp must be divided by the first of our efficiency factors, "duct efficiency" η_d, to convert baffle drop which the engine manufacturer finds necessary to the drop which the airplane manufacturer must provide by virtue of his own propeller shank losses, ducting restrictions, and other turbulence losses. The total thrust horsepower devoted to internal cooling then becomes

$$\text{Internal cooling thp} = Q\,\Delta p/\eta_d\,.550 = Q\,P/550 \quad (2)$$

Lest this be considered a minor item, let it be pointed out that in some relatively recent airplanes ΔP is about double Δp, that is, duct efficiency η_d is about 50 percent.

Given a fixed engine and installation design, what is the ratio between internal cooling hp. and over-all total cost of cooling? Loss in relative velocity through the cowl from flight speed V_0 to V_4 gives us another way of expressing energy expended in the internal system in terms of velocity (kinetic energy loss or $\frac{1}{2} m V^2$) and can therefore be used in the comparison we are seeking:

$$\text{Internal thp} = \frac{\frac{1}{2} m\,(V_3^2 - V_4^2}{550} \quad (3)$$

For comparison, we now take the ratio of internal thp. to total cooling thp. first determined (equation No. 1), and this turns out to be the long-famous "pump efficiency":

$$\eta_p = \frac{\text{Internal cooling thp}}{\text{Total cooling thp}} = \left(1 + \frac{V_4}{V_0}\right) \quad (4)$$

The ratio of drop through the cowl passages and engine to dynamic head available $\Delta P/q$ is of enormous importance to performance, and we will need to express pump efficiency in these terms instead of velocity. Since velocity is nearly proportional to the square root of the pressure differential creating it, pump efficiency, as expressed in Equation (4), becomes:

$$\eta_p = \frac{\text{Internal cooling thp.}}{\text{Total cooling thp}} = \frac{1}{2}\left(1 + \frac{\sqrt{q - \Delta P}}{\sqrt{q}}\right)$$

$$= \frac{1}{2}\left(1 + \sqrt{1 - \frac{\Delta P}{q}}\right) \quad (5)$$

Thus ends the chase for something we can use to approximate cooling drag. The important objective is still to understand the vast implications of this expression. It explains many a disappointing shortage in performance and offers many a partial fix for built-in trouble.

It is readily seen from either of these expressions for pump efficiency that if P/q could ever equal 1 (that is, if all the dynamic head q available were dissipated in overcoming the cowl ΔP required) cowl efficiency would be only 50 percent. This means that for such a condition the airplane would be deprived of twice the thp. consumed in the cowling and engine passages.

If now we assume values of the ratio P/q, we can plot pump efficiency against $\Delta P/q$ or $\Delta p/\eta_d/q$ (Fig. 2). Note the trend of rapidly decreasing efficiency or multiplying penalty in total thp. robbed from airplane as ΔP required by the cowling and engine becomes more and more nearly equal to the available head q.

Above expressions for cowling efficiency become imaginary for values of $\Delta P/q$ greater than 1, which condition represents the induced cooling (cowl flaps) to obtain more than available dynamic head across cooling system. But we all know there is nothing imaginary about the increased drag encountered in the wind tunnel with flaps open. Extending cowl flaps into the passing airstream to obtain some depression beneath them increases the total drag even more disproportionately for the increased differential across cowling. Since our results are now being influenced by parasite drag as well as by further pumping loss energy added to discharged air all in the interest of cooling, and all nacelle designs differ, no accurate universal curve of pump efficiency above values of 1.0 for $\Delta P/q$ can be computed. But there is experimental evidence that it continues to decline for further increase in $\Delta P/q$, then probably flattening off, as indicated by dashed line of Fig. 2, to values at best as low as 15 or 20 percent at 1.3 $\Delta P/q$.

Furthermore, contrary to the simplified algebra above, the cowl flaps actually must be opened before the $\Delta P/q$ required is increased to unity. The reason for the drop through the system is that a predetermined cooling air flow is necessary. Without additional drop across the cowl induced by the flaps, no flow would exist when $\Delta P = q$, which implies zero velocity out the exit, contrary to the principal objective of achieving a flow. The flaps must begin to be used when $q - \Delta P$ leaves just sufficient total pressure P_4 before the exit to cause the specified volume to flow out of the chosen size of exit opening with flaps streamlined. This means that the ΔP at which flaps must begin to be used varies with the choice of normal position exit opening area allowed.

Lower line of Fig. 2 shows effect of making an approximate allowance in calculations for additional pressure drop as $\Delta P/q$ approaches unity. Some designers defeat their purpose of reducing the drag by designing the exit area so low that flaps must be opened in the more frequently encountered regimes applying penalty of induced cooling which could have been avoided.




Fig. 7. First geared fan designed in 1939




Fig. 8. Complete installation of high-altitude geared fan




Fig. 9. High-altitude geared fan rotor

Examine again the disastrous effect on cooling thp. consumption caused by excessive over-all drop through cowl and engine passages. Assume, as an extreme case, that the total cowl drop, ΔP (or $\Delta p/\eta_d$) is twice what it might have been, due to unsatisfactory engine design, to cowl and ducting design to propeller shank effects, or all three. If by this increase we find ourselves operating with the flaps open at a value of $\Delta P/q$ of 1.2 when we might have operated with the flaps closed at a $\Delta P/q$ of 0.6, the curve of Fig. 2 tells us we are saddled, roughly speaking, with a pump efficiency of only about 20 percent, instead of about 80 percent. Having previously seen that the internal thp. consumption is also doubled (proportional to the $Q\Delta P$, and Q is a prescribed constant), then the total cooling thp. with the higher ΔP is —

$$2 \times \frac{80}{20}$$

or eight times what it might have been with half the drop P through the cowl and engine.

This is not just another minor variable of interest to those specializing on cooling problems, for hp. and performance costs can be extremely large. The more favorable values above are moderate enough—between 50 and 100 thp. per nacelle for the larger engines, depending on altitude. That means the unfavorable case just assumed is costing 400 to 800 thp. per nacelle. Gains from recent external refinements look small indeed by comparison with possibilities missed here. If these horsepowers are extreme for actual practice, it is only because the manufacturer has decided not to permit flaps to be opened enough to pay this penalty. With far less pressure drop from flaps, however, he runs into cooling difficulties.

So much for built-in cooling drag and its effect. A fan can eliminate the disproportionate fall-off in pump efficiency accompanying high values of $\Delta P/q$, in marginal cooling regimes cutting cooling drag perhaps to one third. Fig. 3 represents the same flight conditions as Fig. 1, and the same installation, except for addition of a fan. Let $P_2 - P_0$ be that portion of ducting loss now included as a part of the fan structure and P' be boost added by fan at cylinders. ΔP is the remainder of original total P which must still be provided by cowl system after subtracting fan contribution.

To simplify this first illustration, assume that the fan provided the entire ΔP re-

(Turn to page 258)




Fig. 10. Velocity diagrams for Keller and Schicht type fans



Inside view of Convair's tooling dock, showing massive framework. Note catwalk halfway to top. Fluorescent lights are to be installed under this catwalk. Dark beams (top and bottom) are horizontal straightedges for aligning work.



In this view, vertical and cross straightedges have been set in place. Overhead gantry crane handles parts which are too heavy for movement by other methods. White object in center is jig being lined up either for checking or addition of parts.

TOOLING DOCK TECHNIQUE SAVES TIME, SPEEDS ACCURACY

By **LELAND A. BRYANT**, *Consulting Engineer Consolidated Vultee Aircraft Corp.*

Convair finds automatic elimination of errors and increased tool production are direct results of adoption of this principle of assembly and checking of jigs and fixtures.

NEW DEVELOPMENTS in the use of jigs and fixtures in place of older layout systems have so revolutionized this part of aircraft manufacturing as to make it quite probable that production costs will shortly be reduced to a level paralleling those in the automobile industry.

There are two reasons which may be cited—one old and one new. The new reason is the master tooling dock, the old reason is a system known as paneling which has been used for years in the automotive and other industries, although it was only recently adopted by aircraft manufacturers.

Essentially, the idea of paneling is as simple as the basic idea back of the tooling dock. It consists of breaking down an airplane or automobile, into numerous small subassemblies or panels which can be fabricated with considerably more speed.

Before paneling was introduced, the practice was to construct huge jigs and fixtures used to assemble each major part of an airplane in a single series of complicated operations. The number of workmen that could be placed on a job was limited, due to lack of working space, and, because of the involved nature of the work, an aircraft mechanic had to be a combined craftsman and contortionist. The process was slow and tedious, because only a limited number of operations could be accomplished simultaneously.

Breaking down airplane construction by paneling makes it possible to utilize comparatively simple jigs and fixtures spread over a large work area. Many workmen can be used on each job, because there is no lack of space. Even unskilled help can be employed, because the individual operations are simple and easy.

One difficulty presented by paneling in the aircraft industry was the problem of obtaining appropriate tools. With inadequate dimensional control that prevailed in aircraft building before the war, paneling was impractical because it necessitated precision assemblies. To be successful, all components must be interchangeable. There must be precise means of coordinating the assemblies well within stipulated manufacturing tolerances.

Considering the complications involved in setting up accurate jigs and fixtures, aircraft tool designers were inclined to conclude that it would be easier to build a few large tools rather than many small ones. What the aircraft industry really needed was a universal mastering device, and it was with this in mind that the master tooling dock was adopted by Consolidated Vultee Aircraft Corp. Besides speeding up the entire building process, we have been able to attain dimensional tolerances seldom before considered practicable.

Skip stations are located by strip template, shown on top corner of straightedge. Next station fittings are set in place, then bolted firmly down. Strip template is then used to locate other parts requiring same dimensions, thus insuring same spacing throughout stations.



The dock is a three-dimensional positioning apparatus used for setting up assembly tooling fixtures and master jigs and for production checking. Besides facilitating precision duplication of lofting, it provides automatic coordination in the making of both fixtures and prototype assemblies. It eliminates the use of transits, surface plates, and height gages. It provides precision checking and speeds up the job of duplicating previously fabricated fixtures.

Thanks to the tooling dock most errors have been eliminated in building fixtures. Dimensional control over templates is fixed by the sources that control parts fabrication—that is, in the loft and template departments.

The tooling dock is a reproduction of the loft grid lines or planes. Its dimensional positioning in any of the three geometric planes is accomplished by means of coordinated strip and index templates, generally referred to as dock templates. Since a permanent record of each fixture exists in the dock templates, and since the dock is unchanging, it is only necessary to re-set the templates in the dock to check, realign, or duplicate the original fixture. This practice is limited only by the size and availability of the jig.

In some instances, the size of a fixture might prohibit its being moved to the dock, or it may be shipped to a location where a transportation problem exists. Thus, it is advisable to construct a standard master gage.

When a master contour model is required, the dock is used to align the templates. The master contour model is not completed when the station contour templates are secured to the backbond of the steel skeleton; it must still be filled and faired to produce a smooth, curved body.

Upon the surface of this model the lines layout is developed, with indications of trim lines, hole patterns, stringers, and lines of other secondary parts. From this contour model are lifted the form and layouts for stretching and forming dies, and drill fixtures required form the parts. The normalized steel skeleton, in conjunction with the inert plastic filler, insures preservation of line and form in the model. Through use of the tooling dock in positioning templates identical with the assem-



After location of stations vertical straightedges are set in place by overhead crane. Weight is taken by jack under lower end while positional accuracy is assured by ground and tapered dowel pins set through straightedge into fitting, the location of which was shown in top illustration.



Transverse straightedges are next set in place and their accuracy checked by some methods used in locating vertical units. Note that two straightedges—upper and lower—are used, with identical cross dimension markings so that vertical accuracy can easily be obtained

bly fixtures automatic coordination with the jigs is established.

For lack of means by which the loft and template departments might control the making of fixtures, it has been the practice to use dimensions and measuring apparatus in the jig and fixture department. As a consequence, the tool makers constructed assembly fixtures in a series of individual enterprises. Obviously, the difficulty of effecting coordination under such circumstances has been a great source of trouble in every tooling program throughout the whole war effort.

Through the use of the tooling dock assembly tooling can be started almost at the inception of the design of an airplane. The first accessory, the strip template, can be completed as soon as the basic station dimensions are determined, and the second, the index plate, may be completed as soon as hole locations are shown on the master layout, well ahead of other detailing.

Prior to the advent of the tooling dock, accuracy of dimensions in setting up assembly jigs was difficult to attain. Since each dimension must be linear—and since fixation of a point in three dimensions involves not only an accumulation of tolerances but also requires that each of the three measurement be in precise relationship—the difficulty is evident.

In lofting it has been general practice to work to tolerances of .010 in. and less, but in lofting all work is done in the second dimension, i.e. upon flat surfaces.

The tooling dock affords means of projecting the products of two dimensional layout into the third dimension without reduction of these tolerance limits. The straight edges of the tooling dock, set up in three planes, afford positive means of

(*Turn to page 263*)



As vertical adjustments will be required in mounting templates slotted angle blocks are attached to transverse straightedges. Drilled and numbered holes line up angle plates accurately

Last stage is attachment of index template, with one edge on center line of jig. Angle blocks enable adjustments to be made without changing position of straightedges

SO YOU'RE GOING TO PRESSURIZE?

By **CHARLES W. MORRIS,** *AiResearch Mfg. Co.*

What the Sales Department wants to sell and the Engineering Department wants to deliver are two different things. Here are some of the basic kinks and how they can be ironed out.

It is obvious to the technically minded that the problem of supplying air to an airplane cabin and controlling the pressure in the airplane cabin is not difficult. All that is necessary is to provide a source of air of adequate pressure and to provide a control valve in the cabin which will maintain the conditions desired in flight i.e. a "low altitude" cabin although the airplane may be flying at higher altitudes.

We may assume for convenience the example of a transport-type airplane which may be likened to the *Stratoliner* operated commercially by TWA and Pan American Airways. A certain amount of air must be provided, with control by some cabin inflow measuring means. This will assure an approximate constant quantity of airflow to the cabin. The outflow may be controlled so as to maintain an essentially constant pressure in the cabin.

In current advertising we note the trend toward promotion of the future probability of pressurizing airplane cabins for the comfort of the passengers and crew. In these advertisements we see a beautiful, shapely airliner with glistening surfaces, and the reading matter tells us it is operating in the stratosphere or substratosphere—depending upon the optimism of the Sales Department.

Such a future possibility is shown in Fig. 1. An airplane of this sort may be the one which is purchased by an airline operator for commercial transport work, to afford the maximum economy of operation and maximum sales appeal to potential customers.

In selling this airplane, the Sales Department of the particular airplane manufacturer will undoubtedly extoll the pressure-type cabin in which the passengers are riding "in luxuriant ease" and that with the new speeds, the passengers "will hardly have doffed their hats in settling themselves for their trip before putting their hats back on again, preparatory to disembarking at their destination."

But in order to meet the Sales Department's promises for an *airtight* cabin the airplane would have to look somewhat as shown in Fig. 2. The practicability of such construction *may* be subject to question. The engineers will probably deliver an airplane more like that shown in Fig. 3.

Every imperfectly driven rivet, each skin-seam wrinkle, each door and window has some bit of leakage. There are leaks inside the airplane where the controls pass through packing glands. Each point that a bolt, screw or rivet passes through the skin is a potential source of leakage.

It becomes obvious that when we consider the cabin pressure control problem, the leakage and the expected variation in leakage with altitude must be given close consideration.

Current practice to provide more than a minimum of 10 cu. ft. of air per person per min. with a maximum of 30 cu. ft. of air per person per min. being used for an upper limit. The derivation of these requirements is not known by the author.




Fig. 1. This is what the Sales Department would like in the way of pressurized-cabin planes for stratosphere operations




Fig. 2. To meet sales desires for an airtight cabin, engineering would have to deliver something like this




Fig. 3. What might be delivered, by way of compromise, could easily look like this, with every rivet hole, door, and window "busting at the seams".

Based on a paper presented before the American Society of Mechanical Engineers annual meeting.




Fig 4. Passenger air requirements. Half a cubic foot per minute for normal breathing, two per minute for ventilation plus 100 percent for safety factor.




Fig 5. Relationship of actual airplane altitudes to cabin altitudes.

but it is believed that they were developed as a result of experience in airplanes at least 10-yr old. Some question has arisen as to the applicability of this ventilation requirement. It is interesting to analyze the actual physiological needs of passengers in determining basic air requirements.

For respiration, while riding relaxed in an airplane or walking passively, approximately 0.5 cu. ft. of air is required by each person during 1 min for breathing. Additional air is needed for removal of body moisture, which is accomplished by ventilation though the clothing. Under normal room temperatures, approximately 2 cu. ft. of air per min are required at 60 to 70 percent humidity to meet this need, as shown in Fig. 4.

By simple addition, it is apparent that the total air need per passenger is only 2.5 cu. ft. of air per minute. Let us now double this total air requirement, so as to provide a 100 percent margin of safety, which will indicate a need for approximately 5 cu. ft. of air per minute per passenger. This may be used as a minimum requirement, and would be applicable during conditions of normal room or cabin temperature of approximately 70 deg. F.

With warmer air in the cabin, the

(*Turn to page 261*)




Fig. 6. Cabin air inflow curve, showing constant rate to 14,000 ft., above which it decreases with air density.




Fig. 7. Slight pressure differential (needed for ventilation) can cause a surprising amount of leakage.




Fig. 8. Combination of Fig. 6 and 7, to show air outflow variation which must be controlled by cabin pressure regulator.




Fig. 9. Service wear increases air leakage; this graph shows how cabin supply and leakage might appear during a plane's life.

The B.F.Goodrich Airline of the month

ALL AMERICAN AVIATION, INC.

FIVE ROUTES radiating from Pittsburgh Pa., serve 107 cities and towns in six states with a new form of fast communication—the Air Pick-Up. All American Airlines, Inc., operate a fleet of light, 2-man planes over these routes. They swoop down at pick-up stations—drop a bag of mail and express, and pick up another—all on the fly. By acting as a feeder to main trunk lines, and serving areas without regular airport facilities, All American is bringing closer the day when air service will be available to everyone.


B.F.Goodrich, maker of Airplane Silvertowns, Expander Tubes for brakes, De-Icers, and more than 80 other aviation products, salutes All American for their excellent service record. They've earned the nomination as this month's "Airline of the Month."

In war or peace

B.F.Goodrich

FIRST IN RUBBER





STRONGER, LIGHTER HOSE OPERATES AT LOW TEMPERATURE

Here's the new B F. Goodrich Hose (Spec ANH6a) that simplifies front-line repairing of the medium pressure hydraulic lines in our warplanes. Since it has no free rubber to stretch or flow, new couplings can be attached and not pull loose under pressure. Specially compounded for use in working conditions as low as —65° F, this hose is now Army-Navy standard for medium-pressure control lines.



New hydraulic hose means faster front-line repair

WHEN A WARPLANE comes back to base with its hydraulic lines shot up, they must be replaced before that plane can get back in the fight. Replacing damaged hose sections used to be a complicated, time-consuming process. Attaching stock hose to couplings required a giant press . . . and not many advanced bases had them. The only alternative was to keep thousands of different hydraulic assemblies on hand at all times.

To improve this difficult supply situation, manufacturers developed special couplings which could be attached quickly and easily to the stock hose then available. But they weren't successful, because the rubber in the hose would stretch and flow when squeezed between the parts of the coupling—then pressure would pull the coupling loose.

B F. Goodrich engineers were asked to develop a hose which would make the use of these couplings practical. The result was a hose with no layers of rubber outside or between the cord plies. Instead, protecting rubber was forced down into the fibres of the cord as it was braided around the inner tube. Thus there was no free rubber to flow—the jaws of the couplings bit into hard rubberized cords only, and held!

This new hose is 30 to 50% lighter and from 20 to 50% stronger than the old type. It is the only hydraulic hose that is size-controlled within such close dimensions that reattachable couplings can be used.

Now Army-Navy standard for aircraft medium pressure control lines, this B F. Goodrich hose is greatly simplifying front-line repair. For instead of having to stock thousands of different complete assemblies, a few sets of couplings and a few reels of hose are all a base needs to keep its planes in the air. Assemblies are made up on the spot.


The use of this hose has benefited the war effort in another important way. Demand for the type of hose formerly used for both medium and high pressure lines far exceeded production capacity. The adoption of this new B F. Goodrich Hose for all medium-pressure installations has greatly relieved a critical supply situation. The B F Goodrich Co., Aeronautical Division, Akron, Ohio.

ARMY E NAVY
Awards to 9 plants

In war or peace


B.F.Goodrich


FIRST IN RUBBER



All these advantages make the RIVNUT an ideal blind fastener

- Installed and headed from one side
- Serves as rivet, as nut plate for attachment, or as both at once
- Simple one-piece construction
- Corrosion-resistant aluminum alloy
- Light weight—low cost
- Requires very small hole
- Forms compression fit
- Ready for use "as received"
- Can be used in metal, plastics or plywood





New Folder, "Rivnut Data," Free

If you're not already using B F Goodrich Rivnuts, get complete facts now about these versatile fasteners that cut costs and speed production. For your copy of a newly edited data folder, write today to the B F Goodrich Company, Aeronautical Division, Dept. 0770, Akron, Ohio.



B.F.Goodrich
RIVNUT
IT'S A RIVET...IT'S A NUT PLATE



In many small assemblies hole piercing and riveting is done in one or two operations along this conveyor belt line at Glenn L. Martin Baltimore. Set up combined with careful planning extending back into design department has meant great time-and-tool savings

HOLE PIERCING PROVES FASTER—AND CHEAPER

PART I

By HERBERT CHASE

Obviating use of drills, Martin system combines with conveyor belt line to simplify and boost production of small assemblies.

WHY DRILL RIVET HOLES—when they can be pierced with a punch and die many times faster? Though the answer may appear obvious, its implications have brought about far-reaching production method changes at the Glenn L. Martin Baltimore plants. Since the remarkable economies realized offer similar "fair shooting" at other plants, the Martin procedure is reviewed here.

First, however, it should be pointed out that Army and Navy specifications do not preclude driving rivets in holes that are merely pierced with a punch and die and not subsequently reamed or drilled out. Although the Navy, at least, once had a specification to this effect (apparently based on a belief that cracks occur around pierced holes), it no longer applies. The current Navy specification SD 24-E reads in part:


"Holes for structural rivets, bolts, and pins may be punched or drilled . . . All holes shall be clean-cut and shall show no evidence of excessive deformation at the periphery."

Today, millions of rivet holes, up to 3/16-in. dia., are being punched ("pierced" is the usual term in the stamping industry) daily in aircraft factories, especially on the West Coast, though Martin, in the east, is believed to be making most extensive use of piercing. While it may not be feasible to displace drilling by piercing in making major or large final assemblies, especially of the fuselage, some informed opinion implies that more than 75 percent of all rivet holes can be pierced if the design of parts and production system are devised with this end in view.

Moreover, there is excellent evidence to support the contention that pierced holes, when properly made, have smoother walls, are more precisely sized, and yield superior joints than those commonly produced with drills. Such holes, when pierced with punch and die kept in proper conditions, require no burring, which alone often yields a marked saving in time.

At the Martin plant it is realized that,

For Erco and many other operations, light and simple fixtures (such as these) suffice. Often only slots and stops or pilot pins are needed to position work. Clamps or buttons sometimes needed, are fast to operate and facilitate loading and unloading. In some cases two small fixtures like these are applied separately to same assembly to save weight and avoid using cumbersome single fixture.



though hole piercing alone affects substantial economies, these savings are greatly increased when the operation combines automatic insertion and driving of the rivet and also, when required, dimpling of the hole. For this reason, preference is given to the Erco machine, since it pierces, dimples when necessary, inserts and drives the rivet in a rapid sequence of semi-automatic operations. During this sequence no shifting of the work is necessary. Where this type of machine is not applicable, one machine is used to pierce (and dimple, if required), and a second to insert and drive the rivet.

The third alternative, in order, is to pierce and dimple the hole or holes in one machine, insert rivets by hand and squeeze preferably in a machine that will squeeze more than one rivet at a time. A fourth choice (often necessary when parts have to be fabricated separately and assembled later (perhaps on the airplane) is to pierce the holes in one part slightly under size and drill through them and the mating during assembly. In this case the piercing, which may be done with multiple punches, serves to spot the holes and shorten drilling time, but rivet insertion is by hand and the rivet is set by a squeezer or riveting gun.

As a last resort, and commonly where none of the foregoing operations are feasible, the entire hole is drilled and dimpled if necessary. Even then, of course (if the assembly is adaptable to machine riveting), rivets are preferably inserted and driven by an automatic riveter, though hand insertions and multiple or individual squeezing or hammer driving may be required.


When drilling can be avoided, no drill jig is required. This often saves heavy tooling expense as well as the time of applying and removing the jig or clamping and then removing the work. On the other hand, although jigs and fixtures are often needed for piercing holes and subsequent riveting, these tools are low in cost. They are commonly made from Masonite or similar material, as will be shown later. In much piercing, however, no jig is needed, because holes can be located with ample precision either by eye or by spots of paint or dye sprayed on the work through a template. When piercing in a machine, these spots are brought in line with the punch usually by directing a beam of light at the spot where the end of the punch is to make the hole.

For maximum economy, especially in building small assemblies, it is often necessary to employ at least a simple fixture and to arrange the series of operations to follow in logical sequence and reach the necessary machines with a minimum of handling and delay. At Martin much study has been give to simple fixtures that are light, easy to handle and rapid to load and unload. The same is true of the set-ups required for performing at a maximum rate the succession of operations necessary to effect the assembly.


To realize these economies in small-to-medium-size assemblies normally handled on a bench (where one or more workers commonly perform several hand operations) Martin operates several assembly lines, each with a conveyor belt running through the center. None of the lines is designed for effecting a single assembly or even a few different assemblies, each handles a great many different assemblies on which similar or identical operations are performed. Though there are some



Numerous Martin parts have been designed for speedier assembly through piercing rivet holes. This Erco machine punches holes, dimpling them when necessary, and inserts and drives rivets, usually in cycle of 1.3 sec. Such operations call for some size-and shape rivets unless conditions permit changing set-up or use of more than one machine.



Where several holes of same size have previously been pierced or drilled and take same type and length of rivets, automatic riveters such as this Chicago machine insert and drive rivets. Work is located by pilot pin entering hole from below.



Assemblies in which holes are to be pierced at points where jig location is unnecessary are sprayed or spotted, paint or dye going through holes in template as shown. If burring is necessary it is done at next station on conveyor belt line.

benches, the usual bench work is avoided along the conveyors. The belt really serves many stations, some of which have no bench space. The operator merely takes the assembly from the conveyor, performs the operations assigned, and replaces the assembly on the belt for transfer to the next station.

In general only one set of duplicate assemblies is on the line at a time, and most assemblies are handled in batches of 50 or 100. A new batch is usually started before the preceding one is finished, to keep the line operating continuously. Each machine is equipped with the proper tools, which seldom need changing while a given batch of duplicate assemblies is in process.

When machines at a particular station are not needed for a given assembly, the conveyor merely carries the assembly past this station. In every case, however, the aim is have the individual operations done under the most favorable conditions with the choice, as far as making holes and riveting is concerned, following the order of preference given above.

Where semi- automatic machines need a given set-up (such as Erco and Chicago riveters) use may be confined to one type and size of rivet. If other odd sizes are needed they may be hand-inserted and driven by a slower machine, for the time for changing set-ups on semi automatic machines to handle different rivets has to be considered. For similar reasons, an occasional odd-size hole may be drilled rather than pierced if it is faster to use a light electric drill than to change a punch and die.

A line of this type naturally requires proper planning to operate with maximum advantage. In the Martin plant where

(*Turn to page 262*)



Pierced holes in locations where Ercos cannot be used are usually punched in tubular rivet and stud machines. Assembly is located (1) by sleeve surrounding punch below work and fitting holes in Masonite jig as shown, or (2) by spray spots brought into position under light beam from projector lamp attached to head of press. Note proximity of conveyor belt at operator's right.

Load Characteristics Of Cellulose Acetate Plastic

PART II

By **WILLIAM N. FINDLEY**, *Assistant Professor of Theoretical & Applied Mechanics, College of Engineering University of Illinois*

Changes in strength and resistance of this material caused by age, torsion and moisture are considered in this second article of Mr. Findley's significant series.




Fig. 10 Effect of time and conditioning on yield point in compression and specific weight vs. time elapsed




Fig. 11 Fatigue machine of repeated bending constant-amplitude type

HAVING DISCUSSED the various properties of cellulose acetate, we now proceed to describe the actual experimental tests

Fifty specimens were machine treated as follows Twenty-five of them were immersed in water for a period of 48 hr then removed to a rack, where they remained until tested The other 25 were placed in a desiccator over anhydrous calcium chloride for a period of 48 hr removed, and placed on a rack. Both groups of specimens were then stored in the testing room (at constant temperature and relative humidity) for the duration of the tests

Two from each group were set aside as control specimens, and their weight and length were recorded, both before conditioning and at intervals after treatment. The remaining specimens were tested in compression at intervals over one year One specimen was tested immediately after removal from the water bath and another immediately after removal from the desiccator The others were tested at specific intervals to give a uniform distribution of data when test results were plotted against the logarithm of the time elapsed after removal from the conditioning medium All tests were run at a no-load head speed of 0 06 in. per min Thus resulted in a rate of strain of about 0 002 per min

It was observed that a definite yield point in compression existed for cellulose acetate plastic. This was determined by the fact that the load remained constant for a period during the test. Since fracture did not occur during compression the yield point was used to measure the effect of moisture on strength. In Fig 10, the compressive yield point for these tests is plotted against elapsed time.

It was observed that about 1½ mo (1,000 hr) was required for the compressive yield point to approach a stable value, and it is significant that the final value of compressive yield point was nearly the same for both the moistened and dried specimens Some scatter in these data was observed, due in part to the fact that the air conditioning of the laboratory was interrupted for 4 or 5 hr on two or three occasions

In the lower part of Fig 10 is shown the average specific weight of the two control specimens, plotted against time. These control specimens were weighed and measured at the same time that tests of the others were made. Data in Fig 10 indicate that about one month was required for the specific weight to return to the value obtained before conditioning was started No explanation is offered for the fact that specific weight of initially dry specimens decreased after 7,000 hr, unless perhaps the specimen was losing plasticizer

No appreciable change in length was observed as a result of the above treatment Wet specimens decreased about 0 4 percent in length during the testing period, while no measurable change in the dried specimens was observed.

Fatigue tests were conducted on the repeated bending constant-amplitude fatigue machine, equipped with a V-belt drive to provide variable speed In this machine (see Fig 11) the specimen was repeatedly bent back and forth as a cantilever beam by a variable eccentric. Procedure was as follows The bending moment M corresponding to the desired stress σ was computed from the equation $M = \sigma I/C$

Maximum force exerted by the connecting rod on the specimen holder was determined by dividing the bending moment by the moment arm. Deflection required to produce this force was determined by calibrating the specimen itself as a dynanometer, while deflection under load was measured by a dial gage. In a few of the tests a dynanometer (Fig 11) was used to measure the applied force. An adjustment also was provided to permit changes in the range of stress of the stress cycle For example, in the first series the mean (or average) stress was zero—the stress being completely reversed

In a later series of tests the mean stress was 2 000 psi, and the amplitude of the alternating stress was 1,100 psi, so that in this case the range was from 900 psi. to 3 100 psi The number of cycles was recorded on a mechanical counter and a toggle switch was arranged to stop the machine when the specimen fractured Thus for each specimen in the machine, stress corresponding to deflection during the test was calculated from the bending moment measured while at rest, and the number of cycles for fracture was obtained.

These data were then plotted with stress as ordinates and number of cycles as abscissa using semi-logarithmic plotting For cellulose acetate a well-defined endurance limit was found. The endurance limit is defined as the alternating stress cycle maximum amplitude which will not cause fracture for an indefinitely large number of stress cycles

In Fig 12, $\sigma - N$ (stress vs. cycles) diagrams are plotted for tests of specimens having several different shapes Curve 1, a circular cross section specimen shown in Fig. 1k (see page 146, June AVIATION), curve 7, a rectangular specimen, Fig 1f, curve 6, a square specimen, Fig. 1g of ¾ in. radius, and curve 4, a




Fig. 12 Stress vs cycles tests (σ-N) for different shapes of specimens.




Fig. 13. Diagram of σ-N for several testing frequencies.

square cross section of 2 in radius The endurance limit for these tests is shown in the third column of our accompanying Table I It was found by re-tests of the same material (after a lapse of 1 yr 3 mo) that the endurance limit increased with age. The $\sigma - N$ diagram for specimens aged 11,000 hr. is shown in curve 2 of Fig 12. Comparing this endurance limit—1 380 psi with 1,100 psi for the same shape tested 11,000 hr. earlier—it was found that the limit had increased about 25 percent in 11,000 hr. (about 15 mo)

In order to compare data obtained at different periods, the endurance limit for several shapes tested was adjusted approximately to the value which was obtained at an age of 11,000 hr (measured from the time of the original test). The adjustment was made on the assumption that the change of limit with time was nearly a linear function during the interval. The age as defined above for each set of tests is shown in column 4, Table I

TABLE I—Endurance Limits for Different Shaped Specimens

Curve No.	Specimen	End limit (measured) p.s.i.	Age hr	End limit at age 11,000 hr (calculated*) p.s.i.
1	Circular Fig. 1k	1,400	1,400	1,700
2	Rectangular aged Fig. 1f	1,380	12,000	1,380
3	Const. temp., Fig. 1g	1,350	4,400	1,540
4	Square, 2-in. rad. Fig. 1h	1,250	3,600	1,440
5	Machined Fig. 1f	1,175	2,000	1,410
6	Square ¾-in. rad., Fig. 1g	1,120	1,800	1,380
7	Rectangular, Fig. 1f	1,100	0	1,300
(Not Shown)	V-Notch (not shown)	380	1,000	670

These values were obtained by correcting all endurance limits to the value which would be found if tested at an age limit of 11,000 hr The correction was based on an assumption that the endurance limit increased linearly with time. Rate of increase was found from curves 2 and 7.

and the endurance limit adjusted to an age of 11,000 hr. is shown in column 5

Comparing different shapes of specimens by means of column 5, it was found that the square specimen with ¾ in. radius had nearly the same endurance limit as the rectangular The square specimen with 2-in radius had an increase of about 4 percent, whereas the circular cross section specimen had an endurance limit markedly higher than any of the other two shapes showing an increase of about 27 percent over that for the rectangular specimen Reason for this is not known though a similar effect has been observed in some metals and not in others The phenomenon may be associated, in part, with the quantity of material subjected to high stress, compared to the quantity immediately adjacent to high stress material available to receive additional stress, resulting from the redistribution of stress after a minute crack has formed

The notch "sensitivity" of cellulose acetate in flexural fatigue was obtained from fatigue tests of rectangular specimens having a V-notch machined across one face. The notch used had a 45 deg included angle with a 0 01 in. radius at the bottom The depth of the notch was 0 02 in. The endurance limit obtained for the notched specimens was 670 psi when adjusted to age at 11 000 hr. This value represents a decrease of about 53 percent from that of the rectangular sample having a machined surface (discussed below) The effective stress con-

(*Turn to page 263*)




Fig. 14 Effect of speed of testing on endurance limit.



Rubber mats are placed over dies in first step of blanking by Guerin process.

Methods for Forming Sheet Aluminum

PART III

Here, blanking and piercing are carefully detailed . . . Final installment of this practical process-and-formula series.

BLANKING—the cutting of sections from sheet-metal stock for use in subsequent forming operations—may be done with shears, by power-driven presses or by use of routing equipment.

Most common method of blanking aluminum is in a mechanical or hydraulic press. The blanking operation shears the material between the outer edge of the punch and the inner edge of the die. As the punch is pressed into the stock it produces a true cutting action for about one-third of the metal thickness and a fracture thereafter.

In blanking aluminum, the punch is usually made of annealed tool steel, while the die is almost always formed of hardened tool steel. Faces of both punch and die must be ground to keep cutting edges sharp, otherwise burrs will result. When it is desirable to keep the load on a press at a minimum, the top of the die surface may be ground so that the shearing edge around the die opening is not on a single plane. By tilting the die on opposite angles during grinding, two opposite high points are ground on its face, which should differ from the low points by at least half the thickness of the material, but preferably the full thickness. If the blanks must be kept flat the punch should be ground flat regardless of high and low points on the die surface.

Correct clearance between punch and die is determined by the type and thickness of the sheet to be blanked. If clearance is too great, blank will be "broken out" rather than sheared. If too small a clearance is used, tools will be excessively strained. Improper clearance produces rough blanks, is hard on tools, and requires more power. Table I shows clearances between punch and die for blanking aluminum alloys. In general, a clearance equal to one-eighth the thickness of the sheet will prove sufficient.

The walls of the die opening should be tapered away from the cutting edge 3 to 5 deg. to permit the blank to drop through easily. There is a tendency for the sheet to cling to the punch on its up-stroke unless a stationary stripper is attached to the die or a spring stripper is attached to the punch.

It is important that the designer lay out the work to assure the least possible waste. Table II shows the recommended scrap on the sides and between blanks for various gages and diameters.

Danger of shearing or scoring the punch is great unless there is some means of aligning it accurately with the die. The time required, as well as maintenance cost, can be lessened by mounting punch and die in a leader pin die set.

Both the sheet to be blanked and the cutting edges of the tool should be generously lubricated to keep maintenance costs down and to cut the blanks smoothly. A medium grade engine oil, plus a little fatty oil diluted with kerosene, is best for the harder or thicker sheets of aluminum. For softer alloys and tempers, dilution of the mixture is not necessary.

The sheet may be lubricated by hand brushing, or by passing it through saturated felt pads. Thin coiled sheet is usually fed into the press automatically on feed rolls. The metal before entering the die, passes through oily pads which are attached directly to the press bed. A saturated ring of felt above the stripper will lubricate the punch by permitting the oil to trickle over its edge.

Where necessary to maintain bright


(*Turn to page 264*)

Blanking Table I—Punch and Die Clearances
(t = thickness of sheet, inches)

Aluminum sheet alloy	Clearance: On a side	Clearance: On the diameter	Aluminum sheet alloy	Clearance: Side	Clearance: On dia.
2S0	0.10t	0.20t	24S0	0.13t	0.26t
2S1/2	0.12t	0.24t	24ST	0.15t	0.30t
2SH	0.14t	0.28t			
			52S0	0.12t	0.24t
3S0	0.10t	0.20t	52S1/2H	0.14t	0.28t
3S1/2H	0.12t	0.24t	52SH	0.18t	0.36t
3SH	0.14t	0.28t			
			61S0	0.11t	0.22t
17S0	0.13t	0.26t	61SW	0.12t	0.24t
17ST	0.16t	0.32t	61ST	0.14t	0.28t

Blanking Table II—Scrap Allowances

Gage	Blank dia. in.	Scrap on side in.	Scrap between blanks in.
No. 25g. (0.018 in.)	0 to 10 incl.	1/8	1/16
to	10 to 20 incl.	3/16	3/32
No. 15g. (0.057 in.) incl.	20 to 30 and over	1/4	1/8
No. 13g. (0.087 in.)	0 to 10 incl.	5/32	3/32
to	10 to 20 incl.	7/32	1/8
No. 12g. (0.081 in.) incl	20 to 30 and over	5/16	5/32
No. 12g. (.081 in.)	0 to 10 incl.	3/16	1/8
to	10 to 20 incl.	1/4	5/32
No. 4g. (0.238 in.) incl.	20 to 30 and over	3/8	3/16



When thin sheet (under 1/16-in. thick) is fed from coils into press, it is automatically lubricated by swab.




Cone has been perforated on this horn press. Automatic index revolves work to give equal spacing of holes.

Routing machines with swinging cutter can cut many sheets in single operation.





Single action press is used to pierce holes in fabricated parts. (All photos by Aluminum Co. of America.)



When many holes are to be punched at one time, punches should be stepped to prevent all entering metal at one time.

Electronics Smooth Supercharging

How a new, sensitive supercharger control substitutes precise electronic impulses for the manual control by the overly busy pilot.

THE DEMAND for increased engine power and efficiency at great altitudes has rendered the turbosupercharger a necessity for high-flying combat.

Design problems—as compared to those faced by the stationary turbo compressor engineer—are extremely complicated, both because of the great range of atmospheric pressures and temperature to be considered and also because the problems of pilot, who is frequently far too occupied with combat problems to be able to give his power plant controls the attention required for best efficiency.

For these reasons, some kind of automatic control is essential in order that the pilot may have maximum power when he requires it, even though he is momentarily prevented from checking either his engine or the instruments which tell him how it is performing.

The turbosupercharger itself is a simple exhaust-driven turbine, directly coupled to a centrifugal compressor or impeller which compresses atmospheric air to the pressure predetermined by the pilot.

This compressed air undergoes a considerable rise in temperature, making necessary an intercooler to extract much of the heat of compression before the air proceeds to the carburetor and internal gear-driven blower which delivers it to the engine cylinders.

Minneapolis - Honeywell's electronic turbo control system automatically regulates the output of all superchargers on multi-engine planes by means of a central boost selector operating through amplifiers which boost inverter current on its way to the waste-gate motors. These motors open or close the waste gates, which permit more or less of the engine exhaust gas to reach the atmosphere without first operating the turbine which drives the supercharger. Operation of the waste gate motor is controlled by electrical signals from the turbo boost selector, the Pressuretrol, and the turbo governor.

Air pressure of the supply from the supercharger to the carburetor is regulated by the Pressuretrol using two bellows to operate a potentiometer.

Waste-gate motion is controlled by the turbo amplifier, which translates the signals received from the other units into motor action, either to close or open the waste gate and thus regulate the speed of the turbine and with it, the delivered air pressure.

Great operational advantages can be obtained from the use of a device, such as this, which substitutes sensitive electronic controls for slower human reactions and subsequent manual operations. In addition to being fully automatic and accurate within a very small degree, this equipment minimizes the probability of inexperienced or overstressed pilots setting up excessive manifold pressures, with resultant damage to their engines.

Because the safety margin between safe operating speeds and dangerous ones is extremely narrow, a suitable control will permit higher output without liability of damage through overspeeding the turbine.

Another advantage of this type of equipment is its successful operation under sub-zero conditions, which do not affect the action of electronic controls.

Through almost instantaneous power control through regulation of exhaust pressure by means of the waste gate, engine speed control is simplified, since boost change gives better regulation than throttle operation. Meantime, hand-throttle control is at no time interfered with, so the pilot may, if he desires, use the manual method for varying the speed of his plane.




Diagram of four-engine installation of Minneapolis Honeywell electronic turbosupercharger controls

CONVAIR CLASSES "BROADEN THE SPECIALISTS"

By H. L. WHEELER

Chief Group Engineer, Armament, Consolidated Vultee Aircraft Corp., Ft. Worth, Tex.

Engineers teach engineers and instructors learn from their students in this unique plant school instituted to widen the knowledge of "the man who knows more and more about less and less."

CONSOLIDATED VULTEE Aircraft engineers are again going to school to add postscripts to the engineering degrees and sheepskins" tucked away in their trunks.

Expert in their own special fields, the engineers are now attending semi-weekly classes where they get opportunities to peer beyond the barriers of specialization by discussing what's happening in the other fields of aircraft engineering.

Producing an airplane has become a job of specialization, hence as development of airplanes broadened, study of their component parts became channelized into narrower and narrower fields. Complexity of the modern airplane makes it virtually impossible for any one person to have an over all knowledge of the many specific tasks of its engineering, and so specialization resulted.

The Convair classes sprang from a growing realization that the specialists—while perhaps working side-by-side—increasingly were losing perspective of the over-all technical functions of the other parts on the plane.

In addition to broadening the personnel's acquaintance with the general developments in aircraft engineering, the school is also utilized to introduce specific new design methods and to instruct regarding new materials, equipment and processes. Net result is a shorter time lag between the introduction of a new idea and its incorporation in the building of the airplane.

Wide List of Subjects

At Convair's Fort Worth division, 55 subjects have been, or are in the process of being, discussed. This list, covering the field of aircraft engineering, includes such subjects as cockpit arrangements, general hydraulics, levered suspension and caterpillar landing gears, propeller controls, soundproofing, anti-icing, and blind landing equipment, each presented by a specialist.

Where the opportunity offers, particularly in the introduction of a new idea, experts from outside are brought to address the classes.

The speed with which ideas may be 'sold' through this method underscores the obvious advantages of a visual and auditory presentation over the standard method of utilizing a memorandum.

Each subject leader prepares a discussion which can be presented in approximately one-half hour. While the subject leader is supposed to do most of the talking, engineers are making liberal use of their right to comment, to ask questions, or perhaps to argue a statement.

The group is broken into three sections. As a result, leaders present their topic on three successive days. While the same discussion may be presented at each of the three sections, questions raised at the first usually mean development of additional discussion material for the second section. And answers to questions raised at the second session are also included in the discussion for the third.

The speakers' reactions have been as beneficial as those of the engineers attending the classes. For it has been brought out that, while the topic leader may have a good knowledge of his subject, he meanwhile may have somewhat lost sight of various prior-functional or post-functional details. Hence the subject leader "goes back to school" himself in presenting his material to other engineers.

Training Aids Used

The class idea has been received favorably in every instance by the engineers, and if discussion of the subject matter may be taken as a criterion, interest in the series is certainly running at a high level.

The program has been developed to the point where models, charts, diagrams, or actual working mechanisms are utilized in illustrating the discussions. Initially, the classes were launched on a temporary basis at the Fort Worth plant, but they have now been adopted on a similar pattern at Convair's San Diego division. Enthusiasm for the idea indicates it will likely be continued indefinitely and on a constantly broader scale.



Convair's engineers go to school to keep up with latest developments in the other man's department.

There is no shortage of DZUS* FASTENERS



Dzus—the most widely used fastener in the aviation industry. Only ¼ turn to lock or unlock.



Flush head type showing side view.



End view showing unique spring design

Dzus—the positive-action fastener for all airplanes.

We can produce fasteners to meet your requirements

Here at Dzus our business has always been to make the best fastener in the world. Long before the war, that was true. The Dzus Fastener was designed to meet a pressing need in the aircraft industry, and over the years it has proven its worth by keeping pace with new developments. The Dzus is no longer an experiment, but a time-tested product. Relentless research to meet the ever more exacting requirements has developed The Dzus—so that it has literally grown up with the aircraft industry.

Dzus production has been continually stepped up to meet the industry's requirements. No shortage. No delay. Write today, and let us know your requirements.

*TRADE MARK

DZUS TRADE MARK FASTENER CO. INC.

BABYLON, NEW YORK

How to Get Top Efficiency From Your Vacuum Pumps

Detailed here are Pesco's precise methods of installing and maintaining these essential units—and instructions are provided for building a suitable test bench.

NOTE FIRST that installation instructions for Pesco vacuum pumps should only be used as a general guide, for problems vary with different plane designs.

Initial step is to remove shipping plugs from inlet and outlet ports before turning pump coupling. Next remove cover plate and gasket from engine pump pad and then wipe clean, noting carefully direction of rotation of engine drive gear. Refer to arrows on machined surface on rear of pump and determine which is intake port. Test pump for freedom of operation by turning with fingers. If pump is intended for lubrication through mounting pad, check oil holes to insure free passage.

If pump is equipped with hex head plugs next to mounting flange, make sure that plug marked "suct" is installed on same side as intake. Interchange the two plugs if necessary, and tighten and secure with safety wire.

Place gasket over mounting flange, making sure that it does not block hole in pad if pad lubrication is employed. Mount pump in most desirable position for air line connection, then tighten mounting nuts evenly and safety wire. If external oil lines are to be used, block holes in pad by turning gasket.

Install suction and discharge lines to pump ports. Inlet port for either rotation is designated by arrows on exterior surface next to cover. Tighten all connections and see that tubing is properly supported and bonded.

If engine has oil ducts to mounting pad and pump has oil holes, no further provision for lubrication is necessary; otherwise, an external oil line must be installed. Either system must be tested before installation is complete. Probe oil passages to make sure they are free from obstruction.




Fig 1 Diagrammatic layout, showing installation of pump and accessories




Fig. 2. Sectional views showing parts to be inspected and points to note for tolerances which are given in Tables I and II.

Be sure also that oil holes in pump pad line up with those on engine drive pad. If no oil holes are provided on engine pad, turn gasket to block holes in pump and use external oil line to port in pump body.

Because of engine vibration, all valves and fittings connected to pump must be braced to relieve pump of unnecessary weight and prevent failure of flange.

Relief Valve. Install valve in suction line near pump intake. Between pump and valve install 6 in. to 24 in. length of tubing, using hose connections and pipe nipples. Mount valve with screen facing *downward or to one side, never upward*. Screen should be easily accessible for inspection or cleaning.

Oil Separator. Install separator in pump discharge line. Mounting brackets or tubular mounting supports will give proper angle. Some larger separators have cushions on sides to minimize vibration. Mounting at specified angle is essential for proper operation.

Safety valve is installed in discharge line after oil separator, using 6 in. to 12 in. tubing with pipe fittings so that valve guide assembly can be easily removed for inspection or cleaning.

Check valve, installed in pump suction line to protect instruments from momentary back pressure from engine backfire, also acts as safety valve in multi-engine installations where, if pump fails, valve closes off line so that leakage cannot render rest of system inoperative. In *3V-226 series*, the valve is a spring-loaded disk in an aluminum housing with hose connections; in *3V-311 series* the valve is a two-piece swing-gate type in two-part housing with pipe tapped ports.

Either check valve can be installed in the suction line, using rubber tubing and hose clamps or pipe-tapped hose nipple. Make sure arrow on valve points toward pump. In twin engine installations install a valve between each pump and common suction line. On *3V-311* be sure the valve is installed in position indicated by "this side up" on casing.




Fig. 3. Pesco Designed stand for testing vacuum pumps. It can be built in any average shop.

Inspection and Maintenance

Hundred hour inspection of pumping system is as follows. *Pump.* Check security of mounting and possible leaks in air lines. *Relief Valve.* Examine screen and if it is dirty remove valve and loosen screen assembly with wrench. Clean with gasoline. Valve is properly adjusted when shipped. If necessary to alter adjustment, loosen locknut and turn adjusting nut counter-clockwise to increase suction, or clockwise to decrease it.

Safety valve. Remove valve guide and wash in suitable cleaning fluid. If disk is worn, smooth carefully on flat oilstone. Test spring tension by measuring the force required to compress to 1⅛ in. Force must be at least 37 lb.

Oil separator with removable screen. Remove oil screen and outlet fitting; clean and wash unit in suitable cleaning fluid, drying afterward with compressed air. (For type without removable screen, remove entire unit and wash out thoroughly in cleaning fluid.)

Check Valve. Remove and disassemble at engine overhaul periods, and examine bakelite disk and dress lightly on smooth oilstone, if required. If disk is badly worn replace with new one. When reassembling, make sure gasket will still provide effective seal.

Coupling. If wear is shown or it has failed, remove snap ring, extract coupling and replace with new one.

All vacuum pumps must be thoroughly lubricated internally and externally as protection against corrosion before being stored. Pour several cc of SAE 30 oil into one port. Turn coupling several times to insure complete lubrication. Install shipping plugs tightly in ports to prevent leakage. Coat all external parts (likely to become corroded) with light grease.

Table I—Fits in Inches

LET	PART FIT Models 3P207 211 B-3 B-7 & B-12	MIN.	MAX.	WHEN NEW B-4 & B-8
A	Rotor slot	.065	.065	.065
	Blade thickness	.0638	.064	.0633 .064
B	Blade width	2.744	2.747	2.244 2.247
	Shaft bore	2.751	2.753	2.2500 2.2533
C	Sleeve I.D	2.0000	2.0005	2.1250 2.1255
	Bearing O.D	1.9997	2.0000	2.1248 2.1248
D	Shaft dia.	1.0000	1.0003	1.1250 1.1253
	Bearing I.D	.9997	1.0000	1.1245 1.1250
E	Cover hole	.3120	.3125	.3120 .3125
	Metering pin dia.	.3140	.3142	.3140 .3142
F	Collar I.D	.3147	.3196	.3147 .3150
G*	Sleeve length	3.995	3.004	4.003 4.003
	Rotor length	2.9995	3.0000	3.999 4.000
H*	Blade length	2.9955	3.0002	3.9970 3.9977
J	Sleeve I.D	1.3780	1.3786	1.5748 1.5756
	Bearing O.D	1.3776	1.3780	1.5743 1.5745
K	Shaft dia.	.8998	.9004	.8993 .8998
	Bearing I.D	.8991	.8998	.8995 .9000
M	10 Tooth spline	.3114	.3127	.3114 .3127
N	12 Tooth spline	.7112	.7174	.7112 .7174
	Model 4P-194	B-1 & B-1A		B-2A & B-5
A	Rotor slot	.3128	.3136	.3128 .3136
	Blade thickness	.3105	.3112	.3105 .3112
B	Blade width	.9951	.9956	.9479 .9354
	Center pin dia.	.7445	.7445	.6795 .6860
C	Sleeve I.D	2.7530	2.7535	2.6260 2.6265
	Cover I.D	2.0000	2.0010	2.0000 2.0010
D	Bearing O.D	1.9983	2.0000	1.9995 2.0000
	Bearing I.S.	.9997	1.0000	.9997 1.0000
E	Rotor shaft dia.	1.0000	1.0003	1.0000 1.0003
	Cover hole	.3745	.3750	.3745 .3750
F	Metering pin dia.	.3735	.3767	.3788 .3797
	Collar I.D.	.3772	.3778	.3772 .3778
G*	Sleeve length	3.008	3.004	2.1265 2.1275
	Rotor length	2.9925	3.000	2.1243 2.1255
H*	Blade length	2.9968	3.002	2.1242 2.1255
J	Sleeve I.D.	1.3780	1.3786	1.3780 1.3790
	Bearing O.D	1.3775	1.3780	1.3775 1.3780
K	Rotor shaft O.D	.8998	.8998	.8998 .8998
	Bearing I.D	.8991	.8995	.8993 .8995
M	Engine drive spline	.7112	.7174	.7112 .7174

* Use gaskets as required for proper clearance at G & H.

Table II—Clearances in Inches

LET	3P-194 B-1 & B-1A	B-2A & B-5	3P207 211 B-3, 7 12	B-4 & B-8
A	.0016	.0015	.001	.001
	.003	.003	.0027	.0027
	.003*	.003*	.003*	.004*
B	.0053	.0113	.004	.006
	.0115	.0132	.009	.0092
C	.0015	.0015	.0008	.002
	.002*	.002*	.0025*	.0025*
D	.0037T	.0006T	.0007T	.0007T
	.0005	.0000	.0006	.0000
E	.001*	.001*	.001*	.001*
	.0022T	.0015T	.0022T	.0022T
F	.0015T	.0015T	.0015T	.0018T
	.0005	.0005	.0005	.0005
G	.001	.001	.001	.001
	.0018*	.0015*	.0012*	.0012*
H	.0015	.0015	.0016	.0015
	.0023	.0025	.0023	.0025
J	.0027*	.0027*	.0027*	.0027*
	.0015	.0015	.0015	.0015
	.0025	.0025	.0025	.0028
	.0027*	.007*	.007*	.007*
K	.0000	.0000	.0002	.0000
	.0011	.001	.0011	.0011
	.0025*	.0025*	.0025*	.0025*
M	.0005T	.0005T	.0006T	.0006T
	.0001	.0001	.0001	.0001
	.001*	.001*	.001*	.001*

* Maximum wear. T Tight.




Fig. 4. Diagrammatic layout of test stand with connections.

To remove ball bearings, place rotor with outer edge on block with hole ⅛ in larger than o.d. of bearing. Insert thin piece of brass or aluminum in each rotor slot successively and tap lightly to force bearing off shaft. Strip metal should be at least an inch longer than blades.

Metering collar is anchored to rotor by a pin pressed lightly into hole in shaft. To remove pin, bump end of shaft lightly on wooden bench.

Sleeve can be removed by forcing out anchor pin and heating body to about 250 deg. F. in gas oven or oil bath. Part can then be bumped out on wooden bench.

Relief valve may be disassembled by removing seat assembly and lock nut. Parts may be removed with wrench (place valve body securely in bench vise).

Check Valve. Remove and disassemble at engine overhaul periods, and examine bakelite disk and dress lightly on smooth oilstone, if required. If disk is badly worn replace with new one. When reassembling, make sure gasket will still provide effective seal.

Coupling. If wear is shown or it has failed, remove snap ring, extract coupling and replace with new one.

All vacuum pumps must be thoroughly lubricated internally and externally as protection against corrosion before being stored. Pour several cc of SAE 30 oil into one port. Turn coupling several times to insure complete lubrication. Install shipping plugs tightly in ports to prevent leakage. Coat all external parts (likely to become corroded) with light grease.

Overhaul

Overhaul should be undertaken only where complete facilities for repair and testing are available. Pumps can be readily disassembled without special tools, and removal of cover gives access to all working parts.




Fig. 6. Details of water manometer for use with flowmeter.

Disassembly of oil separator, other than screened outlet is neither advisable nor practical.

Safety valve may be completely disassembled by removing valve guide.

Check valves (both *3V-226* and *3V-311*) may be disassembled by removing cover screws.

After disassembling pump, wash all parts except front bearing in cleaning fluid. Don't wash front bearing because fluid would dissolve grease with which it was packed by manufacturer. Inspect all parts carefully (Fig. 2) and replace any which are defective or which show signs of wear in excess of tolerances shown in Tables I and II.

If blades are rough or scored, dress on flat oilstone. Wearing edges may be dressed, but original curvature must be retained. Particles of aluminum from blades in smaller pumps may build up in rotor slots to cause excessive scuffing, in which case slots should be dressed carefully with flat, thin oilstone.

Replace bearings if rough turning. To test for roughness, hold outer race in one hand and turn inner race with fingers, pressing endwise. Test both sides this way. Check for radial roughness by turning inner race while pressing radially with finger. Repack front bearing with high temperature grease after every 1,000 hr. operation. To open bearing for inspection, lift out snap ring with knife blade and carefully remove seal disk.

Metering pin and collar should not be lapped or reamed but should be replaced if worn. Excessive oil consumption will result from changing dimensions of either by reaming or lapping.

Examine coupling for broken, cracked or weak springs. If any parts show signs of wear or weakness, replace immediately.

Measure all parts to assure that allowable fits and clearances (as given in Tables I and II) are within limits. If these measurements cannot be maintained by replacements, renew the worn part.

Relief valve bakelite disk should be redressed on smooth flat oilstone, if necessary. Spring pressure should be not less than 16 oz when spring is compressed to 1¼ in.

Pump Reassembly

Heat body to about 250 deg F. and insert sleeve so that anchor pin hole corresponds with hole in body. Insert pin and peen edge of hole to retain pin. Insert metering pin in cover carefully to prevent tilting, which would cause misalignment with collar.

When mounting cover assembly on pump, take care that pin does not wedge in collar. Rotate collar from side to side, as metering pin engages collar, until dowel pin in body enters locating hole in cover.

Test pump for freedom by turning by hand. If coupling will not turn, bump assembly in wooden bench to free parts. Also wash out pump with cleaning fluid to remove any particles of foreign matter. If necessary, disassemble pump to recheck clearances and eliminate tight spots. When pump turns freely after reassembly, proceed with—

Final Test

A satisfactory service test for pumps can be performed with any equipment which will give reasonably accurate indication of amount of air passing through pump and rate of consumption of lubricating oil. Factory test equipment is more extensive than required for routine service testing (Fig. 3). For this reason, only essential apparatus is described here, virtually all of which may be made in any hangar workshop or will be found already on hand. Equipment should be arranged according to diagram.

It is important that pump coupling have good alignment with mounting stand drive gear. Mounting unit consists of base fixture with drive shaft supported by ball bearings.

A 3- or 5-hp electric motor coupled to mounting-stand drive gear through speed control is recommended for all vacuum pump testing. Three essential test speeds —1,500, 2,250 and 3,750 rpm—must be provided, either by variable speed reducer or by simple pulley combinations. If speed control is such that a wide selection of speeds is available, a means of indicating pump shaft spred is required, but if variation is limited to a few predetermined speeds, as with fixed pulley ratios or with certain types of electric controls, a tachometer is not necessary, though occasional checking with a hand tachometer is desirable.

Bench should be at least 35 in. high and large enough to accommodate all test equipment (Fig. 4).

A flowmeter (Fig. 5) is required to measure capacity. One type consists of a cylinder with a steel plate secured to one end and a pipe-tapped connection at other end. In the steel plate is a sharp-edged orifice through which air is drawn into cylinder to which suction port of vacuum pump is connected. Slight vacuum created in cylinder next to orifice varies with air flow and can be measured by a water manometer, with scale graduated to show capacity in cu ft. per min (Fig. 6).




Fig. 5 Details of flowmeter for measuring airflow of small vacuum pumps.




Fig. 7 Layout for oil consumption metering tank.

Intake suction and discharge pressure can be controlled by valves in intake and discharge lines and is indicated by mercury manometer connected close to pump ports.

Test set requires a means of supplying lubricating oil at pressures of 50-70 psi. in such a way that the quantity consumed in a given time can be measured. This can be accomplished by a supply tank (as shown in Fig. 7). Air pressure is introduced on top of the oil. Glass tube not only indicates quantity of oil in tank but also serves as a measuring device. When it is desired to measure pump oil consumption, valve at lower end of tube is closed, so that only oil in tube itself will flow into feed line. Scale mounted next to tube indicates volume in cc. With this device, pump oil consumption can be measured accurately over a given period.

A pair of mercury manometers will serve for measuring intake suction and discharge pressures, when connected close to pump ports. Suction and discharge pressure are controlled by valves in suction and discharge lines.

Two thermometers are required for measuring air temperature rise. One is mounted next to orifice in flowmeter and the other in the discharge line. The latter should have a range up to 350 deg. F.

Power absorbed may be measured by a dynamometer, or a wattmeter may be used to measure power in watts absorbed by motor both with and without load.

Tubing of ¾-in. dia. is large enough for test work. Care should be taken to avoid sharp kinks, and as few restricting fittings as possible should be used. The discharge line should terminate in a large expansion tank.

Test Procedure

Before mounting pump on the test stand, remove shipping plugs and check freedom of operation by hand. If pump tends to stick or bind, hold it by flange and tap end of coupling sharply with wooden mallet. This will free parts and prevent scoring. When pump operates freely by hand mount it on test stand and connect the oil line to ⅜ in. P.T. connection on top of pump. During test runs, oil must be supplied to pump at 50-70 psi. Test procedures for all vacuum pumps are essentially the same; however, constant reference to test specifications in Table III is important. Recommended procedure is as follows:

Vacuum pumps must be run in after overhaul to make sure they are functioning properly. Prelubricate slightly with several shots of oil in intake port and run for 1 hr. at 3,500 rpm with minimum suction and discharge pressure. During this period, grade 120 lubricating oil must be supplied at not less than 50 psi. One of the tapped holes on top of pump may be used for this purpose.

(Turn to page 267)

Table III—Test Specifications

In accordance with latest Army and Navy specifications following test procedure should be used on all vacuum pumps. A 10 per cent deviation is acceptable on pumps overhauled after 800 hr. operation.

Capacity Test

Series	Rpm	Inlet Suction In. Hg	Outlet Pressure In. Hg	Oil Pressure Psi.	Capacity Cfm
3-P104	1 500	4 2	2 0	50	4 5–4 9
3P-207	1 500	4 4	1 8	50	7 9–8 7
3P 207	2 250	4 5	17 1	50	9 8–11 0
3P-211	2 250	4 1	17 5	50	17 0–19 0

Temperature Rise and Oil Flow Test

Series	Rpm	Inlet Suction In. Hg	Outlet Pressure In. Hg	Oil Pressure Psi	Temp. Rise Deg. F	Oil Flow cc/Hr
3P-194	3 675–3 825	6 85	3 4	50	142-152	40-120
3P-207	3 675–3–825	6 4	12 5	50	275 Max	75–215
3P-211	3 675 3 825	6 6	17 5	50	247-257	75–190

Seal Leakage Test

Series	Rpm	Inlet Suction In. Hg	Outlet Pressure In. Hg	Oil Pressure Psi	Seal Leakage cc/Hr Max
3P-194	3 750	8 0	3 35	50	10
3P-207	3 750	8 7	5 5	50	10
3P-211	3 750	7 2	19 3	50	10



Over-all view of colossal overhaul job tackled by Pan American's airline maintenance department. Photo shows how PAA's Atlantic Division is making structural replacements to Boeing 314 'Clippers'. Massive jigs attached to wing center section hold craft in flying position for removal and replacement of both vertical hull and hull bottom truss members. Note location of wing jigs close to airplane which has been nosed into hangar corner to be out of way of routine servicing of other craft. (All photos by PAA.)

REBUILDING THE "CLIPPERS"

Pan American's Atlantic Division maintenance department has taken on its biggest job yet — replacing structural members of Boeing 314's. And through pre-engineering they're doing it in strikingly fast time.

WHAT IS UNDOUBTEDLY the most comprehensive overhaul job yet undertaken by an airline maintenance department is today in progress at Pan American Airways' Atlantic Division headquarters at LaGuardia Field, N. Y. where the first of eight Boeing 314 *Clippers* scheduled to 'get the works" is literally being rebuilt.

This project is no mere refurbishing of eight large flying boats for it includes as a precautionary measure, replacement of a minimum of eight wing spar-chord members, more than 20 wing web members and 23 hull bulkhead members. Magnitude of the job is best shown by the fact that it was necessary to build jigs capable of supporting not only wings but also hulls of these 84 000-lb gross weight craft.

And, as the size of both the military and commercial planes increases, the project assumes more than mere interest it becomes important as a handbook of experience.

First step in the completely pre-engineered process was to remove tail surfaces, propellers, engines, hydrostabilizers ("sea wings" peculiar to this type of craft), wingtips and, finally, outer wing panels. Inasmuch as the airplane had major parts removed, precautions had to be taken to keep the airplane in balance while it was moved on the beaching gear. This was accomplished by using sandbags in the bow.


All components were removed under the chain hoist in the center of the marine terminal hangar, then the hull was nosed into a corner where the craft would not interfere with routine servicing of sister ships remaining in service.

Here the hull and its beaching gear were raised—20 in. at the aft end of the step to get it in flying position—then the hull was attached to jigs at the wing center section fittings. These jigs, 28 ft. high and weighing approximately 6,000 lb. each, were attached along the bottom by heavy steel tie-through members to assure alignment and eliminate the necessity of anchoring them to the hangar floor. Additional alignment checks are provided by jigs attached to the hydrostabilizer fittings.

With the hull attached to the jigs the beaching gear was withdrawn from the aft end of the airplane and six hull bot-



Close-up at hull bottom cradles, used both to distribute weight over hangar floor and to help maintain hull position during removal and replacement of structural members. Jig at left attaches to hydrostabilizer (or 'sea wing') fittings and serves to maintain alignment during project. All jigs of welded steel construction were built by PAA's Atlantic Division maintenance department. Wood and canvas padding is used between cradles and hull bottom to protect the hull from damage by motion during repair.



Three-level work stands built by maintenance department to facilitate under hull work. This view, looking aft along Clipper' hull, shows how bottom skin has been peeled back to give access to truss members slated for replacement. Great care has been taken in removal of rivets and bolts so that same sizes can be used when new structural members are in place and skin is again attached. All structural members removed are handled with extreme care, since they serve as templates for new members going into planes.

tom cradles were installed, three forward and three aft of the hydrostabilizer jigs. These hull-bottom cradles are constructed of welded steel angle members with wood and canvas padding cut to fit the hull curves. They serve both to distribute the weight of the hull bottom and also to hold it in position while main structural members are being replaced.

Interior of the airplane was completely stripped, with the multitude of parts going to storage, salvage, or specialized repair departments and then replacement of hull structural members began.

These include the vertical square tubular members running from the wing center section spars down through the hydrostabilizer attaching points to the truss structure forming the bottom of the hull, also the majority of the tubular members in the corresponding bilge trusses.

To do this, it was first necessary to disconnect the deck (or cabin flooring) from the main lounge, as well as the next two compartments, so that both front and rear spar bulkhead lower truss structures could be removed as units. This, in turn, required removal of chine and keel sections to permit loosening of the hull bottom skin to give access to the truss sections. Similarly, skin along the sides of the hull near the vertical members was loosened and peeled back to give access to them.

In each case, skin was loosened by very careful drilling of rivet heads, then popping out the rivet. Thus, replacement of the skin can be made with the same size rivets used in original construction of the *Clippers*.

Removal of the vertical hull members would appear to be a simple cutting-away job, but such was not the case, for the members themselves have been used as templates for replacement members. Thus it has been necessary to remove bolts and rivets with extreme care to avoid making the holes in the gusset plates and other attaching members any larger than allowable limits called for in the original design.

Members being replaced in both wings are the front and rear spar upper and lower chord members from the wing attachment terminal through the first splice, or from the outer wing panel attaching point outboard through seven ribs, a matter of 174 in., and web members in the area. Replacement order is as follows: Rear spar lower, front spar lower, rear spar upper, and front spar upper.

After the hull had been nosed into the hangar corner the outer wing panels were placed in their jigs at right angles to each other and close enough to the hull to permit uninterrupted normal maintenance on other craft.

As in the case of the hull jigs, wings—also constructed by the Atlantic Division's maintenance department—were made of welded steel angle and I-beam members with machined fittings. One of these jigs supports the wing at the wingtip fittings, the other at the outer panel to center section fittings. In addition, there is a flap jig, consisting of four pyramidal stands supporting a heavy steel bar attached to the flap fittings and serving as an alignment jig to insure accuracy during removal and replacement of the rear spar chord members. Load distribution is effected by a wooden framework placed under each spar extending from the wingtip jig inboard to the splice where chord members were being replaced.

With the wings in jigs fabric covering (which extends from the rear spar to the trailing edge) was removed. In order to gain access to the rear spar chord chip-attaching bolts, the lower chord



Looking through hydrostabilizer jigs. Hull bottom skin has been loosened and peeled back only far enough to give adequate working room for removal of structural members being replaced. Vertical jig member at left attaches to both top and bottom hydrostabilizer leading edge fittings that at right to top and bottom trailing edge fittings. This is first of eight 'Clippers' scheduled for program.

members of seven trailing edge ribs were cut approximately 12 in. aft of the spar. This 12-in. section was removed by drilling out rivets through chord and spar clip and also the rivets attaching the trapezoidal rib chord gusset plates to the rear spar cap.

In all wing work, as in the hull, removal of rivets and bolts required extreme care to keep holes from being enlarged. And here, too, removal of the members themselves required extreme care both to utilize the members as templates for replacement structures and to prevent scratching of gussets and webs remaining in place.

Four types of alignment checks are

(*Turn to page 269*)



Inboard wing jig with wing in place and leading-edge skin peeled back to permit removal of spar-chord member. Beyond outboard engine nacelle a long wooden cradle has been place beneath spar to distribute weight and maintain alignment. Similar jig is used at outboard end attaching to wingtop attachment fittings. In addition, four pyramidal stands form basic structure of flap alignment jig.

Inspection and Top Overhaul On the Franklin

By F. B. CHADWICK, *Service Manager, Aircooled Motors Corp*

Power plant check-up and service—by a precise routine—comprises the small plane owner's "performance insurance." Here are the 10, 25, and 100-hr. steps, plus top overhaul details.

LIKE ITS LARGE high-power brother on fighters bombers, and airlines, the modern light aircraft engine is the product of years of experience and superlative engineering talent. But, also like the big fellows, it must be carefully inspected and serviced if it is to give the satisfaction which the designer claims and the owner has a right to expect.

Inspection is divided into three period categories 10, 25, and 100-hr The first is merely a checkup requiring a few minutes, for there is nothing which can normally require much attention after only 10 hr flying The 25 and 100-hr inspections and top overhaul comprise the maintenance necessary to keep the engine operating successfully until the regular 500-hr (or more) overhaul period.

Ten-Hour inspection calls for the following routine Remove and clean fuel strainer When replacing glass bowl, do not tighten until fuel has been allowed to run for a short time so that air will be driven from pipe line and strainer The air will leak out round loose bowl, which is tightened after gasoline leaks out.

Wipe off sparkplugs and ignition cables to prevent danger of short circuits from oil or spot Inspect all cable terminals on ignition system, both at sparkplugs and magneto

Twenty-Five-Hour inspection It is considered good practice to drain crankcase of oil at this time refilling with SAE 20 Used oil should be passed through 20 mesh (or finer) strainer which is then examined for metal particles that would serve as a danger signal regarding condition of engine.

Controls should be checked for operation through their full range, then lubricated

Check and clean sparkplugs. Champion J-10 plugs should be used, with the gap set at .020 in. When tightening plugs use torque wrench with force of not more than 20 ft.-lb. Use a good mica base lubricant on sparkplug threads before installing for this will obviate chances of stripping threads in cylinder head through overtightening

If any of the high tension cable terminals are corroded or if the cable shows signs of being cracked, the defective length should be replaced This is important because breaks in the insulation may cause sparks resulting in gasoline fires during operation During this inspection, magneto points should be checked for pitting and tightness. Slight pitting is not harmful, but roughened surfaces call for refinishing of the points.

One Hundred Hour inspection is made after completing every fourth 25-hr inspection Valve covers are removed and valve guides checked for wear by pressing sidewise on spring with a screw driver Excess clearance indicates that the valves are not only seating incorrectly but that the lubricating oil is probably being blown out by the pressure of the exhaust gas In addition, air is often admitted on the intake stroke, resulting in too lean a mixture, which causes head overheating and warped valves Minimum clearance should be 0025 in., maximum 0043 Carburetor should be cleaned by an experienced mechanic jets being *blown out with air*—not cleaned with a wire which usually results in an enlarged jet, cause of bad metering

Clean out all fuel lines and strainers, including that in shut-off at tank Wash out tank with clean gasoline and make sure all sediment is removed.




Fig. 1. Franklin cylinder head and valve rockers. Here, feeler gage is used to check side clearance between rocker and bracket.




Fig. 2. When replacing cylinder ring compressor of thin sheet metal is employed to prevent rings from catching or breaking

Top Overhaul

This work is not always required between major overhaul periods, but experience has proved that increased efficiency and operating economy are often realized because of top overhaul at about 250 flying hours

Before "revving up" engine at full throttle on ground to determine need of top overhaul, perform following inspection and adjustment Check spark timing, seeing that spark occurs in position given on engine nameplate Check over items in 10, 25, and 100-hr inspections Check throttle lever to make sure throttle opens fully when lever is against forward stop.

While engine is cool check compression by swinging prop with throttle wide open and listening through exhaust ports




Fig. 3. Cross section of Franklin engine cylinder showing parts which receive attention during top overhaul

and carburetor for blowing valves.

Warm up engine until oil is about 100 deg F, then open throttle and note maximum rpm with standard prop If minimum rpm. is not reached, top overhaul is probably necessary

Top overhaul is accomplished without removing engine from plane Select a spot free from dust and remove engine cowling and air housings Take out sparkplugs and remove cylinders If gasket sticks, tap cylinders lightly with wooden hammer Raise cylinders slightly in removing them, being careful that pistons do not fall against crankcase It is considered good practice to slip pieces of split hose, or about ½-in dia., over connecting rods to prevent damage to aluminum crankcase. Remove propeller or tie it tightly to prevent movement, otherwise it may be turned with resulting damage to engine.

With valves in place, scrape carbon from inside head Then remove valves by placing wood block 7 in. long inside cylinder, with cylinder resting on bench Remove valve cap and press down on springs until split cone is removable When removing valve springs etc., tag them so they will be returned to their original location. A steel bar ¾ x 1¾ and about 14 in long with ¾ in. hole in center, makes a good valve removing tool

Clean all parts with gasoline and inspect valves and seats for cracks burning, and wear Do not re-face valves and seats unless absolutely essential since this operation usually results in more metal being removed than is necessary If new valve seats are required, cylinder should be returned to factory, where new seats are shrunk in place by machinery.

If valves are pitted burned or grained, intake valve should be re-faced to 30-deg angle and exhaust to 45 deg Carbon should be removed from valves very carefully to preserve original surface unscratched Emery cloth not coarser than No. 150 may be used on valve stems (coarser cloth has a tendency to remove gloss and surface hardening). After lapping valves, test by pouring gasoline in ports or by using air pressure in cylinders

Valve springs should be thoroughly cleaned and inspected for cracks A pressure of 44 50 lb should be supported by valve stem when spring is installed. If spring does not support 44 lb, remove spring and place washers beneath it until required pressure is obtained. If more than two ⅛ in. washers are required, springs are too weak and should be replaced When valve is fully open spaces in spring should be not less than 010 in. Rusty springs should always be discarded immediately as they are likely to break without warning

Cylinders should be checked for wear and taper with an inside micrometer Cylinders worn more than 002 or 003 should be exchanged for new ones, this method enabling original piston to be used Measurements should be taken upward to a distance of approximately 5 in from the lowest edge of the cylinder skirt Above that point an inward taper will probably be noted—which is normal

In assembling valve mechanisms, make sure chamfer on narrow end of rocker pin is toward center of cylinder otherwise it will rout valve spring Oil hole in rocker pin bearing should be towards cylinder center

Barrel end of rocker arm should line up accurately with valve stem center This line up may be accomplished by slightly loosening the nuts on support studs, tapping rocker arm until it is in line, then tightening nuts again. Palnuts should be used for safetying

Valve rocker caps should be left off until cylinders are bolted down on crankcase—because it will not be possible before that time to check the alignment of the lifter rods at the ball end of the valve adjusting screws

Assembling of cylinders to crankcase (always using new gaskets) should only be done after both cylinders and crankcase have been thoroughly inspected and cleaned. Cylinder walls and also piston rings should be heavily coated with cylinder oil. A band type of ring clamp should be employed when sliding cylinder over

(*Turn to page 270*)

"On and Off" Speed Is Aeroprop Feature

Detailed hern arn installatian and remaval mathads which, it is repartnd, nnable ground crews to mahe completn replacemnnts in less than 20 min.




Fig 1 Shaft nut wrench It may bn made from heavy sheet steel with tabe welded in a socket for 4-ft turning rod.




Fig 2 Aeroprop restallation (1) is rear cone, (2) stop assem bly, (3) propeller (4) shaft nut locking screw, (5) spinner adapter, (6) adapter screws and washers (9 required) (7) spinner patent attaching screws, and (8) spinner shell.




Fig 3 Removal of spinner shell Spacing al dowels prevents replacement in wrong position but care should be taken to check serial numbers on shell and bulkhead which should be the same.

FOR INSTALLATION AND REMOVAL of Aeroprop propellers but one special tool is required—that shown here in Fig 7 This tool may be fabricated or purchased from the manufacturer Used in Conjunction with the propeller shaft nut locking sleeve (seen at 4 in Fig 2) this wrench is for tightening or loosening propeller shaft nut

As may be seen by reference to Fig 2, the propeller is centered at rear by rear cone 1 and is secured in front by shaft nut locking sleeve 4, which must be removed before the propeller can be slid forwards off shaft.

Spinner-adapter 5 centers spinner shell 8 and is attached to front of propeller by safety cap screws

Non-rotating parts are held stationary by stop 2, which is variously attached to front of engine reduction gear housing, as shown in Fig 6b

Removal Directions

On planes with tricycle landing gear, hang about 300 lb on front wheel strut, or thereabouts, to compensate for propeller weight removed. Now remove spinner attaching screws (Fig 3) and loosen and detach spinner, using palm of hand only in striking shell *Do not use any hard object on spinner at any time* Marking of the spinner to assure replacement in same position is not necessary, for offset dowels allow it to be remounted only in original position




Fig 4 No 1 blade is turned downward before removing spinner adapter and loosening shaft nut,




Fig 5. On Models A6325-A1 and -A2, adapter plate attaching nuts are removed before loosening propeller shaft nut.




Fig 6 Steps taken when installing Aeroprop.




Fig 6b Methods of mounting adapter stop for various models.




Fig 7. Installation of adapter stop block (Model A6325-C1).




Fig 8. Adjustments of lever stop plate, Models A6325-A1 and A2. (1) is nut; (2) stop plate washer, (3) lever stop plate; (4) control lever stops (5) control lever, (6) studs (these shown unshaded are removed on 8 stud reduction gear case); (7) studs (those shown shaded remain on 8-stud reduction gear case).




Fig. 9 Method of counting teeth on lever stop plate when making adjustments (1) is control lever and (2) control lever stops Control teeth, as shown at (3), are counted, then set back three teeth from end, as at (4).

Turn propeller with oil plug downwards (Fig 4), bringing wide spline on shaft downwards Remove cowling inspection doors directly behind spinner Then take out cotter key and clevis pin from regulator control lever (5 in Fig 8).

If regulator adapter plate is bolted in




Fig 10. Regulator is half filled with oil through filler hole which is turned in horizontal position

place, use a ½ in wrench to loosen nuts as far as possible, as shown in Fig 5 (For Models A632S-A1 and -A2 Aeroprops) Remove safety wire and ¾ – 28 hex capscrews from spinner adpater (Fig 4) then remove adapter, using hands only

Using 4-ft bar in holes of propeller shaft nut locking sleeve, loosen nut two turns If cannon is installed, use shaft nut wrench shown in Fig 1 with same bar Attach slings to two upper blades as close as possible to hub Take light strain on hoist sufficient to take propeller shaft nut until it is clear of threads Then using great care to prevent bruising either of shaft or propeller, slide propeller forwards until it is completely clear of shaft It may be necessary to operate hoist slightly during this operation to keep propeller clear of shaft, splines, etc during this stage of the work

Next, remove oil plug behind lower blade and drain oil from hub Then with an assistant to support free blade lay propeller on flat surface, with rear or regulator side up Finally, remove rear cone and felt insert.

In models A632S-A1 or -A2 regulator propellers, adapter plate and nuts must be removed as propeller nut is backed off After each turn of propeller shaft nut check adapter plate nuts until plate is clear of engine reduction-gear case studs

Since spinner and bulkhead are balanced as a unit, they should be kept in pairs, together with the screws used to attach them

Installation

Clean splines and rear cone seat thoroughly using an approved cleaning fluid Check entire surface for burrs or nicks and dress them off level with a fine stone. Clean again and dry Then rotate shaft to bring wide spline to bottom

Install rear cone dry Do not grease or oil. Set felt insert in rear cone slot Apply light coat of oil to splines and anti-seize compound to shaft threads (Fig 6)

On Models A632S-C1, -B1, or -B3, adapter stop should be installed on third, fourth and fifth studs from top on R H side (as viewed from pilot's seat) of 16-stud engine reduction-gear case Use second and third studs from top for 8-stud reduction gear case (Fig 6b)

On Model A632S-C1, use two engine nose stud spacers between stop lug bracket and attaching nuts And on Models A632S-A1 or -A2, remove thrust plate stud nuts and spacers as shown in Fig 6b.

Clean propeller hub bore thoroughly and wipe dry Next attach slings to two blades opposite wide spline keeping slings




Fig 11. Bleeder teal is used between blade and nut to permit escape of air as grease is forced into hub

as close to hub as possible and providing clearance from spinner bulkhead plates to avoid damage during raising Hoist propeller, supporting free blade by hand, and align wide spline of hub with that of shaft Slide carefully onto shaft until shaft nut engages threads. Insert shaft locking sleeve into hub and turn shaft three turns clockwise, using nut wrench and bar,

Align adapter slot with stop bracket or stop lug on engine gear case. On Models A-632S-A1 or -A2 align lobes of adapter plate with gear case studs as shown in Fig 8, and place lever stop plate on correct adapter plate lobe Turn shaft nut locking sleeve two more turns clockwise while checking the above alignment. On Models A632S-A1 or -A2, start (but do not tighten) adapter nuts using special spacers between nuts and adapter plate lobes Make certain that there are no washers between lobes and engine gear case thrust plate.

Continue tightening shaft nut carefully watching adapter line-up until propeller is solidly against rear cone For A632S-A1 and -A2 models, tighten all adapter plate nuts except the one on lever stop plate lobe

Remove slings, then while blocking one blade, tighten shaft nut, using 175 to 200 lb force on end of 4 ft. bar

Install spinner adapter secure with 1-28 capscrews and washers and safety with .032 wire If screw holes do not line up, remove adapter and rotate it one notch at a time until alignment is obtained If necessary, tighten shaft nut slightly and repeat procedure.

Install stop block in bracket on A632S-C1 models and safety with cotter key (Fig 7)

(Turn to page 270)

SERVICE STEPS FOR THE EISEMANN MAGNETO

By E. J. GOGGINS, *Eisemann Magneto Corp*

Here's the routine of simple operations for keeping new, lightweight 4- and 6-cylinder aircraft "mags" at peak efficiency.

DESIGN OF SMALL lightweight aircraft engines calls for a magneto in which weight and bulk have been reduced to a minimum It was for service on this type of engine that the Eisemann 4- and 6-cylinder magnetos were originated


These magnetos are of the rotary magnet, jump-spark distributor type, with aluminum-nickel-cobalt magnet and ventilated distributor housing To reduce headroom, the secondary leads are taken from the end of the housing, rather than the top

An impulse starter provides an intense spark at cranking speed, while retarding time of ignition to prevent pre-ignition when starting. When the engine is cranked the magneto rotor is held stationary by a catchpin and pawl, while motion of engine winds a spring in the starter When the piston passes TDC a pawl releases the spring, which spins rotor and generates the spark.

When engine rpm. exceeds 200 impulse starter action ceases and the unit acts as a flexible coupling, with spark automatically advanced to exact position necessary for normal operating speed

In servicing the unit the first step to set the magneto in position for connection to the engine is to remove the distributor plate and rotate the magneto shaft in the opposite direction to that when driven, in order not to engage the impulse starter. This rotation is continued until the rotor plate on the distributor points toward the lower left-hand cable position (approximately 7 o'clock), and as the contact points commence to separate, ignition spark occurs


In this position the magneto is ready for installation on the engine, which should have No 1 cylinder in firing position. The exact point at which ignition should occur should be ascertained from the engine maker's handbook.




Eisemann Model AM-4 Magneto. Right, impulse starter and mounting flange with adjusting slots Left Distributor housing and secondary lead terminals.

Cables must be attached to the magneto by means of clips as shown in the accompanying illustration. Only such clips should be used since a projection is provided at the bottom of the cable holding recess to accommodate the projection at the clip end, and 7 mm cable should be used.

The distributor should be cleaned with a



Interior views of 4-cyl. model. At left are winding (top) distributor rotor (center), breaker and condenser (bottom) Right-head view shows distributor housing with secondary lead spring contact (top) and distributor terminals (left)



Method of attaching secondary terminal clips, which have integral catch to snap in place when inserted in terminal on magneto


soft cloth, dampened—but not wet—with gasoline if carbon is found on the face. Only high grade gasoline should be used, and all parts should be wiped dry before reassembling. Care should be exercised to prevent wiping lubricant from the breaker cam face. Abrasives should never be used on the breaker cam distributor plate or distributor rotor.

Contact points should not be filed, but when they require dressing this work should be done with a smooth carborundum stone.


As all ball bearings are grease-packed at the factory, lubrication is unnecessary, except that a *single drop* of medium grade engine oil may be applied to the breaker cam wick after every 500 hr.

Impulse starter pawls should be loosened with a small amount of kerosene at inspection; a small can should be used to prevent flooding. Contact points should separate from .019-.021 in. In checking the gap, the shaft should be turned until the breaker fiber rests atop the cam, at which point the gap between points should be measured with a feeler gage. To avoid action of the impulse starter, the shaft should be turned backward during this operation.


As the entire breaker assembly turns on the breaker lever bearing pin, the gap may be adjusted without altering the relationship between surfaces of the breaker lever contact and fixed contact. If, however, it is necessary to adjust the gap this can be done by loosening the breaker plate fastening screw and moving the entire breaker assembly toward the cam to increase gap, or away to decrease it. The gap opening should be re-checked after the breaker fastening screw has been tightened.



Shielded Model LA, 6-cyl. Eisemann magneto




Elevation (left) and section (right) of Eisemann 4-cyl aircraft magneto. Six-cylinder type is similar so that servicing operations are much the same. (1) is impulse starter, (2) magnet rotor, (3) breaker cam, (4) condenser, (5) distributor gear, (6) secondary terminal socket, (7) distributor plate, jump spark type, (8) distributor center brush, (9) distributor rotor, (10) secondary lead from winding to distributor brush, (11) secondary winding and (12) primary winding.




AAF Collapsible Stand

• Built of tubing and sheet metal, this stand can be taken down and bundled for transportation while the mechanics are picking up tools after completing a repair job. Broad feet at one end prevent movement while in use and braces beneath platform give stiffness without weight.



Carrier-Based Crane


• U. S. Navy uses this type of crash crane for deck work on aircraft carriers. Capacity is equal to lifting entire weight of heaviest carrier-based planes in use at present.



Aileron Lock Bar

• A U-shaped plastic casting (set around vertical wheel spoke in drawing) weighing little more than ½ lb, has been designed by Glenn L. Martin engineers to lock *Mariner* ailerons and elevators when these craft are not in air. Applied at control wheel, this bar (yoke of an original plastic design) attaches to lock bar by chain and hangs free when not in use. When locked, a slot in back of yoke engages lower spoke of wheel, while yoke itself fits around control column and into locking plate which holds it in position. Sketch shows yoke in locked position inside control wheel at left, with chain running from it to lock bar, which extends between two wheels.






"C"-Shaped Adaptors For "One-Shot" Rivet Machine

• Ray M. Williams, Northrop mechanic, designed these "C"-shaped adaptors. For use on "one-shot" rivet machine, they are of great aid in assembling difficult sections, such as riveting two narrow channels together (inside flange to inside flange, as shown), or for "Z" and hat sections, or other formed parts.

Easy-Cleaned Parts Boxes

• By placing stiff paper in bottom of small parts boxes used in shops, Buick keeps these containers and their contents free from otherwise inevitable accumulation of dirt. Paper (shown in two layers) slides through slit too narrow to permit passage of small parts and can be renewed without emptying box.






American Airlines Record-Racker

• This quickly attached rack is used by American Airlines to keep records clean, in sequence order, and convenient during inspection and line overhaul. It would otherwise be necessary to provide a portable desk for this purpose.

Radio Mock-Up

• At its Cheyenne shops, United Air Lines uses this radio mock-up for testing *Mainliner* equipment prior to installation. Incorporated is wiring for both sending and receiving as under flight conditions.





United's Hydraulic Tire Remover

• At UAL's Salt Lake shops, Bill Pitt is seen operating hydraulic tire remover, which he built from converted jack and welded steel frame. This tool has worked so well that United has adopted it at all repair stations, saving time, wheels, and tires.



Pan American Blade Rack

• By using this pigeonhole type rack for propeller blades, PAA saves much valuable shop floor space, and furthermore blades are more easily identified through grouping of tags. Swinging doors keep out dust and protect blades from being marred.





Ryan Hydraulic Hoist Car

• This hoist was built on a Ford V-8 chassis purchased second-hand for $75. After completely stripping chassis, except for hood and windshield, channel steel reinforcements were welded on each side, with cross pipe to form bearing for Gar Wood hydraulic cylinder. This cylinder, with necessary accessories, cost about $90.

Main members of boom are of 3-in. steel pipe cut about 17 ft. long. Front ends are tapered and welded together. At rear is cross pipe serving as pivot for boom when raising. Bearings at ends are 3½-in. pipe welded in place on framework, being kept in line while welding by insertion of 3-in. cross pipe. Radiator is protected by guard, and rest for boom is provided over hood to enable it to be fastened down when traveling any distance.

Oil pump for hoist is run by shaft extending back from V-belt drive at front of engine. This useful piece of equipment was designed and built by Ryan School of Aeronautics. Drawings show specifications.





Three International Policies —*Which Will We Have?*

By A. A. HARTSINCK

With no clues as to what government policy may be, U. S. airlines express their own views which, despite their typical American divergencies, all point toward the same goal.

FOR MORE THAN HALF A YEAR the airlines of this country have been anxiously waiting for some official pronouncement from the government on postwar international commercial air transport. And while there have been a number of semi-official conferences with Lord Beaverbrook of England, both in London and Washington, and such preliminary talks are now again going on with representatives of Russia and China there still has not been any indication as to the "shape and form" which the U. S. Government wishes the airlines to aim for in planning their postwar services.

There have been any number of statements by both British and American officials, most of them confused and confusing. Freedom of the air? No—strict regulation of all services. International regulation of all air services by one body? No—individual authority by each country absolute and complete. These are just a few of the opinions which have been widely publicized.

Small wonder, therefore, that the airlines of this country perplexed and disappointed have begun setting forth their own opinions and plans. Completely in keeping with the individuality of American enterprise all the airlines could not get together on one plan. Some 17 of them—all domestic lines except United, plus American Export—have formed a political action committee, headed by Samuel Solomon, president of Northeast Airlines. This group advocates open competition.

On the other side of the fence stands Pan American Airways, pioneer of the United States' international airlines—in favor of a "chosen instrument" policy, the precise chosen instrument not yet being directly indicated. On the same side of the fence as Pan American but with distinctly different views is United Air Lines, advocating a "U. S. Flag Airline" made up by cooperation of all lines each assigned distinct zones.

In an attempt to throw some light on this situation AVIATION is herewith presenting complete details on these three rather widely separated views on the manner in which the United States should obtain, and maintain, a prominent position in postwar commercial air transport outside the United States. These views are presented together for the first time as a comprehensive over-all picture of postwar plans.

Which of the three methods will be used is a matter which, eventually, will be decided upon by both the CAB and the State Department probably after the long heralded international air conferences have been held late this year or early in 1945.

The policy adopted by the 17 airlines—American, American Export, All American, Braniff, Chicago & Southern, Colonial, Continental, Delta, Eastern, Inland, Mid-Continent, National, Northeast, Northwest, Penn Central, TWA and Western, can briefly be stated as calling for—

1 Private ownership of all airlines and private management free from government direction or interference.

2 Encouragement and development by this country's government of a well-based and worldwide air transportation system.

3 Complete and open competition without geographical restriction, subject if necessary to some form of regulation by suitable governmental agencies.

4 "Freedom of transit" on a world-wide basis, and,

5 Establishment of such civil and commercial outlets as are required in the public interest.

The points set forth above comprised more or less a reply to the series of questions sent all airline operators early last year by the Civil Aeronautics Board also supplemented direct statements made to that governing body by the airlines in question. The group does not advocate duplication of effort along routes except where traffic potentials exist which would support more than one or two airlines. The matter of assigning routes would be left strictly to the CAB along lines already laid down, limited by the commercial rights which this country has and will acquire from foreign nations.

A very important point set forth by this group of airlines is its insistence that this country retain certain rights

(*Turn to page 274*)

International Applications by U. S. Airlines Through June 1944

American—New York, Boston, Chicago and Detroit to London and Paris.

American Export—New York, Boston, Chicago and Washington to Bermuda, Puerto Rico, Caribbean, Rome, Istanbul and Bombay.

Braniff—Ft. Worth to Rome, London, Stockholm; Houston to Balboa, Rio de Janeiro, Buenos Aires.

C & S—New Orleans to Havana, Balboa, Port of Spain, Rio de Janeiro, Buenos Aires; Chicago to Bermuda, Houston to Mexico City.

Colonial—New York to Bermuda, Nassau and Port of Spain.

Delta—New Orleans to Havana.

Eastern—New Orleans to Mexico City and Balboa; Miami to Nassau, Ciudad Trujillo, Rio de Janeiro, Montevideo and Buenos Aires; Boston to Nassau and Ciudad Trujillo; Houston to Mexico City; Washington to Ottawa and Montreal; any point or series of points in U. S. with any point or series of points in Caribbean area or Latin America.

Hawaiian—Honolulu to Los Angeles and San Francisco.

Inland—Great Falls to Berlin, and Alaska.

National—New Orleans, Tampa, Miami to Havana, Santiago, Mexico City and Balboa; Rio de Janeiro, Montevideo and Buenos Aires.

Northeast—Boston to London, Paris, Prague and Moscow.

Northwest—Chicago to Nome, Manila, and Calcutta via China; Seattle to Nome, Manila, and Calcutta via China.

Pioneer—Belem to Miami; San Juan to Charleston, Baltimore and New York.


Penn Central—U. S. to England via Seadromes, Miami to Barranquilla, and Port of Spain; New Orleans to Belize and Port of Spain; Buffalo to Ottawa.

TWA—Los Angeles to Honolulu, U. S. to Greenland, Iceland, Scotland, London, Paris, Berlin, Venice, Vienna, Budapest, Belgrade, Bucharest, Istanbul, Athens, Cairo, Bagdad, Teheran, Kabul, Karachi, New Delhi, Calcutta, Mandalay, Hanoi, Canton, Chungking, Lanchow, Hankow, Shanghai, Tientsin, Peiping, Mukden, Harbin, Tokyo, Attu, Kiska, Dutch Harbor and Anchorage.

United—Cleveland to Montreal, San Francisco to Honolulu.

Western—Seattle to Anchorage, Fairbanks and Nome; Los Angeles to Buenos Aires and Rio de Janeiro; San Francisco to Honolulu.

CONTRACTS WITH MINORS CAN BOOMERANG



By **LESLIE CHILDS,** *Attorney and Counsellor at Law*

The law makes strange provisions for persons who "aren't of age" —which means aviation organizations must exercise great care in signing contracts with under-21's.

With WTS contracts being cancelled right and left, more and more fixed base operators are again turning to civilian training as a means of keeping the wolf out of the hangar.

But, it should be remembered, civilian training has its pitfalls. One of the easiest ways for a flight school—or any other aviation organization, for that matter—to get into a peck of trouble, and perhaps suffer material financial loss, is to have contractual dealings with persons who are minors.

This is because, as a general rule, a minor's contract for anything save necessities are voidable. According to law, if a minor changes his mind after receiving the benefits of such a contract, he may disaffirm and demand return of whatever money he has paid.

The application of this rule, and the possible danger to an aviation organization in running afoul of it, is strikingly shown in this actual case—

The plaintiff a youth 20 yr. and 2 mo. old, contracted with a corporation operating a flight school for a primary flying course. The youngster paid $300 and took the course.

Then, still before he had become 21, the youth also took a limited commercial pilot's course, for which he paid $1,300. He completed this work before reaching his majority.

About a year later—after he had become 21—he brought an action against the flight school corporation to recover the $1,600 the grounds for the suit being that he had been a minor when entering into the contracts, thus could disaffirm.

The flying school's defense was based on the contention that the instruction had been "necessary," by way of education, for which the plaintiff should be held liable even though a minor. The defense also held that, since the plaintiff could not return what he had received i.e., instruction, he should be held to his contract.

Holds for Plaintiff

The lower court held for the plaintiff. Then the case went, on appeal, to a higher court which, in reviewing the record and upholding the youth said in part:

"It is agreed that the contracts were made in New York where the defendant's aviation school was located also that the questions raised in the case are governed by the laws of New York . . .

"The defendant contends that the contracts were for necessaries and were binding on the plaintiff even though he was a minor. Plaintiff's father was a weaver. The money which the plaintiff paid was in part saved by himself from his manual labor and in part contributed by his family from their savings . . .

"It would be hard to say that education in aviation was less necessary for the plaintiff than it would have been for another more affluent. But the law still guards the interests of minors against their own assumed improvidence and want of sound judgment. The judge found that the courses in instruction were not necessaries for the plaintiff . . .

"Lastly, the defendant contends that there can be no disaffirmance because the plaintiff could not return the instruction he had received by virtue of the contract. In New York, as in this Commonwealth [Massachusetts] a minor who has lost or even squandered what he received under the contract may nevertheless disaffirm it and recover whatever he paid or gave, or its value . . .


"On the whole . . . we think that under the law of New York the plaintiff is not precluded from disaffirming the contract and recovering the consideration he paid . . . Judgment for plaintiff on the findings." (14 N.E. 2d 467.)

—All of which meant that the flight school operator had to return the $1,600. The fact that the plaintiff couldn't return the instruction received constituted no bar to his recovery.

Under different circumstances—had the plaintiff been a wealthy young man for example—the two courses of instruction he had received might have been held to be necessaries, but the reasoning and final holdings in this case are both in accord with the great weight of authority.

And, as an illustration of the possible danger to a flight school or any other aviation organization in contracting with a minor, this kind of a case is hard to beat.

THAT OUR COUNTRY MIGHT *Out-Maneuver* THE ENEMY



Curtiss C-46 Commando Transport!


With the war in high gear, speed is the essence of victory! No nation can hope to wage global warfare and win without a means of moving vast numbers of men and a tremendous tonnage of supplies, long distances at high speed.

The Curtiss C-46 Commando Troop and Cargo Carrier has admirably met this demand for unprecedented mobility.

Today the Commando is a part of the greatest military transport program ever inaugurated. Tomorrow it will fly supplies for the rehabilitation of the world. Hard on the heels of victory, too, will come the Commando's conversion to both a luxury liner and a commercial cargo carrier for civilian service. LOOK TO THE SKY, AMERICA!

Another Contribution of
Curtiss-Wright Corporation
CURTISS-WRIGHT DIVISION
Toward Winning This War
BUFFALO · COLUMBUS · ST. LOUIS · LOUISVILLE

Member Aircraft War Pooling Committee, East Coast, Inc.



From our bomber plant in Georgia are coming B-29 Super-fortresses.

First American jet propelled plane, designed and built by Bell Aircraft.

The Bell Airacobra helped turn the tide at Stalingrad and on other fronts.

On many planes and ships are the Bell designed flexible gun mounts.

Preview of the new Bell fighter—as it will be seen in action by the Axis.

The Bell Helicopter—adaptable for many missions of war and peace.

Bell Aircraft at War

. . . A PROGRESS REPORT

A good fighter plane—basic in modern military operations—must pack plenty of wallop. That's why Bell Aircraft developed its hard-hitting Airacobra around a 37-millimeter cannon firing right through the nose of the plane.

This "cannon on wings"—first American single-engine fighter to carry a cannon in the skies—has turned in a performance which caused the Russians to tell WPB Chairman Donald M. Nelson the Airacobra was one of the American products they liked best. And today the Airacobra is being joined by a new Bell fighter, capable of high-speed, high-altitude performance.

Building such fighter planes is only one part which Bell Aircraft is playing in the war. On another front, the Bell Bomber plant in Georgia is producing the Boeing designed Super-fortresses (B-29's), largest long range bombers ever seen. And from our Ordnance Division in Burlington, Vt., come Bell designed gun mounts, including the new hydraulic power mount, that give the machine guns of many allied planes and surface ships their hitting accuracy.

Meanwhile work is continuing on two other war projects, America's first jet propelled plane, and the new Bell Helicopter.

Post-war activities are being locked in our minds until the day of Victory. Then our organization, staffed with production men of skill and imagination, will turn their thoughts to pioneering in an aviation world at peace.

© Bell Aircraft Corporation

MEMBER AIRCRAFT WAR PRODUCTION COUNCIL—EAST COAST, INC.

BELL *Aircraft*

PACEMAKER OF AVIATION PROGRESS

Niagara Frontier Division, Buffalo and Niagara Falls, N. Y.—Ordnance Division, Burlington, Vt.—Georgia Division, Marietta, Ga.

BUY WAR BONDS AND SPEED VICTORY

Southwest Flies 1,000,000th Training Hour

Civilian organization gives flight instruction to more than 15,000 embryo sky fighters.

LESS THAN FOUR YEARS after initiating training for civilian flight instructors at Sky Harbor, Phoenix, Ariz., as the basis for its part in the War Training Service program, Southwest Airways became one of the first schools to pass the millionth hour of military pilot training flying time.

One million hours, translated into miles flown, would carry an airplane around the world 3,452 times at the equator. In fact, it is enough flying time to send a 661,980-airplane armada on a mission from London to Berlin. Incidentally, approximately 4,638,600 takeoffs and landings were included in that time.

Primary training has been given to more than 15,000 students at Southwest. In addition to student pilots of the Army Air Forces, instruction has been afforded to other nationals representing 29 countries, including every Chinese student sent to this country for primary training. RAF students have received primary, basic, and advanced training.

With the first rush of the AAF's rapid expansion program Southwest Airways, as a preparatory step, began its WTS instructor school at Sky Harbor in Oct. 1940; today Southwest's staff has some 400 flight instructors who have spent nearly half of the 1,000,000-hr. total in the air with students.

First training flights for students were inaugurated at Thunderbird Field in Mar. 1941, with subsequent expansion of activities at Falcon Field and at Thunderbird II. From operations involving three airplanes, Southwest has grown to base more than 500 aircraft of all types.

And to cope with the huge maintenance problems presented, a "production line" aircraft and engine overhaul unit was developed.

In its intensive training program, Southwest has maintained a record of safety which ranks with the best in the nation—as witness Thunderbird Field with only one fatal accident per 167,000 hr. flown.



Jack Connelly (left) co-founder and president of Southwest Airways, checks with pilots just before they take off to fly organization's millionth hour. Pilots (left to right), Ralph Jordan, Al Stairs and Cliff Davis. All of these men were associated with company when it flew its first hour and each is a director of training—of Thunderbird, Falcon, and Sky Harbor, respectively.



Maintenance is handled by "production line" aircraft and engine overhaul unit. Splendid record of safety achieved by Southwest in intensive flying training program is due in large measure to this maintenance activity.




☆ *Meets . . .*

AND *exceeds* AN SPECIFICATIONS

Whether for anti-icing or for heating, this pump exceeds all existing performance requirements. Test run of 1313 hours—over 8 times the requirements and still going strong! Little wonder that it received AN rating. Backed by years of service of 75,000 predecessor units starting with the original ADEL Series "E," introduced in 1938 as the *first* designed specifically for U. S. Air Lines' protection of wind shields, propellers, carburetors.

Value to cost-conscious commercial operators was long ago affirmed by Mr. Luther Harris, P. C. A. Vice-President Engineering and Maintenance (now Col. Harris, Chief of Maintenance, Air Transport Command) who praised capacity, trouble-free performance in May, 1940.



An entire ADEL division is devoted exclusively to their manufacture. Not subject to ASU allocations. Deliveries as rapid as raw materials availability. For industrial application, pumping units available without motor where mechanical drive is preferred. For complete information contact nearest engineering service office.



After Victory the ADEL-AGE

ADEL

Industry's Sales Soar
. . . *But Not Profits*

By RAYMOND L. HOADLEY, *Financial Editor, "Aviation"*

In his annual survey our financial editor finds the aircraft makers' fiscal conditions much sounder — better than the perplexed investor might realize as he eyes the "stabilized" income.

WARPLANES may be coming off aircraft assembly lines in ever-increasing numbers, but profits of the industry have long since become stabilized around the 1942 levels.

The average aircraft maker's 1943 earnings were slightly below those of 1942, and stockholders can expect that this year's results will run about the same, depending, of course, on contract cutbacks and the time lag in shifting to new war orders.

But while profit margins decline in inverse ratio to the sales climb, a survey of the 1943 statements of 14 aircraft manufacturers reveals that much progress was made last year in brightening what had been a pretty gloomy financial picture. We would have preferred to have included more companies in the survey, however as this was written several like Curtiss-Wright, North American, Grumman, and Fairchild were still holding up their reports because of renegotiation problems.

The companies surveyed though, are thoroughly representative of the industry. There are plenty of bad spots left in the industry's financial set-up, as will be shown. Yet the over-all picture at the 1943 year-end shows sufficient improvement to indicate that the nation's biggest wartime industry will stay solvent during its critical peacetime reconversion period.

That's something we weren't able to predict with too much confidence a year ago.

Here, in a nutshell, is the way the industry's financial cards stacked up at the beginning of 1944: For the first time since Pearl Harbor the average company's cash position was larger than the taxes it owed, postwar adjustment reserves increased some 60 percent last year (although they're still inadequate), and current assets were up more than were current liabilities. Inventories and bank debt were higher, while the profit margin on sales was the lowest of all America's great industries except one (meat packing).

Now for a more detailed review and interpretation of the aircraft financial facts of 1943, plus a glance into the immediate future.

Sales of all but one of the 14 government contractors covered in this annual survey amounted to $4 870 millions last year against $3 300 millions in 1942. Deliveries of the same group this year may well run better than $6 billion.

On the other hand, net earnings of the group were $83 346 790 last year against $81,590 440 in 1942. This figure, though, is a bit deceptive since in nearly all instances (United Aircraft is a notable exception) the companies have yet to get their renegotiation clearance papers on their 1943 results. When they do get through the renegotiation mill it probably will be found that 1943 profits actually will be a bit under their renegotiated earnings of 1942.

An exhaustive study of the 1943 corporate earnings of more than 2,500 companies recently made by the National City Bank of New York showed that an average of 3.6 percent was earned on sales after taxes were deducted. This represented a decline from 4.3 percent for 1942. But the aircraft group showed an average return of only 1.8 percent, down from 3.2 percent in 1942.

Not only was the aircraft industry's margin on sales well below that of American industry generally in both years but it also was next to the lowest of any individual group. The meat packing industry had a profit margin on sales of 1.1 in 1943 and 1.2 in 1942. In contrast the automobile industry, which is largely engaged in aircraft work at present, showed an average profit margin of 3.2 percent on sales in 1943 and 5.2 in 1942.

In addition to the voluntary refunds (running up into hundreds of millions of dollars) which the industry returned to the government last year, the 1943 tax liability of the 14 concerns studied reached the amazing total of $336 946 000—more in taxes than the industry had in sales four years ago. But while taxes were stepped up from the $285 955 000 paid in 1942, there was one phase of the tax pic-

(*Turn to page 271*)

COLLATION OF 14 COMPANIES' 1943 STATEMENTS

	Sales		Net Earnings		Net Purchase		Dividends		Inventories (in thousands)	
	1943	1942	1943	1942	1943	1942	1943	1942	1943	1942
Aviation Corp	$72,621,507	$45,530,638	$3,519,437	$4,723,894	$0 61	$0 82	$0 20	$0 25	$12,096	$6 791
Beech	126,578,384	59 592 953	4,035,965	2,417,819	7 24	5 93	1 00	1 00	13,183	21,331
Bell	232 134,628	121 863,227	2,462,414	1,711,583	6 24	4 80	1 00	2 00	5,229	4,454
Boeing	493 188 000	386 567 000	4,482 870	5,237,000	4 14	4 84	2 00	1 00	2,742	4,594
Cessna	70 729 401	11 782 060	2,208 414	738 202	6 31	2 11	1 00	1 00	7 988	15,459
Consolidated Vultee	797,199,000#	831,295,000	19,267,000	20,875 000	13 76	14 88	1 50	1 00	158 280	101 464
Douglas	987,687,196	489 781,985	5,952,257	9,229,620	9 92	15 38	5 00	5 00	12,880	17,305
Jacobs	14,652,600	12,989,000	1,519,465	2,961 460	2 46	4 79	(none)	(none)	5 518	4,983
Lockheed	667,680,690	460 233,000	7,988 420	8,163 721	7 42	7 59	2 00	2 00	50,620	38,657
Martin	632 163 870	337,556,000	12,437,583	6,658 809	5 57	5 93	3 00	1 50	95,166	121,297
Piper	11,478,597	5,307,749	315 289	115 865	2 17	0 76	(none)	(none)	1,485	1,287
Republic*			3,025 954	1,105,061	1 20	0 63	0 25	(none)	1,758	5,548
Ryan	19 705,525	16,306,888	597 313	556,444	1 36	1 27	0 35	0 55	5,644	2,557
United	736 638,984	521,748 413	15,396 114	17,096,000	5 30	5 95	3 00	3 00	68,854	53,559

* Sales not available # 1943 sales after government refunds



First customer—and severest critic...

He learned to fly in World War I, without a parachute. He never had a crack at a Hun or a medal, felt that his wings were honor enough. When Uncle Sam gave him a sixty buck bonus and a ticket home, he couldn't go back to the old life—saw his future in flying.

Or maybe he was too young for the War, and hung around hangars with his heart in his eyes until he could trade odd jobs for stick time.


He slaved and saved to own a plane—an Army relic, a rebuilt crash job, a homemade copy. He gave lessons, sold rides, barnstormed, flew in prize meets, carried the mail, sometimes hit the headlines flying serum to a sick baby. But he wasn't a glory hound; just wanted to make a living flying—and often died at it.

If the crate acted cranky or the motor quit, he couldn't tell the crew chief or Maintenance. Maintenance was his affair—or his funeral.

He needed an engine that didn't need a nursemaid . . . one that was easy on gas, simple enough that he could service it, up to hard work and hard knocks on cowpasture airports.

Jacobs gave him such an engine, and later better and larger versions. Our first customer and severest critic, he and Jacobs together developed the workhorse of plane engines.

When the war came, the Jacobs was a natural for the bi-motored trainers, sure and safe for student pilots. On training fields from Canada to Cape Horn, the Jacobs takes more take-offs and full throttle time than any engines in combat . . . yet ran up their service periods between major overhauls from the originally specified 350 to more than 1,000 hours. Helped train fine bomber pilots fast, and cut costs for taxpayers!



We hope that these new pilots and their proud parents will not forget . . . how much of the speed, safety and success of this vast training program is due to the breed of men who believed and lived and worked to make airpower feasible . . . though many of them never survived to see the fact! . . . Jacobs Aircraft Engine Co., Pottstown, Pa.

JACOBS. Pottstown, Pa.


New Auxiliary Engine Gives More Power-Per-Pound

Use of double-acting principle said to save 30 percent weight; unit designed for ground as well as air applications.


To meet the need for larger auxiliary power plants for military and commercial aircraft as well as for ground uses, Tabor Mfg Co., Philadelphia, has developed a new two-cylinder aircooled engine designed to deliver a maximum of 32 hp at 2,200 rpm. Utilizing the double-acting principle, this Tabor-Hedges engine is said to weigh at least one-third less in pounds per horsepower than conventional four cycle engines currently being built.

While the weight ratio is a dominant factor in aircraft applications, the engine is held to be adaptable for furnishing starting power for lighting or fire-fighting equipment, or as an auxiliary unit in boats or other surface installations where light weight is desired.

Cooling, heretofore one of the most serious problems of double-acting internal combustion engines, is said by the manufacturer to have been eliminated by drawing off approximately one-third of the excess heat from inside the cylinder. This is done by pulling carburetor air through the pistons, although the same results could be obtained by using a separate blower if, for any reason, it was undesirable to pre-heat the combustion air.



Cut-away drawing of Tabor-Hedges cylinder shows method of internal cylinder cooling. Air for carburetor intake is drawn through ports shown in cylinder center; piston walls are cutaway to flow of air around them.



Tabor-Hedges double-acting auxiliary engine, developed for ground as well as aircraft uses, is 26 in. high, 26-in. long, and 21 in. wide. It delivers 32 hp at 2,200 rpm.

This cooling action is made possible by the design of the piston which, in a double-acting engine, is in reality a double unit, with conventional rings top and bottom.

However, in the Tabor-Hedges plant, the piston is hollow and the walls are cut away on opposite sides to give a free flow of air through cylinder ports located midway between the heads. The cylinders are long enough so that the rings do not close the ports. Since this engine is the equivalent of a conventional four-cylinder type—both having two power impulses per revolution—there is a continuous flow of cooling air through the pistons. Inner sides of the piston heads are finned and baffles are installed to direct cooling air to those points.

Outside cooling fins run full length of the cylinders from the top head to the crankcase, with extra fins around exhaust valves. A 16-in. four-bladed fan is enclosed in an aluminum cowling, from which 26-gage sheet steel fairing directs the flow of cooling air to the cylinders. The belt-driven fan travels at 1.2 times crankshaft speed.

New design techniques have been applied to the engine's crosshead. It consists of a wrist pin mounted at each end in ball bearings, the pin being securely attached to the piston rod since the outer connecting rod bearing is forked to make this possible. Ball bearings run between

(*Turn to page 272*)

A *Better* RELIEF VALVE
For Aircraft Hydraulic Systems




A pilot-operated piston is used in the Vickers Aircraft Relief Valve instead of the customary spring-loaded direct acting mechanism. The result is smoother operation and greater accuracy throughout a wider range of pressure adjustment. Variation in pressure from cracking point of valve to its maximum capacity is negligible (see curves below).


Vickers Balanced Piston Relief Valves (Model AA-11200 Series) are available in four sizes having rated capacities of 1.2, 3.5, 6 0 and 16 gpm, conforming to AN specifications. Actual capacities are, however, far in excess of these rated minimums. Without parts change all valves have operating pressure ranges from 300 to 2100 psi; adjustment is easy and simple. They comply with Winterization requirements of the Army Air Forces; their dimensions comply with the AN-6200 envelope.

VICKERS Incorporated · 1462 OAKMAN BLVD.
DETROIT 32, MICHIGAN

Engineers and Builders of Oil Hydraulic Equipment Since 1921




Representative of the exhaustive and severe tests to which these valves have been subjected is the Cold and Increasing Temperature Test recorded on the chart. The temperature increased from —65° F to 160° F in 26 minutes (one revolution of chart = 24 min.)




As indicated by the curves above, the variation in pressure from cracking point to maximum rated capacity of the Vickers Balanced Piston Relief Valve is considerably less than permissible under AN Standards. Consequently, less pressure differential is required between relief valve seating and unloading valve pressure.

VICKERS *Aircraft*
Balanced Piston
RELIEF VALVE




Underside view of Republic P-47 Thunderbolt wing with portion of skin removed showing construction at ribs A beneath space for ammunition belts aft of spar No. 1, which is at B. Aft of stringers C ribs are conventional construction, with lightening holes, as at D. Aileron hinges are at E.



Aileron control on Republic P-47 Thunderbolt includes push-pull rod A, with directional change accomplished by idler unit B. Control unit C attaches to aileron near center aileron hinge D. Push pull rod is installed aft of spar No. 2, E and spar No. 3, F.





Oil tank in Boeing B-17 Flying Fortress is installed in wing forward of front spar A fitting under ribs B—which have been reinforced to make up for section cut out for tank—with end resting against padded support on rib C. Tank is held in place by straps D, which fold under tank. Cover plate, removed in this view from below, hinges at E. In this view cover plate F for gas tank aft of front spar is swung down, hinging at G.

Yours— THIS ARRAY OF HELPFUL FACTS ON HIGH-SPEED METAL SAWING



For basic information on how you can operate metal sawing machines at full efficiency . . . to find out what can be done in your plant in the way of upping feed rates . . . to discover how you can assure cleaner cuts, save material and reduce saw servicing . . . get the Atkins Curled-Chip Manual. Here in concise, complete and organized form are all the facts about Atkins Curled-Chip Saws and the near-miracles in metal cutting performance they make possible. Besides details on the scientific cutting principle—described in a way every man will instantly understand as "right"—the Manual includes "SAWING RECORDS," a compilation of actual on-the-job Curled-Chip Saw production on work like your own. Make the Manual part of your file—send for a copy today—clip and mail the coupon now.

Mail Coupon Today for Your Free Manual . . . . . .

E. C. ATKINS AND COMPANY
444 S. Illinois Street • Indianapolis 9, Indiana
Agents or Dealers in All Principal Cities the World Over

E. C. ATKINS AND COMPANY
444 S. Illinois Street
Indianapolis 9, Indiana

Send me a free copy of the Atkins Curled-Chip Manual.


Name_____

Company_____


Address_____

City_____

State_____



Stabilizer of Boeing B-17 Flying Fortress is of conventional construction. Main spar is at A with leading edge spar B paralleling leading edge, both being of conventional I beam construction. Stringers C are dural angle sections. Elevator hinge points are at D



Engine-control bell cranks on Republic P-47 Thunderbolt are located on left side of craft just below top portion of engine mount A. Top bell crank B is part of propeller control. C is for carburetor mixture control. D is for throttle and E forms part of supercharger regulator control.

STUDS

Close Inspection at EVERY Stage Insures Precision Aircraft Studs

Closely controlled processes on a volume production scale have made National Screw a principal source of supply for Aircraft Studs.

Here's what it takes:

1. A special Aircraft Stud Department with personnel trained for this particular work.


2. Close control of every operation, from drawing of wire in our own wire mill to final inspection.

3. Modern heat-treating facilities under expert laboratory control.

4. Inspection at every stage of process, including individual snap gauge inspection of each piece. Additional facilities for projection method of inspection.



Aircraft studs are checked for required tolerance by 100 per cent roller snap gauge inspection



We are equipped to handle a full range of sizes up to ½ inch diameter and to produce precision threads without milling or grinding—steels and plating to meet AN specifications.

National HEADED AND THREADED PRODUCTS




Thread form comparator provides additional check by projection to 50 times actual size.

THE NATIONAL SCREW & MFG. CO., CLEVELAND 4, O.

Identification of Stainless Steels

THIS METHOD of identifying stainless steels is useful in separating various types that show marked differences in their chemical and physical properties. It is assumed that operator making tests will have some technical knowledge of alloys in question. A comparison with known standards is recommended. These tests are not intended to take place of a chemical analysis. If, for any reason, definite information must be known of alloys present in a piece of steel, safest way is to make a chemical analysis.



In preparation of samples, all specimens must be free from scale, which may be removed by pickling or grinding. In making a spot test, always grind a fresh area before applying the solution.

Nitric Acid Test—This testing solution is made by mixing 1 part of concentrated nitric acid and 1 part of water. A drop of the solution is placed on a freshly ground spot on the specimen. Attack is denoted by a boiling action or gas evolution from drop.

Magnet Test—Austenitic Stainless Steels (18-8 types) are non-magnetic in the annealed condition but become slightly magnetic when cold-worked. This slight magnetism can easily be distinguished from the stronger magnetism of the straight chrome types.

Spark Test—A spark test is made to separate Stainless Types 420 and 440 from non-ferrous alloys and ordinary iron and steel, since nitric acid under certain conditions may attack annealed specimens of some Stainless types. These steels are identified by the characteristic short "chrome" spark.

Hardness Test—Specimens are heated to 1,850° F. and oil quenched. Various carbon percentage ranges will be noted by different hardnesses as quenched. The non-hardening types will show low hardness as oil quenched from 1,850° F.

Muriatic Acid Tests. Specimens are placed in a solution of muriatic acid (1 part water, 1 part Muriatic Acid) at a temperature of 180°/190° F. A fresh solution should be used for each of the following tests:

a. After a 5 min. immersion, Type 303 will be coated with a heavy black smudge.

b. Within 2 min. after immersion, Type 316 can be identified by the very slight acid attack.

Data supplied by Carpenter Steel Co., Reading, Pa.

Helping the warbirds take a big bite—



Born of combat experience, the Navy's new Curtiss *Helldiver* is heir to all the improvements developed from battle crowded skies since Pearl Harbor. And one of the things that makes it a plane to write home about is its variable pitch propeller.

The intricate gear mechanism for these 3-bladed, full-feathering props is being built by the Detroit Gear Plant of Borg-Warner's Norge Division.

These propellers adjust to every change in altitude, wind resistance, engine speed.

The skillful engineering needed to produce gear mechanisms of such delicate sensitivity is another result of Borg-Warner's long-time principle: "design it better—make it better." More than 100 war items are today benefiting by it.

With the end of the war, this Borg-Warner principle will again be applied to the task of working with you in the aviation industry toward a better living for all America.

Partners with the Aviation industry in peace and war, Borg-Warner supplies these and other essential parts . . .

HYDRAULIC VACUUM AND FUEL PUMPS
REDUCTION AND PROPELLOR GEARS
UNIVERSAL JOINTS CARBURETORS
ENGINE PARTS AIRCRAFT CONTROL
CHAINS AIRCRAFT CLUTCHES
POWER TURRETS OIL COOLERS
HELICOPTER TRANSMISSIONS
COIL SPRINGS AND FLAT SPRINGS

ENGINEERING B-W PRODUCTION

BORG-WARNER

Peacetime makers of essential operating parts for the automotive, aviation, marine and farm implement industries, and of Norge home appliances . . . these units which form the Borg-Warner Corporation are today devoted exclusively to the needs of war—BORG & BECK • BORG-WARNER INTERNATIONAL • BORG-WARNER SERVICE PARTS • CALUMET STEEL • DETROIT GEAR AIRCRAFT PARTS • DETROIT VAPOR STOVE • INGERSOLL STEEL & DISC • LONG MANUFACTURING • MARBON • MARVEL-SCHEBLER CARBURETOR • MCCULLOCH ENGINEERING • MECHANICS UNIVERSAL JOINT • MORSE CHAIN • NORGE • NORGE MACHINE PRODUCTS • PESCO PRODUCTS • ROCKFORD CLUTCH • SPRING DIVISION • WARNER AUTOMOTIVE PARTS • WARNER GEAR

as compared with the active attack and evolution of gas on Types 302, 304, 321, and 347.

c Immerse specimens for at least 15 min. Type 443 can be identified by a brownish colored smudge.

d Immerse specimens in a separate container for 5 min., then remove them from the solution. A pungent garlic-like odor will be detected on Types 416 (Se) and 440F. This characteristic odor of hydrogen selenide gas will not be present in pickling Types 410 and 440.

Sulphur Spot Test—Three drops of sulphuric acid solution (1 part Sulphuric Acid, 3 parts water) are placed on a newly-ground spot on the specimen and allowed to react for 1 min. One drop of a 5% solution of lead acetate in water is then added to the acid drop and allowed to react for 15 sec. The spot is then washed with water and examined. A positive test for sulphur (Stainless Types 416 (S), 420F, and 430 F) is the presence of a black sulphide deposit.

Nickel Spot Test—Three solutions are required for this test:

Solution No. 1. Mix 125 cc of water, 100 cc concentrated nitric acid and 25 cc of 85% phosphoric acid. Solution No. 2. One part water and 1 part muriatic acid. Solution No. 3. Dissolve 1 gram of dimethylglyoxime in 60 cc of glacial acetic acid. To this solution add another solution, prepared by dissolving 10 grams of ammonium acetate in 30 cc. of ammonium hydroxide.

Procedure. Place one drop of solution No. 1 on a newly-ground spot on the specimen. Allow it to react for 30 sec. and then add one drop of Solution No. 2. This mixture is allowed to react for an additional 30 sec. and is then absorbed with white blotting or filter paper. One drop of Solution No. 3 is then placed on the moist spot of the paper. The formation of a red or pink coloration in the spot denotes the presence of nickel.

Stabilization Test—Test specimens are heated to 1,250° F. for 2 hr., furnace cooled to 800° F., then cooled to room temperature in air. The specimens are then placed in a cold solution of 3 parts nitric acid, 1 part hydrofluoric acid, and 6 parts water and left for 1 hr. Remove specimens from solution and wash with water. Stainless Types 321 and 347 will show a very slight attack from the acid. Stainless Types 302 and 304 will have rough, granular surfaces.

Type	Carbon	Chromium	Nickel	Other Elements	Brand Name
302	Over 0.03/0.20	17.00/19.00	8.00/10.00	Mn 2.00 max	Stainless Steel No. 4
303	0.20 max.	17.00/19.00	8.00/10.00	Mn 2.00 max., S or Se 0.07 min., Mo 0.60 max.	Stainless Steel No. 8
304	0.03 max	18.00/20.00	8.00/10.00	Mn 2.00 max.	Stainless Steel No. 4-A
316	0.10 max.	16.00/18.00	10.00/14.00	Mn 2.00 max., Mo 1.75/2.50	Stainless Steel No. 4-Mo
321	0.10 max	17.00/19.00	8.00/11.00	Mn 2.00 max., Ti 4 x carbon min	Stainless Steel No. 4-Ti
329	0.20 max.	23.00/28.00	2.50/ 5.00	Mo 1.00/2.00	Stainless Steel No. 7-Mo
347	0.10 max	17.00/19.00	9.00/12.00	Mn 2.00 max., Cb 8 x carbon min	Stainless Steel No. 4-Cb
406	0.15 max	12.00/14.00		Aluminum 3.50/4.50	Stainless Steel No. 1-JR
410	0.15 max.	11.50/13.50			Stainless Steel No. 1
414	0.15 max	11.50/13.50	2.50 max		Stainless Steel No. N-1
416	0.15 max	12.00/14.00		S or Se 0.07 min., Mo 0.60 max	Stainless Steel No. 5
420	Over 0.15	12.00/14.00			Stainless Steel No. 2
420F	Over 0.15	12.00/14.00		S or Se 0.07 min., Mo 0.60 max	Stainless Steel No. 2-FM
430	0.12 max	14.00/18.00			Stainless Steel No. 6
430F	0.12 max	14.00/18.00		S or Se 0.07 min., Mo 0.60 max.	Stainless Steel No. 6-FM
440	Over 0.12	16.00/18.00			Stainless Steel No. 2-B
440F	Over 0.12	16.00/18.00		S or Se 0.07 min., Mo 0.60 max	Stainless Steel No. 2-B-FM
443	0.20 max	18.00/23.00		Cu 0.90/1.25	Stainless Steel No. 3

Review of Patents

By A. HARRY CROWELL, *Registered Patent Lawyer*

FOLLOWING are digests of some of the more interesting recent patents on aviation developments granted by the U. S. Patent Office. Mr. Crowell will gladly furnish readers with free information on approximate cost and procedure in applying for patents and trademark registration. Address inquiries to him, care AVIATION, 330 W. 42nd St., New York City (18). Printed copies of any of patents listed here obtainable at a cost of 10c. each directly from U. S. Patent Office, Washington.

New Seaplane Design calls for adjustable sections or steps on bottom of hull to control performance of plane on water. Steps are controlled manually or automatically. Incident to aileron operation to effect hydrodynamic reactions augmenting aerodynamic reactions effected by ailerons and other flight controls.—2,348,541, filed May 14, 1941, patented May 2, 1944, J. F. Parker.

Fluid Pressure Control System automatically actuates landing gear retracting mechanism when parking brake control mechanism of fluid-pressure-actuated braking system is operated during flight. A coordinated control system is provided so pilot can operate landing gear by brake control elements.—2,347,847, filed Jan. 14, 1942, patented May 2, 1944, S. Schnell, assignor to Wagner Electric Corp.

Bomb Rack Mechanism provides for successive release of bombs from pluralities of stations in progressive order. Each rack station has a release mechanism which may be cocked, uncocked and tripped by a common means.—2,347,896, filed Oct. 18, 1939, patented May 2, 1944, L. J. Eyler and C. C. Pearson.

Projectile for use against aircraft and chute troops carries several metal cables wound thereon. One end of each cable is secured to projectile, other end carries a weight. Rotating motion of projectile plus bursting of rocket charges in hollow cables (also providing tracer effect) cause cables to unwind to foul targets fired upon. Means which releases weights from projectile body also serves to ignite rocket powder in cables when projectile has reached desired range.—2,341,094, filed Sept. 24, 1941, patented May 2, 1944, A. J. De Camp.

Gage for Propeller Pitch permits accurate determination of pitch angle without dismounting propeller regardless of angle at which fuselage and engine are positioned. Gage is self-clamping on blade leaving mechanics hands free to make adjustments and record data obtained.—2,348,005, filed Mar. 30, 1942, patented May 2, 1944, H. H. Roby, assignor to Roby, Inc.

High Altitude Mask for use with demand-oxygen supply mechanism is constructed to protect exhaling valve from freezing or restriction of air passageways. Marginal contour arrangement engages face of wearer on each side and under chin to provide breathing chamber completely sealed from outside air. Oxygen and air are supplied from any suitable apparatus. Exhaling passageways have double walls spaced to provide insulating dead air space. Chamber into which exhaling valve opens is kept warm by exhalation gases and transfers heat to inhalation gases which are normally cold.—2,348,108, filed Sept. 23, 1941, patented May 2, 1944, A. H. Bulbulian.

Dualer Bomb. Upon release, this multi-bomb discharges several peripheral bomb units thus forming wide-range pattern for straddling objectives.—2,348,240, filed Dec. 11, 1941, patented May 9, 1944, A. N. Braun.

(*Turn to page 285*)




FIG. 1 FIG. 2

New Aircraft Towing Unit provides lateral range to manipulate steerable wheel while moving plane. Fig. 1 shows perspective view of tow unit and Fig. 2 depicts details in section. Draft bar (1) carries tow ring (2) and slide block (3) to which are connected pivoted arms (4) fitted with axle engaging cup members (5). Arms are also connected to draft bar by pivoted links (6). Spring (7) connects slide block to draft bar at pivoted links. Movement of slide block towards tow ring on draft bar is limited by knurled nut (8) which has integral slit conical sleeve (9) adapted to fit in seat (10) of slide block. Tow unit is attached by grasping ring and pulling one arm outwardly causing slide block to move along draft bar toward ring. Links will tend to straighten, spreading arms so cup members are farther apart than ends of axle of steerable wheel thus permitting attachment of tow unit. Knurled nut is threaded down to cause integral conical sleeve to fit firmly against seat in slide block. Arms are thus prevented from spreading and tow unit is held in firm connection with steerable wheel of plane. Pin members may be substituted for cup members for use with tubular hollow type axle.—2,348,741, filed Feb. 12, 1943, patented May 16, 1944, Le Roy S. Jessen.

Book Reviews

BASIC AIRPLANE MECHANICS, by H. G. Lealey. John Wiley & Sons, Inc., N. Y. 404 pages, illustrations, index. $2.50

Deals with airplane construction, also operation, providing directions for repair and maintenance of plane components. Material analysis, routine procedures and precautions come in for special treatment.

THE BRITISH NAVY'S AIR ARM, by Owen Ruller. Penguin Books, N. Y. 248 pages, maps, photographs. 25c

A definitive picture of the British fleet's powerful air arm. Over 100 photographs illustrate a rapidly moving story of the intricate workings of the vast and many-sided machine which went into operation at its highest pitch of efficiency in the June 6th invasion of Europe. Coverage is accorded to every role of the naval plane working in conjunction with water-going boats. The book is an "official story" bearing the imprimatur of the British government.

BOMBERS, by Keith Ayling. Thomas Y. Crowell Co., N. Y. 194 pages, photographs, index. $2.50

The story of the bombing airplane from its beginning in 1912 through to Feb. 1944. Role of the bomber in this war is also considered in its relations to other types of aerial fighting craft. Included are glimpses into Russian air force details and the bomber strength of Japan.

AIR ACROBATICS ARE EASY, by D. J. Brimm, Jr., M. A. McGraw Hill Book Co., N. Y. Two sections, both of 133 pages, charts, and flat carton containing a three dimensional stereoviewer with interchangeable color plates. $2.50

Brimm's book and accompanying demonstrative paraphernalia comprise a novel approach to the problems of giving student pilots a graphic picture of aerial acrobatics from the viewpoint of the cockpit itself. The handbook lists and explains the many types of aerobatics delineating their origins and procedures, while the stereoviewer theater enables the student to observe them in action, providing visual simulation of the earth as seen from a plane's cockpit at several thousand feet.

(*Turn to page 286*)



HERE is the heart of an Aeroprop. Here are the simple components that produce the unvarying "on speed" Aeroprop performance that adds efficiency to the power and flight of many fighting airplanes.*

The Aeroprop's speed and precision of pitch control is achieved with unique simplicity. The entire assembly is self-contained and self-operated—unhampered by power lines or other accessories. Responding to powerful hydraulic pressures the blades may vary from low pitch to full feather in five seconds. Neither altitude nor temperature affect their swift automatic movement to the precise degree of pitch that produces top performance.

Equally important is the Aeroprop blade design incorporating hollow, rib reinforced, steel construction of exceptional strength and lightness—plus the overall simplicity that makes it possible for one man to install an Aeroprop in as little as 12 minutes.

Today Aeroprops have been assigned to service on two of the most formidable fighters in the Army Air Forces. Their amazing performance on these advanced ships is a guarantee of their high contribution to the conquest of the skies.

*P-39 AIRACOBRA • P-51 MUSTANG

KEEP 'EM FLYING! BUY BONDS!

Aeroprop *In War and Peace, Propeller Production at its Best!*

AEROPRODUCTS DIVISION • GENERAL MOTORS CORPORATION • DAYTON, OHIO



The Greatest American Legend...

He's a man without a last name . . . a fellow known to every American kid as "Uncle." He is everywhere in his great land—yet no one has ever seen him. He is the great spirit of America . . . calm, quiet, peaceful and kindly until he gets his "dander" up—then he is determined, strong and his wrath is relentless.

His is the spirit of sacrifice, toil and patriotism. He has weathered many wars, trials and tribulations—yet he is indomitable. He stood with Washington at Valley Forge . . . Perry at Lake Erie . . . Lincoln at Gettysburg . . . Pershing at the Marne . . . MacArthur at Bataan. He stands with every American to defend America.

Today, he stands with you . . . urging you to do more and more in the cause of Victory. To buy more War Bonds—to contribute to the blood bank—to stamp out Black Markets—to defeat inflation—to be untiring in your efforts to hasten the day when our enemies will fall before our might. Ask yourself squarely if you couldn't be doing *more* to aid this great spirit—then *do* it.

Let's keep this *greatest* American legend . . . *GREAT!*

APEX

THE APEX MACHINE AND TOOL COMPANY • DAYTON 2, OHIO

The AVIATION NEWS

BLAINE STUBBLEFIELD *Washington* HERB POWELL *New York*

20th Air Force Formed; New Global Bomber Fleet Ranged to Strike Anywhere in the World

Light planes' war record keys postwar designs . . . CAA's design for use . . . Airport bill . . . Aviation ROTC urged . . . WAAC appointments . . . Postwar transports visualized . . . SAE and IAS meetings . . . CAA outlines international routes

Creation of an entirely new AAF organization—the formidable 20th Air Force—was announced coincident with the initial bombing of Japan by Boeing B-29 "Superfortresses."

Operating on the bomber command plan, the 20th employs B-29's as a powerful air task force primed to strike anywhere in the world. Headed by Gen. H. H. Arnold, it is under joint chiefs of staff of all U. S. military forces.

As a global, rather than territorial, war arm, this separate aerial battle fleet is being directed flexibly through centralized control at Washington.

Thus, through our industry's development of the super-range bomber, military aviation has entered a potent new global air war phase. Further, the launching of the 20th in the Far East last November, its activation on delivery of B-29's early this year, and its present action against the Japanese prove our industry's ability to put victory-winning air power on both sides of the world at once.

Light Planes' War Record Keys Postwar Designs

When the full story on performance of light (liaison) planes in this war is available it will add much to present knowledge of design and use of private planes in future. Endurance of the little observers despite constant beating, ability to operate with but limited maintenance, capability in bad weather, and performance on restricted ground areas has surprised even the engineers who produced them.

Of the dozen or so light plane makers, all producing for the war various aviation products, most are finding time to work on their postwar programs. Experimentally, they are engineering or flying practically every reasonable design idea of the past and present. Pushers, single seaters, family sedans, two controllers, non-spinners, flying cars, roadable planes, autogiros, and helicopters—all are being tried.

Designers think they are doing pretty well improving utility and safety, and they are less concerned with speed for amateur flying than they used to be. What bothers them most is price. Very few if any producers believe they can turn out a "minimum" two-place plane during early postwar period for much less than $1,500. Still more frequently mentioned tag is $2,000. Those working on four-place designs admit they will have a very hard time getting down anywhere near the $2,000 mark.

Volume production is the only thing that can help the price problem. To get volume production, producers will tend strongly to eliminate choice of two or three engines and various equipment. Some producers will offer a minimum plane (which the purchaser can add to out of dealers' stocks if he wishes) and a de luxe model with every desirable gadget attached.

CAA's "Design for Use"

To facilitate postwar production of light planes, the CAA proposes to authorize the design of planes according to their intended use. For instance, a family plane does not need the same stress characteristics as does an acrobatic type; the weight saved can be given over to fuel. Design categories suggested by CAA are: Acrobatic training, general purpose, transport and special purpose.

Airport Bill; JAV Meeting; Wichita Plans

General opinion is that a well-planned small airport program can help private aviation more than anything else. Charles I. Stanton, CAA administrator, is actively promoting a bill in Congress to provide about 3,000 more airports in addition to the 3,000 already established in this country. Stanton proposes that the States match federal funds for construction of fields, following the plan under which the federal highways system was developed (also see item "Federal-State Airfield Plan" in Transport News).

A large proportion of the fields would be Class Fours for light planes. It is expected that some small fields will be built with private funds. National Aeronautic Association has called for a Joint Airport Users' Conference (July 24-25, Hotel Statler, Washington, D. C.) to assist in planning the program.

Wichita, Kan., may have a series of airparks within walking distance of business and residential areas if aviation



MORE POWER PLUS "THUNDERBOLT"

New Republic P-47 "Thunderbolt" fighter-bomber with greater power and range of action, and stated to carry heaviest bomb load of any single-engine fighter, is now in combat in European and Pacific theaters. Powered with turbosupercharged, 2,000 plus-hp. 18-cyl. P. & W. "Double Wasp" engine, it has larger water injection capacity which adds several hundred extra hp. and doubles time of peak emergency power use. Static tampany "Paddle-blade" propeller increases climbing speed 400 ft. per min. Plane can do better than 400 mph., exceeds 700 mph. in power dive, and with 50 percent more oxygen capacity has longer operation at altitudes up to more than 7 mi. Added internal fuel capacity gives longer range, which can be extended when auxiliary tanks are substituted for 1,000 lb. bomb under each wing. New "bubble" canopy affords "round the clock" visibility and new gunsight provides improved sighting for eight 50-cal. wing guns.

Coming Up

July 17-18: Air Traffic Conference, Denver.

July 24-25: National Aeronautic Association Joint Airport Users' Conference, Hotel Statler, Washington, D. C.

July 27-28: Summer Meeting, Institute of Aeronautical Sciences, Los Angeles.

August 1-2: Eastern Division Meeting, Airworthiness Requirements Committee, New York; Western Division Meeting, Los Angeles.

August 2-3: National Aeronautic Association Business Meeting, Denver.

September 4-6: Annual Meeting, Aero Medical Association, Hotel Jefferson, St. Louis.

September 22: Air Transport Meeting, Institute of Aeronautical Sciences, Hotel Statler, Washington.

October 5-7: Society of Automotive Engineers National Aircraft Engineering & Production Meeting, Engineering Display, Hotel Biltmore, Los Angeles.

November 9-10: Fall Meeting, Institute of Aeronautical Sciences, Dayton.

November 15-18: Second annual Clinic of Domestic Aviation Planning, Oklahoma City.

December 4-6: Society of Automotive Engineers National Air Cargo Meeting, Hotel Knickerbocker, Chicago.

December 17: Wright Brothers Lecture, Institute of Aeronautical Sciences, Washington.

January: Thirteenth Annual Meeting, Institute of Aeronautical Sciences, New York.

January 8-12: Society of Automotive Engineers Annual Meeting & Engineering Display, Book-Cadillac Hotel, Detroit.

leaders have their way It is expected that many other cities will develop similar plans

Urges Aviation ROTC

To provide 50 000 pilots per year for postwar air power National Aviation Trades Association (training contractors) proposes an over-all air reserve ROTC, covering basic military flight requirements with the civil training program NATA believes that training should be given in colleges and high schools, thus producing minimum interruption in the student's life Permanent airports located at the schools would be available for military use in case of war Outstanding students would receive scholarships

Postwar Craft Visualized At C-W Forum

Preparations for the future received consideration at the Curtiss - Wright Production Engineering Forum held recently in St. Louis How the airlines are working toward 'tailor-made" aircraft to meet the various needs of postwar air commerce are described by W. W. Davies, superintendent of research, United Air Lines Chicago in his paper, "Some Thoughts on Design for Airline Operation '

Transport operators, said Davies formerly took planes which were available and adapted them to their needs, but henceforward the airlines would work closely with the manufacturers to attain the best product He specifically mentioned the airlines' interest in cabin and cockpit design Davies described various types of planes as 'rough guesses" of what he believes may be seen on the airways within five or six years after the war Descriptions follow

Adding to the Language

Boston—Acceptance of new aviation nomenclature received endorsement when Jos T Geuting vice president of General Aircraft Corp and chairman of the Aero Chamber's Personal Plane Committee announced a 4-yr personal plane landing facility expansion program

The words are *airpark* identified as a community center for personal flyers, costing from $10 000 up and *fightstop* a runway with pay phone and coin-in-slot gasoline service built adjacent to a highway, costing from $6 000 to $10 000

1 Cargo transport 125 000 to 150 000 lb gross wt day capacity 80-90 passengers night sleeper 50-60 reasonable cargo space speed 125-450 mph operating altitude 10 000-27 000 ft

2 Domestic de luxe sleeper and day plane 70 000-80 000 lb gross wt day capacity 60-80 night sleep 30-35 moderate cargo space speed 275-300 mph operating altitude 10 000-20 000 ft range 700-1 000 mi

3 Domestic standard sleeper and day plane (if above plane required extra fat for speed) minimum 60 000 lb gross wt day capacity 50-60 night sleep 25-30 speed 240-275 mph operating altitude 10 000-20 000 ft average trip length 400-750 mi Also straight day version of this plane carrying 60-70 passengers Intelligent if costs could be lowered to attract general public

4 Trunkline feeder plane 30 000-45 000 lb gross wt capacity 30-37 passengers or 6 000-10 000 lb cargo or combination of both through use of movable bulkhead adjustable at station stops speed 210-227 mph operating altitude 4 000-12 000 ft average range 150-200 mi

5 Domestic off-line feeder plane (essentially same design as trunkline feeder craft but smaller) 15 000-20 000 lb gross wt capacity passenger craft 12-18 speed 200 mph average trip lengths 50-200 mi

6 Full cargo plane Ship probably featuring general characteristics of trunkline feeder to carry shower cargo as different traffic from high speed cargo which would be accommodated in skipping space of passenger planes

Engine Papers Sefare SAE

Two papers featured at the National War Material Meeting of the SAE, held recently at Detroit were Lessons From Aircraft Engines Applied to Heavy Duty Ground Vehicle Engines,' by Vincent C Young, chief engineer Wilcox-Rich Div, Eaton Mfg Co and 'Some Aircraft Engine Production Methods," by Martin M Hoiben, project engineer, Wright Aeronautical Corp

Auxiliaries IAS Topic

Recent meeting of the Institute of the Aeronautical Sciences in New York City featured a comprehensive talk on design, production and installation of auxiliary engines in aircraft by Dr Rowland Burnstan, president, Lawrence Aeronautic Corp Also a short revealing film was exhibited by Jerome Lederer of Aero Insurance Underwriters The latter showed the running 'dial story" of the instruments in a training plane during the test flight in which the ship lost its port wing and crashed, killing the pilot

PAAC Appointments

New members for the U S National Commission of the Permanent American Aeronautical Commission are announced by the State Department, terms of members named to the first commission (Sept 1941) having expired Named are Oswald Ryan, CAB member, chairman, Rep Alfred L Bulwinkle of North Carolina, William Burden Assistant Secretary of Commerce, Sen Bennett Champ Clark, of Missouri, Lt. Col Louis Johnson former Assistant Secretary of War, Arnold Knauth specialist on admiralty and shipping law Department of Justice, Stephen Latchford, air law, State Department, Stokeley Morgan chief, aviation division State Department, Dr Francis Reichelderfer, chief Weather Bureau and T P Wright, director Aircraft Resources Control APB

International Routes Outlined by CAA

CAA's basic route pattern for international air commerce operations as revealed by Chairman Pogue provides for about 50 routes which would expand the 60 000 mi already approved for overseas transport to make a total of 140 000 mi under U S operation (see map and list of routes in article "Three International Policies' page 1901.

Flow of traffic was the criterion in drafting the routes Any consideration of specific carriers must await individual check of the applications filed with the CAB by some 100 carriers. Absence of clarification of U S policy brought formulation of the plans under the present law interpreted by CAB as calling for competitive private operation on some foreign routes (such as across the Atlantic)

The board emphasized that many routes could not be operated without agreements with countries involved Acquisition of foreign landing rights, expected to be by inter-governmental negotiations, would be a function of the State Department

★ SPOT CHECKING ★

Sikarsky helicopters of the YR-4 type allied our forces in the air-borne invasion of Burma Men flying them are volunteer pilots especially trained at the Sikorsky factory They arrived in India last January have their own technicians and ground crews.

Scott Aviation Corp. is now operating a Fairchild 24 as a sales department aid to save company officials time in contacting dealers and customers.

Twenty-fifth anniversary of the NC 4 flight—initial air conquest of the Atlantic in 1919—was observed in late May at a special dinner sponsored by the Aircraftsmen engineering society of the Aircraft Factory Navy Yard Philadelphia with societies manufacturers, and air transport companies participating

Douglas C-54 (DC-4) transports are now flying combat crews and high priority airplane parts direct to New Guinea via Hawaii Old route was by way of Australia with transloading to C-47's for hop to New Guinea Flown by United under contract to Pacific Wing ATC the planes average 41 hr for the run carrying from 8 000 to 11 000 lb of cargo or 6 passengers (including crew of 6)

"Planning the Future of Your Business," is new handbook prepared by Assn of Consulting Engineers for Committee for Economic Development Setting forth detailed concrete steps to attain high postwar levels of production and employment It is available from head CPFF offices (they are organized in 2 400 communities)

Credit for invention of the Army Navy production award program goes to Capt Lewis L Strauss USNR who developed the idea for E Days now flown by nearly 3 000 plants following endorsement from Secretary Knox in 1941


Recent forced landing of a Navy Martin Mariner at Willets Dry Lake Ariz (Unit mean the 20-ton plane had to be dismantled and shipped out Until her hull went a-belly while skidding she was credited on landing gear—a specific rig with two sets of double tire wheels, fitted with reinforced mounts for attachment to plane And with this improvised landing gear she took off and completed her journey After takeoff pressure levers released the shock links and wheels and skid were dropped



IMITATION IS SINCEREST FLATTERY

After struggling for many months against 'Hurricanes' with two 40-mm cannon Germans have brought out this Junkers 88 with gondola mounting 40 mm quick firing cannon in unsightly blister under nose

NOW AVAILABLE } Magnesium Alloy Sheets by REVERE



THE world's largest magnesium sheet and plate mill is now in operation—by Revere Here are produced the three alloys in demand for wartime uses

Revere Magnesium "M" — Magnesium Manganese alloy with moderate strength and good forming characteristics.

Revere Magnesium "FS-1"—magnesium-aluminum-zinc alloy, a general purpose metal combining high strength with good forming characteristics

Revere Magnesium "J-1"—magnesium-aluminum zinc alloy, the highest strength sheet available.

When production exceeds war needs, Revere Magnesium Alloys will be available for use in an ever-increasing number of fields, such as automotive, household appliances, railroads. These alloys will bring revolutionary economies in weight, power, machining, production, labor For technical assistance in planning conversion to these wondrously light magnesium base metals, write Revere

REVERE
COPPER AND BRASS INCORPORATED
MAGNESIUM-ALUMINUM DIVISION
Founded by Paul Revere in 1801
Executive Offices: 230 Park Ave, N. Y. 17, N. Y.

REVERE MAGNESIUM ALLOY SPECIFICATIONS

Grades and Tempers
h = hard rolled o = annealed
r = hot rolled

Alloys M, FS-1, and J-1 can be furnished in these tempers

Revere M	Tempers h, o, r
Revere FS-1	Tempers h, o, r
Revere J-1	Tempers h, o, r

The mill should be consulted regarding these tempers

LIMITS OF MANUFACTURE
Sheets and Plates

Supplied from 0 020 inch and thicker in a wide range of sizes, depending upon the thickness and weight of the sheet or plate

INDEX TO SPECIFICATIONS

Form	Revere Alloy	American Society for Testing Materials: Alloy Designation	ASTM: Sheet Section No	Society of Automotive Engineers: Aeronautical Material Specifications S. A. E.	Navy Bureau of Aeronautics: Alloy Designation	Navy: Sheet-Section No.	Navy Department: Alloy Designation	Navy: Sheet-Section No	U. S. Army Air Forces: Alloy Designation	Army: Sheet-Section No.
Plate, Sheet and Strip	M	11	B90-41T	51	4370		11	47 M 2	1	11339
	FS-1	18X	B90-41T				18	47 M 2		11343
	J-1	8X	B90-41T		4380**		8	47 M 2	2	11338

**4380 annealed 4381 hard rolled



with EMYCEL* - the rot-proof fabric finish!

ABOUT FOUR YEARS AGO Roxalin discovered that fungus attack was responsible for many aircraft fabric failures that were generally attributed to dope deterioration.

To combat this newly recognized cause of an old complaint, Roxalin pioneered EMYCEL, another finish engineered for specific performance. The derivation of the name itself indicates EMYCEL's special function —*Ex* meaning "out"—*mycelium* meaning "fungus."

Special fungicides incorporated in EMYCEL prevent fabric rotting caused by fungus spores which are especially prolific in the tropics and which propagate rapidly in the fabric enclosed areas of wings and control surfaces. In these areas exist the ideal condition for fungus growth—warmth and high humidity.

This positive protection against rotting is obtained with the first coat of EMYCEL; no extra cost or operations are involved.

Second big feature of EMYCEL is equally important. It can be sprayed on in all kinds of weather. Moisture in the air will not cause blushing. You don't have to allow for "rain checks" in your production schedule.

OTHER VITAL ADVANTAGES

EMYCEL is economical. It always reduces the number of coats required—savings up to 30%.

EMYCEL is faster. All-spray system cuts fabric finishing time by eliminating hand brushing.

EMYCEL protects fabric from injury. Super-flexibility resists impact of flying objects at sub-zero or high temperatures.

EMYCEL is C. A. A. approved and backed by three years of world-wide service on all types of aircraft.

ROXALIN *Flexible* FINISHES
INCORPORATED
ELIZABETH • NEW JERSEY

*Patented

WATCH ROXALIN IN AVIATION

Government of India seeks applicants for position of professor of aeronautical engineering in Indian Institute of Science, Bangalore, India. Statements regarding qualifications, salary, etc., can be obtained from India Supply Mission, 2107 F St., N.W., Washington (6), D. C., from the Hon. William Burden, assistant Secretary of Commerce, Department of Commerce, Washington (25), D. C., or from Aviation.

Oklahoma City has created an aviation commission to coordinate its aviation expansion program. Steadman Acker has been named aviation consultant and Commission members are: Fred Jones, who was named chairman, D. Cullinan, Dan James, Maj. Herbert Peck, Dr. C. Q. Smith, Roy J. Turner, and Hosea Vineyard.

Feature of shipment of aircraft from the Atlantic Overseas Air Service Command, Newark Airport, is a liquid spray, which after application to aircraft boiler congeals in less than half an hour to form a thin pinsih protective coat sealing the plane against weather and corrosion during its ocean trip. This coat readily peeled off after arrival. resists —80 to 180— F temperatures. Pealings are salvaged and ground up for re-use. Planes, parts and other equipment processed and shipped from Newark base have constituted approximately 25 per cent of the total shipping out of New York harbor.

Identification has now been released by the War Department on three new combat planes. These are the A-26 'Invader' new Douglas light bomber, which is a more powerful version of the famed A-20 'Havoc'; the P-63 'Kingcobra' larger and improved version of the Bell P-39 'Airacobra' and the P-59 'Airacomet' Bell jet craft.

National Headliners Club has awarded a bronze medallion to Aviation Writers Assn. as special recognition for consistently improved reporting on aviation.

AAF Training Command has instituted a new program to fit former AAF and WTS instructors for flying capacities in the service following discontinuance of various flight-teaching projects.

Shipbuilder Henry Kaiser is publicizing a plan for a non-profit corporation for establishment of 3,000 to 5,000 personal plane fields in the first half year after the war. Cost of the smaller number of fields is put at $750,000,000. It is stated that some 4,500,000 persons could be employed in this broad move to build a market for private aircraft. Details of financing have not precisely jelled but the RFC might be called upon for one-third of the initial cost.

Manufacturing methods relative to aircraft and parts comprised the topic at a recent meeting of some two score Central and Eastern Aircraft Council members held at Goodyear Aircraft.

Newest and biggest cold-test chamber in operation at AAF Materiel Command laboratories, Wright Field. With a 60,000 cu. ft. capacity chamber measuring 25'x20'x8' ft. can accommodate fuselage of a B-17. Temperature can be dropped as low as —95 F. Five engines provide power for refrigeration units.

Design for interchangeability of both parts and assemblies of aircraft was primary consideration at recent four-day National Aircraft Standards Committee seventh national meeting in Los Angeles.

Air Power Spearheads Invasion

Amatica at War
Aviation's Commonique No. 31

Germany's war machine took three staggering blows in one week. (1) When the USAAF completed its over-Europe shuttle terminus in Russia; (2) when Allied forces knocked Rome out from under Nazi Italy; and (3) when—finally and most emphatically—Anglo-American invaders poured into Europe paced by the power of 11,000 planes.

Heavy tactical support of Allied troops by bombing and attack aviation still left thousands of heavies and fighters to continue strategic operations against Germany's production and communications.

Just before the invasion, the biggest air fleet ever mobilized, totaling 7,500 of the massed 11,000 planes, hammered rail stations, highways, bridges, and transport centers all along the invasion coast of Europe—a 24-hr. 6,000-ton punch of fire and explosives.

To what extent the bombing of Nazi industry and transport has weakened the German powers of resistance and how effectively air attack can support ground forces on a big scale, will be observed conclusively as the war in Europe develops. Several Allied weapons not publicly known, some of them in aviation, are being employed.

Both parachute and glider troops dropped behind the Germans with successful results. Allied aviation and airborne troops took many airfields and it was further demonstrated that bombing of sufficient weight can churn up runways faster than the greatest effort can return them to usability. Air bombs were put down to make shell holes for the protection of troops on exposed terrain.

The sparse initial air resistance to the Allied attack seemed to reveal that Goering has not been able to accumulate a strong fighter plane reserve to meet the assault. He had lost fighters heavily through the 'birth control' attacks on his plants, and at least 1,200 by ground strafing plus shot-down losses in the air. 50 and sometimes 100 in a day. His production rate of not more than 2,000 planes, all types, per month, cannot support such attrition.

The Luftwaffe's high command called an emergency meeting, according to a clandestine radio report, when the Russian-based AAF bomber shuttle started. Although B-17's and B-24's formerly could reach all far-eastern Nazi installations they had to limit their bomb loads to do so. With the Russian bases, they can now hit much harder, hence the Germans will have to redistribute their fighters. Via the shuttle, B-29 striking power would also be greater.

Preparation for the shuttle involved shipment to Soviet bases of 12,000 tons of runway steel matting, 10,000 tons of gasoline, and masses of other goods. The work was started last February.



"FLYING DUCK" FIGHTER

This new fighter, offered in both single-engine pusher type (depicted here) and as twin-engine tractor, recently made first test flights in England. Designated the Miles 35 shipboard fighter, diagram (top) indicates features, including contra-rotating prop, heavy armament and good pilot visibility. Plane is somewhat reminiscent of Westland Pterodactyl of 10 yr. ago. Photo (above) shows Miles 35 trial model (about half size) with smallest engine, and using fixed landing gear) at takeoff. Interesting points are very large bulge in tail, apparently housing coolant radiators, and extra wheel under engine to prevent damage to propeller in tail-down landings. (British Combine photo.)

★ CANADIAN NOTES ★

By James Montagnes

Noorduyn UC-64 "Norseman" single-engine transports are now being used by RCAF in removal of wounded from front lines. RCAF is also using twin-engined Douglas DC-3 "Dakotas" as ambulance transports.

Canadian Vickers, Ltd., Montreal, has a government contract for 36 Douglas DC-4 transports, powered with Rolls-Royce "Merlin" engines, for Trans-Canada Air Lines. Delivery of first craft is to be within 18 months of delivery of engineering data to company. Building DC-4's in a government-owned section of its plant, Canadian Vickers will receive 2 percent management fee. A target price has been set at $250,000 for each aircraft and the government has right to increase or decrease the order with reasonable adjustments in this price. Government pays all tooling costs allowing company 1 percent increase or decrease for each $20,000 decrease or increase in the cost of aircraft.

Trans-Atlantic crossing record was set recently by a Canadian-built "Mosquito," which crossed from Lisbon to Northern Ireland, a distance of 2,200 mi., in 6 hr. 40 min.

Rehabilitation of Canadian veteran airmen has started, with first five having been placed as transport pilots with Trans-Canada Air Lines.

Canadian Pacific Air Lines carried 31,833 passengers during the first four months of 1944 an increase of 76 percent over same period in 1943. Freight and express amounted to 3,130,469 lb., a decrease of 11 percent, and mail totalled 612,240 lb., a decrease of 27 percent.

By F. H. Fullerton

Despite a decrease in personnel of some 1,000 workers under peak figures of 4,5, Boeing Aircraft of Vancouver, B. C. has increased its production efficiency and achieved a steady rise in schedules—for production methods have been streamlined via re-tooling and re-jigging, and marked decreases in man hours on certain jobs have been recorded. Bulk of personnel reduction came during past three months through natural labor shrinkage, terminations, army call-ups, and a weeding process bringing current personnel to just under 11,000.

Production of deck plates for Consolidated PBY hulls will be undertaken in Boeing's Chilliwack, B. C., plant, which to date has confined its work to wing assemblies.

American Screw Products

OF LOS ANGELES

Announces Its New Name

THE DEUTSCH COMPANY

This change was found desirable because of confusion arising from similarity of the former name with that of other companies.

The policies and traditions established by American Screw Products – progressive designing, careful engineering, precision manufacturing, and meticulous inspection, are being carried on by the same management.

Thousands of Allied planes flown into battle – equipped with our products – are convincing evidence that these quality standards have been successful.

THE DEUTSCH COMPANY

Manufacturers of Hydraulic Valves and Fittings

7000 AVALON BOULEVARD LOS ANGELES 3 CALIFORNIA



Where Research Develops Quality, Precision Products

★ CALLING NAMES ★

Capt. Trow Sebree, PCA pilot, has been appointed director of the Navy Transitional School to be conducted by PCA at Roanoke, Va.

Ward Canaday, Wittys-Overland president, was awarded a certificate by United Air Lines in appreciation of his contributions to airline progress.

Pan American Airways has awarded to yr pins to **Jesse M. Van Law,** special asst. to the manager of the Atlantic division, and **Albert G. Thomas,** maintenance training superintendent, both at LaGuardia Field, N. Y.

Wolfgang Langewiesche has joined Chance Vought's flight test department.

Harold G. Fitzpatrick was elected secy.-treas. of Jordanell Aviation Corp. and **William C. Hoff** was appointed asst. technical director. Also **Helen Willyoung** becomes promotion manager.

Capt. Ralph J. Johnsen, UAL pilot, was named assistant supt. of the company's Pacific flight operations. **Victor J. Theimer** was named supervisor of tabulating, and **Floyd Drake,** principal of public schools of Pangor, Wis., for the past nine years, joins the Chicago engineering department. **Dale Medland** of UAL's personnel department was named employment manager for the company's system, headquarters in Chicago.

Lloyd Williams, formerly director of finance for Timm Aircraft, was appointed full-time executive secretary of the District Committee for Economic Development.

C. E. Stryker was named west coast representative of Bendix Products aircraft landing gear department.

Garet W. Denise is named general manager of Littelfuse Chicago plant operations.

Irmengarde Eberle, well-known writer, joins publicity staff of Railway Express air express division.

Hollis R. Thompson, V.-p. of American Airlines, was named head of the company's route development department.

Earle Stewart, Glenn L. Martin design engineer on landing gear, was elected to the SAE committees on wheels and brakes and re-elected to a committee on aircraft shock absorbers.

Jane Hintsen, junior materials and process engineer, was appointed to technical committee A of the SAE and ASTM.

Col. Herbert K. Bairley has been named chief of the photographic laboratory of the AAF Materiel Command's engineering division at Wright Field.

Robert E. Black, president of The White Motor Co., was elected a director of Pennsylvania Central Airlines Corp.

Thomas C. Hill, controls design engineer at Glenn L. Martin, was advanced to head a new combined controls-hydraulic design group.

George F. Bauer was named chairman of the Metropolitan Air Shipping Committee in Aviation Section, N. Y. Board of Trade, and **Warren L. Baker,** Socony Vacuum Co., domestic manager aviation sales dept., was appointed chairman of the Metropolitan Fuels and Lubricants Committee.

Gus Lozzar, flyer, airport engineer and CAB safety specialist, was elected a director and v.-p. of Southeastern Air Service and **James V. Carmichael,** attorney, was elected a board member.

N. J. MacDonald, v.-p. Thomas & Betts, was named chairman of newly organized Aircraft Electrical Council of NEMA.

McLean Stewart resigned as executive director of training for the CAA following completion of his work in the pilot training program. He will return to his work as v.-p. and chairman of Harriman & Ripley investment bankers.

Lee J. Robison was appointed sub-division head of industrial and public relations at the Douglas Oklahoma City plant.

R. J. Delacy was promoted to subcontracting supt. of Convair's Vultee Field division.

All directors of the Boeing Airplane Co. were re-elected at the annual stockholders' meeting and organizational meeting of the board of directors.

George H. Clark, v.-p. engineering, Formica Insulation Co., was elected a director of the Society of the Plastics Industry.

Dr. L. G. Lederer, medical director of PCA, was appointed to the Reserve Operations Committee of the Natl. Safety Council.

Lt. T. W. Turner was assigned officer in charge of the Naval Training School at Glenn L. Martin.

Alex Raid, Northwest Airlines district traffic manager at Spokane, becomes asst. traffic manager at Chicago and is succeeded by **W. Robert England,** office manager and traffic representative from Seattle.

George French joins U. S. Plywood Corp. as production engineer. Formerly with the woodworking department of Western Electric, he has done industrial research for U. S. Forest Products Labs. and was a consulting engineer for the Natl. Lumber Mfrs. Assn.

Robert L. Cox, v.-p. Chase Brass & Copper, was re-elected president of the Copper & Brass Research Assn.

Edward L. Warner, Jr., former associate editor of Automotive & Aviation Industries, was appointed manager of the aviation division of Automotive & Aviation Parts Mfrs. Inc.

C. Bedell Monro, PCA president, was awarded the honorary degree of Doctor of Laws, Marietta (Ohio) College in recognition of his many contributions to the development and progress of commercial air transportation.

D. E. Dunlap, Douglas Aircraft engineering manager at Tulsa, returns to the home plant as executive engineer. W. L. Whittier, also at Tulsa, takes on the added duties of engineering manager of the plant.

Albert A. Arnhym, consulting engineer, Solar Aircraft, was named an associate fellow of the Institute of the Aeronautical Sciences in recognition of his pioneering work in the field of aircraft comfortization.

James P. Jeffrey was appointed personnel manager of Hamilton Standard Propellers division of United Aircraft, succeeding **W. T. Beebe** who becomes personnel manager of Pratt & Whitney at K. C.

Frank E. Dunn is named supt. of tool orders for Consolidated Vultee's Ft. Worth division. **J. E. Cranmaly** moves up as supt. of field operations. **Fred F. Gignilliat** becomes general employment supervisor, and **E. L. Williams** is new supt. of major assembly departments.

J. Nelson Kelly is named executive v.-p. of Fibre Locknut Corp., affiliate of Boots Aircraft Nut. He was first manager of Floyd Bennett and N. Y. Municipal Airport fields and was also operations manager at Roosevelt Field.

Obituary

Capt. Lawrence J. Chiapping, Materiel Command, died recently in Dayton. Veteran TWA pilot, he had flown more than 2,250,000 mi. and had been loaned to AAF to run service flight tests on Lockheed Constellation, participating in its record-breaking transcontinental delivery hop from Burbank to Washington on Apr. 17. Capt. Chiapping was a graduate of Univ. of Calif., and army flying schools at Brooks and Kelly fields.

If Your AVIATION Subscription

is about to expire and you want to keep your files of AVIATION complete—your subscription should be renewed promptly.

Because of the paper shortage, the subscription list is 'frozen', hence if your subscription lags by so much as one month, your renewal must go at the end of a long waiting list. In this event, we may not be able to send you the missing issues because no "extras" can be printed.

Also if your copy of AVIATION is late in reaching you please bear with us. The delay is beyond our control—in most instances it is due to wartime transportation.

THE WASHINGTON WINDSOCK



By ELAINE STUBBLEFIELD

Critical war materials were flown across oceans during the submarine blitz—**for safety.** If anyone, back in the Dole Race days had predicted such a development, he would have sounded silly.


In three days, says Sir Richard Fairey, head of British Aircraft Commission, the industry in England could turn out enough planes to last all the world's commercial airlines for five years.

A man suggested to this department that it advocate putting all the world's fastest airplanes on a starting line and run them a hundred miles and see which one comes out ahead. But of course, he said, they will all claim they could have done better at some other altitude.

Overselling aviation is an old and regrettable practice. In the public markets, it has damaged the sale of various aero items in the past. Anyhow, many light plane builders are planning to tell their customers exactly what their machines can do and can't do—so said customers won't re-sell them in disgust as soon as they find out they can't race P-38's with them.

Quite a number of the light plane builders are going into simplified control and non-stall design for post-war production. It looks as if the slow-and-safe school sponsored years ago by the Aircraft Development Section of the Bureau of Air Commerce, may accordingly run even with, or ahead of, the old speed school.

More difficult than say aviation design, production, or operational problem, is development of a workable world air transport agreement. Britain and the United States seem to be trying to fox each other, and countries not consulted are resentful. Here at home so many officials are taking part that some don't know what the others are doing. Reason for the long delay in forming a policy is that aviation is being used as a political weapon to force other issues.



WHITAKER

has the experience and facilities to produce

★ WIRING HARNESSES ★ BONDING JUMPERS

★ CABLE ASSEMBLIES ★ AIRCRAFT and RADIO CABLE PRODUCTS

Roll up your blueprints and specifications—dictate a letter outlining your needs—and dispatch your wiring problem to the nearest Whitaker plant. We welcome inquiries covering either war-time or post-war production . . . Backed by a quarter of a century of specialized experience producing wire and cable products, Whitaker has the facilities for large-scale production—plus the ability and "know-how" for quickly turning out cable assemblies to meet rigid specifications.

In addition to an engineered wiring service, Whitaker also offers a quality line of standard cable products. There will be no obligation involved in your getting the facts, so why not write today!

WHITAKER CABLE CORPORATION

(Formerly Whitaker Battery Supply Company)

Kansas City, Mo. · St. Joseph, Mo. · Philadelphia · Oakland

President Reports 170,000 Planes Built, May Total Was 8,902; Cutbacks Now in Sight

ACC states program . . . West Coast plants in new production phase . . . Termination bills up . . . New wind tunnels . . . Navy cancels "Conestoga"

President Roosevelt has announced that 175 000 airplanes were produced by U S plants between Mar 11, 1941, date of enactment of the Lend-Lease law, and Apr 1, 1944 He said that 33,000 of those planes were sent to the air forces of other nations. Allied governments paid for 7 000 of the planes, and 25,000 were delivered under Lend-Lease

Charles Wilson, chairman of the Aircraft Production Board, and T P Wright, director of Aircraft Resources Control Office, reports that between Dec 7, 1941, and May 1, 1944, the industry produced 171,257 planes having a total airframe weight of 1 430 000 000 lb

Production of warplanes in May was 8 902, a monthly total exceeded only once before (8 118 in March) Record outputs of all three heavy bombers (Consolidated B-24, Boeing B-17, and Boeing B-29) were scored in May

Despite design changes and increasing weight per unit, production in 1944 will come close to 100,000 in units and $18 000,000 000 in value Unit output increased 3 400 percent from Jan 1940 to Mar 1944, as compared with a weight increase of 5 800 percent Average airframe weight has increased from 3,500 lb in 1940 to 10 000 lb in 1944

In 1938, Mr Wilson said, Germany was building five planes to this country's one The Nazis reached a maximum 27 000 in 1942 but were exceeded that year by the United States Wilson estimates that Germany's output is now down 25 percent to around 20 000 or less than 1,700 per month Japan's production, still figured to be going up, is calculated as between 1,000 and 1,500 per month

Sea Production Cutbacks 'Hitting" at Year End

The inevitable cutback in production of warplanes is now in sight If the war should continue on its present scale reductions will be in order around the year-end If Germany should show marked weakness or collapse before then the cutback might come earlier There will be curtailments or stop orders on some types as the character of war changes Gen Arnold recently said it would be ideal if the Air Force had but two fighters The same reasoning applies to other military categories It is hard to standardize on a few models because enemy strategy constantly demands new or revised designs to meet ever-changing conditions

Navy's curtailment in overall production of fighters actually was merely elimination of over-quotas Nevertheless, Navy is taking less than it could get—which amounts to the first aircraft cutback in this war

Charles E Wilson, WPB executive vice chairman, heads a new WPB panel to deal with cutbacks and cancellations

ACC States Program; Lee Handling Reorganization

Fully supported by the industry, the Aeronautical Chamber of Commerce headed by its newly elected president Eugene Wilson, is planning an aggressive post-war program One of ACC's important initial steps is a publicity campaign for (1) practical government policy on termination of contracts and reconversion; (2) favorable policy on labor and taxation, and (3) promotion of U S air interests and strong air forces, backed by a sound aircraft manufacturing industry Avery McBee, of Glenn Martin, is chairman of the Public Relations Committee

John Lee, former manager of AWPC West, has taken over the reorganization of the chamber on a three-month basis. A permanent ACC manager had yet to be agreed upon at this writing The AWPC's activity will taper off as the war nears an end and the ACC will substitute peacetime services The Aircraft Manufacturers' Council a subdivision of ACC, will increase its functions

Eventually there will be a new division in the Chamber as between airframe engine propeller, and parts manufacturers

West Coast Plants Launch New Production Phase

Among West Coast plants end of "preparations" and beginning of a new phase in the war is seen in contract terminations, shifts to other models, and negotiations for new contracts

Douglas announces the approaching termination of its A-20 contracts, the Vultee Field division of Consolidated Vultee turned out its last BT-13 trainer (the 11,537th) Boeing prepared to switch its Plant No 2 at Seattle to B-29's; Consolidated's San Diego division wound up its Coronado" and "Catalina" production; North American announced it would transfer B-25 production to Kansas City; and Hammond Aircraft dropped first its "swing shift," then its graveyard shift '

The Douglas termination, to be tapered off with delivery of the last A-20 some time in September, will affect 8,000 aircrafters Hammond has dropped 1,200, most of them women But Northrop announced its need to hire 2,000 to help step-up production of P-61 Black Widow" night fighters. The Boeing and Consolidated shifts presumably will not considerably affect present personnel

An AWPC memo pointed out that the shift to heavier planes further limits the percentage of women who can be employed because the work is too strenuous It reminded that the full impact of selective service reclassification of plane plant workers hasn t yet been felt Still in the plants, said this new memo, are hundreds of men who have been classified 1-A and will be inducted as soon as the armed services can absorb them"


North American, though still producing B-25 s at its Inglewood plant, proceeded with its preparations for removal of those lines to install P-51 facilities instead Vultee, in announcing completion of its BT-13 contracts, stated its plant will be devoted to "combat craft projects" It has been operating B-24 engine, wing panel, and tail unit assembly lines for several months and recently added P-38 wing center sections

Lockheed added its bit to the brighter side of the picture by releasing first photos of its new "Constellation" final assembly line, with a striking line of Connies ' tip to tip

Termination Bills Up

Legislation on termination of contracts is expected late in July There are two bills S 1718 by Senator Murray and a bill by the House Judiciary Committee These bills differ on questions of simplified appeal to courts from settlements by procurement agencies and in methods of accounting. Most serious controversy centers on claims by the controller general of the Treasury that he should audit settlements before payments are made

But probably both bills in their final form will limit the controller to post-audit of settlements only In cases where fraud is suspected Nearly all government officials agree that settlement and payment should be expedited and that contractors should suffer no losses at the hands of the government.



ALLISON'S NEW 'W" PACKS "3 000 HORSES"


New 3,000 hp Allison V 3420 series liquid cooled engine features W ' design (four 6-cyl banks) Weight per hp has been reduced, and parts in power section are reparied 97 percent interchangeable with Allison V 1710 Adding "hundreds of horses" new engine can be employed in either buried installation of large craft or in conventional fighter plane nacelles




Puts planes in the air faster

Designed and engineered by Hartwell, this new inspection door latch, H-4525 can save as much as 30 minutes in the inspection of a single plane. It rivets to the inspection door, and *fits flush with the outer surface*. Weighs less than ½ oz.

The new Hartwell latch has been approved for use on aircraft by the Army Air Forces. Application has also been made for Navy approval. The latch can be installed in a standard Army Air Forces' cutout shown on print 43G2853. It consists of four parts: trigger and bolt, made of light gauge steel, aluminum bracket, and twin springs.



Front view of Hartwell latch installation



Back view showing latches in open position

Can be used on inspection doors of any size or shape

Because of its design and construction the Hartwell door latch can be used with *metals, plastic* or *plywood* of varying thicknesses, and on inspection doors of any size or shape. It can also be used without a hinge, where multiple latch installations are employed, as indicated above.

The number of latches used per inspection door depends upon its size, shape and load, and whether or not a hinge is used.



Press and the Door Flies Open!

Finger-tip pressure on the trigger of the Hartwell inspection door latch releases the bolt, permitting the door to pop open. Pressure on the bolt locks the door in place. It eliminates the former slow, tedious removal and replacement of inspection doors.

Single source for 779 different aircraft production parts and tools

HARTWELL
AVIATION SUPPLY COMPANY
3417 Crenshaw Boulevard, Los Angeles 16, California
Dallas, Texas • Detroit, Mich. • Kansas City, Kansas

NACA Conferences; New Wind Tunnels

The NACA has conducted executive conferences at Cleveland and at Sunnyvale, Calif. for the East and West Coast sections of the industry, respectively. Technological means of putting greater pressure on the enemy were discussed. NACA has completed an altitude wind tunnel (at the Cleveland engine laboratory) capable of simulating temperatures encountered at 30 000-ft. altitude, and of evacuation to an air density of 50 000-ft. altitude. The tunnel can take propellers near 20 ft in diameter, so that engines of 3 000 hp can be tested.

Meantime, AAF Materiel Command announces that construction is underway at Wright Field on a funnel-shaped 10-ft. wind tunnel for testing models of high altitude bombers and fighters. It will generate winds of more than 600 mph at temperatures as low as —67 deg. F. Temperatures and pressure conditions ranging from sea level to 50,000 ft. will be simulated.

Navy Cancels "Conestoga"

It is now revealed that Navy has cancelled its contract with the E. G. Budd Mfg. Co. for 175 of the company's "Conestoga" stainless-steel cargo planes. This is reported to put Budd back to a mere 25-craft order out of the original 800 total, since the Army has already cancelled a contract for 600 of these planes.

Navy, it was said, will meet its transport needs with Douglas craft. The statement mentioned delayed deliveries of the "Conestogas" and further "pointed to production costs substantially more than the company's original estimates."

Erratum

Through a typographical error, a formula was represented incorrectly in Richard G. Smith's article, "Graphic Simplifications in Computing True Airspeed" (May AVIATION). The wording (col. 2, page 155) was "... the value of K (= actual temperature rise + adiabatic temperature rise)." It should have read "... the value of K (= actual temperature rise — adiabatic temperature rise)."

★ ASSEMBLY LINES ★

American Propeller Corp. has received new contract for additional propeller blades for Navy's Curtiss SB2C "Helldiver."

The 5,000th P-38 — 13,000th plane to come off Lockheed's assembly line—was painted bright red, named "Tipped" and highlighted ceremonies at presentation of "E" Award to company.

Allison hitting 5 000 mark—for P-38's—was Consolidated Vultee, San Diego Div.

Westinghouse Electric's meter division is now producing electronic blind-landing instrument which guides pilots back to home fields.

Curtiss Wright announces delivery of approximately 29,000 warplanes to the services to date. Between Jan. 1938 and Dec. 1943 it is planes were built in company's six plants. 6,880 before Pearl Harbor.

Consolidated Vultee observed its second production anniversary with announcement that more than 2 000 bombers and transports had been turned out during past year.

Weyerhaeuser Timber Co. has commenced production of plastic molding compounds for commercial markets, at Longview, Wash., plant.

Aircraft production by Convair's San Diego Div. has enrolled trainees of 16-704 employees and 3,000 supervisors.

B. F. Goodrich Co. will issue licenses for Ledu. and Defaur patents on high frequency heating in rubber applications. H. H. Glodvad Grell (33 University Pl., N. Y.) will issue licenses for application to plastics, wood, and other products.

Production - Battle Citations: Four Stars—Bullard Co., The. Ferrol-Birmingham Vendo Co.; Two Stars—Klekhafer Corp. Alloy Steel Gear & Pinion Co.; Electromaster, Inc.; Switlik Parachute Co.; One Star—Fansteel Metallurgical Corp., Tantalum Defense Corp., Berry Bros., Inc.; Caterpillar Tractor Co. Army-Navy "E"—Lockheed Aircraft Co., Panelyte Div. St. Regis Paper Co., Electric Sprayit Co., Voss Bros. Mfg. Co.; Republic Aviation Corp., Douglas Aircraft Co., Superior Plant Guard Gridan—Cook Electric Co., National Security Award—Bausch & Lomb Optical Co.

★ FOR THE RECORD ★

General Controls Co. opened two new branch offices at Boston and Cleveland with William Marsh manager at former, L. F. Rusly Wetzel at latter.

The Bristol Co., Waterbury, Conn., opened a new branch office in Houston, Tex. with D. D. Ault on manager.

Revere Copper & Brass Dallas division, opened a district sales office in Indianapolis under supervision of F. H. Anderson.

General Engineering Co. assets have been acquired by Thomas H. Speller who will continue the business.

Helicopters, Inc., has now reorganized under the new name Bendix Helicopter Inc.

Worthington Pump & Machinery Corp., Harrison, N. J. has taken over the Electric Machinery Mfg. Co. of Minneapolis, synchronous motor and electric generator maker. Not long ago Worthington also purchased Ransomes Macalmery Co. of Dunellen, N. J.

Photoprint Co. has changed its name to Template Reproduction Co., division of D. L. Ward Co. and has moved East Coast plant from Elizabeth, N. J. to 401 N. Broad St., Phila. (8), Pa. However company's West Coast plant will continue to operate under old name at 1137 S. Olive St., Los Angeles (15), Calif.

Jacobs Aircraft Engine Co. has appointed L. E. McGlvena & Co., N. Y., to direct its advertising.

Western Electric has taken a three-year lease on 250,000 sq. ft. of industrial property in St. Paul, Minn. The company will also take possession of DPC factory at Scranton, Pa., adding 87,000 sq. ft. of manufacturing space to Western facilities.

Eclipse-Pioneer Div. of Bendix Aviation Corp. announces opening of a new West Coast branch office to serve Western users at 7360 Wilshire Blvd., Los Angeles.

Selas Corp. of America is new name of The Selas Co. No change is being made in organization, personnel or service.

American Chain & Cable Co. has acquired Wilson Mechanical Instrument Co. maker of "Rockwell" hardness testers.

Offices for designing consulting aeronautical engineering and airlines operations engineering have been opened by Frederic Flader in Buffalo, N. Y. under name Frederic Flader Co.

Reynolds Molded Plastics Div., of Reynolds Spring Co. has been acquired by Continental Can Co. No change in personnel, policies or plant location is planned.

Cleveland Automatic Machine Co. has opened new district offices at Hartford, Conn. under managership of W. O. Aldrich, formerly special representative of Cleveland office.

Industrial Hard Chromium Plating Corp. has been formed with headquarters at Newark, N. J. The new corporation holds exclusive manufacturing rights to hard chrome plating equipment under patents owned by Metals Protection Co., Indianapolis, Ind.

Rheem Mfg. Co. has purchased a large stock interest in Platt-LePage helicoptar manufacturers. Rheem which will take an active part in the management is licensed to use Platt-LePage patents and designs.

Glenn L. Martin Co. reports that production Instrument section of its Instrument laboratory has been transferred from engineering department to inspection department in line with policy to keep engineering research and development activities separate from production and inspection functions. Gordon T. Ball continues as chief of Instrument laboratory in new set-up.

Midwest Aircraft Products interest has been sold by L. L. Duncan, who has retired as president. M. M. Culver, former v.-p. engineering, becomes president and A. M. Fargo, secy.-treas., assumes additional duties as v.-p. charge of sales.



BIGGEST TUNNEL GOES INTO OPERATION

World's largest wind tunnel, capable of testing aircraft with spans up to 75 ft., recently placed in operation at NACA Ames Aeronautical Laboratory, Moffett Field, Calif., can measure lift forces of 180,000 lb. and drag forces of 32,000 lb. Six 6,000 hp. Westinghouse motors furnish power to circulate 24,000 cu. ft. of air through structure. New Douglas Navy scout bomber was first plane tested in huge tunnel throat (60x40 ft.), size of which is indicated by men seen at base of supports. With tunnel determination of undesirable characteristics corrective measures can be applied direct to full-size plane. Tunnel will also act as check on smaller wind tunnels in which only models or parts of planes are tested. Relationships determined between tests on models and on actual planes will lead to new accuracy in checks on models representing larger aircraft too big for mounting in tunnel.

★ KNOW-HOWS ★

Automatic "hardness certifier" to test sheet metal parts and impress personal inspection and heat-treat stamps in one operation has been devised by A. Vleek, Glenn L. Martin Co. inspector. If metal is too soft machine remains inoperative. It is stated to save half time formerly required.

Lubricating oil compounded to thicken when heated and thin when cooled in order to give more efficient operation of engines through wide temperature ranges is new experimental development announced by California Research Corp., a Standard Oil subsidiary.

Made of duPont "Lucite," new airfield guide-light lenses are stated to provide good weather resistance and dimensional stability while affording a sharp reduction in weight which is important consideration because equipment must be light for quick transportation and ease of handling required in swift advances of air forces to new bases. Lenses were developed by Stimson AGA Plastics, Chicago.

Target for Tomorrow



WHEN you take a grip on the Lumarith training model of a Colt 45 (molded over metal) you may not think right off of a postwar automotive steering wheel (or even of Lumarith warplane controls). But the analogy is there.

The army indoctrination "gun" fits your grip perfectly. Its fine balance and business-like detail give a sense of confidence. Agreeable temperature comforts your hand.

These are qualities important to future automotive steering wheels, handles and knobs—improved grip, better looks, more comfort—all assured by Lumarith, the foremost plastic for molding over metal. These are advantages inherent in the toughness, lightness and thermal stability of all Celanese plastics, plus high flexibility and impact strength, surface and color permanence, moisture resistance.

Unlimited choice of color and the big range of Lumarith formulations for molding over metal (and assuring compatible expansion and contraction coefficients) provide materials precisely suited to individual jobs.

*Reg. U. S. Pat. Off.

P. S. Our Technical Staff talks your language. Celanese Celluloid Corporation, The First Name in Plastics, a division of Celanese Corporation of America, 180 Madison Avenue, New York City 16.

Executive Order Increases Airline Fleet To 300 Planes, Two "Surplus" Plans Offered

Minnesota upheld against Northwest . . . USSR, China in air policy talks . . . ATC's third birthday . . . Court backs CAA code . . . Federal-state field plan urged . . . EAL, Braniff, National win safety awards

Maximum fleet to be operated by the airlines has been "upped" by executive order from 200 to 300 planes. For military work Army has liked Douglas DC-3's as well as its own Douglas C-47's, mainly because of the small doors and some observers believe the airlines will get back enough of their requisitioned ships to re-attain their prewar fleet of 350.

Col. Edgar S. Gorrell, Air Transport Association president, explains that the airlines gave up, by sale and lease, a total of 650 airplanes—that is, 45 to foreign governments, mostly to Britain, 295 to the armed services, and 310 on order with manufacturers or approved by WPB for delivery.

Transport operators especially the smaller ones, have a hard job converting the returned planes from military to civilian use. All operators have difficulty finding crews to fly them, but release of pilots from the discontinued WTS program is easing this problem. Chances are that some small airlines will be released this year from the ATC contracts for domestic operations.

Probably some suspended airline schedules will be restored as planes are returned. The average prewar workday for a plane was 7 hr. Now it's about 12 hr. Thus the fleet of 300 planes already authorized will do 3,600 hr per day, as compared with 2450 hr per day by 350 planes before the war.

Offer Two Disposal Plans For War-Surplus Craft

Two plans for disposal of war surplus transport planes have been proposed. The Pogue Aircraft Subcommittee of the Surplus War Property Board suggests that the airlines be permitted to lease as many of the planes as they want for five years, with privilege of terminating the lease upon purchase of new replacements from manufacturers. And Air Transport Association urges in addition a proposal that airlines be permitted to do conversion work on planes themselves. However, manufacturers object, they want each plane returned to its original designer for conversion.

Second disposal plan is one favored by some aircraft manufacturers. They suggest that U. S. military transport planes be sold to operators the world around, who will obtain parts from the U. S. makers, accustom themselves to U. S. planes and buy new equipment of the same types. Opinion is there would be enough surplus transports to make both plans feasible.

USSR, China in Air Policy Talks at Capital

The business of formulating a postwar overseas air transport policy is deeply involved in international politics. Delegations of five Russians and three Chinese have been in Washington, talking with the State Department's air group. Latter is headed by Joseph C. Grew, who is technically advised by CAB Chairman Welch Pogue and Assistant Secretary of Commerce William Burden.

Assistant Secretary of State Adolph Berle recently conferred in London with British air authorities. Later, during a House of Lords debate on international air policy, Lord Beaverbrook said that the British consider the United States committed to an effort to obtain a world agreement providing right of innocent passage and technical stops. Beaverbrook based this conclusion on President Roosevelt's remarks at a press conference months ago. Observers believed at the time that Mr. Roosevelt was quoting from the secret report of his Interdepartmental Committee on International Aviation.

The British debate indicated the two countries have agreed to seek, at the forthcoming international air meeting, establishment of a world body which would govern world air transport.

Minnesota Upheld In Case Against Northwest

State taxation of interstate air transport properties will be an issue for a long time. On May 1, 1936, Northwest Airlines computed its personal property tax on the basis of planes in Minnesota on that day. Minnesota disagreed—assessed all planes owned by Northwest. The company appealed from a state court ruling for the state, and the Supreme Court upheld the Minnesota court five to four.

Chief Justice Stone wrote the minority's view that the tax was unconstitutional. Justice Jackson, concurring with the majority, said the court would need the help of Congress in solving the problem. CAB has suggested that Congress act upon the question. As a result of the court's two-sided decision, there is revived interest in the side-tracked Lea Aviation Bill (HR 3420) calling for a Civil Aeronautics Commission which would consult with the states to avoid multiple taxation.

Federal-State Field Plan Urged at Air Forum

Addressing one-day Southwest Civil Aviation Forum held at Oklahoma City, May 26, CAA Administrator Charles I. Stanton advocated a federal and state government partnership in establishing the nation's postwar civil airport system. It should, he said, include approximately 6,000 airports.

Stanton declared that federal funds should be made available to states on a formula basis, taking into account four factors—area, population, number of aircraft, and number of existing accredited airports. Under his plan, each state would have to match a percentage of its quota of federal funds. Foreseen was operation of 300,000 civilian planes within four years after the war.

A feature of the forum was a question-and-answer program in which representatives of 16 cities in three states took part.

New Heli-Bus Project

Faith in the future of commercial helicopters continues boundless. Arthur Hill, president of the Atlantic Greyhound Corp., announces that the bus industry proposes to establish helicopter-bus service to 1,000 towns and cities, without subsidy. Operating over 50-to-200-mi. distances, such service, he said, would carry the multitude who are entitled to the benefits of aviation.

EAL, Braniff, and National Win Safety Awards

Awards were recently made by the National Safety Council in connection with its Air Transport Safety Contest covering 1943. Sixteen of 17 domestic airlines were noted to have flown 1,225,000,000 mi. without a fatality and on a passenger-mile basis, the record was stated to be 160 percent better than in '42—75 873 - 368 passenger-miles per passenger fatality.

Group A award, for lines flying more than 100 million passenger - miles annually went to Eastern Air Lines; Group B leader (from 10 to 100 million passenger-miles) was Braniff Airways; and Group C (less than 10 million passenger-miles) was led by National Airlines.

Special certificates went to Chicago & Southern, Colonial,



"BOMBER-SIZE" GLIDER

New giant glider, British "Hamilcar", used for large scale airborne invasion landings, has nose access compartment to carry light tank. Glider with span exceeding the 202 ft. of "Lancaster" bomber, requires towing by plane of "Albemarle" type. (British Combine photo.)



Pattern indication gives the pilot a visual "picture" of his attitude at all times, regardless of the degree of bank, climb, or dive.



No angular limitations! The Sperry Attitude Gyro indicates pitch and bank without any angular limitations!



No caging! Because there are no angular limitations, the instrument never has to be caged . . . not even in acrobatics!



Attitude Unlimited!

New Sperry Attitude Gyro provides pattern indication . . .

has no angular limits . . . needs no caging!

WITH THE NEW Sperry Attitude Gyro Indicator a pilot can, *for the first time*, loop, roll, dive, climb, or fly at any angle with visibility zero, and still always know the attitude of his plane relative to the earth.

The spherical dial is marked to provide the same "pattern" type of indication whether by daylight or by any artificial light . . . a single glance tells the story.

The suspension for the spherical dial of this new Sperry instrument allows full 360° freedom of indication in the roll and pitch axes of the airplane.

A small gyro spinning at 23,500 r.p.m. stabilizes the sphere and keeps it erect in relation to the earth's surface. *The airplane actually maneuvers around the indicating sphere.*

The Sperry Attitude Gyro makes instrument flying safer, easier, and facilitates maneuvers and acrobatic training.

With it there is no possibility of the gyro's tumbling, even in extremely turbulent air. And, of course, its advantages in combat are obvious.

Sperry Gyroscope Company
INC.
GREAT NECK, NEW YORK • DIVISION OF THE SPERRY CORPORATION

Gyroscopics • Electronics • Automatic Computation • Servo-Mechanisms

Continental, Delta, Hawaiian, Inland, Mid-Continent, Northeast, Northwest, Penn-Central TWA, UAL and WAL. To Wright Aeronautical went a citation for performance of company's "Cyclone" engines in transports of three winning airlines.

Court Backs CAA Code

Federal authority to require all civil planes and pilots to be certificated by CAA was recently tested in the Reno, Nev., U. S. District Court, which upheld CAA's recent assessment of penalties against a Nevada pilot for violating the civil air regulations, forbidding him to operate airplanes until he obtained a CAA pilot certificate.

ATC's Third Birthday

Army Air Transport Command celebrated its third birthday May 29. Having become by far the world's largest air transport and ferrying system, invasion found it playing one of the most important roles in the war. Its personnel has grown to 20,000 officers, 88,000 enlisted men, and 20,000 civilian employees. In Apr. 1944, ATC flew 29,000,000 airplane ferry miles and 20,000,000 transport service miles, mostly abroad. In March, 60,000 persons were flown to scattered destinations. The ATC, now adding 200 new transports, will take over all operations of the Army Air Transport Service within the continental U. S. before the year's end.





SIKORSKY'S "5" AND "6" IN ACTION

Latest Sikorsky helicopters. XR-6 (top) and XR-5 (above) are more streamlined and faster than earlier R-4 model. Powered with 245 hp Franklin aircooled and P & W 450-hp "Wasp, Jr." engines, respectively, these craft can do better than 100 mph. Conventional anti-torque rotors are employed on tails of ships. Feature in each is provision for carrying externally a litter for wounded on each side of maximum visibility cabin. XR-5 is to be made at Sikorsky plant, while Nash-Kelvinator will build XR-6.

★ CROSS COUNTRY ★

South American Republics celebrated the 15th anniversary of the first airmail service linking the U. S. with Peru, Colombia, Ecuador, and Chile.

Braniff Airways marks its 10th anniversary of flying mail. When it was awarded the U. S. mail contract in 1934, two Lockheed Vegas carried approximately 111 lb. of mail between Chicago and Dallas. Today, company's DC-3's carry as much as 3,000 lb. plus passengers, in each direction on same route. Word also comes that company's application to serve Lubbock, Tex., on its Dallas-Amarillo-Denver route, has been granted by CAB.

Pan American Airways "Clippers" have re-opened service across North Atlantic. Regularly scheduled mail, passenger and express service will continue through summer. Since inauguration of these flights, Clippers have carried 60,000 passengers and flown 10,000,000 mi. in 1,875 scheduled Atlantic crossings.

War Department recently authorized $2,250,000 to provide for fills and extension of two landing strips at San Francisco Municipal Airport as part of $10,000,000 to be spent on improvements at Mills Field by Army and Navy. Agreements entered into by city and federal government in April guaranteed improvements in exchange for deeding of Treasure Island in San Francisco Bay to Navy.

A calendar has been prepared by UAL for air shippers giving quick reference material on maximum cargo sizes, DC-3 door dimensions, types of materials that can be shipped by air, rates, priorities, etc.

All American Aviation celebrated 9th anniversary of its air mail pickup inaugurated May 12, 1939.

Southwest Airways set a new record in April when its planes flew 99.6 percent of scheduled mileage on its California-based ATC feeder routes for Army. They missed perfect score when weather prevented one plane from reaching final station.

United Air Lines has applied to CAB for a route from Seattle to Ketchikan, Juneau, Yakutat, and Anchorage, Alaska. Proposed airway is approximately 1,400 mi. long. Company officials believe passengers and cargo could be flown from N. Y. to Juneau in 10½ hr. and to Anchorage in 10 hr. Elapsed times from Seattle to Ketchikan would be about 3 hr., to Juneau 4½ hr., to Yakutat 5¼ hr., and to Anchorage 7 hr.

UAL has again modified its stewardess qualifications maximum height now being increased from 5 ft. 5 in. to 5 ft. 6 in. and maximum age from 25 to 28. Other requirements: Minimum age 21, minimum height 5 ft. 2 in., maximum weight 125 lb. and 20/40 vision. Since war, United waives requirement of nurse certificate, substituting two years of college education.

Plans by Colorado Public Utilities Commission to regulate intrastate aerial transportation in same manner as ground carriers is being opposed by Continental Air Lines, United Air Lines, Braniff Airways and Inland Airways, which say such a code would cause confusion and is not needed for air carriers operating under federal authority. Proponents, Maj. Ford Williams and E. F. Evans, contend CAB regulations do not meet problems arising from feeder line operations. Intrastate airlines did not challenge commission's authority.

Contract for construction of a 1,800 ft. runway extension and additional taxiways at Cheyenne, Wyo., airport have been awarded to Peter Kiewit Sons' Co., Omaha and Big Horn Construction Co., Sheridan, Wyo., joint low bidders at $200,000. Financed by CAA, extension will make Cheyenne runway 8,000 ft. long.

What is believed to be fastest flight between Anchorage, Alaska, and Seattle—6 hr. 42 min. for the 1,500-mi. trip—is reported by UAL flying for Air Transport Command. Pilot of plane, a Douglas C-47, was Capt. Hugh C. Worthington. Only one stop was made en route (at Annette Island), and with strong tail winds average speed was 225 mph.

Central Airlines has filed an application with CAB to start an intrastate non-scheduled service between Oklahoma City, Duncan and Lawton. This new $100,000 corporation plans to transport passengers on a contract basis. Founder and president is Guy O. Marchand, v.-p. and gen. mgr. is Keith Kahle, oper. mgr. Hennigar and chief pilot is L. L. McMillon, and traffic manager is Edwin Keith Cornish.

Three organizations. — UAL, Wayne University and the Great Atlantic & Pacific Tea Co.—have joined forces to explore postwar possibilities of shipping perishables by air.

Fourteen planes retained by Army to civilian use will go to airlines as follows: Braniff 3, UAL 3, PCA 2, TWA 3, American 2, EAL 2, and Chicago & Southern 1.

The New Feeder Airlines Assn. held its first permanent organization meeting in June.

American Airlines figures for first four months of 1944 compared with same period in 40 are: 9,139,248 revenue miles, an increase of more than 800,000; 142,840,854 revenue passenger miles against 130,978,554, more than 10,000,000 lb. of mail an increase of 3,000,000, 804,240 lb. express loads, an "up" of 403,284.

Colonial Airlines added additional trip between New York and Montreal, originating daily round-trip total between these points up to four.

TWA recently inaugurated new daily (except Sun.) round-trip all-cargo flight between New York and Chicago in addition to its daily transcontinental round-trip cargo-flight. Also company has applied to CAB for round-the-world air route to bring any point in itinerary within 38 hr. of N. Y.

Declaring he cows, pastured near Allentown-Bethlehem, Pa., airport, were frightened by low-flying planes, farmer Frank Dingee got an injunction ordering aircraft to keep higher than 100 ft. over his fields. Accordingly, UAL had to discontinue landings at the port. Now, however, a rehearing has reversed order and airliners are again operating at A-B field.

Approval for construction of 14 airports required for specific military purposes and 27 for emergency use was recently announced by Secretary of Commerce.

Braniff Airways employees now receive aircraft electrical systems course under Illinois Inst. of Tech. "In service training program. Course is given in company plant and paid for by U. S. Office of Education.

Transport plane models now under construction will carry transatlantic traffic until 1955, possibly longer, in the opinion of William Enrden, Assistant Secretary of Commerce. Talking at a recent meeting of the Foreign Commerce Club in New York City, he predicted a transatlantic fare of $250 per passenger.

Poll taken by Des Moines, Iowa, Sunday Register indicates a third of state's residents have flown. Ten women are almost as airminded as men, and that nearly as many farmers as urban dwellers have taken flights. To question "Have you ever thought you would like to buy a plane for your own use?" 21 percent said "Yes"; six percent replied, "Perhaps."

Railway Express Agency has conducted a quiz contest among its many thousands of employees aiming to bring greater awareness of the work of its air express division. A total of 13,805 employees in 1,500 communities participated.

Aviation Abroad

British 12-Mo. Production Totaled at 27,273 Planes

Atlantic flown 15,000 times since start of war.

In the first detailed statement made thus far, Sir Stafford Cripps disclosed actual British plane production figures for the past years. With 27,273 new aircraft completed in the year ending Mar. 31, 1944, the industry, which now employs more than four women for every ten workers, showed an increase of 82 percent over 1940 and 240 percent over 1938. In addition to the 27,000 new planes, the industry rebuilt more than 18,000 others, thus actually making more than 45,000 aircraft available for combat. An earlier announcement gave 90,000 planes as the total British production since the beginning of the war.

Sir Stafford pointed out that spare parts constituted an additional 80 percent of the total production which would make the net production more than 43,000 planes for the year. It must be noted that while the figures may appear low, England for a considerable period was under heavy and constant air attack. Still, its industry consistently managed to bring out new models.

Atlantic Flown 15,000 Times Since War's Start

A recent British Air Ministry report showed that the Atlantic has been flown more than 15,000 times since Sept. 1939, with more than 5,000 of the crossings taking place in the periods between December and May. Little more than 75 planes have been lost to date, the majority during the beginning of the program. The announced figure includes all military ferry flight and transport command traffic crossing in both directions, but it does not include any flights made by commercial airlines. Most recent figures indicate that a plane leaves every 45 min., while at least 25 planes are en route across the ocean at any time of the day.

★INTERNATIONAL BRIEFS★

A modification of FW-190 (probably known as 390) features a new 3,000-hp. in-line engine. Performance is not known yet, but it should be shown "upped" by this increased power.

Reports from England say a new "bomber killer" plane featuring prodigious climb and firepower is now in full production. This job is probably Hawker Tempest V.

Add to list of new British commercial planes: the Short Shetland flying boat, first model of which is being readied.

According to latest reports, Germany's best glider bomb can be controlled from 18,000-ft. distance. This is improved Hs-293, generally carried by He-177 bomber.

Henschel is also building a new bomber known as Hs-219. So far it's seen only limited action.

ON SCHEDULE . . . . . By "VISTA"


Pertinent details on airline operations in Central and South America have been made public by the DSC. On the last day of 1943, there were a total of 386 aircraft in operation in these countries, of which only 57 were U. S.-flag aircraft. Of these craft, 246 were multi-engine, but only 67 were manufactured after 1938. Among the multi-engine planes, American built equipment predominated, accounting for 198 of the total, while 29 were of German manufacture and 18 were built in a miscellany of other countries. There were a total of 113,800 route miles in operation.

Mexico had 18,400 local-service miles of Central America's 37,000-mi. total. In South America, Brazilian internal services accounted for 33,500 of the total of 60,800 mi. Foreign-line aircraft utilization stood at a remarkably low figure of 2.4 hr. 125 percent of the U. S. average), with 5.8 hr. for U. S.-flag operators. Total ton-miles sold amounted to 82 million, compared with 215 million over 42,650 mi. of routes in the U. S.

Britain's magazine *Aeronautics* recently carried details on current operations of the Belgian SABENA. Maps show that this all-line has quietly developed an astonishing network of lines in Africa, connecting the Congo with Cairo, Capetown, and Takoradi on the Gold Coast, also with extensive services within the Congo.

While this line's postwar plans only mention resumption of its previous European and to-Africa routes, further extensions to Poland, Russia, the Balkans and Near East are anticipated. The line, which used Savoia transports for some time, recently purchased its first DC-3's.

KLM has completed its 2,000th England-Lisbon flight, a landplane service started in May 1940 and which has carried over 11,000 passengers with the loss of only one plane (that which carried Actor Leslie Howard and KLM Pilot Tepas). Three of the six original DC-3's are still in use, and three planes have recently been replaced by Douglas C-47's under American lend-lease.



P & W POWERED "WARWICK"—COMPLETE WITH FOOTPRINTS

Second new commercial plane to appear in England is this Vickers "Warwick" mid-wing monoplane which, with Avro "York," is becoming a standard transport for RAF. A bigger sister of famed "Wellington" bomber, "Warwick" is some 20,000 lb. heavier, grossing 45,000 lb., but has only 10 ft. more span (96 ft. 8½ in.) and 6 ft. more length (70 ft. 6 in.). Height is 18 ft. 6 in. and gross wing area 1,006 sq. ft. Mounting two P & W 1,850-hp. engines, plane's top speed is expected to approach that of "Wellington III" (some 265 mph.). Notable features are geodetic construction, sharply tapered wings, and very long engine nacelles. Black marks on wings are painted footprints—a precise indication of restricted walkways to guard against damage to underlying "basketweave" construction. (British Combine photo.)

Richard Archbold's "Guba" flying boat (Consolidated PBY) has finally been retired from BOAC fleet after many years of service.

Rolls Royce has built more than 180,000 "Merlin" engines since July, 1937.

German "Siamese Twin" glider tug—two He-111 bombers joined together—mounts four DB-601N in-line engines plus one BMW-801 radial engine at joining point of two planes.

Production of Albemarle glider tug has been taken over by a new British firm, A. W. Hawksley, Ltd., a subsidiary in Hawker Siddeley group.

Australia plans manufacture of an in-line, liquid-cooled engine of as yet undisclosed type, also several transport type craft for postwar use.

At least twelve companies have registered in India for postwar commercial air transportation.

Nazis have been using new Arado Ar-240 reconnaissance airplane over England lately. To be slow and hence easy prey for Allied fighters.

It's said Germany is developing her monster Me-323 six-engine glider into a bomber.

Qantas Airways of Australia offers following 1943 resume: 18,231 passengers carried 17,285,000 mi. plus 1,376,000 lb. freight and 827,000 lb. mail. Line now employs nearly 1,400.

Swedish ABA again has suspended its Sweden-Scotland service due to British travel restrictions, but it may re-open its route to Moscow via Baltic states.

Two new records have been set by Mosquitos—one flew Atlantic in 6¾ hr., another covered distance from London to Moscow in 3½ hr.

A new Portuguese airline has been formed—Aero Portuguesa Limitada—it proposes air routes to Portugal's colonies and Brazil.

Reports indicate Heinkel has developed a transport plane known as Ho-274 from the He-177 bomber, featuring four engines in two nacelles and driving contra-rotating propellers.


SNCA du Midi is building a special plane for flights at 50,000 ft. It is to feature a pressure cabin, mixed construction, two Hispano 12Z engines, inside pressure section of fuselage, and contra-rotating propellers. SNCA du Midi is a French organization.



knockout specialist

from stratosphere to sea level

Having won a reputation as master of the stratosphere, the Republic P-47 Thunderbolt now demonstrates its power as a low-level fighter-bomber in clearing the way for invasion. After attacking without warning at tree-top levels, the Thunderbolt speedily heads skyward at a new, faster rate of climb—aided by new wider Curtiss Hallow Steel blades.



CURTISS ELECTRIC PROPELLERS

Curtiss-Wright Corporation, Propeller Division



CLEARING all Wires!

Breeze Flexible Conduit Shields and Protects Communications and Wiring Systems

Any current-carrying wire in an aircraft electrical system is a potential source of interference with radio communications unless properly shielded. Breeze Flexible Shielding Conduit, produced in a wide range of diameters, can be used in conjunction with Breeze Conduit Fittings and Multiple Electrical Connectors to meet practically any shielding requirement.

The custom design of complete radio ignition shielding harnesses is a Breeze specialty, based on years of pioneering experience in the field.

Breeze Flexible Shielding Conduit is in service today with fighting units of land, sea and air, supplementing the many other well-known items of Breeze equipment that are helping the United Nations along the road to Victory.



Breeze Shielding guards communications against high frequency interference from spark plugs and ignition system circuits

Breeze BREEZE MARK CORPORATIONS, INC. NEWARK, N. J.

PRODUCTION FOR VICTORY • PRODUCTS FOR PEACE

Douglas Aircraft Co. has arranged a $75,000,000 revolving credit with 17 banks—the largest credit ever floated by an aircraft manufacturer without involving a government credit. The new credit is for three years, with the company agreeing to maintain a $25,000,000 minimum net working capital. Douglas working capital topped $35 000 000 at the end of 1943.

Cessna Aircraft Co. has voted a 100 percent stock dividend, increasing the outstanding stock from 350 000 to 700 000. Another 800 000 remains in the treasury unissued and the company does not contemplate any financing at this time.

Grumman Aircraft stockholders it is understood, will be asked to increase the authorized capital stock from the present 600 000 to 3,000,000. The increase will be requested so that the company will be in position to raise money by stock sale if it is needed at some future time.

Bendix Aviation reports net income of $14 722,704 or $9 95 a share for the year ended Sept. 30, 1943 against net of $12,464,136 or $5.60 a share in the like 1942 period. Net sales were $822 510 234 compared with $459 159 029 in 1942. Expenditures for research and production engineering were $14 900 000 against $11 700,000 in 1942. Last year 82 percent of total volume went into the aircraft field.

Loans: Continental Motors Corp has negotiated a $30-000 000 VT-credit with 18 banks. Aircraft Accessories Corp has established a $12,500,000 V-loan with 12 banks. The Square D Co has arranged a V-loan with several banks to provide capital for war production and to free working capital during the immediate postwar adjustment period. The terms prohibit payment of cash dividends equal to more than 75 percent of annual earnings after preferred charges. It was also agreed not to permit net current assets to fall below $3,200 000, this amount to be increased at the end of each year by 20 percent of net profits.

Fairchild Camera & Instrument Corp (formerly Fairchild Aviation Corp.) reports net sales of $47,559,896 in 1943 against $15,284 387 in 1942. Net profit was $1 443 110 or $4.28 a share against $407,644 or $1.20 in 1942.

ADDING IT UP.....By RAY HOADLEY

Came the deluge. Most of the airlines are more than pleased with the rapidity with which the Army has been releasing transport planes to them recently. In fact, after the last 28 were returned some lines said they had just as soon have a little breathing spell before very many more came their way because of the personnel factors involved. The lines are determined to maintain their current safety record above all else. Meanwhile this additional equipment will greatly step up 1944 traffic volume although little if any of the extra business will seep down to net profits.

Foggy weather. The Supreme Court decision in the Northwest Airlines state tax case has the airlines worried because of the ruling that states in which lines are incorporated may tax the full value of the company's fleet of planes. No opinion was given regarding the tax rights of states through which the planes fly. The best bet for the airlines seems to be to convince Congress that it should include a provision, in one of the pending postwar bills, limiting such state taxation. The high court indicated that Congress has the power to enact such limitations.

Warplane cutbacks. Cancellation of Brewster's Navy contracts served to bring into the open a matter which has bothered all plane makers lately. With Brewster the "guinea pig" in the situation, both government officials and Congress can see the wide ramifications, both political and economic, of abrupt cancellations. The rest of the industry will benefit from the Brewster experience through provision of more reasonable notice in the future, with gradual reductions in operations and better government planning to find other war work for idle plants and facilities.

Dismissal pay. It is becoming a generally accepted fact that provision for released war workers is a responsibility of government. Any private monetary solution to the problem would, of course, bankrupt most aircraft companies. It is noted that even the automobile concerns have no plan to cope with unemployment when contract cancellations flock in. These companies appear to be relying on benefits provided under state unemployment compensation laws.

Surplus inventories. Plans whereby aircraft manufacturers can turn over excess inventories to the RFC will enable the companies to get rid of inventories that would prove an intolerable burden in the event of sudden cancellation. It is expected that the plan will start functioning early in the fall. The effect on many a company's cash position at the year-end should be most favorable.

National Airlines is selling 113 333 shares of common stock. The proceeds of the issue will be available for general corporate purposes pending specific application.

Airline Earnings: Eastern Air Lines reports net profit of $178,520 or 30c a share in the March quarter against $279,235 or 47c a share in the like 1943 period. . . . TWA reports a first quarter net loss of $92 419 against a net profit of $357,352 or 37c a share in the like 1943 period. . . . United Air Lines reports net income for the quarter of $1 110 063 or 86c a share against $1,178 779 or 79c a share in the same 1943 quarter. . . . Western Air Lines showed a net loss of $17,564 against a net profit of $21,697 in the like 1943 period.

Dividends: Glenn L. Martin Co declared a $1.50 common dividend payable June 12. . . . United Aircraft made a similar payment on June 15. . . . Other second quarter payments were: From Continental Motors, 15c; Delta Air Lines 50c; Air Associates, 20c; Grumman $1 a share; Rohr Aircraft, 25c; Bell Aircraft $1 a share; United Air Lines, 50c, and Bendix, 75c.

Backlogs. Bendix Aviation meanwhile reports that unfilled orders on Mar 31 were $791,200,500 compared with $1 018,501,000 on Sept 30 and $1,074 498 500 on Mar. 31, 1943. . . . The Douglas Aircraft Co. has almost $3 000,000 000 in unfilled orders, which it would take theee years to complete at the 1943 production rate. . . . Glenn L. Martin Co has letters of intent which call for some additional facilities and a higher employment this year.

Continental Motors Corp announces sales of $196,499,812 in the year ended Oct. 31, 1943 against $128,389,000 in 1942 and $31,564,000 in 1941. Net profits were $7,493 820 or $2 50 a share against $5,472,884 or $1.82 in 1942.

Production Outlook. Republic Aviation, now operating at peak levels on the "Thunderbolt," does not expect any cutbacks this year. . . . Pres. Breech of Bendix expects dollar volume for Bendix products in the 1944 fiscal year will not exceed that of 1943. . . . Consolidated Vultee Corp anticipates a larger 1944 volume on "Liberators" and long-range fighters than in 1943. . . . Pres James Ogsbury of Fairchild Camera told stockholders that the company has had some cancellations but that there is still sufficient volume of unfilled orders on hand to keep the plants busy for "some months."

Ex-Cell-O Corp. reports net profit for the quarter ended Feb 29 of $434 978 or $1 21 a share against $723,478 or $1 91 a share in the like 1943 period.

Future Outlook: Jacobs Aircraft Engine Co. reports that research shows possibilities for wide developments in the helicopter field after the war. . . . Postwar planning by Boeing is being continued by its engineering department and by an independent agency looking to possibility of manufacturing and marketing of other products in addition to aircraft.

Western Air Lines has taken over active operation of Inland Air lines, the CAB having approved the sale of Inland to Western Air.

Airplane Manufacturing & Supply Corp. reports net income of $165,420 or 44c a share in the year ended Nov 30, 1943.


United Air Lines will, in five years after the war, be doing a business five times the best prewar year, according to Pres. W. A. Patterson, or $100,000,000 against the $19-000,000 reported for 1941.

Sandy Hook Lighthouse, built in 1764.

ON THE BEAM— *for nearly two centuries*

Tobe Capacitors, too, are "on the beam"—giving years of dependable service . . . for, at Tobe, *long life* is as integral a specification as the dimensions themselves. That is why, with millions of Tobe Capacitors operating under all conditions, "returns" are practically negligible. Continuation of this enviable record rests on long, specialized manufacturing experience—intensive inspections—and constant research. Illustrated below is the Tobe OM-Capacitor. This capacitor is a mineral oil impregnated unit in a streamlined drawn container, hermetically sealed. The hold-down bracket permits the use of either inverted or upright terminals, with wiring underneath or on top of chassis. You will find Tobe engineers ready to cooperate on your own capacitor problems. Why not inquire now?

TOBE DEUTSCHMANN CORP. TOBE CANTON · MASSACHUSETTS



SPECIFICATIONS

OM-CAPACITORS	
TYPE	OM-*
RATINGS	.05 to 2.0 mfd. 600 V. D. C. .05 mfd. to 1.0 mfd. 1,000 V. D. C.
STANDARD CAPACITY TOLERANCE	20%**
TEST VOLTAGE	Twice D. C. rating
GROUND TEST	2,500 Volts D. C.
OPERATING TEMPERATURE	-55° F to 185° F
SHUNT RESISTANCE	.05 to 0.1 mfd. 20,000 megohms .25 to 0.5 mfd. 12,000 megohms 1.0 to 2.0 mfd. 12,000 megohms
POWER FACTOR	At 1,000 cycles—.002 to .005
CONTAINER SIZE	Width ⅝", length 1⅝", height 2¼"
MOUNTING HOLE CENTERS	1½"

MIDGET OM-CAPACITORS	
TYPE	OMM-*
RATINGS	.05, .1 and 2 x .05 600 V. D. C. .05 x .1 1000 V. D. C.
STANDARD CAPACITY TOLERANCE	20%**
GROUND TEST	2,500 V. D. C.
OPERATING TEMPERATURES	-55° F to 185° F
SHUNT RESISTANCE	20,000 megohms
POWER FACTOR	At 1,000 cycles—.0075
CONTAINER SIZE	Width ⅝", length 1⅝", height 1 1/16"
MOUNTING HOLE CENTERS	1½"

*Data sheets showing complete code number for units having a specific capacitance value and voltage rating available on request. **Other tolerances available

A SMALL PART IN VICTORY TODAY...A BIG PART IN INDUSTRY TOMORROW

Aviation People



COMDR ROLAND G MAYER, former assistant manager at Consolidated Vultee's Fort Worth division, recently was named manager at the plant in an announcement by L M Laddon, executive vice-president of the corporation (Hill & Knowlton photo)



MRS MARY S JACKSON recently named director of counselling for Consolidated Vultee Aircraft Corp, is the company's first woman executive The counselling of women employees has been given the status of a full department under Mrs Jackson's direction



COL CLAIR A PETERSON recently flew an Army Mustang from Los Angeles to New York in the record time of 6 hr 31 min He is a former United Air Lines pilot on leave with the military services as personal pilot to Gen Henry H Arnold




GRANT C EHRLICH is president of the newly formed Resin Industries Sante Barbara, Calif., which will produce synthetic alkyd timers, including vinyl resin ethyl cellulose, and similar compounds as well as radar engineering and production service.




S PAUL JOHNSTON, former editor of Aviation, one time coordinator of research for the NACA, more recently Washington public relations representative for Curtiss Wright Corp and author of several aviation books, is presently on active duty with the Navy



JOHN W WHITE has been elected president and general manager of the Westinghouse Electric International Co., subsidiary of Westinghouse Elec & Mfg Joining the company in 1907, he lived abroad for 18 yr managing WEI affairs in the Caribbean area, the Far East, and many South American countries WILLIAM E KNOX has been elected vice-president of the company He is the proud holder of the Westinghouse Order of Merit as well as the Chilean Order of Merit, which carries with it the rank of commander (Blank & Stoller & Pach Bros photos)





COL PHILIP J REILLY, managing director of the Associated Merchandising Corp, was appointed head of a distribution program for The Aviation Corp.'s post war production of household appliances, planned to supplement their aircraft parts production



ANDREW "DUKE" REID has been named assistant chief inspector of the aircraft division of the Willys Overland Co He has been in the aviation industry for the past 31 yr, and before joining Willys Overland was field service representative for the Brewster Co



VICE ADM AUBREY FITCH was named Deputy Chief of Naval Operations for Air, succeeding Vice Adm John S McCain Former commander of aircraft in South Pacific, Vice Adm Fitch is credited with having driven the Japanese from the air in that area



CARL F BAKER has been appointed chief engineer of Hamilton Standard Propeller Div of United Aircraft Corp He will have responsibility for all activities of the engineering department concerned with production, including inspection, metallurgy, installation, etc,



JOHN P "JACK" DODS Director of Research and Advertising Manager for Summerill Tubing Co., was appointed director of advertising and sales promotion for the affiliated interests of Columbia Steel & Shafting, and The Edgar T Ward's Sons Co,



CAPT L D "HAP" ANDERSON has been named chief pilot in charge of all flight officers for Chicago & Southern. He has logged more than 12,000 hr during his 16 yr. of flying, and until last Dec 1 he was president of C&S's pilots' council J A YOUNG (center) general manager of the modification center at Memphis, has been named assistant to Bruce E Brown, v-p operations





and will have the maintenance, modification, engine overhaul, engineering, purchasing, stores, and coordination of Army contracts under his supervision CAPT REEO KNIGHT, former chief pilot was named superintendent of flying and director of military cargo He will direct all pilots, first officers, and the company's military cargo operations (Chicago & Southern News photos)

BROACHING BY *American*

PROVEN

on Tanks Today . . .
Ready for Tractors TOMORROW



War's demands necessitated an increase in the speed of precision production. Broaching met the challenge successfully. Forward-looking manufacturers will plan to cut costs, use manpower efficiently in peacetime by broaching—the *American* way.

Here is a typical example: Increased output, uniform accuracy, and excellent finish are obtained by broaching the internal bolt pads in tank track connector links. An *American* T-15-36 3-way type machine, provided with a manual positioning device to prevent loading a part of the wrong hand, does the work quickly, economically.

Let *American*'s complete broaching service—machines, tools, and engineering—help you in war production or in postwar planning. Phone, wire, or write for complete information.

Enlist the services of an expert broach manufacturer when broaching tools are to be designed. Obtain the benefit of his experience.

American
BROACH AND MACHINE CO.
ANN ARBOR, MICHIGAN
•
BROACHING MACHINES
PRESSES
BROACHING TOOLS
SPECIAL MACHINERY
DIVISION OF SUNDSTRAND MACHINE TOOL CO.

Side Slips

WITH A SIGH, we recall those halcyon days when the 'man at the controls"—whether he tooled a vehicle on land, on sea, or in the air—proudly wore dashing headgear as the badge of his profession. Anyhow, we sadly report the final defilement of that honored tradition. With our very own eyes we recently witnessed the engineer of our crack Westchester commuter train wearing [illegible]. It hurts us to reveal this [illegible] yes, wearing a straw hat, one of those unbending "sailor" affairs. Then at Wichita the other day we saw a renowned test pilot slip unconcernedly out of a B-29 and—you wouldn't believe it, but his lid was one of those blue-and-white-striped roundhouse engineer's caps.

So our glamorous railroaders are voluntarily back hatting to crass civilian status and our intrepid flyers are assuming the relatively plebian toppers of engineers. Seems that the boys of the rocket fraternity—the ones who'll be calling themselves astronauts—are now left in exclusive possession of those grand old aero chapeaux, the well-upholstered helmets. "Fair enough," says the flyer chap who's leaning over our shoulder. "They'll sure need 'em when they start shooting landings on the moon!"

• There's at least one British pilot who's found lend lease tanglesome in a rather personal sort of way. Lad we're referring to picked up a new fighter job at an East Coast plant, buzzed her off the runway, and headed for a regional modification field to get her camouflaged. But just past New York City his charge developed a bit of engine trouble, so he landed at Port Newark, now Atlantic Overseas Air Service Command base, and there he found ready assistance. "Sure thing, said the AOASC'ers, pausing in their labors of trimming down warplanes for shipment. "We'll fix your engine. Ship'll be all set for you in the morning."

But when he came back next day, the Briton didn't see his plane on the line. He hunted up and down, still couldn't locate it. Finally he checked back at the hangar. "I say," he intoned, "where is my aircrawft?" The silence was thick, nobody seemed to know. Then suddenly a call from the apron broke the impasse: "B'geez! *There* it is—trimmed, plastered, an' goin' down th' slip on a barge!" Conclusion: The Briton had to go back to the plant and get a new plane.

• Of course, Ford's public relations department regularly paints us potent pictures of Willow Run's great *Lib* production. However, this story didn't come from Ford's PR, it was told us by an old friend of ours, a scientist at the U. of Mich. Recently he was watching some kids playing in a town near the Run, when a small training plane modestly put-putted by. And he was amazed at the youngsters' reactions. They abruptly stopped their game, craned their necks, and vociferously exulted. "Look at that!" "It's a PT-17!" "Bab eee!"

Wonderingly, our friend asked, "Why all the excitement?" Whereupon one of the boys crooked a thumb toward Willow Run and began monotoning in Kipling-esque "Boots! Boots! Boots!" style. "B-24's! B-24's!," he muttered. "More B-24's! Still more 24's! I wanna tell you, mister, them B-24's get mighty monotonous."

• Heaven knows we have trouble enough with typographical errors, but one we read in a newspaper the other day seemed just a *little* too prophetic. Reporting on a large aviation company's future plans, the dispatch said, "[illegible] this household appliance manufacturing program will supplement the corporation's over-all-aircraft parts production and will badly diversify postwar operations."

• We never thought the science of aeronautics would change the methods of raising babies, but it has. Friend of ours mentioned taking care of his year-old heart-breaker and we asked (naively it now appears) if he was good at changing three cornered pants. "They're four-cornered now," he replied in a superior tone, "wing area is much greater and boundary layer control is much better."

• Lagging behind formation, the bomber was really taking a beating; fighter planes were ripping in from behind and bullets galore were going out the front through the windshield. Quite naturally, both pilot and co-pilot were pressing hard against their armor plates, wishing to heaven they were midgets. Nodding at the control quadrant out in the middle, the pilot said casually to the co pilot—over the inter-com—"May I have a little more boost, please?" Said the co pilot,—also over the inter-com, but not so casually—"Brother, if you want more boost, you stick your own damn hand out there."



Maguire wants everybody to know he's been to one of our bomber bases in Russia."

KEEP POSTED ON

Products and Practices

This selected information on new publications and products is offered by the "AVIATION" Reader's Service through cooperation with the manufacturers. It helps executives save valuable time, provides profit through convenience. To obtain literature or additional data on new products described, simply fill in form below, clip it to your letterhead, and mail. There is no cost, no obligation.

ENGINEERING DATA

Aircraft Hydraulic Control 1

New development in lighten and simplify hydraulic control system for operation of wing flaps, landing wheels, and other mechanisms of large cargo and transport planes is disclosed in paper entitled *Aircraft Hydraulic Pumps and Related Accessories*, by J. A. Lauck, chief engineer of pump developments, Pesco Products Co., Cleveland division of Borg Warner. New device is power package unit weighing 8 lb. which combines no electric pump, pressure relief valve and pressure switch.

Process Converts Wood 2

News release from E. I. du Pont de Nemours & Co., Wilmington, Del., describes new chemical method of changing properties of wood so that it may be used in many new ways, even substituting for steel in certain machinery parts. Wood derivatives such as sawdust, shavings and paper are reported to lend themselves to the process, also rotten, leathery and farm wastes.

Aluminum Alloys 2

National Smelting Co., Cleveland, offers new booklet *Red X Aluminum Alloys*, story of custom-made alloys giving their composition properties and specifications.

Synthetic Rubber 4

Acadia Synthetic Products Div., Western Felt Works, Chicago, has published 70 page spiral bound book *Synthetic Rubber Data*. Laboratory evaluations of various compounds when exposed to oils, fuels and solvents are presented, much of this data having been developed from research in alignment by problems of unconventional engineers, also charted are tests of such criteria as freeze resistance, hardness, heat, fuel resistance, aging, etc.

Flexible Coupling 5

Bulletin describing space-saving flexible coupling has been released by Farrel-Birmingham Co., Ansonia, Conn. Couplings are for applications where spare limitations make necessary close-coupled connections. Included are engineering details, application diagrams and tables of sizes, ratings, and dimensions.

Special Purpose Machines 6

New 72 page Blue Book for Management, *Ship & Production Engineers*, issued by Delta Mfg. Co., Milwaukee, presents case histories of 140 special purpose machines. The designs employ standard Delta drill press heads and columns and other company tools.

Micro Inch Measurements 7

How to Measure in Micro Inches deals with fundamentals of precision measurements, showing how principles are applied in control of quality. Photographs show many applications for gage blocks, vernier gages, sine bars, master parallels, bars, etc. Published by Continental Machines, Minneapolis.

Metal Plating on Plastics 8

In *The Metroplast Process and License Plan*, Metroplast Co., New York, explains process of metal plating on plastics, gives general properties and information on preparation. Note surfaces that can be "metaplated" and describes activities and operation of the Metroplast Guild.

Carbide Tools in Machining 9

Carboloy Co., Detroit, offers bulletin *The Machining of Metals on Automatic Screw Machines With Carbide Tools*. Suggestions cover speeds and feeds, horsepower required, cuts, roll-off tools, rake angle, feed, grinding coolant, and chatter.

Finish Control 10

New feature on inspection and control of surface finishes offered by George Scherr Co., New York, describes Spencer binocular microscope and illustrates its operation.

Chain Belts 11

Chain Belt Co., Milwaukee, has issued new catalog of chain belts for driver and conveyor service. Used in brine, dry, metal, abrasive, corrosive and metal with high tensile strength.

Alkaline Copper Plating 12

Bulletin from Lustrid Chemicals, New York, describes Unibronz alkaline copper plating process suited to produce lustrous deposits of high speed in a non-cyanide solution.

Low Temperature Welding 13

New developments in Aircraft Welding describes low temperature welding rods made by Eutectic Welding Alloys Co., New York, designed to give smooth, clean, machinable welds at tending temperatures of alloy.

Aluminum Color Finishes 14

Bulletin from Mutual Chemical Co. of America, New York, describes process of *Dyeing Chromic Acid Anodized Aluminum* and gives tables showing results obtained with various colored dyes.

Removing Metal Coatings 15

Technical service data sheet on removal of metal coatings such as copper, zinc, lead, cadmium and magnesium from steel, nickel, chromium or aluminum is offered by American Chemical Paint Co., Ambler, Pa.

Steel Ball Manufacture 14

Making Them Round, booklet describing processes in ball bearing manufacture has been issued by New Departure Div. General Motors Corp., Bristol, Conn.

Shipping Containers 17

Gruwell Box Co., Chicago, offers booklet *The Gruwell Box*, which describes many types of shipping containers, including export boxes.

Packing Engines for Export 19

Fuller descriptive of methods of packing engines for export shipping has been issued by Augier Sons Corp., Framingham, Mass. Photographs illustrate various types of crates and use of company's product "Brownskin."

Metal Sealing Compound 19

Ault & Wiborg, Cincinnati, Ohio, has developed a new synthetic resin sealer for impregnation of magnesium, aluminum and other metal castings. Known as No. 988 magnesium sealing compound—styrene soluble sealer is described in bulletin.

MACHINERY & ACCESSORIES

Welding and Tool Data 20

Handbook of construction data, welding methods and heat treatment procedures for tool and die steels has been published by C. E. Phillips & Co., Detroit, titled. *Arc Welding in the Manufacture and Construction of Tools and Dies*. Two types of electrodes are described and furnished are data on deposit characteristics, physical properties and special details of application procedure.

Hydraulic Press 21

Watson Stillman Co., Roselle, N. J., offers bulletin No. 870 A covering a general purpose hydraulic press suitable for diversified work in the metal forming, ceramic, or plastic industries. There are detailed descriptions of five sizes.

Repairing of Cutting Tools 22

How to Repair Broken Cutting Tools With Easy Flo is treatise issued by Handy & Harman, New York.

Electric Chain Hoist 23

Bulletin No. H-23 describing new Hand-Lift electric chain hoist is offered by Harnischfeger Corp., Milwaukee. Unit is rated at 500 lb.

Sight Flow Indicators 24

Complete line of "Bull's Eye" sight flow indicators is shown in new catalog 92-B issued by Fischer & Porter Co., Hatboro, Pa.

New Carbide Tools 25

Many carbide tipped cutting tools generally classified as special are now listed as standard in new catalog No. 144 issued by Wendt-Sonis Co., Hannibal, Mo. New tools are stated to be specially designed and not adaptations.

Gun Reamers 24

Catalog from Wetmore Reamer Co., Milwaukee, covers complete line of adjustable inserted blade reamers, boring bars, and special tools, including dies, counterbores, and tool engineers.

Ferrule Beading 27

Newly developed ferrule beading machine is described in bulletin offered by Champlain Div., The Fred Goat Co., New York. Machine is mechanical device for attaching aluminum ferrules to flexible shielding conduit.

Compressors, Vacuum Pumps 29

Ingersoll Rand Co., New York, announces new catalog of compressors and vacuum pumps in sizes from ½ to 10 hp. shown are dual-pressure portables, designed for servicing and repair of aircraft.

Accessories for Lubrication 29

J. N. Fauver Co., Detroit, offer new catalog of lubrication accessories for lubrication hydraulic steam, liquid and air applications. Couplings, fittings, and hose clamps are shown.

Oxy-Acetylene Handbook 30

The Oxy-Acetylene Handbook published by Linde Air Products Co., New York, treats range of oxy-acetylene welding and cutting processes in textbook style.

Electrical Circuit Analyzer 31

Description and specifications of new "Unre analyzer for aircraft electrical circuits are found in new bulletin issued by United Hydraulic Mfg. Co., Los Angeles. Unit is reported capable of locating and analysing virtually all electrical and wiring troubles in 75 percent of all Aeroresearch Aircraft.

Electronic Controllers 32

Bristol Co., Waterbury, Conn., announces bulletin No. B-220 describing new line of free-vane electronic controllers for automatically controlling temperature, pressure, liquid level, and humidity. Given are wiring diagrams and principle of operation.

Gage Block Finish 33

New type of finish for gage blocks stated to hold precision accuracy in blocks over extended period, is described by Pond Gage Co., New York, in illustrated new bulletin, *Precision in Millionths*.

Collet Chucks 34

Hedner Air Devices Corp., Chicago announces addition of new sizes to its line of collet chucks which accordingly now give collet capacity up to 1¾ in. Full description is given in bulletin.

New Gage Design 20

Bulletin from Metrical Laboratories, Ann Arbor, Mich., describes the "Metricator," new gage designed for measurement of slots and thicknesses using flow of air as measuring medium.

Foundry Ovens 37

"Corementer" core ovens are described in bulletin just issued by Despatch Oven Co., Minneapolis.

Productive Forge Furnaces 38

Barium combustion production forge furnaces are detailed in bulletin SC 116 offered by Surface Combustion. Toledo. Ohio. Furnaces are equipped for gas, oil or combination of both.

Surface-Roughness Measurement 39

Second edition of *Practical Surface Roughness Measurement* is published by Physicists Research Co., Ann Arbor, Mich. Contained is information on importance of surface finishes and on equipment of profilometer.

Carbide Tipped Tools 40

Haynes Stellite Co., Kokomo, Ind., div. of Union Carbide & Carbon Co., offer revised pamphlet, *Stellite Star J Metal Cutting Tools* giving clues and information on tool holders and adapters.

Remote Controls 41

Designed to meet requirements for aircraft engine controls, "ISOdraulic remote control is now have additional features, as described in new folder issued by Aircraft Precision Products Corp., Bayshore, Calif.

Infra-Red Appliances 42

New principles in infra red appliances are described in bulletin issued by Infra Red Engineers & Designers, Cleveland.

Light-Duty Tapping 43

Bulletin LTM-44 describes new light duty tapping machine made by Detroit Tap & Tool Co., Detroit.

Industrial Jacks 44

Simplex lever screw and hydraulic jacks are described in new catalog issued by Templeton, Kenly & Co., Chicago. Jacks from ¾ to 100 ton capacity are detailed.

Electronic Publication 45

Attied Radio Corp., Chicago announces new publication, *Allied Radio and Electronic News*, monthly bulletin of developments in electronic field for engineers, purchasing agents and department heads.

Thermocouple Data 46

Wheelco Thermocouple Data Book and Catalog (Bulletin 824) issued by Wheelco Instruments Co., Chicago, gives description of products and suggests substitutes for restricted materials. Also offered are temperature conversion tables, millivolt tables, tables on pipe and wire sizes, decimal equivalents and wire resistances.

Disconnect Electrical Fittings 47

Bulletin 522 gives engineering details on Tiki-Sta-Kon all-metal wiring system based on application of special tips to ends of wires by pressure tools. Issued by Thomas & Betts Co., Elizabeth, N. J.

Moulding Electronic Products 48

Assembled from many sources best methods for moulding materials to charge into electronic and electrical work are given in new booklet, *QA Methods*, issued by American Phenolic Corp., Chicago.

Micro Switches 49

Micro Switches for aircraft are described in detail with uses illustrated in new catalog issued by Micro Switch Co., Freeport, Ill.

Solderless Wire Connections 50

Illustrated bulletin No. 81, from Aircraft Marine Products, Harrisburg, Pa., describes complete system of solderless knife-disconnect splicing.

Battery Catalog 51

Aircraft batteries and their specifications are shown in new *Special Liner* catalog issued by Willard Storage Battery Co., Cleveland.

AVIATION READER'S SERVICE — JULY 1944

AVIATION 330 W. 42nd St. New York City

Please send me additional information according to key numbers circled

INFORMATION TIPS 1 2 2 4 5 4 7 9 9 10 11 12
13 14 15 14 17 18 19 20 21 22 23 24 25 24 27 28 29 30
31 32 33 34 38 34 37 38 39 40 41 42 43 44 45 44 47 48
49 50 81 52 83 54 55 56 57 59

NEW PRODUCTS 59 40 41 42 63 64 66 66 67 68 69 70 71
72 73 74 75 76 77 78 79 80 81 82 93 84 85 84 87 88 89
90 91 92 93 94 95 96 97 98 99 100 101 102 103 104 105 106 107
108 109 110

NAME TITLE

FIRM OR AFFILIATION

ADDRESS

COOK ENGINEERING Produces

"Extra-ORDINARY" METAL BELLOWS

Metallic bellows that withstand 600 million flexures. Bellows from ¾" O.D to unlimited diameters and length. Construction that affords a choice of metals from phosphor bronze, copper, stainless steel, Monel, Inconel, beryllium copper or alloy steel.



"Extra-ORDINARY" RELAYS



Cook relays are built to do the unusual jobs, and are engineered by request to meet "extraordinary" requirements. Illustrated is the new Cook Type 598 "Aeroelectric" Relay.

"Extra-ORDINARY" PRESSURE SWITCHES

Cook's Family of Pressure Actuated Switches cover a complete operating range, from extreme sensitivity requirements of ¼" water column differential to high pressure, hydraulic applications. Illustrated is the new Cook Weather-proof Miniature, for aircraft use.



● Let Cook engineers solve your bellows relay or pressure switch problems. Cook can give you the right answer QUICKLY.

COOK ELECTRIC Company

2700 SOUTHPORT AVE. CHICAGO 14, ILL.



It is generally appreciated that the item of perishable tool costs is an important factor in manufacturing accounting. The possibility of savings offered by using molybdenum high speed steels, instead of tungsten types, is therefore worth consideration.

The savings are due first to the lower cost per pound of molybdenum steels, and second to their lower density. The latter results in more tools from an equivalent poundage.

The net savings effected naturally depend on tool performance. It is an established fact that, in a substantial majority of careful comparative tests made in the past, the performance of properly heat-treated molybdenum steels equaled, where it did not better, that of tungsten steels.

A consultation with your supplier should confirm these statements, but it would be a simple matter to check them in your own plant.

CLIMAX PUBLISHES AUTHORITATIVE ENGINEERING DATA ON MOLYBDENUM APPLICATIONS.

ARMY NAVY

MOLYBDIC OXIDE, BRIQUETTED OR CANNED • FERROMOLYBDENUM • "CALCIUM MOLYBDATE"

Climax Molybdenum Company

500 Fifth Avenue · New York City

MANAGEMENT & EMPLOYEES

Aircraft Engine Facts 52

Originally published in Weight weekly newspaper to present engine facts in terms understandable to average employee, Wright Aeronautical Corp., Paterson, N. J., now offers entire series in book titled *Engineology*.

Marketing Chart 53

Basic marketing data in workable form is detailed in *Basic Marketing Chart of the United States*, published by Research Inst. of America, New York. Nation is divided geographically and figures are given on population, taxes paid, income, life insurance, electrical sales, and many other details.

Business Reports 54

Gen. Am. Transp. Corp., Chicago, has published following reports on business subjects: *How Waste Reduction Boosts Production*, *How Business Engineering Improves Business*, *How Accountancy and Purchasing Share in Effective Tool Control* and *Preventive Maintenance in the Railway Industry* (concerned with methods which have common industrial application).

Postwar Cargo Flying 55

Air Cargoes, booklet issued by Robert Gair Co., New York, contains information for shippers interested in air freight and express.

Express Pamphlet 56

Air Express Now and Tomorrow by Railway Express Agency discusses air shipping from standpoint of the carrier.

Corrective of Workers 57

Elliott Service Co., New York, announces publication of a working guide for department heads, supervisors, and foremen titled *How to Correct Workers*. Shows how small errors, wrong attitudes, and bad practices may be caught and corrected early and without offense to workers.

Contract Termination 58

Lyon Metal Products, Aurora, Ill., details its experience and methods in war contract termination procedure, reproducing forms used.

NEW PRODUCTS

Latest Machine Tools

Internal Grinder 59

New internal grinder with electric hydraulic control, high speed table feed and short stroke, is announced by **Say-Way Industries**, Detroit. Solenoid operated valves and aircraft type microlimit switches are designed to provide constant control and reduce time lag. Machine is also equipped for table feed and is available with either manual or electrically controlled power cross-feed which gives a cross-slide ratchet feed of .0001 in. per tooth, resulting in .0002 in. increase in diameter of hole. Cross-slide hand wheel is graduated in increments of .00025 in. Standard machine is equipped with manually operated wheel-truing mechanism with cam return, and it is also available with semi-automatic diamond wheel dresser. Spindle is driven by 3-hp. 3,600-rpm. dynamically balanced motor while workhead spindle is driven by ½ hp. 1,140-rpm. motor. Workhead spindle speeds of 90, 145, 255, and 365 rpm. are provided through adjustable V-belt drive.—**AVIATION**, July, '44.






Hydraulic Drilling Units 60

Barnes Drill Co., Rockford, Ill., announces completion of new hydraulic production drilling unit which can be arranged for drilling, reaming, facing, boring, counterboring, or tapping operations in any one or combination of horizontal-, vertical-, or angular positions. Available in three sizes, each is motorized according to requirements. Nos. 10 and 20 have essential parts built in complete with single motor, driving spindle rotations and hydraulic pump for any automatic hydraulic feed cycle. No. 5 (illustrated) is equipped with separate motor driven hydraulic system. Used vertically as a hydraulic production machine, this unit performs simultaneous drilling, reaming, and counterboring operations. Each unit has a flange support for mounting interchangeable auxiliary heads of any desired number and arrangement of spindles. One standard unit, equipped with an 8-spindle auxiliary head and used horizontally as a self-oiling production machine, is capable of facing and counterboring as many as 8 bosses simultaneously. Hydraulic system of built-in motor on Nos. 10 and 20 is automatically cooled by a fan blower mounted on shaft in front of motor. Chip conveyor removes chips. All controls are located on one side.—**AVIATION**, June '44.

Spot Welder 61

Rocker arm welder, Model "C", for continuous production spot welding of aircraft structural aluminum sections up





IF IT'S A

PLOMB PULLER

Any pulling job is likely to be a mean job—unless you use a Puller you can depend on. Expert mechanics throughout war industries like Plomb Pullers because of the better, safer, longer-lasting service they give.

They choose the other service tools in the complete Plomb Line, too—for the same reasons. From tiny screw drivers to mammoth industrial wrenches, all are built to highest quality standards. Select the ones you need for your war job from the Plomb dealer in your neighborhood.—*Plomb Tool Co., Los Angeles 54, Calif.*



FINE SERVICE TOOLS FOR ALL INDUSTRIES


to ⅛-in Alclad is announced by **Progressive Welder Co**, Detroit. Unit is rated at maximum point pressure of 8,000 lb (at 90 lb factory airline), and deflections are held to a minimum, it is said. Welder will handle fairly large work, throat depth being adjustable from 36 to 42 in. and throat opening from 7½ to 17½ in. In addition to 2-in. working stroke of rocker arm, latter is also provided with retracting stroke which provides 4¾-in. clearance between points to permit insertion of flanged work. Controls are provided for three different pressure conditions. Normal forging and light forging. Arms are designed to handle standard electrodes and holders, but refrigerated points may also be used. Electrodes may be mounted vertically or at 22½-deg. angle. Transformers are pancake type with 600 turns. A four position tap switch affecting selection of various turn ratios. Floor space of base is 35 x 66 in., height about 5 ft.—**AVIATION, July, '44.**

Wet Belt Grinder 62

Great coolant capacity and rigid construction are reported features of Model AG-8 wet belt grinder made by **Perfect Cable Machine Co**, Syracuse, N. Y. Unit is equipped with 35-gal self-contained recirculating pump system. Other features listed are whole clean-out drawer, toggle type switch, high table, and flexible tube as guide for coolant.—**AVIATION, July, '44.**

Chip Breaker, Finish Grinder 63


New heavy duty chip breaker and dia. mond finishing grinder has been designed by **Hammond Machinery Builders**, Kalamazoo, Mich., to meet requirements where large volume of carbide tools are being ground. Features newly designed angle vise to handle all types of hex and single point tools up to 2 in. larger if required. Vise has universal adjustments



and dials are direct reading. Diamond finishing grinding side (at left in illustration) is for use of either 6 or 7-in. dia. cup wheel. Tilting table assembly is moved by screw adjustment. Wheels may be changed without removing table assembly. Grinder is powered by ½-hp. motor, and coolant tank is of 1½-gal. capacity. Total weight is 750 lb.—**AVIATION, July, '44**

Straightening Press 64


Hydraulic press with 80-in. square table for straightening large gear blanks and metal rings has been designed by **Andersen Bros. Mfg. Co**, Rockford, Ill. Press illustrated has capacity of 25 tons and is operated by hand hydraulic pump. Similar presses for 10- to 50-ton capacity with hand or power control can be furnished. Hydraulic gage, calibrated in pounds, indicates actual pressure on ram



Stroke of ram is 6 in. and maximum vertical opening is 8 in. Floor space is 40X48 in., and net weight is 1,500 lb.—**AVIATION, July, '44.**

Lapping Machine. 65

Designed for simultaneous finishing operations on one or several cylindrical surfaces, Simplex lapper, it is stated, will also handle concentric and/or eccentric cylindrical portions of same time, as well as such sections on pins of short-throw cranks on compressors and journals and eccentric members of small camshafts. Machine's capacity is from ½ to 2 in. on diameters with lengths up to 24 in. Uses abrasive coated paper strips



applied to those surfaces on which reduced friction and initial wear is desired. Manufactured by Norton Co., Worcester, Mass.—**AVIATION, July, '44**



ShopEquipment & Accessories

Aluminum-Weld Electrode 66

Electrode with new coating for use in welding aluminum sheets and castings is announced by **Eutectic Welding Alloys Co.**, New York City. Stated to open a new field for arc welding—salvage and reclamation of aluminum castings—it is said that EutecTrode 2106 can be used to add metal without completely preheating casting and without overheating metal adjacent to weld. Metal may be added to faulty or improperly machined castings in overlaying of surfaces improperly cast, filling of low spots, filling faultily drilled holes and welding casting to sheet, says maker. Available in ⅛, 5/32, and 3/16 in. sizes.—**AVIATION, July, '44**

New Shear 67

Reported to incorporate best features of shears produced by **O'Neil-Irwin Mfg. Co.**, Minneapolis since 1946, this new shear No. 3 has precision adjustment for



stopping blade travel, metal stripping guide and built-in chute which delivers all materials at any speed. Net weight is 150 lb.; max. shearing width 12 in.; max. shearing capacity full width 18 gage steel plate (.048 in.).—**AVIATION, July, 44**

Shock Absorbing Mallet 68

New mallet offered by Taylor Mfg. Co., Milwaukee, is designed for use by air-

NORTON ABRASIVES



METALITE CLOTH SLOTTED DISCS

⅜ to 6 inch diameters


Speed War Jobs


(*Upper Illustration*)
This 2-Bore Aluminum Throttle Body has a finished bore. There was slippage with hand scrapers. Two 1½" unslotted Metalite discs, grit #60, back to back, were used. This method proved twice as fast as the former hand scraping.

(*Lower Illustration*)
In this illustration 5" Slotted Discs, grit #100, are used to put 1/16" radius on the edges of these Magnesium 3-Bore Throttle Bodies. This method saved tooling and additional machines. Time for the 3 bores is .68 of a minute.

These SLOTTED DISCS, in almost endless sizes and grits, are but one of many Metalite Cloth "Gadgets" ready for instant use on power tools. A few others illustrated below. We'll gladly help you select the proper "Gadgets" for improving a wide variety of your own sanding and finishing operations. Write us.

BEHR-MANNING (DIVISION OF NORTON COMPANY) TROY, N. Y.





Lives hang by threads aboard aircraft, — the screw-threads that hold together the component parts. And the screws most famous for HOLDING-POWER are those most favored for mechanical assemblies where hollow screws are used in plane or plant.

ALLENS have strength for set-ups with weld-like grip, not to be budged by shock-stresses or sustained vibration. Thread tolerances are held to a high Class 3 fit, for a high degree of frictional holding-power... Screws cold-drawn and *"pressur-formed"* of special-analysis ALLENOY steel, heat-treated under scientific controls. Hexagon sockets handily reached with Allen hex Keys in the hardest-to-get-at places. Adapted to high-speed assembling with power drivers.

Allen Hollow Screws and "Tru-Ground" Dowel Pins supplied only through Industrial Distributors in all centers.

THE ALLEN MANUFACTURING COMPANY
HARTFORD, ★ ALLEN ★ CONNECTICUT, U.S.A.

craft manufacturers where finely finished surfaces must be protected. Mallets are made in three weights 12, 18, and 24 oz. However heads are all same size and no weighted cores are used—AVIATION, July, '44

Detachable Hose Fitting 69

Developed for hydraulic installations in aircraft detachable hose male fitting consists of two pieces and swivel type fitting of three pieces each of which is replaceable individually. Assembly is accom



plished by screwing nipple into socket. Suitable for AN Standard medium pressure (three braid) and medium high pressure single wire braid hose. Made by Aeroquip Corp., Jackson, Mich.—AVIATION, July, '44

Bronze Facing of Steel 70


Method of bronze-facing steel pistons involves flame spraying of one material on another. In case of pistons, light steel blanks are sprayed (with special bronze alloy) to desired thickness, and bear on surface. This is rough machined in initial production, then given required high finish with oil grooves. Having extremely fine porosity sprayed bronze is stated to absorb and retain oil and to become self oiling after short use. Process was developed by Cleveland Pneumatic Aerol Div. of Cleveland Pneumatic Tool Co., Cleveland.—AVIATION, July, '44

Angle Drills 71

Offered by Atlas Tool Co., Pittsburgh, Pa., is new chrome plated angle drill stated to feature long life through thru absorption eliminating wear. Incorporated is grease retaining ring designed to prevent drip. Angle plates are equipped with 5/16-24, ¾-28, and 10-32 threaded spindles.—AVIATION, July, '44

One-Piece Hose Clamp 72

New one-piece clamp for hose has no gears or thumb screws. Clamp is snapped over hose by hand and locked by hand pressure on pliers. Designed for low



pressure connections. It may be had in wide range from 2 in. up. Made by Tinnerman Products, Cleveland.—AVIATION, July, '44

Asbestos for Air-duct Systems ... 73

New fire resistant asbestos product for use in air-duct heating and ventilating systems in aircraft has been developed by United States Rubber Co., New York City. It is stated that this product made of fabric, asbestos and synthetic coating of resin, can be completely deformed and still return to its original shape—AVIATION, July, '44

Precision Square 74

New feature of Ellatron master square offered by Dearborn Gage Co., Dearborn



Mich., is cylinder-form upright member screwed to base. As wear develops fresh new surface can be brought into use by turning cylinder slightly. Squares start at 4 in. size and can be obtained in larger models as desired.—AVIATION, July, '44

Combination Socket Wrench 75

Having same dimensions as a single socket wrench new "Tesco" multisocket wrench automatically accommodates No. 10 and No. 12 standard, ¼-in. standard and light, and 5/16-in. light hexagon nuts. By pressing over any of three sizes of nuts wrench automatically selects proper nested hexagonal tube, says maker, The Eastern Specialty Co., Philadelphia. Designed for heavy duty service, it provides clearance through barrel for studs up to 3/8 in. length. Handle and barrel are insulated.—AVIATION, July, '44.

Aluminum Surface Cleaner 76

New method of cleaning aluminum surfaces chemically and metallurgically is announced by Turco Products, Los Angeles. Product named Tuleo-etch is chemical bath to free surfaces of oxides, corrosive salts, grease and oil films, laying foundation for sound spot welding.—AVIATION, July, '44

Snap Gages 77

Gaarge Scherr Co., New York City, announces four new models of adjustable limit snap gages known as midget type for checking and inspecting small and



delicate parts. Work from .000 to .700 can be handled.—AVIATION, July, '44

Diamond Hand Hone 78


Designed with diamonds set in hard metal bond hand hone, made by Diamond Tool Replacements, Baltimore, provides new method for keeping cutting edges keen. Few strokes quickly sharpen high speed steel and hardest grade of carbide tipped tools it is stated. Made in three grit sizes—coarse 180 grit, medium 220 grit and fine 320 grit. Hone is approximately 4 in. long.—AVIATION, July, '44

Hand Model Infra-Red Lamp 79


Stated to be capable of developing temperature in 1,500-deg.-F. range, new tool for quick heating is announced by Fostoria Pressed Steel Co., Fostoria, Ohio. Suggested uses: Melting or flowing grease, pitch, oils, syrups; preheating materials prior to shearing or stamping; rapid drying of liquid coats; touch-up paint finishing, etc.—AVIATION, July, '44.

Indicating Light 80

Graybar Electric Co., New York City, distributor for H. R. Kirkland Co., Morristown, N. J., announces new indicating light with bayonet-locked lens cap. Unit,



for use with T 3¼-type single contact bayonet lamp bulb, embodies new design of lamp socket to provide direct connection from shell and center contact pin to terminal spades.—AVIATION, July, '44.



● Alert aviation procurement men have discovered that a single call to Graybar gets many aviation electrical needs faster, and on one order. It automatically puts at their service a network of more than 80 warehouses all over the United States, stocked with the superior aviation electrical products of over 200 manufacturers.

They have learned that items often unobtainable anywhere else may be secured through Graybar. This fast, efficient, all-inclusive service costs no more than buying from many smaller, scattered suppliers. Frequently it costs less.

There is a local Graybar Man who will make your business his personal responsibility. Call him today.

3344

GraybaR
IN OVER 80 PRINCIPAL CITIES
Executive Offices: Graybar Bldg., New York 17, N. Y.

GraybaR QUALITY 75 YEARS OF Electrical Distribution

"Air Transport" Speed


FOR MATERIALS HANDLING

with CRESCENT Electric Industrial Trucks



Crescent NA—Aviation leaders pick the Crescent NA because it's the super utility truck. The one shown is fitted out as a "travel leg tool room" at Pratt & Whitney Aircraft, East Hartford, Conn. The large platform area of the NA is adaptable to bulky loads, dump bodies, cranes and other auxiliaries.

Crescent NCR8—This Crescent model, in use at Rose Machine Foundries, Chattanooga, Tenn., offers the versatility required in many operations. A self-loading unit, it provides both high and low lifting forks and can also be used for trailing loads.



NEW CRESCENT CATALOG—FREE!

Here's the *new*, 24-page Crescent Catalog—yours for the asking. Shows large size illustrations of all Crescent models now being manufactured under WPB Limitation Orders L-112 and L-112a. Describes each model and its particular use. Contains complete specifications and engineering drawings. Write today for this valuable data book on electric industrial trucks—*it's free!*



Look around the factories, warehouses and loading platforms of America's big aviation plants. Watch the trucks go by that speed materials and parts at the stepped-up pace which aviation production demands. You'll see the Crescent emblem again and again. You'll notice that the models pictured are favorites. They're chosen for good reasons . . . and the captions tell why.

CRESCENT TRUCK COMPANY, 112a Willow St., Lebanon, Pa.

Crescent ELECTRIC TRUCKS and TRACTORS

Industrial Truck and Tractor Specialists for More Than 25 Years

Aircraft-Fitting Thread Taps 81


Special Acme multiple taps for threading quickly removable type aircraft fittings for fastening cowling, etc., are offered by Detroit Tap & Tool Co., De



troit. Taps currently produced range from 1-in. dia., both 10 and 12 pitch, while available types range from double to sextuple thread taps.—AVIATION, July, '44

Torque Wrench 82

Set at torques specified by buyer, these wrenches, known as socket drive models of Livermont Torq-Stop wrenches are stated to give both an audible and physical signal when desired torque load is reached. Socket drive uses lock connection and is adaptable to innumerable heads, extensions, crowsfeet, etc., it is said. Drive or working member is con




centric with rocker-pin. Settings are available on order at from 5 to 7.8 in.-lb. Maker is Richmond Inc., Los Angeles, Calif.—AVIATION, July, '44

Seam Welding Control 83

Control designed exclusively for seam welding, incorporating electronic timing circuit, is announced by General Electric Co., Industrial Control Div., Schenectady. Designated Type CR7560-B110, control is suited for operations where frequent changes of timing pattern are required. Operating on 230/460/575v., single-phase 60 cycle power supply, it consists of timing panel, firing and heat control panel and power panel, each of which can be separately disconnected and removed. An electronic circuit is designed to provide accuracy of timing pattern. Calibrated heat control dial is located on compact panel. Snap switches for independent adjustment of "heat" and "cool" time from 1 to 30 cycles are also located on this panel. Row of indicating lights show instantly when water flow is adequate, power has been applied and time delay has timed out.—AVIATION, July '44.

Replaceable-Point Dividers 84

Nerk Products, Los Angeles, has produced new toolmaker's dividers with replaceable steel points to maintain preserve accuracy and original length of dividers.—AVIATION, July, '44.



Portrait of an Ex-Problem

● At the start of the war our tremendous plane program called for millions of instruments which required a type of ball bearing *not then made in this country*. It was little larger than the head of a pin. It used steel balls so small that it took 111,111 to make a pound!

New Departure took on this problem and in the space of ten weeks had developed the process, built the special machinery and started producing these miniature pivot ball bearings. Now they are standard equipment in Artificial Horizons, Turn and Bank Indicators and Fuel and Manifold Pressure Gauges.

Each tiny ball bearing is complete with race, balls, separator and a retaining shield—as finely built and precisely made as *any* New Departure product.

Each is inspected, gauged, assembled, tested and packed without being touched by human hands—hospital clean and free from any hint of rust, lint or other foreign matter.

This is just another example of a new departure by New Departure—an organization with vast resources for research and a reputation for getting things done even under the most difficult conditions.

New Departure, Division of General Motors Corporation, Bristol, Connecticut. Principal Sales Offices in Los Angeles, Chicago and Detroit.

Nothing Rolls Like a Ball

NEW DEPARTURE

BALL  BEARINGS

3250

Push-Type Circuit Breaker 85

For aircraft use Square D Co., Detroit offers new line of push-type circuit breakers for employment in protection of low voltage circuits not requiring switching. Bimetallic trip element gives time limit protection against momentary overloads as well as protection on heavy overloads and short circuits. It is stated After tripping it is only necessary to push re-set button down to its farthest position. Class 9310 circuit breaker available in sizes 5 to 50 amp. is equipped with luminous indicating rings visible in darkness and with red indicating ring for daylight.—AVIATION, July, '44

Plastic Binder 86

Heinn Co., Milwaukee, announces new plastic Ring post binder stated to be lighter and stronger than metal. A combination of ring and post construction it is reported that arrangement prevents sheets tearing out simplifies sheet changing and eliminates bulging at center of binder. Made in colors and wide selection of cover materials.—AVIATION, July, '44




Resistance Measurer 87

Combining both Kelvin and Wheatstone bridges, Type 638-2 bridge provides resistance measuring instrument having range to 11.11 megohms in single portable instrument, states maker, Shallcross Mfg. Co., Collingdale, Pa. Low resistance measurements using Kelvin range utilize current and potential terminals to eliminate lead and contact resistance. Rheostat is variable in steps of 1 ohm for Wheatstone bridge measurements and 1 micro ohm for Kelvin measurements. Separate keys are provided for battery and galvanometer circuit.—AVIATION, July, '44

Bracket for Switches 88

Adjustable actuator bracket for switches is announced by Micro Switch Corp., Rockford, Ill. It is described as retaining sealed-in features of basic switch while providing tabs on steel actuator bracket and lever arm which may be bent to change mechanical characteristics of unit. Referring to sketch by bending tab "A" downward, lever mechanism is held nearer to operating plunger. The more tab is bent the less pretravel



Lever arm is returned to free position after each operation by spring "D". Operating point of combination is lowered or raised by bending tab "B" up or down. This tab is part of steel lever arm "B" and carries the overtravel spring mechanism "C", which consists of a spring which is pre-loaded above operating point of unit so that it compresses only after switch operates. Motion of actuator mechanism is carried by lever "E".—AVIATION, July, '44

Micrometer Grinding Gage 89


Distributed by Clawson & Bals Chicago the Sinarl micrometric visual grinding gage is for application while machine is in operation. Dial indicator guides operator as work is ground to size. Unit it is stated has no gears, levers, or angles. Dial is actuated by direct parallel thrust. Made in two models gage has ranges of ⅛ to 1¼ in. and ⅝ to 2½ in. Additional calipers for larger model provide ranges 2 to 5 in. and 5 to 8 in.—AVIATION, July, '44

Quick Access Fastener 90

M-Loo new type of quick access fastener for aircraft use, is made by Simmons Aerocessories, Long Island City, N. Y. It lies flush with exterior surface and finger pressure on plate opens door. Made of light stampings fastener has angle bent in tongue to by pass reinforcing flange around door opening.—AVIATION, July, '44.

(Continued on page 249)





Courtesy Pan American Airways System

"YANKEE" TOOLS

SPEED SERVICING!

Turn-around servicing of a Pan American Airways Clipper Ship is accomplished in 48 hours or less by a ground crew of 186 mechanics and inspectors . . . and "Yankee" Fine Mechanics' Tools help to speed and simplify this vital job. Designed to save time, trouble, and money, their inbuilt ingenuity is lengthening man-hours on the home front; their simplicity, strength, and compactness are upholding more than half a century's reputation for dependability. . . . Provide priority ratings whenever possible. Order from your industrial supply distributor, or write to us — Dept. AV-744.

"YANKEE" SPIRAL SCREW DRIVER No. 130A

"YANKEE" TOOLS

make good mechanics better

North Bros. Mfg. Co., Phila. 33, U. S. A.

Established 1880



TYPE OG

LOUIS ALLIS

OPEN "PROTECTED" MOTORS


Frame 225 Illustrated

Available Now — A Complete Line

Type OG Louis Allis motors have given a splended account of themselves in the war program for over two years—they are not a "new" line—They have been tried and proven in the most exacting and critical work of the present war effort.

These motors are now available in a complete line—in AC they are available from ½ to 500 HP and in DC from ¾ to 200 HP.

THE LOUIS ALLIS CO., MILWAUKEE 7, WIS.



Simple, Sturdy, Precision Construction Throughout.

Every part of the Louis Allis Type OG open "protected" motors are carefully engineered and precision built to assure long life of dependable service on the tough jobs.

Fourteen points of in-built quality construction are pointed out in the above disassembled view. Upon request a copy of new fully descriptive bulletin will be sent.

THE LOUIS ALLIS CO., MILWAUKEE 7, WIS.

"Sailable" Plastic 91

Announced by Monsanto Chemical Co., St. Louis, Mo., is Corex, new plastic which, it is stated 'can be boiled or sterilized and still retain strength and shape.' Present supply is reported going into such war products as radar, radio equipment, and other military electronic items where light weight, suitable electric insulating properties, and heat resistance characteristics are required. Employment




of the product in making aircraft instruments is noted by the company and as other possible aircraft part applications tubing, pulleys and decorative parts are listed along with general items which must withstand severe temperature conditions. Product is described as a thermoplastic readily molded in standard molding machines. It need not be plasticized and requires no filler; it can be made transparent but has light amber tint, and it is reported to have good resistance to low temperatures as well as to high (where ASTM heat distortion point is put at 220 deg. F.). Further details reported. Flexural strength stated to run about 18,000 lb. per square inch; water absorption, said on ASTM test is 0.3 percent; dielectric strength, more than 500 v. per mil, and rating as 'slow burning' in flammability tests. Accompanying photo shows of boiling-water immersion test on two plastic radio parts of identical size and shape. Black part right, made of company's product, is seen to have withstood test.—AVIATION, July, '44.


Portable Lighting Unit 92

Armored portable lighting unit made by Hoffman Co., York, Pa., has convenient handle and large hook. Light globe is aluminum finished with one side plain and clear for concentration of light. Wire guard is made from flat, die-cut sheet steel. Units, using 40 w., 110 v. globe, are available with any length of cord.—AVIATION, July, '44.

Post-Forming Plastic 93

Panelyte grade 800 is a new post-forming material supplied as a fully cured laminated thermosetting sheet which can be stamped, bent, and drawn in process similar to that used in metal stamping. It is stated that processing is simplified because molds of Kirksite,





FOR *Vital* JOBS IT'S AIRCRAFT... "Tailor Made" NUTS

Vital Precision equipment such as the Lord RL-25 Dynofocal assembly for Wright R-2600 Radial Aircraft engines demand the finest precision made nuts on the market. That is why Aircraft "Tailor Made" nuts are used.

These assemblies must withstand the unbalanced forces produced by these engines and Aircraft "Tailor Made" nuts have the very important role of keeping assemblies tightly held together at all times under every conceivable condition.

Perhaps you have a need for precision made nuts; if so, send us your blueprints; we will be only too glad to quote prices.

Aircraft
NUT CORPORATION
2029 EAST 102nd ST.
CLEVELAND, OHIO



When a Thunderbolt strikes . . . anything can happen

A THUNDERBOLT roars over the Channel Calais coming up! An ack-ack gun barks in German from a flak tower. But not for long. Eight 50 caliber machine guns ram hot steel down its throat.

Work to be done upstairs? A flight of Thunderbolts swoops down from high heaven to scatter a cloud of ME's harrying Fortresses on bombing runs over Berlin.

Work to be done on the "deck"? Two earth-quaking bombs slip from beneath a diving Thunderbolt's wings at tree top level. A bridge blows up . . . and with it the last chance of Nazi reserves to reach the invasion front.

Flown by the finest pilots in the world, the Thunderbolt comes alive. When it strikes, high or low, anything can happen. Guided by skilled hands, it's a fighter that *does everything*. And when hundreds of them strike, everything *does* happen.

The newest Republic P-47 Thunderbolt, with bubble canopy, gives a pilot around-the-clock vision. With hundreds more "emergency" horsepower, he makes and breaks contact with the enemy at will. New propellers add 400 feet per minute to his climb. With a doubled radius of action, the protection of the Thunderbolt's devastating fire power permits heavy bombers a deeper penetration into enemy territory.

Stratosphere fighter, long distance escort, dive bomber, ground strafer—the Republic P-47 Thunderbolt is a busy plane these invasion days.

Republic Aviation Corporation, Farmingdale, Long Island, New York, and Evansville, Indiana


Republic *firsts* in war point to *firsts* in peace

REPUBLIC AVIATION
CORPORATION
Specialists in High-speed, High-altitude Aircraft

cast phenolic, laminated phenolic or wood may be used. In this process, material not metal is heated. High pressures are not required it being reported that small air cylinders are suitable and in some cases hand presses will suffice. Developed by Panelyte Div. of St Regis Paper Co. —AVIATION, July, '44

Self-Adapting Electrode 94

Frostpoint spot welding electrode self-adapting for use with standard electrode holders, thus eliminating need for adapters, is announced by Frostrode Products, Detroit. Retaining other features of standard Frostrode, new electrode is stated to be interchangeable with conventional electrodes. When electrode is inserted in standard holder deflector tube is engaged by full-length coolant guide providing metered flow of coolant through internally fined "Frostcap". Return flow is through parallel passages. Available in ⅝- and ⅞-in. od and any standard length.—AVIATION, July, '44





Adjustable Hole Cutters 95

New set of adjustable hole cutters to cut all diameters from ⅝ in. to 3½ in. is announced by Reist H. Clark Co., Beverly Hills, Calif. These cutters—with straight shanks for use as hand tools, in portable electric and pneumatic drills, or in light drill presses—are stated to produce clean holes requiring no grinding, reaming, or filing. They are also said to be suitable for use in lathes and other spindle-type machines. Consist of straight shank on hexagon body into which are set three high-speed steel blades at 120-deg intervals. Largest of three tools has capacity ranging from thin sheets to ⅝ in. thick (1¼ in. where work can be reversed). It is reported possible to cut holes in curved or irregular surfaces such as pipe or tubing. Smallest cutter has ⅜ in. straight shank, cuts holes ⅝ in. to 1⅛ in., equipped with ¼-in. drill pilot. Second size has ½-in. straight shank and is for cutting all diameters between 1 in. and 2½ in. Largest cutter has ⅝-in. shank or No. 2 Morse Taper and covers all diameters between 2 in. and 3½ in. Other sizes up to 10 in. and thickness capacities to 3 in. are available.—AVIATION, July, '44

Electronic D.C. Motor Drives 96

Line of adjustable speed electronic motor drives to provide d.c. performance from a.c. power without requiring special motors is announced by Weltronic Co., Grand River, Mich. Self contained package units are applicable to any machine driven by d.c. shunt motor. Electronic rectifier tubes are employed for conversion. Each circuit being individually controlled through other electronic tubes for speed adjustment and current regulation. Full field strength of motor and limited armature current is utilized in starting so that maximum torque may be had without causing excessive power line surges and speed may be varied without sacrificing torque. It is said Stepless control of motor speed is obtained by setting a dial. Dynamic braking, dual-control stations, limit switches, or sequence and time controls may be used with units which may be wall- or floor-mounted, and external transformers are not required. Capacities: From ½ to 3 hp. single-phase and 5 to 10 hp. three-phase (other sizes or special designs for specific applications). Standard voltages are 220/440 at 60 cycles. 550 v. and 25 or 50 cycle machines may be had.—AVIATION, July '44





Precision

HYDRAULIC TESTING MACHINES

. . . . have repeatedly demonstrated the practical truth in the words, 'One Test is Worth a Thousand Expert Opinions.' Because they have simplified the science of testing the physical properties of materials they are widely used throughout the wartime industries today. Here Riehle Testing Machines "ferret out" material weaknesses and defects, avoid failures before they occur. This technique of progressive testing on the production line and in research laboratories saves valuable machine and man-hours. Write for descriptive literature and quotations.


Pendulum load indicators are more accurate and dependable because it operates on the natural laws of gravitation. This principle of operation is not affected by temperature changes or subject to metal fatigue.

ARMY NAVY

RIEHLE *HYDRAULIC TESTING MACHINES*

Riehle Testing Machine Division, American Machine and Metals, Inc.
EAST MOLINE, ILLINOIS

Other Products: IMPACT TESTERS • VICKERS HARDNESS MACHINES
BRINELL HARDNESS TESTERS • MEASURING INSTRUMENTS



IT IS gratifying to obtain prompt shipment of materials and parts! Even more so, if they exactly suit your purpose. This double achievement is routine occurrence at plants where Booth "prescription" felts — precision die-cut to specifications — are overcoming critical material shortages. Aircraft and other vital war industries thus bypass many a production problem!

THE BOOTH FELT COMPANY
402 19th Street Brooklyn, N. Y.
745 Sherman Street Chicago, Ill.

APPLICATION CHART AND SAMPLE KIT . . . Contains swatches of S.A.E. felt types, with specification tables Write for it. (No sales follow-up.)


2070

Booth
TRADE MARK

PRECISION CUT FELT PARTS

Switch Combinations 97

New Duraswitch unit is available combined with Ashcroft gage. Gage has slide rule dial for accurate adjustment of switch to control point. Type illustrated (series E-100) is for pressure only, while models in series E-200 are for both



gressure and temperature applications as a pressure control and pressure gage combination, or temperature control and thermometer combination, in single or duplex types. Made by Electro Mechanical Div., Manning, Maxwell & Moore, Bridgeport, Conn.—AVIATION, July, '44

Oil Separator Filter 98

New oil separator filter for ventilating systems, made by Air-Maze Corp., Cleveland, is designed to remove oil, kerosene, etc. entrained in air as well as dust and dirt. Unit consists of permanent viscous-impingement filter and a removable oil collecting media to trap liquid particles.—AVIATION, July, '44.

Parts-Cleaning Booth 99


A small parts cleaning booth, designed to meet needs of aviation manufacturing and maintenance shops, is announced by Twin Products Co., Los Angeles, Calif., and is available in three sizes: 15 in. deep, 20 in. wide and 20 in. high; 20 in. deep, 30 in. wide and 30 in. high and 24 in. x 60 in. x 60 in., the latter being a floor model on 60 in. legs and equipped with a ¾-hp electric motor pump, filter, and exhaust fan. A tank on one side of booth contains a penetrating solution which liquifies or loosens stubborn deposits such as burned on oil, heavy dried grease and carbon. A wire basket facilitates handling of parts. Spray gun is sturdy, simple to operate and positive in action. Booth drains into a sump where used solvent is collected for re use. At rear of booth a vent provides a suitable place for installation of an exhaust fan (if one is required), for two smaller models.—AVIATION, July, '44

For Removing Broken Drills 100

Broken drills and taps are removed from nonferrous castings and machined parts without altering threads or holes. It is stated by means of an electrolytic process which disintegrates and dissolves embedded fragments. Specially designed electrolyte unit operating on 110 v. a.c. controls process. Up to three dozen taps can be removed at one time. Special formula solution is furnished for every nonferrous metal and alloy, and full line of solutions is available for anodizing, chromatizing, phosphatizing, cleaning and plating all metals. Distributed by Mechemel Eng. & Sales Co., Chicago.—AVIATION, July, '44

Aviation Engine Starter 101

Eclipse-Pioneer Div., Bendix Aviation Corp., Teterboro, N. J., announces new starter for aircraft engines in 1,200-2,500 hp class, with reserve for engines up to 3,000 hp. Series 46 starters provide



four methods of cranking: (1) Combination inertia and direct-cranking for normal operation; (2) direct cranking alone for warm engine starting; (3) inertia cranking alone; and (4) hand cranking for emergencies. During normal operation with nominal engine cranking torque of 400 lb ft, starter is designed to provide initial cranking speed of 115 rpm followed by direct-cranking of 60 rpm. Starters are available for one-wire, 24 v. d.c. operation either clockwise or counterclockwise rotation with 8 or 15-tooth jaws. Incorporated is built-in meshing solenoid for automatic control of starter jaw engagement and a pre-set friction-disk overload clutch, sealed against entrance of oil. Specifications: Weight, 42½ lb. with 8-in. mounting flange and 43½ lb. with 7-in. flange; measurements 6⅝-in. dia. and 12⅝ in. from mounting flange to back head.—AVIATION, July, '44

Dimension Checker 102

Check-Matic is device for checking dimensions of production parts individually and at high production rate, reports maker, Interlake Engineering Co., Detroit. Provided it is stated is automatic inspection of parts up to 1½ in. dia. and 2 in. in height, checking "go" and "no-go" on such dimensions as outside and inside diameters, depth of counterbores, wall thickness, and depth of holes. Parts are placed in holes of machine's revolving dial, which carries them to various gages. Parts failing to meet test are ejected through tubes running from each gage. Standard model has 18-hole dial and is designed to check up to 13 dimensions.—AVIATION, July, '44

Portable D.C. Power 103


Designed for use on assembly lines, in laboratories, and in maintenance departments by P. R. Mallory & Co., Indianapolis, new portable d.c. power supply provides power for manufacturing, testing, and operating all electrical and electronic equipment in aircraft. Can also be used to taper charge batteries or battery carts. Unit is designed to



operate from 3-phase a.c. lines of 208 and 230 v. Three models are offered. No. VA1000, with d.c. output of 10 to 16 v. at 100 amp. or 20 to 32 v. at 50 amps. No. VA8000, with d.c. output of 0 to 16 v. at 250 amp. or 20 to 32 v. at 100 amp. and No. VA4500 with d.c. output of 20 to 16 v. at 300 amp. or 20 to 32 v. at 150 amp. Models with similar d.c. output, but for operation on 460 v. a.c. are also available.—AVIATION, July, '44

Large Capacity Collet Chuck 104

New line of Master collet chucks with larger capacity is being marketed by United Industries, Detroit. Included are four sizes: ⅞, 1, 1⅜ in. and 2⅝ in. round and special larger sizes are available.—AVIATION, July, '44




PROGRESS
is born of experience

Simmons hydraulic engineers and production experts have demonstrated time and time again their leadership in the hydraulic field by producing intricate hydraulic equipment for the aviation industry. No other industry demands such painstaking accuracy.

Among other things we are now producing is the Landing Gear Uplock Mechanism on Republic's famous P47 Thunderbolt fighter. Here close tolerances means exacting precision work, no deviations. Our intricate mechanisms represent the acme of accuracy, because, throughout every step of production, they are checked, inspected, gauged again and again.

If you need hydraulic equipment or if you need information on the adaptation of hydraulics to your particular problems, get in touch with our engineers. You're under no obligation and we may already have your answer.



SIMMONS
Manufacturing Co.
ASHLAND, OHIO

Surface Finish Standards 105

University Machine Co., Cambridge Mass., has developed set of surface finish comparison standards for specifying and checking surface roughness. There are 23 specimens with roughnesses range from 2 millionths of an inch (rms) to 500 millionths. Blocks are of stainless steel and include representative specimens of all ordinary machine tool operations, such as polishing, grinding, turning, shaping and milling. Each specimen is engraved with machine operation and microinch reading.—AVIATION, July, '44

Coated Electrodes 106


Wilson Welder & Metals Co., New York City, announces new coated aluminum-bronze electrode No. 288, which is a shielded arc electrode and can also be used as a filler rod in carbon arc welding. It is stated it will produce deposits of great strength and hot ductability; also that it can be used in welding most bronzes, malleable and cast iron, and steel as well as dissimilar metals. Wide range of sizes is offered.—AVIATION, July, '44

Synthetic Rubber Stock 107

General purpose synthetic rubber stock for use in oil seals, gaskets, O rings and other types of seals and parts requiring resistance to heat and oil, has been developed by Los Angeles Standard Rubber, Los Angeles. New Buca ¾ stock 1148-18) is flexible to —5a deg F. It is stated.—AVIATION, July, '44

Hydraulic Shut-Off Valve 108

For aircraft controls "KwikKlog" is single seated, balanced shut-off valve stated to be unaffected by back pressure either in closed or open position. Maker is Automatic Products Co., Milwaukee.



Designed to operate at low temperatures valve is reported to close instantaneously against maximum pressure of 3 500 lb psi, and to enable quick change for either clockwise or counterclockwise operation. Outside dimensions of valve illustrated are 2½x3 2⅞x1¼ in.—AVIATION, July, '44


Glass-Asbestos Textile 109

New textile made by combining glass and asbestos fibers is being used in protective boots in aircraft—gun boots, tail wheel boots—also to protect landing gear from hot exhaust of supercharger. Moreover it is used in cord form for shroud lines of military flares. Made by Owens Corning Fiberglas Corp.—AVIATION, July, '44

Enclosed Pilot Light 110

Primarily for ungrounded panels this new enclosed pilot light is equipped with two solder terminals. Models No. 1110 (faceted jewel) and No. 1111 (plain jewel) take long bulbs. Models No. 1112 (faceted jewel) and No. 1113 (plain jewel) take round bulbs. Unit is also available in shutter type for applications that require variable intensities. Here a 60-deg. turn of shutter provides gradation from bright light through intermediate glows and down to dim or total blackout. These latter models (1111, faceted jewel and 1113 plain jewel) provide for round bulbs. Can also be furnished with polarized lens. All models mount in an 11/16-in. hole and have ½-in. jewels. Made by Gelhard Mfg. Co., Springfield, Ill.—AVIATION, July, '44





GIVE YOUR OPERATOR AN EXTRA HAND!

Because Nature gave us two hands, it is natural to envision "hand work" such as riveting, as limited to what can be accomplished with two hands in an operation.

With Milford's varied line of automatic rivet setting machines, FOOT OPERATED, the practical effect of three hands is obtained, thus putting the emphasis on the element of time saving in rivet application.

May we recommend the type of machine best suited to meet your individual requirements? An inquiry will bring quick response.

★ ★ ★ ★ ★

The MILFORD RIVET & MACHINE CO.

Post Road, Milford, Connecticut

GENERAL RIVET & MACHINE DIVISION, ELYRIA, OHIO

Russian Women Flyers

(Continued from page 117)

us brief the latters background. Born in Moscow in 1912, the daughter of a music teacher Marina after finishing secondary school chose to work in a factory while continuing to study. Since Marina soon became interested in aviation she gave up her factory job and took a position as secretary to a profes-or in an aeronautical institute, in this way she felt she would be better able to continue learning about flying. And she did pick up much knowledge of flying instruments in the course of preparing material for the professor's classes.

At 23, Marina was graduated from flying school, where her talents as an aviator, as an organizer of people, and as a commander possessing dynamic energy brought her to the attention of her teachers.

Raskova made many epic flights—from Leningrad to Moscow, from Moscow to Sevastopol, and between other key points—before she became a co-pilot on the Sevastopol-Archangel non-stop trip. Success of this flight later brought Capt. Ossipenko and Senior Lt. Raskova together for their record-making 3,669-mi. non-stop flight from Moscow to a maritime village in Siberia in September 1938.

Marina, then 26, was aviator; while Valentina Grizodubova was again commander, and Paulina Ossipenko was second pilot. The three women brought their plane the *Rodina* (Russian word for 'Motherland") to a safe landing after 26 hr. 29 min. in the air. The date was Sept. 24, 1938. The women flyers received national honors, additionally, a special-issue postage stamp was dedicated to them.

As for bombing activities, only recently Maj. Stepan Grigoriev of the Red Air Force, reported that a night-bomber outfit staffed by women under the command of a woman flyer, E. Bershanskaya, had performed such valuable services in bombing enemy railroad junctions, supply trains, and ammunition dumps that grant had been made of the honorary title, "Guards Air Unit." Each of the 36 women received a distinguished service medal.

A women's fighter unit flew with signal brilliance at the battle of Stalingrad; at many other points on the long front women are combatting the enemy. Nor is participation of women in the science and mechanics of aviation something new. From the very beginning, when Russia decided that its citizens should become familiar with aircraft and with parachute jumping, airminded young women as well as young men swelled the membership of the Ossoviakhim, society for defense.

As civilian aviation increased, the number of women pilots grew larger. Mail, passengers, and cargo were soon being transported over the enormous length and breadth of Russia by air, and many of the planes were put under command of women pilots. One of them, Claudia Berezhnaya, made the long run from Moscow to Vladivostock in 53 hr., something of a record.

Planes were needed to transport fresh fish from the north to the cities in the central regions of the USSR. Fruits were brought from distant places without being spoiled. Furs arrived in time for specific sales. Sulphur was flown from the Kara-Kum Desert, and gold was delivered to the big cities in record time. For such transport jobs, women pilots were eligible, since their value in civilian aviation was acknowledged and there were no objections from any section of the population to their playing a major role in this field of Soviet life.

It was the leading women diplomat, Madame Alexandra Kollontay, who paid tribute to civilian women aviators before World War II. Mme. Kollontay (who served successively as Soviet Minister to Mexico, Norway, and now Sweden under the Commissars of Foreign Affairs Chicherin, Litvinov, and Molotov) said she experienced one of her proudest days when, at the signing of a commercial treaty for a new Moscow-Stockholm air route she found that the director of the Russian civilian line was the very personable young Vera Lomako, graduate of the aeronautical services.

Women introduced parachute jumping as a sport in Russia, and the names of the pioneer jumpers—Kuleshova, Grokhovskaya, Churkova, and Fyodorova—are often repeated today. Two women, Shishmareva and Pyasetkaya, made women's world record jumps of 26,158 ft. without oxygen masks. Another woman, Kamneva, rang up a delayed-jump mark of 8,856 ft., and young Kouza Malinovskaya, of the Young Communist League, recently won a certificate of honor for a record parachute jump, details of which are awaited.

Such women have inspired others to follow their leads. Before the war, girls used their spare time to learn to fly at the air clubs; and when they showed sufficient skill, they were accepted as pilots. For instance, Katya Mednikova, a worker in the Calibre plant, went on to win records in brilliant speed flights. Katya is now a war flyer, as is also Russiko Zhordana, recently decorated with the Order of the Red Star and made instructor at the Tbilsi Air Club. Among other female military flyers who have distinguished themselves in the war are Podlerova, Lomako, Nestereoko, Uruzovaia, Kazarnovka, and Khomyakova.

Today, 150,000 women engineers, technicians, and mechanics—like Maria Tarkova, singled out for her splendid work at Tushino Flying Field—are working throughout Russia. Women are piloting ambulance planes, and they are also flying the planes carrying medical supplies. Women pilots likewise transport blood plasma and fly surgeons from one part of the front to another for emergency operations.

Difficult terrain has not fazed the Russian women pilots. They have not hesitated to fly over snow-capped mountain peaks. On the other hand, in operating seaplanes over the broad Russian waters they perhaps hope to emulate Ekaterina Mednikova, holder of an international women's seaplane record. They can also be found crop dusting in the farmlands and giving aero-chemical battle to the malarial



Put the job up to this

WELDED STAINLESS TUBING

When it comes to exhaust bends and collector rings there are qualities in Carpenter Welded Stainless Tubing that should not be overlooked in their design and manufacture.

Heat Resistant

Type 347 used in this application will not scale up to 1700° F.

Corrosion Resistant

It stands up under severe corrosive conditions especially when high temperatures are encountered and welding is done in the fabrication.

Easy to Fabricate

It is sufficiently ductile to permit easy bending, flanging, expanding, etc.

Lightweight with Strength

The uniform wall thickness of Welded Stainless Tubing allows use of lighter gauges without sacrificing strength.

Send for Engineering Data

This convenient file folder will help you select the correct type of Welded Stainless Tubing for your needs. It contains data on physical properties, corrosion resistance, sizes and shapes available. Just drop us a line on your company letterhead.



THE CARPENTER STEEL COMPANY
Welded Alloy Tube Division, Kenilworth, N. J.


Carpenter
WELDED
STAINLESS TUBING

PEOPLE WHO NEVER MAKE THE HEADLINES




From the unrecognized private in the front lines, to the modest factory worker, there's a job to be done to the limit of their endurance.

One of the things our workers make is this automatic safety control used on anti-ice equipment for bombing planes. Another product built for our flying forces is this motorized temperature modulating control. It is used for maintaining cabin, cockpit, carburetor, or air intake temperatures, where close control is required. It may be adapted for other temperature controlling requirements.





In addition, for use as "muscle motors" in many types of applications requiring automatic or electrically controlled power, our workers make several types of Servos, such as the one illustrated below. Its operation can save planes and pilots when called upon to act!



If you build aircraft and this type of equipment will help make your planes better or safer to fly, we will be glad to supply engineering data and application information on request.

LET'S GO! U.S.A. KEEP 'EM FLYING!

WHITE-RODGERS ELECTRIC CO.

SAINT LOUIS

mosquito On this aviation front expert pilots like young Irene Vishnevskaya and pretty Zuleika Seid Mamedova have been in the lead.

Aviation behind the lines, in all civilian pursuits, has long been encouraged for women. In 1939, Marina Raskova aided this movement with a pointed article in *Pravda* in which she asked young women to study to become meteorologists radio operators, engineers and technicians—for she foresaw a great need for these services

But she could not prevent others of her sex from becoming, like herself, full-fledged members of the Red Air Force. A year ago, two young women sky fighters who had seen service at Stalingrad—Lilya Litvak and Katya Budanova—were each given the Order of the Red Star They had run up a joint score of eleven Nazi planes in one year of service. Junior Lt Litvak had accounted for three planes in single combat and two in group combat, while Lt Budanova had downed three German planes in single flights and three more in group fighting

Lt. Litvak's heroism won foremost praise In a flight on Mar 22, 1943, she was assailed by four Messerschmitts, yet managed to down two and elude the others. She had expended all her fuel and ammunition, moreover suffered a bad leg wound, but somehow she got to safety A few months later, however (August 1943) she was killed at the battle of Kharkov, dying without knowing that the city had been recaptured from the enemy.

Last summer, Marina Ivanova, a 22-yr.-old bomber pilot, received the Order of the Patriotic War for having successfully carried out 125 missions in 70 days Later, she was badly injured while bombing a Nazi artillery dump

Another receiving acclaim is the slender 28-yr.-old Vera Mustakova the mother of two children A flyer for more than eight years, she is now a war pilot. Her husband, a night pilot, was killed in a raid; accordingly she is determined to fight harder than ever.

Among the men flyers, Russia is naturally proud of war aces like Kostilev, who has 42 enemy planes to his credit. Twice Kostilev was awarded the Order of Lenin and the Order of the Red Banner; also he was recently given the Gold Star and a medal for the defense of Leningrad.

But Russia is also proud of its women flyers, who, in the line of active fighting as well as behind the front and in plane factories are performing 'round the clock. Russia hails their heroism.

Blitzkrieg Goes to Sea

(*Continued from page* 115)

cupies the position of a mobile air base, and as such it must be adequately defended because it provides the point of contact from which aviation can strike at the vitals of the enemy Development of these points of contact from sea is in direct ratio to the number of carriers employed, but carriers must have proper support, and surface guns must move in after long range air attacks have cleared the way in order to exploit a thrust completely

Aircraft carriers certainly are the new queens of the seas Air war is glamorous and tremendously effective. Sometimes we airmen, in our enthusiasm, convey an impression that we believe we can fight a war single-handed. This is not the place to discuss the functions and importance of various branches of surface support, but we must remember that, while air power is certainly the sparkplug of the modern war machine, a sparkplug without the rest of an engine is just as impotent as the engine minus the spark.

The Navy's strength is and traditionally always has been its unity, that split-second teamwork of all arms, each one of which understands the aims and capabilities of the others


Carrier warfare in the Pacific, although ever more brilliantly successful, is no longer an end in itself. Two years ago it was Its aim was to stop the enemy, and it stopped him cold Now, however, the Navy has shifted from a strategic *defense* to a strategic as well as tactical *offense*. The carrier and its aircraft have become part of a team setting the pace and clearing the way for surface operations and amphibious advance. Without carriers, such advance would be most difficult; but without surface and amphibious superiority, victory might be impossible

The Jap's carrier strength apparently has been cut to ribbons His carrier pilots are now operating from fixed island airfields, their ranges limited by the immobility of their bases Although Japan still holds powerfully fortified, strategically located islands, the scores of carriers and hundreds of aircraft which the United States can concentrate at any of those points on any given D-day make us immediate masters of Pacific tactics

While the fact that those scores of carriers are already in action is a spectacular production achievement, some of the credit for the speed with which this nation recovered from the Pearl Harbor blow must go to foresighted congressmen who authorized new carrier construction before Japan attacked. Progressive Naval leadership which embarked on an escort carrier program six months before the nation was actually at war also must be recognized.

Such foresight was, however, based on facts, not fantasy Today, varied opinions are being voiced about carriers and aircraft of the future. Some are sheer guesswork and wishful thinking—dreaming, actually—which must not be confused with foresight nor with current needs. Dreams are not the stuff from which victory is fashioned. History records the fate of nations which, whatever their dreams, learned to their sorrow that there is no easy, halfway route to victory. Wars are won with weapons at hand, or in sight.

Aircraft carriers, which have taken the lightning of 'lightning war" to sea, provide whatever easy route we can expect. With them we have the weapons of victory in sight.



WELDON *Aircraft* FLUID METERING PUMPS

● Because of its unfailing performance at extreme temperatures, the WELDON Propeller Anti-Icing Pump illustrated above has been granted "Yellow Dot" approval according to Army Air Corps specifications WELDON electrically driven pumps have proved their dependability also for carburetor and windshield anti-icing and for delivery of aircraft cabin heater fuel.

Write for data on Engineering, Pressure Ranges, Engine Driven Pumps and Special Pump requirements.

THE WELDON TOOL CO. Cleveland 4, Ohio

3000 WOODHILL ROAD



The aircraft industry relies on

Ampco Metal, Inc.

. . . and for resistance to severe conditions of wear, shock, and corrosion, the industry relies on Ampco Metal itself. This superior aluminum bronze alloy is used for a growing number of critical parts on almost every American-made plane. Known for its closely controlled combinations of physical properties to meet specific needs, Ampco is fabricated with the skill of 30 years of specialized experience, and with the speed and precision possible only with the most modern, varied, and extensive production and machining facilities. Why not avail yourself of this superior product and service? Investigate! A letter or post card will place a competent field engineer at your service without charge. Write for free bulletin "Ampco Metal in Aircraft." *Ampco Metal, Inc., Dept A-7, Milwaukee 4, Wisconsin.*

AA 3

Reg U. S. Pat Off.

AMPCO Metal

The Metal without an Equal

Fan Cooling

(*Continued from page 151*)

quired, that is, $\Delta P'' = \Delta P - (P_1 - P_s) - \Delta P' = 0$. In this simplified case, total pressure P_1 before cowl exit (available to accelerate the leaving air to atmospheric pressure outside) is restored to full q_s. Thus the leaving relative velocity V_1 is restored to equal flight velocity V_s, and the forward absolute velocity energy remaining in the air after it has been discharged is reduced to zero.

This is the physical condition representing 100 percent cowl pumping efficiency (also evident from Equation (4), when $V_s/V_3 = 1$, or Equation (5), when $\Delta P''/q = 0$). The power $Q\Delta P$ to overcome the internal cowl and engine resistance is, in this case, all provided by the fan, which deprives the propeller shaft of somewhat more bhp (depending on fan efficiency), this in turn depriving the propeller of somewhat less thp (depending on propeller efficiency).

Further assuming for the moment that the fan efficiency and propeller efficiency are equal, the propeller thp is, by these exchanges, deprived of exactly the internal cooling thp of the cowl and engine.

Again removing the fan, the internal cooling thp value is restored to the propeller thp, and the cooling air is pumped through the ducting and engine by the cowl but not at 100 percent efficiency, far from it, at from 80 down to 20 percent efficiency. Thus by removing the fan we may be paying five times as much for our cooling in this highly simplified and special case.

This probably represents the irreducible minimum of cooling drag obtainable by the addition of a fan to a given engine and installation design. Further reduction of ΔP through reduced cowl losses or reduced baffle drop would give further reward in direct ratio to this pressure-drop reduction, but whether this is determined feasible or not it is seen that under marginal cooling conditions the gain from the fan is very worth while.

In a fan located at the cowl inlet the pressure drop ΔP which must be charged against many current cowls, may be greatly reduced, with the large rewards described earlier—because pressure losses as high as $3q$ to $4q$ are occurring before the engine in a number of modern installations. Uniform flow conditions achieved with an engine nose fan may or may not cut down these losses; a certain portion perhaps will remain, caused by propeller shank effects.

In any event, in computation of performance with a fan installed, loss actually occurring within the entrance is eliminated entirely from the cowl ΔP requirement, since this region becomes a part of the fan, and the loss is already included and discounted in the figure of static fan boost designed for and delivered at front of engine, not at cowl inlet.

Since a fan helps most when $\Delta P/q$ is high, that is, when cooling conditions are marginal, benefit is greatest in climb, or level flight near ceiling. Fig 4 represents a typical pair of airplane power-required and power-available curves. The ordinate "B," as is well known determines the rate of climb at any indicated airspeed selected, since it is the power left over to raise the weight of the plane after deducting ordinate 'A,' the power required to fly it level at the airspeed. Application of the fan reduces the power available by a certain small increment, but at a high value of $\Delta P/q$, application of the fan also reduces the power-required curve by several times this increment, resulting in a net gain in power, B', available for climbing, with proportionately increased rate of climb.

Like earnings on common stock after heavy fixed charges, a moderate improvement on a total power basis gives a large percentage gain for climbing dividends. In many cases a fan should improve the rate of climb 20 percent—in extreme cases, more.

In 1942 we were all reminded quite emphatically what a fine rate of climb the German Focke-Wulf 190 had (see Fig 5). Was it coincidence that this ship completely eliminated induced cooling and energized the cooling air by a fan? No indeed. The fan and sliding gill contributed, in all probability, a very substantial percentage of the rate of climb of the FW 190 and they still do.

Ceiling likewise benefits materially from a little boost of thp. Since ceiling also is one of the high $\Delta P/q$ operations, involving marginal cooling and reduced indicated speed, it stands to gain much with rate of climb, by fan application. The two engined transport (whose single-engine ceiling leaves a good deal to be desired) or the overloaded bomber offer interesting possibilities for application of this principle in improvement of ceiling.


It should be emphasized that it is unnecessary to overcome the entire cowl ΔP with the fan leaving zero energy wasted in the discharged air. This will usually be found impracticable. When improvement of an existing installation is the goal, the lion's share of the gain from a fan is to be had in raising cowl pump efficiency from values of .20—.40 up to values of .70—.80. Diminishing returns in cooling power reduction are achieved at efficiencies above the latter range. This being the case, reference to Fig. 2 will assist in approximating the power fan boost.

The proper fan boost for a nose installation is that which after deducting both the no-fan entrance loss $(P_1 - P_s)$ (Fig 1) and the proposed fan boost $\Delta P'$ from the total ΔP required without a fan, leaves a value of $\Delta P''$ to be provided by the cowling such that $\Delta P''/q$ lies between 5 and 6 (see Fig 2). This asks relatively little of a fan in order to accomplish much.

Suppose, still as a simplified example, that q in climb is 7 in. of water and the entrance loss (exclusive of any adverse propeller shank effects) is 15 q. Assume further that the no fan cowl ΔP required is 9 in. Then the fan boost $\Delta P'$ which will bring us to the borderline of diminishing returns in performance gain is only—

$$\Delta P' = 9 - (15 \times 7) - (6 \times 7)$$
$$= 9 - 1 - 4$$
$$= 4 \text{ in. fan boost}$$

As stated, the preceding examples have been special cases, in the interest of



Sedgwick LIFTS A 50-TON FEATHER

—AND STOPS ON A DIME

Sedgwick Roto Drive elevators lift 100,000 pounds with ease. Behind the tremendous load-lifting capacity is an exclusive Sedgwick principle of operation called 'Roto Drive".

Roto Drive is simple. It is based on the controlled movement of endless chain. Because it is so simple it is adaptable. Sedgwick Roto Drive airplane elevators on carriers ferry fighting planes from hangar deck to flight deck—*fast*. Roto Drive ammunition hoists, food lifts, passenger and freight elevators are serving with our Navy, Army, Coast Guard and Merchant Marine.

Roto Drive has many advantages. Chief among these are:

1. Roto Drive's load lifting capacity is unlimited. It can lift massive loads weighing *well over* 100,000 pounds or loads weighing as little as one pound or less with equal efficiency.
2. Roto Drive can be used equally well on land or on sea.
3. Roto Drive's unique operation prevents the car of load lifting platform from travelling beyond a predetermined point. Sedgwick Roto Drive Airplane Elevators, for example, *always level flush* with the flight deck—never stopping above or below the lips of the water ways.
4. Roto Drive, because of the "no overtravel" feature, can be installed in tight places where there is a minimum of overhead and/or pit clearance.
5. Roto Drive operates with a smaller output of power, effectively reducing costs by having gravity and the load assist in starting.

If your problems—present or postwar—include questions of how to lift loads safely, surely, economically Sedgwick Roto Drive may be the answer.


"MEN WHO KNOW ARE SOLD ON SEDGWICK"

SEDGWICK MACHINE WORKS

146 WEST 15TH STREET NEW YORK 11, N. Y.

Since 1893 designers and manufacturers of specialized lifting equipment

ELEVATORS • DUMB WAITERS • HOISTS • AUTO-WAITERS • MATERIALS HANDLING EQUIPMENT



FAST FREIGHT *and mail will cross the oceans via the Martin 170-22. Ideal for transportation of perishable foods, using high-altitude cold for refrigeration.*

The MARTIN MARS affects your POSTWAR PLANS!


IN the Mars flying boat, airline operators will have a successful type thoroughly tested in overocean transportation. She's the most efficient airplane yet built, per pound of material used, per horsepower, per gallon of fuel, and has the lowest ton-mile cost.

Start revising your postwar plans! For these are no visionary, far-distant ships. They are commercial versions of the Martin Mars. The original Mars is now in regular trans-Pacific service with the Navy, while 20 larger 82-ton Mars Navy transports are under construction. The plane of tomorrow is flying today!


At war's end, Martin production lines will be tooled and manned for fast delivery. If the industry is permitted to set aside funds for such postwar construction and employment, American aviation will be first in peace as it is in war.

THE GLENN L. MARTIN COMPANY, BALTIMORE 3, MD.
THE GLENN L. MARTIN NEBRASKA COMPANY—OMAHA

Martin AIRCRAFT
Builders of Dependable Aircraft Since 1909



LUXURY LINER *of the air, the Martin 170-21 is designed to provide complete living facilities for 54 passengers during flights of 24 hours or less.*



COMBINATION *cargo and passenger carrier, the Martin 170-23 provides accommodations for 34 passengers plus an 18,000 lb cargo. Range, 3,500 miles.*

simplicity. Fan and propeller efficiencies have been assumed equal. The lower the fan efficiency, the less of an even swap takes place in the sacrifice of propeller thp. for cooling thrust power contributed by the fan. Also, the smaller the portion of the required pressure drop the fan is asked to provide the greater the contribution the cowl must make in relation to dynamic head q, resulting in lower cowl pump efficiency, per Fig. 2. However given the assumed values of fan and propeller efficiency, fan boost, drop across the engine and adjacent system passages and volume of airflow together with an approximation of cowl pump efficiency vs $\Delta P/q$ per Fig. 2, a logical approximation of performance gain from a fan is mathematically straightforward and easy.

Concluding Part II of Mr. Campbell's article will be presented in August AVIATION.

Going to Pressurize?

(*Continued from page* 156)

amount of body moisture is appreciably increased, hence a greater quantity of air is needed for body comfort. This requirement is frequently handled by recirculation of air. In the normal household, recirculation is accomplished by the use of electric fans. Aboard present-day air liners, the individual ventilator furnished at each passenger's seat does the job. It is probable that if a suitable means of recirculating air is provided, the maximum airflow requirement per passenger will not exceed 10 cu. ft. of air per minute with cabins maintained at temperatures not exceeding 85 deg. F.

These considerations automatically provide the basic air input requirements to any given airplane design. Hence, it is practical to consider that the air source (say, cabin blower) should provide approximately 2/3 lb. of air per passenger per minute. This air mass requirement is based on an air density equivalent to that at 5,000 ft. under standard air conditions, or that which would prevail at 2,000 ft. altitude with an air temperature of 80 deg. F. in the cabin.

In an airplane which normally can carry 40 passengers and a crew of 4 or 5, it would be desirable to furnish a maximum airflow of approximately 30 lb. per minute to the entire cabin. This is based on a maximum airflow of 10 cu. ft. per minute at a density of 0.066 lb. per cu. ft. This, remember, is the *maximum* air flow into the cabin.

In the event that two blowers are to be furnished for the airplane, each would need to furnish only 15 lb. of air per minute and still be capable of furnishing the minimum requirement in the event of failure of one driving engine or supercharger. This is also premised on the probable need of maintaining the cabin at a temperature of not over 80 deg. F.

But what happens when cabin air temperature reaches 90 or 100 deg. F., or possibly higher, as occurs in tropical areas? This condition must be handled in one of two ways: Either provisions will have to be made for at least trebling the maximum airflow mentioned above, to provide greater quantities of ventilating air, or provisions must be made to not exceed the 80 deg. F. mentioned previously.

The combination of high temperature and ventilating flows of 10 cu. ft. per passenger will give the impression of stuffiness in the cabin. Some sort of fan or other recirculating means becomes necessary. It has not been normally realized that increasing air temperature from 70 to 120 deg. decreases the ventilating air mass by 10 percent. This results in an actual, as well as apparent, reduction of available ventilating air mass.

Assume, for example, the cabin level is maintained at sea level pressure to an airplane altitude of 14,000 ft. In this instance, the cabin has been designed to withstand a maximum working pressure of 6 lb./sq. in. Fig. 5 shows the relationship of airplane altitude and cabin altitude, the cabin figuratively bumping along at sea level while the airplane climbs.

The curve indicates that from sea level to 500 ft. the cabin level is "coming up to sea level." While seemingly enigmatic, this is true of *every* airplane of the present day which uses a ramming air intake.

Above 14,000 ft., the cabin rises the proper amount to maintain the cabin-to-atmosphere differential pressure within

ACW ALLOY BARS



SHIPPED
AT A MOMENT'S NOTICE
FROM RYERSON STOCK

• Aircraft quality alloy steel bars—8630, X4130 and 4140—in a wide range of sizes, are in stock for immediate shipment from Ryerson plants at Chicago, St. Louis, Cincinnati and Jersey City. These steels conform to specifications AN-S-14a, AN-QQ-S-684a, and AN-QQ-S-752 respectively and are readily available to aircraft manufacturers and their subcontractors under the ACW program. A booklet of stocks on hand, "Aircraft Alloy Steels," including condensed specifications for AMS and AN-S steels, will be sent on request.

Other steels at eleven Ryerson plants comprise over 10,000 different kinds, shapes and sizes. Call Ryerson first for quick action on steel.

Joseph T. Ryerson & Son, Inc., Plants at: Chicago, Milwaukee, St. Louis, Detroit, Cleveland, Cincinnati, Buffalo, Boston, Pittsburgh, Philadelphia, Jersey City

RYERSON STEEL-SERVICE



★ An entirely new design for tandem controls. New mold provides unit castings that nest and lock together. Metal end-pieces and tie-rods insure rigid assembly—even up to 20 units in tandem. Single shaft passes through and locks with rotor of each control.

Each section accurately wound to precise circuit requirements—resistance, taper, taps, hop-off. Interlocking resistance ratios provide any desired voltage or current at given degree of rotation. These Multiple Controls are now in regular production and meeting the most rigid multi-control requirements.

★ Send us that problem . . .

CLAROSTAT Controls and Resistors

CLAROSTAT MFG. CO., Inc. • 285-7 N. Gee St., Brooklyn, N.Y.

the safe strength of the cabin structure.

While pressure is thus maintained, the supercharger, blower, or chosen means for furnishing air to the cabin, should be capable of maintaining an essentially constant inflow of air. It is probable that the cabin air inflow should be constant to 14 000 ft. above which it will decrease with air density, somewhat as shown in Fig. 6. While it is possible to maintain the airflow absolutely constant with some complex form of controlled mechanism for the supercharger, it is not considered necessary to maintain inlet airflow absolutely constant. As Fig. 6 shows, the airflow decreases from 30 lb./min. at 14 000 ft. to approximately 25 lb./min. at 25,000 ft.

While it is not expected that a practical airplane will look anything like the craft in Fig. 3 (which appears to be "blowing a lot of fuses" simultaneously) our airplane *will* be subject to leakage which gradually increases as the airplane ascends. Fig. 7 shows an example wherein the slight differential of pressure needed for ventilating purposes at sea level causes a rather surprising amount of leakage. This is based on the assumption that all leaks maintain constant area. Such an assumption may not be correct, since deflections may cause variations in the leakage openings in the airplane structure.

The break in the curve at 14 000 ft. is consistent with previous considerations wherein the cabin air density decreases gradually above this altitude.

Fig. 6 and 7 are combined in Fig. 8 to show the variation in air outflow which must be controlled by the cabin pressure regulator. Obviously a large quantity of air must be passed through the outflow valve under sea level conditions when only a small pressure differential is allowable to cause this amount of air passage. At altitude where a large pressure difference is available to accomplish the outflow of air only a small amount of air must be expelled through the valve. Thus, the outflow valve must have a sufficiently large and properly shaped opening to pass a large amount of air at sea level, but it must also be sufficiently sensitive and stable to control the outflow when the net valve opening is very small at altitude.

Experience on the *Stratoliners* has shown that while the leakage of air from the cabin was between 6 and 7 lb. per minute when the airplane was brand new, this leakage tended to increase with time, due to the effects of engine vibration, landings, and other service conditions. It was also found that the handling of baggage and freight through the cargo hatches damaged door and hatch seals, which also increased leakage. Hence it is to be expected that the over-all leakage may double or treble the initial leakage of any airplane.

At some time in the life of the airplane, the cabin air supply and leakage may become like that shown in Fig. 9. In this case, the regulator valve would reach the fully closed position at approximately 9,000 ft. If the airplane reaches this condition it is desirable that a major overhaul be scheduled so that joints may be tightened to permit the regulator to maintain the desired control of airplane cabin pressure.

It is possible for the airplane to continue flying for a considerable time, however, because the closure of the cabin outflow valve will indicate that insufficient air is available to maintain the originally specified cabin altitude at the higher airplane altitudes. The airplane cabin will "climb" with the accompanying reduction in cabin air density. Leakage will decrease in relation to cabin air density, to the point where leakage balances inflow. It is not evident that this could ever become a dangerous condition, but it might cause some apprehension on the part of the crew.

While considerable analytic and experimental studies have been made on specific combinations of cabin air supply and cabin leakage, it is not possible to cite the precise results of these studies at this time. It is hoped that within the next year or so it may become possible to present this information for it will prove to be of considerable interest.

In conclusion it is suggested that engineers keep Fig. 3 in mind when preparing specifications covering the pressurization and the pressure-control of commercial air transports of the future. For this conception should aid in preventing over-optimism, thus smoothing the path to most practical results.

Hole Piercing

(*Continued from page 163*)

each conveyor line is able to handle scores or even hundreds of different assemblies, job organization is well worked out.

A temporary storage space near the start of each line contains parts and tools for each assembly which are placed in bundles, tote boxes, or other containers. Groups ready for work are then transferred to "ready" shelves, from which they are taken and distributed along the conveyor as needed. The accumulation is supervised by a planner who acts as foreman of the line and who has two assistants or leadmen. These workers do most of the detail supervision along the line, help operators who encounter trouble, and see that new set-ups are properly made.

Before any assembly is put into work however, tools and a set of parts are proved at a bench near the head of the line. There, skilled workers build an assembly, using the jigs, fixtures, and other special equipment provided. If it does not pass inspection the trouble is immediately found and remedied. This proving assures that when parts and tools are delivered to the line, the assembly will progress as intended.

The foreman-planner selects only those jobs adapted to equipment on his line, and he keeps his line producing even though some items of equipment may be idle temporarily. Company and government inspection are both made at the end of the line. One worker near the end is usually assigned to catch and remedy "squawks."

Part II concluding this series will consider the application of automatic riveting to large assemblies.

Tooling Deck Technique

(*Continued from page 154*)

positioning. In fact, the planes in the tooling dock are set to a tolerance of .002 in. and make it comparable to the jig bore and boring mill in the establishment of machine shop tolerances.

Extreme accuracy of the tooling dock at San Diego can be attributed to the fact that we were able to lay a firm foundation. Despite natural earth tremors and nearby drop hammer operations, the position of the members of this dock have varied less than .001 in. in a period of three months.

The dock method is of particular value in connection with a mass production paneling program, because it cuts time for setting up fixtures by more than 75 percent. This does not mean, however, that the value of the apparatus will decline when the war is over and orders for aircraft becomes smaller.

In point of fact, the tooling dock promises to do away with the old practice of sacrificing production efficiency by cutting tooling costs when producing aircraft in small lots. By utilizing the tooling dock, the manufacturer can avail himself of the advantages of line production by planning his assembly tooling upon the basis of ideal manufacturing methods.

The tooling dock has a pronounced effect upon tool design. It tends to simplify this work because the blueprints and reference dimensions are no longer the medium that controls precision and coordination.

Up to the present time, the principles and methods of this system have been applied only to the assembly of aircraft jigs and master gages. However, the underlying principles will soon be applied in other industries where precise assembly tools and gages are required.


Cellulose Acetate Plastic

(*Continued from page 165*)

centration factor for the notch was 2.1, obtained from the ratio of the endurance limits of the notched and notch-free pieces. The notched specimen was compared with the rectangular machined one because the material in the notched examples, being at the root of the notch, is equivalent to that tested in the machined specimen.


In order to determine the effect of the molded surface on the endurance limit of cellulose acetate plastic about 0.025 in. was removed from both surfaces of rectangular specimens (Fig. 1f). The $s - N$ diagram obtained for those specimens is shown in curve 5, Fig. 12. It was found that the endurance limit adjusted to an age of 11,000 hr. was about 2 percent higher for the machined surface than for the molded surface (see column 5, Table I). Apparently the molded surface has very little effect on the fatigue strength.

Temperature measurements with a thermocouple showed that the temperature of the specimen during a fatigue test was a few degrees above room temperature. It was also shown that a blast of air from a low-pressure high-velocity fan would reduce specimen temperature nearly



Cannon Quality Control makes some exacting demands—for instance die castings so intricate and precise that ordinary sources can't supply them profitably and in quantity.

So we built, equipped and staffed our own die casting department. It's a big one—rates among the five largest aluminum alloy die cast plants in the country. It has a huge capacity—much more than even we need. But its size assures our customers prompt delivery of almost any quantity of Cannon Connectors, on short notice without the slightest sacrifice of the well-known Cannon qualities—easier assembly, better fit, greater strength with less weight, longer trouble-free life.





Cannon slide films with sound covering assembly and soldering techniques are available on request. Address Department A-110, Cannon Electric Development Company, 3209 Humboldt Street, Los Angeles 31, California.

CANNON ELECTRIC

Cannon Electric Development Co. Los Angeles 31, California

Canadian Factory and Engineering Office: Cannon Electric Co., Ltd., Toronto

REPRESENTATIVES IN PRINCIPAL CITIES — CONSULT YOUR LOCAL TELEPHONE BOOK

to that of the room. An endurance limit was obtained under an air blast of about 2,500 ft./min. when the temperature measured by a thermocouple taped to the specimen was less than 1 deg. above room temperature. The $\sigma - N$ diagram for for these tests is shown in curve 3, Fig. 12, for a square specimen (Fig. 1g). The endurance limit, adjusted to age at 11,000 hr., was about 14 percent higher than the corresponding figure in still air (see column 5, Table I).

Five different endurance limits were obtained at various speeds of testing ranging from a frequency of 42 cycles to a frequency of 2,900 cycles per min. The $\sigma - N$ diagram for these tests are shown in Fig. 13. The endurance limit of curve 8 is not quite as well defined.

Fig. 14 shows the effect of frequency on endurance limit. In this curve endurance limit is plotted against test frequency. The circles represent the actual value of the endurance limit as obtained. The square plotted points represent data corrected for aging on linear variation of endurance limit with time. For this series the age effect was determined from a different set of tests than in the former. Curve 11, Fig. 13, having an age of 8,000 hr., corresponds with curve 4, Fig. 12, at 3,600 hr.

The effect of age from this set of tests does not agree exactly with that in the previous ones. This may be due in part to the fact that laboratory humidity control was interrupted for a short time during the first tests or it may indicate that the effect of aging is not a linear function of time. The square plotted points shown in Fig. 14 represent data adjusted to an age of 11,000 hr. It was found that the endurance limit markedly decreased with increased testing frequency up to about 750 cycles per min. From that point to about 2,900 cycles the endurance limit remained substantially constant.

Thus for low frequency the magnitude has an appreciable effect on endurance, but above 750 cycles the endurance limit is unaffected by change in frequency. The effect may in part be due to relaxation of stress during each cycle as a result of creep at the low frequencies of testing.

Forming Sheet Aluminum

(*Continued from page 167*)

finish and avoid scratches when blanking bright-finished sheet, the stripper and the faces of the punch and die should be covered entirely with cloth except at the cutting edges. Shellac is commonly used to hold the cloth on the tool.

Combining two or more dies to take advantage of odd shapes for less waste is called "gang blanking." In "stagger" blanking, the sheet is manipulated back and forth to obtain the maximum number of good pieces. Blanking down one side of a strip and up the other is called "progressive" blanking.

The airplane industry has developed a way of blanking aluminum called the Guerin, or rubber pad, method. The metal is placed over small dies which have been carefully laid out so as to use the metal most economically. The bottom of the ram, covered with a heavy rubber pad, comes down, then as the rubber (confined to prevent lateral flow) adjusts itself to the shape of the various dies it blanks out the aluminum pieces. The flexible operation is especially suited to the production of parts in relatively small quantities and saves the construction of costly die-sets.

Blanks can also be cut by several other methods. Guillotine shears, may be used for straight cuts. If provided with a mechanical hold-down, a clearance of one-eighth of the thickness of the sheet is required. A low rake or shearing angle on the upper shear knife will aid in reducing twist in thin stock. When the quantity is too small to justify a special blanking die, circular blanks may be cut by circle shears. The umishear may be used to cut either straight or curved lines, and when sheets are thicker the nibbler can be used to cut to any pattern.

A band saw or circular saw will prove satisfactory if the blade is kept well lubricated by frequent applications of the grease stick. Light metals can be cut very readily with either type saw, provided it has the right size teeth. High blade speeds (5,000 fpm. for band saws and 10,000 fpm. for circular saws) are desirable for best results. The following figures will give an idea of the performance that can be expected in sawing pure aluminum (2S) on a band saw running at 5,600 fpm.:

Thickness of plate in.	0.47	0.79	1.02	1.18
Feed fpm.	21.8	17.7	13.0	12.4

The band saws generally used are of 0.032 to 0.79 in. pitch and of 0.24 to 0.40-in. depth. The teeth should not have sharp internal corners because the sawings would stick at these places. Tooth spacing in band saws usually is about 4 to 5 teeth per inch in the "hardened throughout" type, and either 6 or 8 teeth per inch in the "flexible back" type.


Circular saws with chip breaker teeth (better than the broad tooth type) have teeth so profiled that one cuts deep and the next one cuts wide. Another preferred type of saw blade has alternate side rake teeth (about 15 deg.) arranged so that one cuts on one side and the next one on the opposite side of the saw cut. Tungsten carbide tipped saws are recommended for cutting aluminum alloys which contain substantial amounts of silicon.

The use of the router machine is a more recent method for cutting stacks of sheet metal blanks. The cutter is a small diameter, high speed, vertical milling tool and is guided by a template clamped to the surface of the sheet. Resulting edges are smoother than those of sawed blanks, while the versatility of these machines and the speed with which templates can be provided have made routing the standard method in many aircraft plants for cutting odd-shaped blanks.

Piercing (fundamentally the same as blanking) is the term used when the part cut out is scrapped. If the holes are quite

(*Turn to page 267*)





Miracle TODAY-



Routine TOMORROW!

LIGHT metals are forging's problem children . . . especially for products whose end use is as critical as aircraft engine pistons made of aluminum. Heat treats must be precise to the *n*th degree, in *number* and *control*.

Tube Turns solved the perplexing dual problem of *volume production* and *absolute quality control* by utilizing their huge upset forge equipment and modern heat treating furnaces — then developing a streamlined production technique which today serves as a pattern for the industry. Proof that light-metal forgings can be produced on a mammoth scale, as evidenced by Tube Turns' success, may well revolutionize postwar thinking in many industries.

TUBE TURNS (Inc.) • • • Louisville 1, Kentucky

"Close-Quarter Action." With thrilling realism, artist Sessions presents his conception of an engagement between an American destroyer and a Japanese light cruiser. Destroyer is shown in the left foreground.



TUBE TURNS *Forgings for Industry*

small and close together the process is called perforating. Either regular blanking presses or horn presses may be used for piercing and perforating. The tools consist of the usual punch and die. The shape of the hole conforms to the die in blanking, but in piercing it conforms to the punch. The die is ground flat so as not to distort the work, and the punch may be contoured with high and low points.

When a gang punch is used, it is much easier on the press to "step" the individual punches slightly so that they do not all enter the metal at the same time. This practice also gives more accurate alignment of holes. If the punches are small and close together, "stepping" will also prevent "crowding" the metal and pushing some of the delicate punches out of line.

The gage of the metal determines how much metal should be ground off the punches. Each step should be a little less than the thickness of the metal, since too much difference produces a jerky operation. The longer punches should usually be on the outside, surrounding smaller ones. However big punches should always be longer than small ones regardless of position. For thus there is prevention of deflection and chipping which results from crowding.

For piercing, the clearance between the punch and die should not be more than 5 percent of the thickness of the aluminum. If the clearance is incorrect the slugs will be lifted with the punch on the return stroke. Also only the punches should be lubricated; light oil applied with a brush is best for this purpose.

Vacuum Pump Efficiency

(*Continued from page 174*)

Capacity Test. Open oil feed line and start motor, allowing pump to run in at speeds given in specifications, until it reaches terminal temperature (given in Table III). Capacity may then be checked at required speeds and setting.


Temperature Rise and Oil Flow. Run pump for 10 min. at speeds and settings specified, recording temperature rise and oil flow (which should be substantially the same as in the table).

Seal Leakage. Immediately following the above, check pump for seal leakage at increased inlet suction and outlet pressure settings indicated in specifications for at least 3 min.

Should pump fail to provide specified capacity, disassembled and recheck clearances from tables. Substitute new blades if necessary, to reduce clearances in rotor slots. End clearance for rotor and blades can be reduced by using fewer cover gaskets. Do not remove too many gaskets for step on rotor may bottom on end of sleeve, causing gasket leakage and warping of cover.

If the pump absorbs too much power, recheck assembly to eliminate tight spots; then check lubrication.

In event of excessive air temperature rise, check oil consumption to make sure that pump is properly lubricated. If oil



Above is a photograph of a specially designed Annealing and Heat Treating Basket for use of the aviation industry. Adjustable shelves and sides

It Takes Years of Experience To Produce a Product Like This

For 19 years, The Pressed Steel Company has met the requirements of fast, efficient mass production for American industry. With such experience, advance demands have been anticipated and well calculated, until today Pressed Steel can create, recommend and build the aviation equipment of tomorrow.



Lightweight Cover built of special alloy. Reduced weight means efficiency in handling, reduced annealing time and longer life. Specially built.

THE PRESSED STEEL COMPANY
of WILKES-BARRE, PENNSYLVANIA

BRANCH OFFICES: 312 Curtis Bldg., Detroit; 607 Nicholas Bldg., Toledo, 1915 Engineers Bldg., Chicago; 51 E. 42nd St., New York; 415 Petroleum Bldg., Houston, Texas; A & M Accessories Ltd., 13 Melinda St., Toronto, Canada

PRESSED STEEL COMPANY PRODUCTS. Carburizing and Annealing Boxes, Thermocouple Protection Tubes, Seamless Steel Cylinder Caps, Seamless Steel Neck Rings, Welded Alloy Tubing for High Temperature and Corrosive Application, Basement Tubes, Inner Covers and Base Sheathes for Steel Mills

BRANIFF AIRWAYS *says:*

"BG PLUGS HAVE BEEN STANDARD EQUIPMENT ON BRANIFF PLANES FOR MANY YEARS."



DOUGLAS PLANE • WRIGHT ENGINES
BG SPARK PLUGS



Kay C. Shrader, Vice President — Operations
Charles Johnson, Sup't of Maintenance

BRANIFF AIRWAYS
GREAT LAKES TO THE GULF

NATIONAL SAFETY COUNCIL
INCORPORATED
Founded 1912
A Non-Profit Organization Devoted to Securing Increased Safety to Human Life

AVIATION SAFETY AWARD
TO
BRANIFF AIRWAYS, INC.
In recognition of its contribution to Safe Air Transportation having operated as of December 31 1943
232,283,741 Passenger Miles
without a passenger or crew fatality

Ned H. Dunbow
John Hellwig

ARMY E NAVY

BG

THE BG CORPORATION
136 WEST 52nd STREET, NEW YORK 19, N. Y.

Contractors to the United States Army, Navy and Coast Guard and Aircraft Engine Builders

consumption is too low, probe oil passages with wire to make sure they are not choked or restricted. If oil consumption is not satisfactory, disassemble and check clearances. If it is excessive, check clearance between the metering pin and collar and replace either or both parts. Also make sure the metering pin fits tightly in cover.

Trouble Shooting

If, when installed, pump fails to provide sufficient suction, look for (a) Leaks in air lines or fittings, (b) kinks or sharp bends in lines or presence of right angle fittings, (c) suction and discharge lines at wrong ports. Check direction of rotation and see that connections are correct.

If pump fails to run smoothly or becomes overheated, difficulty may be (a) Lack of oil (see that oil passages are not clogged; if lubricated through mounting pad, probe oil passages with wire and make sure gasket does not block oil ducts; if external oil line is used see that it has no sharp kinks or restrictions), (b) Misalignment (coupling and shaft must be properly engaged and mounting flange must fit snugly against engine pad); and (c) Overload (restrictions in either discharge or intake line may make load excessive, no vacuum pump is properly installed if it shows over 7-in mercury suction close to pump port at normal cruising speed; in no case should suction load measured near pump, exceed 10 in. mercury)

Every installation should be checked carefully to determine exact conditions under which pump is to operate, and where suction loads in excess of 10-in mercury are found a relief valve should be installed close to intake port set for a maximum of 10 in. suction. If it is not possible to obtain desired suction at instruments without exceeding 10 in at pump, lines from pump to instruments should be increased in size and every restriction eliminated.

Overloading causes overheating, excessive oil consumption, loss of capacity, and excessive replacements of parts

Rebuilding the Clippers

(Continued from page 177)

scheduled for the job. They are, first: Airplane assembly check, made with the craft mounted on its beaching gear before removal of any component parts, such as hydrostabilizers, tail surfaces, etc.; second, hull check with hull mounted on support jigs before disassembly of the hull structure; third, wing check with wings mounted on jigs before disassembly of outer wing structure; and, fourth, airplane assembly re-check made on beaching gear after all replacement work is completed and component parts re-installed.

Checks are also made for both hull and wings after replacement of each member and the engineering schedule calls for additional checks to be made at any time desired by the engineering department.

Long before the first of the eight craft scheduled for the replacement program

Where PRECISION is All-important...




'Too much depends on the reading-clarity of a blueprint to let a better tracing-quality pencil pass without investigation! **HI-DENSITY** line from a modern *Hi-Density Microtomic Van Dyke* pencil will hold crisp, sharp clarity in your finest details. Even on a high speed blueprint machine, or other quantity reproduction processes. 18 degrees from 9H to 7B, and 6 degrees (4B–2B–HB–2H–4H–6H) with rectangular "chisel point" leads.

HI-DENSITY

MICROTOMIC VAN DYKE

DRAWING PENCILS



IF YOU WISH THIS 20" SLIDE RULE created by Eberhard Faber as a war-time service to engineers and draftsmen sign below and mail with **25¢**

EBERHARD FABER PENCIL CO.,
Dept. A T
37 Greenpoint Ave., Brooklyn 22, N. Y.

For enclosed 25¢ please send VAN DYKE 20" SLIDE RULE—war-time card printed edition.

Name_____
Street & No. _____
City & State_____

had been taken from service, the entire operating plan had been organized in minute detail by engineering and shop personal. The section of the report dealing with "Preparation of Airplane," for example, listed and described 34 separate steps in this preliminary procedure

"Removal of Aircraft Equipment," broken into three divisions, embraced a listing and description of 36 steps Procedures for disassembling and replacing wing members embraced introductory and general note instructions together with details on 129 steps for the jobs Hull work procedure includes a general section and 35 steps Even re installation of component parts and equipment are established in detail, this part of the job being broken into 19 separate steps

This "forehand" work was all done while the *Chippers* remained in service (as one means of getting them back in the air at the earliest possible moment). Despite the fact that a very tight schedule has been set, A. P. Elebash, division engineer, F. J. Zerilli, project engineer, Walter Smith, assistant shop superintendent, and F. Licari, assistant chief of metal shop, firmly believe they will be able to reduce the time on the second plane by 25 to 30 percent with succeeding craft being "given the works" and put back in service in just about half the time required for the first.



Fronklin Overhaul

(*Continued from page* 179)

piston, otherwise rings may be damaged or broken Cylinder hold-down stud nuts should be evenly tightened.

Adjustment for valve clearance should be in accordance with instructions on page 165, AVIATION for June, 1944

Check gaps on sparkplugs and adjust to .020 in. If plugs cannot be screwed into place with the fingers, there are burrs or bruises on the threads. These defects should be removed. On no account should the plug be forced in, for cylinders may be ruined by faulty or cocked threads

Exhaust stack nuts should not be overtightened but merely drawn up snugly

If new piston rings are installed ring grooves should be thoroughly cleaned before rings are placed on piston, the top of which should be cleaned with Crocus cloth and kerosene

It is not necessary to remove piston from rod to perform the above operation, but if it is desired to do so, all that is required is to push out the pistou pin Crocus cloth will remove scratches on piston unless they are very deep, in which case a new piston should be used, fitted with a new pin to assure correct clearance between pin and rod,

When new rings are installed, the hard glaze on cylinder walls should be removed with a *spring-loaded* cylinder hone, otherwise several hundred hours may be required to seat the new rings during which period the blowby will probably ruin both the rings and piston After reaming, it is advisable to steam-clean the cylinder bore to remove abrasive

Three different types of Perfect Circle piston rings are used on Franklin engines —3/32 in Type "200" in top groove, 3/32 in Type "70" in middle and 3/16 in Type "85" in groove directly above piston pin No ring is to be used in groove at bottom of piston.

Top overhauled engines should be run-in on the following schedule From 1 000 rpm. to 1 400 rmp 30 min at each 100 rpm increase, total time 2½ hr ; and from 1 500 rpm. to 1,900 rpm , 20 min , at each 100 rpm increase, total time 1 hr 40 min. This gives a total run-in time of 4 hr 10 min

Aeroprop Replacement

(*Continued from page* 182)

On Models A632S-A1 or -A2, adjust regulator control lever stop plate (Fig 8) as follows (a) Facing propeller loosen stop plate nut and disengage teeth from adapter plate teeth, (b) slide stop clockwise as far as possible, (c) rotate control lever clockwise toward left of airplane to end to travel, (d) slide stop counter-clockwise to contact shoulder of control lever (Fig 9), and count number of teeth visible on upper side of stop, (e) holding stop plate in place, rotate control lever to center position (f) slide stop downward three teeth engage stop plate with teeth of adapter plate lobe and tighten attaching nut (g) move control lever through its full travel checking to see if cable clevis can move full distance, *making sure there is full control travel on high rpm side;* (h) install clevis pin and safety with cotter key, and (i) turn propeller to bring oil filler plug into horizontal position, then half fill regulator with oil (Fig 10), replace plug, and safety with .032 wire.

To lubricate hub (Fig 11) insert bleeder tool between blade retaining nut and shank, taking care not to damage seals Force grease into hub until it appears at bleeder, repeating procedure at each hub fitting and socket Then remove one grease fitting to relieve any pressure built up during the process of greasing During regular refills, bleeder tool is not required, air may be bled by removing grease fittings

Replace spinner, matching serial numbers Tap shell into place with hands only, using a special screwdiver to set the countersunk screws If old model has standard type screws, do not replace with patent head screws.

After installation of a new or overhauled propeller, air must be purged from hydraulic system by setting control in "increase rpm." position and then running engine at about 2,300 rpm Next while keeping manifold pressure constant by use of the throttle, move control back to "decrease rpm." setting Repeat this procedure three times, after which any movement of the propeller controls should bring a corresponding change in engine rpm, indicating that propeller system has been satisfactorily purged of air

Before flight test, governor action should be tested by running engine up to slightly above normal speed for a few seconds (the plane being secured against moving) when the governor should bring the rpm back to normal speed This will indicate that the governor is correctly set to hold the engine rpm at this figure.

After ground run-up, check oil level and repeat greasing procedure (as outlined for installation)

Industry's Sales Saar

(*Continued from page* 197)

ture showing considerable improvement. In 1942 these companies held only $277,-900 000 in cash in their treasuries—$8 000 000 less than their current tax liabilities alone One year later their cash holdings had grown to $441,884 000 or $105 000,000 above their 1943 tax liabilities

A year ago there was some reason to hope that Congress would enact legislation aiding the establishment of postwar reconversion reserves There was much talk about it and many hearings, but nothing has happened and nothing probably will be done about it at this late date. However, the industry is gradually setting up fairly respectable reserves for adjustment, contingencies, inventory losses, etc On Jan 1, these reserves totaled $90 911,000 against $62,175,000 the previous year, and today they are well over $100 000 000.

But they will quickly melt away unless the various companies have their financial



houses in order respecting employee dismissals, excess inventory, and other like matters. These reserves also are small in comparison with the wartime reserves set up by the financially well-heeled automobile, steel, rubber, chemical, and many other war industries.

One striking change in the 1943 balance sheets was the substantial increase in bank debt, wholly apart from government facility contracts. This debt climbed to $192,684,000 against $72,659,000 in 1942. In peacetime such a spurt would surely be called a danger signal for an industry that was singularly free from bank debt before 1940. But in the latter stages of the war it is a decidedly healthy sign. It is the "ounce of prevention" that the industry has taken to ward off any temporary insolvency when cancellation telegrams suddenly come flocking in.

The industry has over $500,000,000 in V and VT credits arranged with the banks and the government. And now that Congress is in the process of legislating a purely-termination type of loan it is expected and hoped that the industry will take advantage of this new credit facility as soon as it becomes available. In fact, the new T loan is designed primarily to supply cash to the aircraft maker and supplier whose quick assets become tied up in terminated contracts.

One of the financial factors that gives greatest concern to aircraft executives is that matter of inventories. Last year the inventory item for the 14 companies surveyed increased to almost an even $430,000,000 against $399,000,000 in 1942. But in view of the huge jump in sales last year the wonder is that the gain was not even larger. The fact is that inventory is being brought under better control every day for most companies.

In the case of Douglas Aircraft, for example, it is understood that company-owned inventories, which stood at $12,800,000 at the beginning of 1944, were under $8,000,000 at a recent date. It is these company-owned inventories not specifically earmarked against a specific governmental contract, that give the greatest promise of causing future trouble.

The necessity of carrying excess inventories because of raw material shortages largely disappeared in 1943. And with all the current emphasis now being placed on surplus disposal, there is reason to feel that major inventory problems are moving nearer solution, to the obvious benefit of every company's forthcoming 1944 balance sheet.

What is the 1944 composite fiscal outlook for the aircraft stockholder? In the first place he is likely to get a breathing spell from the dire warnings and predictions that aircraft executives felt duty-bound to make during the struggle last year to secure Washington recognition of their problems. And a moratorium on pessimism will help no end to create a better atmosphere for aircraft stocks in Wall Street as well as a better psychological effect upon present stockholders.

Dividends, in the final analysis, are the yardstick with which stockholders measure the success of their capital ventures. Such payments by the 14 companies totaled $23,166,000 in 1943, up from $19,759,000 in 1942. Some small further gain in average payments may be registered this year, although every concern will want to continue the process of plowing back the major part of its earnings into the business. Only by this policy has the industry been able to keep its head above water.

More and more will be heard about cutbacks in war orders this year. Requirements of both the Army and Navy are changing so rapidly that it would be foolish to try to look very far ahead on production figures. But it seems clear now that 1944 will be the peak year for wartime aircraft output.

The cutback in the trainer program is water over the dam. The reduction in Navy fighter production is well under way. Next comes a general cutback in Army procurement schedules for shorter-range fighting planes and possibly light and medium bombers. Changes in the Army program, where emphasis is now on offensive rather than defensive aircraft, will mean no substantial reduction in production until early next year.

The aircraft stockholder's interest has been largely centered in the ability of his company to maintain its financial stability during the last three years of ever-expanding production. The improvement shown in the 1943 reports indicate that the industry is moving more rapidly than the layman appreciates in getting its financial house in order.

Six months more of good wartime housekeeping should see the industry safely over its more serious financial hurdles. It is now becoming a question of gaging the industry's earning power in the first few postwar years. In later articles we will take soundings and submit what clues we find for the aircraft stockholder's consideration.

New Auxiliary Engine

(*Continued from page 199*)

two hardened steel guides of 0.003–0.005-in. clearance. These guides are self-aligning, which simplifies assembly procedure and maintains even pressures in operation.

Since, in a double-acting engine, the crosshead takes all angular thrust, the piston "floats" in the cylinder, main contact between the two being through the rings. Design of the seal between piston and crankcase is such that no bending strain is imparted to the piston rod, thus it is only under normal compression and tension, there being no force other than inertia of the rod, wrist pin and connecting rod resisting the shift from one set of guides to the other.

Only two crosshead shifts take place in each cylinder during the full cycle. One at the end of the second power stroke, when the crosshead is practically stationary and the connecting rod changes from driving the crankshaft to being driven, the other between compression and the first power stroke. This latter occurs at the moment the horizontal component of the power stroke set up by the angularity of the connecting rod is sufficient to overcome the inertia of the moving parts involved.

Since this is a negligible force at the top of stroke, hammer has been eliminated. This has been borne out by an exhaustive test run especially to check the theory.

For the test, soft steel guides were installed and the engine run continuously till the guides were well worn. No wear was found at the ends of the stroke where crosshead shifts occur, but increasing wear was evident up to the point where maximum pressure was set up by connecting rod angularity.

Difficulty due to failure of the seal around the piston rod between the lower piston head and crankcase is said to have been eliminated in the Tabor-Hedges engine by a simple method. Set in the lower head is a non-ferrous plug, the bore of which is large enough so that the piston rod does not make contact with it. In this bore there are square recessed ring grooves, in each of which are three contracting cast iron rings. The two outside rings have flat outer faces—for contacting the flat sides of the grooves—and inwardly inclined inner faces. This leaves a wedge-shaped space, the apex of which is toward the piston rod, in which the center ring fits.


After cutting, the outer rings are lapped to a true fit around the piston rod. The internal diameter of the center ring is large enough so that no contact is made with the piston rod; outer diameters of all rings are small enough to permit the assembly to move freely in a radial direction in the groove. Contraction of the center ring against the slanting sides of the outer rings holds them in contact with the sides of the postwar and the piston rod. This results in a labyrinth seal which is reported to have proven so effective that there is no measurable leak through to the second seal. Moreover, this type of seal has proved to be unaffected by heat and has shown no noticeable signs of wear after hundreds of hours of test. Normally two grooves, with sets of rings, are used, but more can be installed if greater compression is desired.

Valves, cams and camshafts, crankshaft, lubrication, ignition and carburetion follow standard practice.

Since high speed increases cost and shortens the life of mechanical units, the Tabor-Hedges engine has been designed for continuous operation at 2,200 rpm., as compared with units which run at speeds up to more than 4,000 rpm. Test runs have shown the engine will deliver 30 hp at 2,200 rpm. for continuous operation, under which conditions it is rated at 5.45 lb per hp. At its maximum horsepower output the engine weighs 5.1 lb per horsepower.

Designed to use 68–72 octane gasoline the engine consumes 54 lb. per hp./hour at maximum rated horsepower. However, test runs have been made with 90–100 octane fuel without increasing the 6-to-1 compression rates, and it was found the engine ran cooler than with the lower rated fuel.

Specifications and performance data of the engine are given by the manufacturer as follows:




WIRY JOE has taken to the air! Long famous as the largest independent manufacturer of automotive replacement wiring, Wiry Joe today is an important source of aviation wire and cable.

Produced under the Dostam method of manufacture, to assure uniformity . . dependability . . high efficiency . . long life, Wiry Joe electrical wire and cable for aircraft conforms fully with rigid Army and Navy specifications.

Inquiries concerning electrical wire and cable for any type of service—aviation, marine, automotive, industrial—will receive prompt answer.



Wiry Joe
AVIATION CABLE
manufactured by
THE CRESCENT COMPANY, INC.
Pawtucket, Rhode Island



Recently the TWO MILLIONTH
Briggs & Stratton engine moved off our production lines. We are now well started on the THIRD MILLION.


Air-Cooled Power

CYCLE BRIGGS & STRATTON GASOLINE ENGINE

We of Briggs & Stratton are proud of the endorsement of manufacturers, dealers and owners — and proud to be recognized as leaders in design, engineering and research, as well as precision production — the results of *twenty-five years* of continuous production of air-cooled gasoline engines.
BRIGGS & STRATTON CORP., MILWAUKEE 1, WISCONSIN, U. S. A.

ANOTHER EXAMPLE OF YOUNG ENGINEERING SERVICE

WARMING-UP THUNDERBOLTS ★★★ FASTER ★★★



YOUNG engineers may now announce the development of a new Aircraft Oil Temperature Regulator which cuts the warm-up time of Republic's famous Thunderbolt fighter planes. Tests demonstrate that in addition to permitting a quicker take-off, this regulator decongeals more rapidly after power glides . . . provides excellent anti-congealing characteristics for high altitude operations . . . thereby increases the over-all efficiency and usefulness of the plane. Its installed weight (filled) is two percent less than the previous model. Young research and development is abreast of the ever changing modern aviation picture. Let Young Heat Transfer Engineers help you keep pace with progress.

● 12 years experience building Aircraft Oil Temperature Regulators enabled Young engineers to achieve the results obtained with this unit.



Young also makes 'STREAMAIRE" Air Conditioning Units which incorporate all the recognized features in design and engineering plus regular Young Quality. Available in 8 floor models (similar to above) — and in 8 horizontal models for ceiling suspension. Capacities range from 400 to 16,625 cfm. Write for Catalog No. 7541.

YOUNG

BUY BONDS • PRODUCE MORE • SALVAGE SCRAP • WIN THE WAR

HEAT TRANSFER ENGINEERS

Manufacturers of Oil Coolers • Gas Gasoline Diesel Engine Cooling Radiators • Intercoolers • Heat Exchangers • Engine Jackets Water Coolers • Unit Heaters • Convectors • Condensers • Evaporators • Air Conditioning Units • Heating Coils • Cooling Coils • and a line of Aircraft Heat Transfer Equipment

YOUNG RADIATOR COMPANY, Dept. 294-G, Racine, Wis., U.S.A.

Distributors: Pacific Airmotive, Burbank, Calif. Aircraft Steel & Supply Co., Wichita, Kans.

No. cylinders	2
No. cycles	4
Bore & stroke	3⅜ x 3/58 in.
Compression ratio	6 to 1 (for 68–72 octane fuel)
Maximum hp	32 @ 2,200 rpm
Continuous operation horsepower	30 @ 2,200 rpm
Wt. (without SD proof box or elec. equip.)	163 lb.
Lb./hp (maximum hp)	5.1
Lb./hp (continuous operation)	5.45
Ignition	mag
Height	26 in.
Width	21 in.
Length	26 in.

Three International Policies

(Continued from page 191)

for the use of the hundreds of air bases built under lend-lease and defense programs all over the world—not necessarily assuming sovereignty over the airports, but retaining landing and commercial rights.

In addition, the 17 airlines recognize the right of foreign carriers for reciprocal rights in U. S. territory, with certain commercial opportunities and the right of innocent passage.

The lines are fully aware of the fact that international "horse trading" would require that an equal number of foreign airlines (or at least an equal number of schedules) would be granted authority to operate over all routes. Thus, for example, if seven different American companies each operated one schedule a day from New York to London, then seven British schedules—whether operated by one or more companies—would have to be authorized.

These lines further stated that proper government consideration of the proposals made would create maximum employment for people now engaged in such operations as the Army Air Transport Command and Naval Air Transport Service. In addition, manufacturers could be definitely informed as to the types of aircraft needed, so that preliminary development could take place, with a further opportunity for employing in postwar at least part of the great body of hundreds of thousands of workers now engaged in aircraft production.

The 17 airlines are definitely opposed to a monopoly, whether in the form of a "chosen instrument" or a "U. S.-flag airline," stating that competition has been a traditional policy of this country and is essential to the airlines' continued growth and development. It was pointed out that the majority of developments in commercial air transport in this country had taken place under the competitive system. This position can perhaps be best summarized in the group's following statement:

"The airlines believe and insist that competition is one of the first principles which must be adopted and which should be the base for the establishment and operation of U. S. foreign air routes if the continued progress of civil aviation, its particular technique, the expansion of U. S. foreign commerce, an adequate system of national defense and maximum efficiency in the American aviation industry are to be maintained and developed."

Actually there has been no official stand on the part of Pan American, or its spokesman-president, Juan Trippe. However, during a speech in the last months of 1943, Mr. Trippe pointed out that most countries had concentrated their efforts behind one single company—the so-called "chosen instrument" policy. He told his listeners that the British Government had concentrated all overseas air transport in a single strong company, British Overseas Airways Corp., while formerly there were four British airlines competing with one another and with other foreign airlines as well.

When the other foreign trading nations consolidated their airlines better to meet world competition, the British followed suit and merged their international airlines, pointed out Mr. Trippe, so that now Britain has a single powerful unit, BOAC. Behind this great air transport company, he said, is the full power and prestige of the British Government. The airliners of BOAC, manned by British crews, will fly all the postwar trade routes of the world. In dealing with foreign governments British air transport enjoys the same advantages that British Communications has had since Cables & Wireless was created.

Mr. Trippe declared that the United States can profit by the experience of Britain and other great trading nations. To consolidate the American position he held that Congress should approve the pending measure which would merge into a single company all U. S. communications facilities abroad, so that they can compete on equal terms with foreign nations. He also stressed the necessity of the early establishment of a national air policy, citing three alternatives, one of which our government will have to choose:

First, shall we have 10 or 15 different airlines, each competing with the other as well as with powerful foreign monopolies? Mr. Trippe pointed out that this system had been tried as long as 20 yr. ago in Europe. Second, shall we have three of four airlines each restricted to a separate zone? Britain, France, Germany and Japan tried this scheme for several years, then abandoned it in favor of the single-company system. Or, third, shall we have one strong American international airline, strong enough to compete on even terms with the great foreign flag air transport monopolies—a community company—owned and controlled, not by any one aviation interest, but by all American transportation interests able to contribute under an organization plan approved by the government?

Mr. Trippe also declared that although Pan American World Airways System has pioneered this country's international airlines the government should not consider the position of any one airline or any group of airlines—for the problem is too big for that, the policy must only be determined by what is best for the country as a whole.

While it is rather obvious which policy is advocated by Pan American it will be recalled that PAA has enjoyed strong political influence with the highest government quarters in Washington. Would this tend to create a single, large Pan American World Airways System, with minor roles being played by other transportation interests?

It has been learned from well informed quarters that this is, in fact, Pan American's hope that it will be named *the* international representing all U. S. interests, with other American airlines relegated to the position of feeder service.

Of all airlines in this country, United Air Lines has perhaps done more work in actual figures, surveys, and estimates to show the possible trend of postwar commercial aviation. For two years this company has had a full-time staff busy making complete studies of every phase of the past, present, and future air transportation picture. This survey group has been actively assisted by the research and development group of the company's engineering department.

UAL's calculations would indicate that domestic air traffic would increase by 3,000 percent in the 20 yr. after the end of the war, requiring the use of more than 5,000 planes of a 32-passenger type such as the DC-4 (C-54). On the other hand, it is also indicated (even if the figures are contradicted by such authorities as Grover Loening) that but 43 airplanes of 100-passenger type would be able to transport all Class A transatlantic traffic, with a peak of not more than 1,500 passengers per day in both directions.

United while believing implicitly in the principle of healthy competition where it can be wisely applied, has taken a stand against "free, wide open" competition in international transocean flying. It has proposed that one or more chosen instruments should represent this country under private enterprise, in coping with the competition of government-owned foreign monopolies in the international flying field. It points out that the plans of the large group of airlines would mean in effect that, if the figures of the surveys are correct, 8 to 17 additional operators would have to share an amount of traffic which could be carried with perhaps as few as 43 airplanes, not even taking any foreign competition into account.

The prospects of postwar air transportation, United points out, are exceedingly bright. States this company: "They can best be realized—as the airplane attains its maximum utilization as an instrument of social and economic progress—if we move forward on a sound, business like basis, independent of public subsidy. The airlines of this country have attained world leadership. Their aim should be to maintain the position of the United States flag under private enterprise on the world's airways and to make the best possible use of this splendid instrument for building a better world in years to come."

United's recommendation as sole dissenter among all domestic airlines is as follows: That the domestic and transocean fields be considered separate and distinct with a realization that one entering the field of the other will contribute nothing that will strengthen our position

Small but LUSTY



You get maximum power per ounce of weight in this small fractional H.P. Motor. Designed for speeds from 3,000 to 20,000 R.P.M. and for voltages from 6 to 115. Engineered to your exact performance specifications. Precision-built of quality materials for long life, dependable operation. How many do you need—and when?

Small Motors, Inc.

1312 ELSTON AVE., CHICAGO 22, ILLINOIS

Manufacturers of special small universal, fractional H.P. motors, dynamotors, shaded pole motors, booster motors, generators

Design • Engineering • Production

WELDRAWN

THE SUPERIOR *WELDED-AND-DRAWN* METAL TUBING FROM 5/8" OD DOWN

WELDRAWN is the trademarked Superior Tube Company welded tubing which combines esssntially all of the physical and metallurgical qualities of ssamlsss . . . smooth bright finish, homogenous structure, close toleranceа, high tensile strength—with economy. **WELDRAWN** has a firm preferred place in industry . . . the result of wids usage and highly satisfactory performancs.

Produced in Stainless Steels (various analyses), and "Monel."

WELDRAWN Stainless meets U. S. Government Specification AN-T-43—a typical example of the standard of performance which you may expect when you specify Superior **WELDRAWN** for a wide variety of small tubing applications.

SUPERIOR TUBE CO. NORRISTOWN, PENNA. WELDRAWN (TRADE MARK REG. U.S. PAT. OFF.) (THIN WALL SEAMLESS TUBING)

SUPERIOR

THE BIG NAME IN SMALL TUBING

SUPERIOR TUBE COMPANY, NORRISTOWN, PENNSYLVANIA

ARMY NAVY

FOR EVERY SMALL TUBING APPLICATION FROM 5/8" OD DOWN

SUPERIOR Seamless in various analyses. WELDRAWN Welded and drawn Stainless, "Monel" and "Inconel"

SEAMLESS and Patented LOCKSEAM Cathode Sleeves

as a nation in the field of international trade. Free American enterprise in air transportation can accomplish what is desirable nationally in that field without resort to wasteful subsidy stimulation.

Certain authoritative persons have pointed out that United's policy would form a "United States Airline," in which all airlines would join as an equal partnership. For example, spheres of influence would be allocated, and (we are merely visualizing) they might be arranged something like this: Eastern and National would fly into the Caribbean and South American countries. TWA, United, and AA (the latter via American Export Airlines) would serve Europe, Africa and India. Northwest and Northeast would serve the northern routes—to Iceland and Moscow via great circle routes, and to Alaska together with Western. United, and possibly American and TWA, would serve the Orient and Australia, and other airlines, such as Braniff and Chicago & Southern, would serve the Central American countries and the West Coast of South America.

Thus the United States would have one over-all airline, with one insignia, but it would be operated by the airlines best situated to fly in the areas as assigned, all very much in the manner in which the Air Transport Command and Naval Air Transport Service today detail the domestic airlines to operate "divisions" of a global air transport system.

Here, then, are the three views of the airlines of these United States, through different approaches but all having one common goal—an aerial transport supremacy for the American people. Only the *method* is under dispute, not the *goal*.

D-Doy Air Power


(*Continued from page* 111)

really learned from the students the true meaning of vertical envelopment for the Allied invasion of *Festung Europa*, paced by our paratroopers and airborne infantry, far eclipsed anything the Fuehrer had ever even attempted.

Here was the answer to the question repeatedly asked by thousands of Douglas workers, by airline operators, and by passengers: Why so many C-47's, and where are they going? Here was the answer to countless aircraft piano, and furniture workers: Why so many Waco CG-4 gliders, and where are *they* going? And here was the final word for the "up-and-down" glider proponents—yes, the late Richard duPont, Col. Gable and their untiring successors had been right.

But back of the initial operation itself is a story of tireless planning and coordination, planning for months down to the most minute detail, coordination not only with the ground and sea forces but within the Air Forces themselves. For this was the greatest air operation ever undertaken—11,000 aircraft of all types working on split schedules from widely scattered bases into a concentrated area. It was an epic of teamwork not only by flight and ground crews but by those always-in-the-background boys, the opera-

Here's a "Tip" that SAVES DRILLS And Templets



- Uses standard length twist drills
- Protects costly templets
- Reduces drill breakage
- Assures accurate location of holes
- Large chip clearance ports
- Foolproof

Replaceable tip lowers maintenance cost. Tips are available from stock in many standard sizes

This simple drill guide operates with either bench or portable drill and permits unskilled or skilled help to do faster and more accurate work. Reduction of drill breakage is assured. Adaptor mounting assures rigid alignment and smooth operation. Tip only requires replacement. When ordering specify tip and drill diameters.

There is less lost time when this Drill Guide is used . . .

Keeps drills in "one piece"

It helps turn out better work in less time

How could even inexperienced help fail to do a good job with a tool like this?



Order a quantity for test in your plant.

ZEPHYR

High Quality Precision Tools

ZEPHYR MANUFACTURING COMPANY
Factory and Head Office
201 Hindry Avenue, Inglewood, California
Eastern Branch Office
609 Stephenson Bldg., Detroit 2, Mich.

Write for our catalog

IN AIRCRAFT VISION for VICTORY

with a

LIBERTY AIRCRAFT MIRROR

The pilots of thousands of Allied fighter planes, now in action over our widely scattered battle fronts, are getting a perfect image of things behind them without eye-strain or fatigue, by means of Liberty Aircraft Mirrors.

Liberty Aircraft Mirrors are all first surface mirrors, and as permanent as their glass base. They give the pilot a clean, well defined image without distortion, immediately.

Each fighter plane equipped with a Liberty Mirror has a mirror built to meet the specific requirements of that plane. Thus the pilot changing from one plane to another gets uniformly good vision at all times, in all planes.

All Liberty Mirrors are now built only for War service, but later these battle tested vision devices will be available to all operators, military, transport or private.

LIBERTY MIRROR DIVISION

LIBBEY · OWENS · FORD GLASS COMPANY

BRACKENRIDGE PENNSYLVANIA

ARMY E NAVY

The Army - Navy "E" was awarded Liberty "For high achievement in the production of war material".

tions and the traffic control personnel.

Allied airpower had, as a matter of fact, inaugurated the invasion long before the actual amphibious and airborne operations of D day itself, for the long-range, deep-striking strategic bombing attacks—not mere air raids—of the American 8th, 9th, and 15th Air Forces and their RAF compatriots were as much a part of the job as the naval gunfire covering the landings.

This was clearly evident during the two months preceding D-day, when British-based American and RAF planes topped their schedule of 130 550 tons of bombs by more than 30,000 tons. It became even more clear during the last month before invasion, when the AAF's 8th Air Force operated 27 days out of the 31 for a total of over 30,600 strategic sorties—16 400 plus by the heavy bombers, 14,200 plus by the fighters—and the 9th loosed more than 20,000 tons of bombs in tactical or semi-strategic flights.

Approach to the climax came the night before invasion, when 1,350 heavy American Bombers, together with strong RAF forces, worked their way up the beaches to loose 10,000 tons of bombs. Many of these heavies, because of tireless work of unsung ground crews, flew two, sometimes three sorties that night and next day.

Then, in the first hour of June 6, the 9th Troop Carrier Command came into its own flying two complete divisions—the 82nd and 101st—in C-47's and gliders to hold the wedge open through five hours of darkness, paving the way for the first assault forces which landed around six o'clock.

Only these pre-invasion strategic, tactical, and troop carrying operations made possible the sea and ground forces' reports on the initial operations of "casualties low" and "losses unbelievably light." Perhaps even the future historians will never be able to assay with complete accuracy just how many Allied lives were saved by airpower. But for comparison, there is the tragic lesson of Dieppe where, without adequate air cover, some 3 000 out of a force of 5,000 men did not come back.

This time Allied airpower was such that Gen. Dwight Eisenhower, Supreme Allied Commander, was able to tell a Canadian unit just before embarkation, "If you see any planes, don't worry—they're ours."

Here, too, was the final answer to prove the American doctrine of a balanced air force. Heavy bombers for strategic missions with, of course, fighter protection all the way, medium bombers for tactical operations, again with fighter protection, and, finally, ground cooperation craft to finish paving the way for air transport.

Versatility of Our Aircraft

But perhaps most important of all was the convincing proof—if such were still needed—of the versatility of American aircraft, a versatility built in from their very conception by the men who designed them, and backed up all the way through production workers to the men who fly and maintain them.

These were no planes designed for one type of operation against a known enemy from known bases, they were the planes designed to operate—as they have and will continue to—from the Far North to the South Pacific.

Here were Douglas C-47's, military versions of a ship designed for peacetime airline use, serving as paratroop carriers, airborne troop carriers, and glider tugs. They didn't even stop at that role; for within four days, with their fixing medicos and nurses, they were evacuating casualties, rushing wounded to base hospitals that they might live instead of dying on a beachhead.

Here were Douglas A-20 *Havocs*, performing both their original light bomber tasks, then turning into ground strafers of blistering firepower.

Here were North American B-25 *Mitchells* and Martin B-26 *Marauders*, medium bombers come downstairs to go in under 250-ft. ceilings to bomb and strafe Nazi reinforcements and communications.

Here were some of the Lockheed P-38 *Lightnings*, North American P-51 *Mustangs*, and Republic P-47 *Thunderbolts*—the latter lugging up to two 2 000 lb. bombs—dive bombing and ground strafing. The word "some" is used advisedly, for others of these craft were "way upstairs in their original fighter role, seeking a challenge from a still-reluctant Luftwaffe and helping to provide 'ten tenths' air cover.

Here were some of the Boeing B-17 *Flying Fortresses* and Consolidated Vultee B-24 *Liberators*, called in from strategic operations to help do a tactical job. Again that word 'some' is used advisedly, for Allied air power had been built to such a point that others of these types with their P-38, P-47, and P-51 fighter escort, continued their strategic job of pounding the enemy's sources of supply far back of the beachheads.

And that is a job no less important today than it was before D-day, because the enemy still has resources which must be destroyed before he can be crushed. In fact, the invasion meant not the end of strategic bombing, but called for even more as part of American airpower's prime role—reducing the cost of war in Allied lives.

Boeing *Superfortress*

(*Continued from page* 111)

Through pressurization, efficiency of the combat crew is decidedly enhanced. Pressurization, it is stated, is used in high-altitude approach to, and return from the target where, while in action, the cabin is de-pressurized and demand oxygen employed. The additional comfort of the supercharged cabin in the approach flight makes the men more alert over their objective.

There are two cabin pressure regulators (by AiResearch), and again since one regulator suffices, there is a 100 percent reserve. Seals are built into the joints of the fuselage. Nose compartments are pressurized and also the 30-in. tunnel catwalk over the bomb bays and the connecting waist compartments. Aft of the latter is an unpressurized compartment. The [illegible] however, [illegible] through the [illegible] by two [illegible] conduits to [illegible] tail-gunner's position.

Use of pressurization brought experiments with double-pane plastic glass having an intervening air space. However, considerable distortion in depth perception through these panes resulted in a return to the single-pane. Later an improved laminated-plastic pane was devised.

Difficulties with the original blister fittings, notably a blister blow-out which sent a man out into empty space (he saved himself with his chute) brought development of the metal grille (seen in one of our photos) for reinforcement. But later a rubber blister-rim was devised which absorbed the stresses, and the grille was abandoned.

On a number of the initial planes cabin superchargers were used. Development of the present system of pressurization with GE turbos followed, it being found that the dual superchargers could supply this added service without drain.

Weight of System Negligible

The circular section of the B-29 fuselage is best for holding pressure, as was determined earlier in the circular-section Boeing *Stratoliner*. Since the pressurization system automatically supplies cabin heat and also reduces the amount of oxygen that needs to be carried, the extra weight of the installation is almost negligible. There is flow control as well as pressure control in the system, and the cabin re-pressurizes very quickly following the de-pressurization phases.

Gross weight of the *Superfortress* is roughly, twice that of the *Flying Fortress* and printed reports have said the plane is capable of carrying more than 16,000 lb. of bombs. Striking range of the B-29's may be judged by the fact that after flying the Western China to-Yawata round trip in their debut bombing of Japan, most of the planes, according to the press, landed back at their bases with encouragingly big supplies of gasoline left in their tanks—enough to fly hundreds of miles (or translatable into a heavier bomb load).

Roominess of the B-29's cockpit contrasts with the tight nose accommodations of earlier bombers. There is considerable space between pilot and co-pilot and on the panels facing them the former multiplicity of instruments has been minimized, a comprehensive control panel being fitted in the flight engineer's alcove immediately aft of the co pilot. A step-down position in the nose greenhouse accommodates the bombardier who, by virtue of the sealed cabin's sound-proofing, can converse freely with the pilots. Speaking of this sound proofing, the *Superfortress* is the quietest bomber we've flown in. With noise and racket obviated and shouting unnecessary there is decidedly less crew fatigue.

In the compartment next behind the bridge are positions for the radioman (starboard) and the aviator (port). Then the 30 in. dia. passageway extends rearward over the bomb bays to connect with the aft compartments for the remaining crew. Here are found the waist firing positions, followed by a bunk room sleeping four. Finally a long compartment leads to the tail turret.



Announcing A NEW WELDING PUBLICATION

THESE FEATURES EACH MONTH

★ Welding Metallurgy

★ Cost Analysis

★ Welding Design

★ Production Ideas

★ Salvaging Tools

★ New Maintenance Economies

★ Useful Tricks and Tools

★

For WELDERS • ENGINEERS

. . . Created to disseminate factual information and knowledge gained from the experience of successful users of EUTECTIC *Low Temperature* Welding, the new welding process which is gaining wide acceptance in production, salvage and maintenance. All metals from aluminum to zinc die-castings can be joined by this process. Applicable with oxy-acetylene torch, metallic-arc induction and furnace heating.

The EUTECTIC WELDER is prepared by the engineering and research staff of The Eutectic Welding Alloys Company, and supplemented by contributions from users of the process in all fields.

Welders, welding engineers, and metallurgists have acclaimed the arrival of The EUTECTIC WELDER. An engineer writes:

"Found your publication a real boon to our welding department. Please add the following names to your list and make sure to send us current issues every month."

EUTECTIC® LOW TEMPERATURE® WELDING

EUTECTIC WELDING ALLOYS COMPANY 40 Worth Street New York 13, N. Y.

Originators of the Low Temperature Welding Process

GET IT FREE Mail Coupon Today

®Reg. U. S. Pat. Off.


EUTECTIC WELDING ALLOYS COMPANY Dept.
40 Worth St., New York 13, N. Y.

Please send me The EUTECTIC WELDER every month.

Name.....

Company..... Position.....

Address..... City.....


765 Series
SHUT-OFF COCKS


770 Series
DRAIN COCKS


771 Series
DRAIN COCKS

by McDONALD

88 YEARS' EXPERIENCE IN PRECISION MANUFACTURE

Precision-made to rigid Army Navy Aeronautical specifications— mod available in sizes and types to meet all requirements. Write for special folder—

A. Y. McDonald Mfg. Co.
Dubuque, Iowa

McDonald
AIRCRAFT VALVES

True, the ship, a mass of compact installations, is complex throughout. We will provide more of the details a little later on But our initial interest here is the mastery of manufacture it represents Few accounts have highlighted the point which was most striking to us—that is *simplicity* of fabrication.

In choosing a cylindrical-design fuselage, Boeing did much more than achieve speed through clean lines. The company thereby greatly simplified manufacture of the plane—for the 9-ft-dia sections of the body and accompanying bulkheads are initially turned out much like huge metal vats and vat covers Built up-ended in large jigs, the sections are speedily fabricated by a number of employees working simultaneously both outside and inside.

These sections are quickly fitted together into the larger components In final assembly there are five portions— Nose, bomb bay, bomb-bay-to-tail, three-part tail, and three-part wing The wing center section weighing 11 tons minus engines is carried by overhead crane from the wing portion of the plant and lowered into place in the center section It is noted that at Wichita the B-29 wing is made in three parts (center section and two tips) whereas it is understood that at Renton, now in production, the wing is made in five parts in accordance with differing plant accommodations

The whole scheme of simplified production is evidenced in the strikingly low number of man-hours required to build the ship The exact figures cannot be given but it can be revealed that current *Superfortresses* take but ⅓th the number of man-hours which were required to turn out the first model In fact, the B-29 today is less expensive in man-hours than was the famed B-17 *Flying Fortress* at the same stage Wichita is practically at the Army-set rate of production now and an extra capacity of some 20 percent is still available

Particularly noted was the exceptionally smooth riveting on this bomber Virtually all rivets are driven flush and the aluminum sheets are butt-jointed externally throughout Likewise, the landing gear doors close exceedingly flush (drag of the *Superfortress* is reported to be double when the landing gear is down —additional evidence of the fine aerodynamic qualities built into the plane).

Greater-Range Airfoil

The B-29's Boeing 117 airfoil section represents further ingenuity Specially developed for greater-range performance through refinements in drag characteristics, the resultant wing admittedly is given a high loading But despite this, the desired high ceilings are obtained. The 117 section is strictly a Boeing development, though an NACA section is said to approximate it. The 117 is somewhat similar to the airfoil used on the Boeing *Sea Ranger*

In internal structure, the wing is of web type rather than tubular-spar type as on the B-17 The web type again is simpler Multi-cellular, it particularly gives more space for intra-wing fuel tanks Trailing edge of the wing is approximately straight, except for a portion between inboard nacelles and fuselage Here, the trailing edge of the huge wing flap hooks downward decreasing aerodynamic interference between wing and body and minimizing tail buffeting during climb Dihedral of the wing is 4½ deg, and there is a 7-deg sweepback Inboard portion of the wing employs ¾-in. Alclad, termed the thickest so far used. Aspect ratio of the wing is 11.5. Maximum wag on the wing tip in flight is 48 in as compared with 30 in. on the B-17.

The exceptionally large wing flaps constitute nearly 20 percent of the wing area. In takeoff, these flaps are extended 25 deg. In extended position, they increase the wing area 19 percent. Using additional flap in landing, the B-29 "sets down" with comparable speed to the B-17 Incidentally, the *Superfortress* has been landed without flaps (And it may be noted here that the plane can fly on two engines and has taken off using only three.)

Operation of the flaps is of special interest. Actuated through threaded rods, two on each wing they roll out and down on five "T" tracks on either wing Their control is synchronized.

The B-29 is virtually an all-electric plane, using 150 electric motors of 49 different types Only hydraulic use is in the landing gear braking system Included in the craft is some 11 mi of wiring A Lawrance Aeronautical Corp. 12-hp auxiliary gasoline engine gives extra power for operation of the gear in takeoff and landings

Boeing's design of control surfaces and control elements give accent to stability and ease of handling throughout takeoff, flight, and landing Control forces are termed even lighter then in the B-17 through refinements in design and employment of tab surfaces in the airstream to facilitate control-surface movements The pilot "feel" is "right on the touch", in fact, operation of the rudder is stated to require less effort than that of the B-17

Combination servo tabs and trim tabs reduce the control force on the aerodynamically and statically balanced ailerons to a minimum Although of different airfoil section and construction, the stabilizers and elevators are identical in plan form to those on the present B-17's. It is interesting to note that the stabilizer airfoil's leading edge turns up giving in effect an inverted airfoil This is to obviate stalling of the stabilizer at a critical flight attitude

The ease with which the ship handles repeatedly impressed us when we flew in the superbomber We observed that she taxied lightly, belying her great size. She was airborne with little more than a 2,000-ft. run And in her subsequent climbs, banks, and bursts of speed which demonstrated her fine performance, the smoothness and power seemed incongruous with her weight We sat cross-legged in the nose, between pilot and co-pilot, as she landed, and we can report that she came in with precision It was (if posy will be pardoned) as though she were guided in an invisible groove curving gently to merge with the runway

With such a mammoth craft we had expected something of a jar at impact, but none materialized. It is stated that the B-29 can land and take off in shorter space than the B-17

To continue with the description of the plane, design of the B-29's nacelles called for incorporation of a single large air duct in the nacelle nose, thus giving a frontal oval shape Further, sufficient space is provided in these units to accommodate the retracting landing gear and the dual superchargers while still retaining reasonable accessibility to the nacelles The practical final design was an adjudication between the project engineers (who strove for a unit housing all needed equipment) and the aerodynamic engineers (whose purpose was minimum size and maximum streamlining for speed).

In development of the bomb bays, versatility as well as size was achieved. The initially planned bays accommodated a great weight of bombs, but only in the larger sizes Through lengthening of the bays (and accordingly the ship itself) there is now accommodation for as great a weight in small "eggs" as in large ones.

First Dual Nose-Wheel

Use of a dual nose wheel in the B-29 landing gear—first such double unit ever devised—was necessitated by the extreme weight of the *Superfortress* There were, accordingly, the problems posed by weight of the unit, also its steering and retracting Wheels of 3-ft dia were finally decided upon, while those of the main undercarriage measure 56 in The latter are Goodyear 16-ply Nylon S. C synthetic tread tires It is noted that the B-29's C.G lies 15 ft forward of the main landing gear. Weight of the landing gear totals slightly more than 7,000 lb.—roughly 6,000 lb for the main undercarriage and 1,000 lb for the nose-wheel gear.

Turning to the engines, the reduction gear employed affords an extremely low ratio, revolving the propellers only 35/100ths times as fast as the rpm of the engines For aerodynamic reasons, it was essential to keep the speed of the prop tips sub-sonic, yet utilize maximum engine power Thus, the airscrews turn unusually slow, but speed of the tips, at the periphery of the 16 ft. 6 in dia., compares with the speed of tips on other planes

Construction of Boeing's *Superfortress* was actually underway—in certain components—before its entire design was completed Thus, in numerous instances portions of the airplane virtually were blueprinted after, rather than before their construction. The B-29 is stated to have had no major "bugs"—except the "lack-of-time bug" Yet even this one was ironed out. With painstaking stick-to-it-iveness, the men behind the B-29 kept pushing the job to completion They concentrated their efforts on whatever phases of the program could be attacked "fustest" with the "mostest" of designs, materials, and workers. The sequence didn't matter, getting the job done did.

Preliminary tunnel tests, made at the

Inexpensive BUT VITAL



All of the TITE SEAL needed to completely service a 1000 plane armada could probably be carried on just one of those planes. But if it had not been for the discovery of the TITE SEAL principle, few of those planes could ever reach Berlin.

TITE SEAL was the *original* non hardening gasket and sealing compound and was the first to overcome the dangers from vibration. It permitted the development of 2000 HP motors and made long flights possible.

The small mount of TITE SEAL used to protect an aeroplane may be unglamorous and inexpensive, but it is extremely important. For Safety's Sake, always specify the original—specify TITE SEAL.



FOR DETAILED INFORMATION ABOUT
TiteSeal
WRITE

RADIATOR SPECIALTY COMPANY
CHARLOTTE 1, NORTH CAROLINA
Branches • LOS ANGELES 1, CALIFORNIA • TORONTO 2, CANADA




Pan American Clippers Use

WITTEK

AVIATION HOSE CLAMPS



Pan American World Airways mechanic adjusting Wittek Hose Clamp in nacelle of Clipper Ship



Wittek Aviation Hose Clamps are standard equipment on military aircraft, aircraft engines and are also the standard service clamp of leading Commercial Airlines. Outstanding among this group is Pan American World Airways whose great Clipper Ships have amassed an amazing record for *Safe Air Miles* in essential air transportation throughout the world. Wittek Hose Clamps have flown each of these safe miles with Pan American. The performance and dependability of Wittek Aviation Hose Clamps is recognized by Pan American World Airways —where only the best is good enough. Wittek Manufacturing Co., Chicago 23, Illinois.

War Bonds for Victory—

ARMY E NAVY

Buy MORE in '44!

WITTEK Aviation HOSE CLAMPS Since 1923 WMCo

University of Washington and California Institute of Technology, won the Army order for three 'X' models. But flight testing a plane which you haven't yet built is impossible. Not *entirely* impossible though. Fact is that Boeing did flight test many portions of the B-29 control systems including all tail surfaces, before a single *Superfortress* was flown.

Various B-29 control surfaces scaled down to B-17 size, were tested on a B-17C *Flying Fortress*. Thus the ailerons were checked. Next scale-model tail surfaces were put through their paces on a B-17E. And tests on a scaled-down B-29 nose-wheel gear were made on a Douglas A-20 at Wright Field.

Hydraulic-Jack Static Tests

In later tests of the wings 300,000 lb. of pressure was required to prove the structures and the former lead shot-sacks method of static testing was impractical. Answer was a specially designed system of hydraulic jacks, which brought a great saving of labor and more accurate application of loads. Finally, according to Army stipulation the complete airplane frame, with weight inside to simulate full equipment, bombs, fuel, crew and ammunition load, was free dropped from a point 27 in. above the floor. The *Superfortress* successfully passed two such tests, one in horizontal position and one in inclined position.

Vibration in the plane has been reduced to a minimum. At first, magnesium was employed in the fabrication of the tunnelway over the bomb bays, but because this structure tended to vibrate, there was a switch to dural.

Manufacture of the *Superfortress* involves basically the same principle as that used in building the B-17's—that is, precompletion of major sections on separate lines before final assembly. Because of the economy of production effort achieved in the B-29, it has been possible to employ hastily recruited, specially trained personnel. Boeing at Seattle had started the tooling project while the bomber was still in the preliminary design stages.

A major consideration was the joining of the various sections of the plane, and therefore many man-hours were initially expended to obtain a production joint to fit together various sections of the plane with bolts, using a torsion wrench, and with no splicing of beams or skin laps required.

Master gages were designed and manufactured to maintain interchangeability of all major *Superfortress* parts no matter where built. Moreover design for production is further evidenced by the clips which tie the circumferentials to the stringers, inside the fuselage skin. B-29 stringers, unlike those of the B-17, do not pass through slots cut in the circumferentials. Instead, the stringers are riveted to the skin and the circumferentials are attached to the stringers by clips.

Number of clip designs required in the plane was finally narrowed down to six, three left-hand and three right-hand. Rivet holes on the clips are pre-punched, full size, as are the matching holes in the circumferentials and stringers. The clip is riveted to the circumferential as a



KOLD-HOLD . . . *Co-Pilot*

Performance builds the confidence of our fighting pilots in their ships . . . but, long before enemy objectives are sighted, PERFORMANCE is demanded in the testing of vital instruments and materials. . . KOLD-HOLD Sub-Zero equipment meets this challenge in assuring accuracy and dependability.

DO YOU
Have a Cold Processing Application:

DO YOU
Require Temperature Testing Units with pressure and humidity control:

DO YOU
Know that Cold Temperature Processing Is Vital to Modern Production Methods:

Then you can use KOLD-HOLD'S Sub-Zero Industrial equipment. Machines from 2 to 400 cubic feet and —100° F. to +200° F. temperature range.

KOLD-HOLD Stratosphere and "Hi-Low" Machines will do a specific job for you, accurately, thoroughly, rapidly and economically.

Hundreds of important War Production plants using KOLD-HOLD low and dual temperature machines daily demonstrate that cold processing is one of the foremost time savers of modern manufacturing.

● KOLD-HOLD units are productioneered* to YOUR specific problem. . . Catalog S-Z 431 illustrates many types of machines available now. Write for your copy today.

KOLD-HOLD
MANUFACTURING COMPANY

**Engineered for Production*


442 NORTH GRAND AVENUE ● LANSING, 4, MICHIGAN



Rough, rip-snorting, oil-starved air tools smooth right out—sweet, well-behaved as shop angels!—with Norgren air-borne lubrication on the air lines that serve them. The NORGREN Lubro-Control Unit filters the air . . . controls pressures . . . automatically injects exactly enough oil into the air stream to create a lubricating fog around each working part of the tool. Installs directly into any air line. Starts, stops with the tool. Prevents corrosion. Boosts production. Lengthens the life of your air tools.

NORGREN *Lubro Control* UNIT

A size and type for every need. Get the facts! Write for data! C. A. Norgren Company, Denver 9, Colorado.



subassembly operation. The stringer is positioned in the jig by pre-located coordinated holes, and the circumferential and clip is attached to the stringer by one Cleco pin.

In the other hole a rivet is driven. Then the Cleco pin is removed and the second rivet is driven. In effect, this is pre-matching holes on a large aircraft structure so that parts will fit together handily, yet very close tolerances are achieved.

In outline, there are five airframe plants in the B-29 program—Boeing at Seattle, Renton and Wichita; Glenn L. Martin at Omaha, Neb.; and Bell Aircraft at Marietta, Ga. A major subassembly operation is handled by the Fisher Body Div. of General Motors at Cleveland. Instituted was a B-29 Committee, similar in pattern to the successful Boeing-Douglas-Vega Committee coordinating production of B-17's.

Working through various subcommittees, the B-29 Committee coordinates procurement of materials and the key phases of the work through the hundreds of subcontractors and numerous subassembly operations. Further, it prepares and maintains master production schedules, coordinates tooling requirements and distributes all design-change instructions among prime contractors. The Committee's offices are located in Seattle, where sessions are held regularly. It may be noted that there have been no subcontracting delays.

Firms Contributing

All the companies contributing to the program cannot be cited in this short space, but a few specific mentions may be made for perspective: The 2,200 hp engines are now coming from the huge Dodge-Chicago plant of the Chrysler Corp., though Wright is biggest producer; General Electric developed the fire control system which actuates the *Superfortress* guns; Bendix Aviation Corp. supplies a super generator; De Soto Div. of Chrysler makes noses, wing edges, and engine cowling covers; Minneapolis-Honeywell produces the automatic pilot; Libbey Owens-Ford contributes the bullet-proof glass employed; and United States Rubber Co. delivers to the ship more than 200 rubber parts weighing nearly 5,000 lb. Others which may be named are A. O. Smith Corp. (landing gear); Jack & Heintz (landing gear motors); Goodyear Aircraft (fuselage center sections and empennages); Chandler-Evans Corp. (carburetors); also Briggs Mfg. Co., Cessna Aircraft, Firestone Tire & Rubber Co., Hudson Motor Car Co., Maytag Co., Murray Corp. of America, Ohmer Register Co., Ryan Aeronautical, and Shakespeare Products Co.

Boeing of Wichita makes some 40,000 of the total of approximately 55,000 parts (not including rivets, etc.) employed in the superbomber.

Additional notes: It is stated that to the best of ability design of the B-29 *Superfortress* aimed at ease of maintenance of the ship and interchangeability. Means to supply the B-29's operating in the 20th Air Force have, wherever possible, followed the channels already set up (see news section for story about the 20th Air Force). Because of the huge size of the bomber, it was necessary to devise large handling facilities for outside maintenance and repair.

The company reveals that a transport version ship, as yet undesignated, will be coming. It is stated that the new 117 airfoil and pressurized-cabin development are well fitted for such a craft. However, the specific bomber design is not considered suited for transport work.

Of leading interest in our Wichita visit was the detailed demonstration of the construction of the wing. A total of 34 extrusions are incorporated in the wing, 17 on each side. A heavy extruded duralumin chord is used for the web spar. Weighing 255 lb. when machined, this chord is termed the largest employed in a production airplane.

Wing Spar Chord Practice

The following traces the right-hand front wing spar chord from the time it is received at the Boeing-Wichita warehouse until it reaches its ultimate position in the *Superfortress*.

Raw material is received in West Warehouse No. 1 at Crib No. 47.

To Shop 120. Farnham-Mills. 1 Straighten (spar chord, 25½ ft. long, supposedly is straight when received, but process here is to make sure); 2, Mill face (process of milling down face of chord to specifications. Skin is later fastened to milled face); 3 Mill leg; 4, Mill taper on inside face; 5, Mill inside face of flange; 6 Mill warp on outside face; 7 Saw to length (this calls for chord to be cut to exact length of 202 in.); 8, Straighten (milling and sawing reduced spar chord to approximately 217 lbs., second straightening process is to make certain no bends have resulted); and Saw; 9 Rough cut scarf (process of cutting out scarf, or section, where right hand spar chord will eventually be joined with left hand chord to center of airplane); 10 Mill scarf; 11 Mill side scarf, outboard (for later joining with outboard portion of inboard spar).

To Shop 122. 12 Router operation (sections of chord are routed out for later fitting in of other sections of wing); 13 Drilling operation (this is drilling of holes which later will be used in fastening on panels, or skin); 14, Inspect.

To Shop 420. 15 Anodize (chord is immersed in a liquid bath to give it a protective finish); 16, Inspect.

To Production Stock No. 11. Completed as an individual piece chord is placed in production stock until needed. After being taken out of production stock, next route is as follows:

To Shop 260. Assemble into spar assembly, Station 202-202 (where lower and upper chords are joined to make a spar assembly); 1 Drill chords and webs, make joint at Station O (lower and upper chords are joined by means of a web, then right hand and left hand assemblies are placed together by means of a scarf joint at Station O, which is center of airplane); 2 Rivet assembly; 3 Inspect.

To Shop 410. 4, Paint; 5 Inspect.

To Production Stock No. 11.

To Shop 260. Assemble into spar assembly, Station 510-510. 1 Make scarf joint at Station 202 (two outboard portions of inboard spars are scarf joined to inboard portion at this point. Station 510 to 510 means it is 510 in. from extreme ends to Station O, which is center of plane); 2 Complete inboard front spar assembly.

To Shop 265. Wing jib. Assemble spars and ribs, rivet panels (skin), and join trailing edge. (Front and rear spar assemblies are joined at this point by means of ribs; fuel tanks are later fitted between ribs).

To Shop 270. Wing floor (complete structure of inboard wing).

To Shop 271. Wing primary assembly (installations on inboard wing including fuel cells, landing gear, nacelle fairings, inlets, cabins, etc.).

To Shop 261. Joining position No. 1 (join inboard wing to fuselage, and complete nacelle installation and install engines).

Review of Patents

(*Continued from page 210*)

Extendible Wing Flap Mechanism is designed to give maximum efficiency in flap position and gap between main airfoil and flap throughout range of move-



ELECTRICITY
For Any Job . . . Anywhere

For a dependable source of electricity on Aviation projects remote from commercial power, Onan Electric Plants are proven leaders in the field. More than half of the armed Forces' total requirements for Power Plants are built by Onan.


Gasoline driven ..... Single unit, compact design ..... Suitable for mobile, stationary or emergency service

Over 65 models ranging in size from 350 to 35,000 watts 50 to 800 cycles 115 to 660 volts A.C.— 6 to 4000 volts D.C.— Also dual A.C.-D.C. output types

Descriptive literature sent promptly on request

D. W. ONAN & SONS
3124 Royalston Ave.
Minneapolis 5
Minnesota

Airborne
SERIES OTC



ONAN
ELECTRIC PLANTS



ment. Angle of attack of flap can be varied as desired. Guiding tranke incorporated can be variously curved to control position.—2 348 [illegible] filed June 2, 1941 patented May 9, 1944. E. H. Richter, assignor to Lockheed Aircraft Corp.

Mounting for Helicopter Rotor comprises stationary hollow upright column fitted in body of craft and embraced by rotatable sleeve. Mounted on sleeve is head from which rotor blades project. Blades adjustable for variable pitch, or mounted in a horizontal bearing in head. Flange and groove fitting is employed and bearing is split so blade may be readily mounted or dismounted. A second bearing gives further rigidity and support.—2,348,249 filed Feb. 8, 1941 patented May 9, 1944, C. Ferre.

Airfoil Designs. Construction here aims to provide increased values of lift over wide optional range of lift to drag ratios for relatively slow speed flight as in takeoff, climbing and landing, and is also designed to reduce drag in normal high speed range, to provide substantially improved lift to drag efficiency for greater economy with increased loads and speeds. Included are singular slot permeation passage, movable leading edge slat section intermediate relatively fixed main airfoil portion and one or more separately disposed movable sections or flaps terminating at the trailing edge. The several components combining to form a basic airfoil profile.—2 348,248 filed Nov. 28, 1940 patented May 9, 1944, and 2,348,-249 filed Aug. 1, 1941, patented May 9, 1944. R. W. Griswald, II.

Airplane Pickup Mechanism calls for catapult which projects article upon pickup of flexible loop connected to article as catapult. Provided is simple form of mechanically operated catapult which release.—2,348,342 filed June 23, 1942, patented May 9, 1944. E. G. Hill, assignor to G. T. Smith and E. G. Hill, as trustees.

Undercarriage Invention Offered here is frictional damping device acting on cylinder member of landing strut, device being controlled by load on strut to afford variable damping increasing with dynamic loading of strut. Degree of damping is reduced substantially to zero when strut is unloaded (i. e., when airplane is airborne) to give free operation of self-centering mechanism acting on strut. A frictional brake acting on cylinder member of strut is operated by pressure derived from and proportional to loading of strut.—2,348,493. Filed Dec. 30, 1941, patented May 9, 1944. S. MacD. Parker, assignor to Automotive Products Co., Ltd.

Book Reviews

(Continued from page 210)

MATERIALS AND PROCESSES, edited by J. F. Young. John Wiley & Sons, N. Y. 628 pages, graphs, photographs, tables, index. $5

A broad study of the materials and manufacturing processes employed by engineering designers for all crafts. Main objective is resolving of the problems of selecting proper materials for any given or projected apparatus. Divided into the two categories of its title. The book treats copiously of the nature of materials and the processes by which they are worked and finished. Covered are late developments in new materials as well as standard metals including consideration of plastics and their uses.

AEROSPHERE, 1943. Aerosphere, Inc., N. Y. Edited by Glenn D. Angle. $15

Packed with factual data. This big 1943 issue of "Aerosphere" offers readers an over-all compendium of flying equipment just as the Allied invasion of Europe brings the air war over the continent to a grand climax.

The historical introduction to the subject is pointed and profusely illustrated and preceded it are a number of short articles by several military and naval experts including Gen. Arnold who lauds this "full record of our airplanes which have gained superiority over the enemy on our eight fighting fronts."

Body of the book is divided into four main parts devoted to Modern Aircraft, Modern Aircraft Engines, Aircraft Statistics and a Buyers' Guide.

The first section devotes 300 pages to a well illustrated gallery of the aircraft of all countries with each plane photograph accompanied by specifications on points of its construction and performance. A subsection includes a listing of the chief aviation sequences of each country.

Modern Aircraft Engines, second of these sections, follows the illustrative plan and includes many diagrams of plane power plants. 11 nonaliides with a table of principal specifications. Aircraft Statistics supplies information on aviation records and compilations, also includes a listing of inspectors for the CAA, foreign diplomatic aeronautical representatives in the U. S. A. statistics on many government bureaus connected with aviation and numerous miscellaneous data tables. The Buyer's Guide, comprising listings of aviation firms and products in foreign countries, concludes the volume.

20th CENTURY ENGINEERING, by C. H. S. Tupholme. Philosophical Library, N. Y. 201 pages, illustrations, index.

Primarily records engineering triumphs of the past few years. Aviation is covered in a highly compact chapter.

AIRPLANE ENGINE MECHANICS QUESTIONS AND ANSWERS by Rolla Hubbard and Angnalin Dilworth. McGraw Hill Book Co., N. Y. 265 pages, index. $3

These questions and answers have been prepared for all types of aircraft workers and assume that the reader is familiar with the fundamental principles of internal combustion engines and their various accessories." They have been designed "principally to aid in the preparation for obtaining a CAA airplane-engine license." The elements of engines are covered, and there is a special section devoted to propellers.

INSTRUCTIONAL TESTS IN AERONAUTICS, by Albert J. Rosenberg. World Book Co., Yonkers on Hudson, N. Y. 92 pages, photographs, charts, key

This booklet covers in considerable detail, the tests offered in CAA private pilot examinations. Questions are to be answered in the book then checked by an accompanying supplemental key. The tests designed primarily for teaching purposes may be used satisfactorily in any course in elementary aeronautics regardless of the text used."

INTO THE AIR AGE, by N. L. Engelhardt, Jr. Air Age Education Research, N. Y. 25c.

Instructional booklet aiming to give an over all picture of this flying age and the forces shaping its future outlines. Directed primarily at teachers for use as a source book in preparing courses on the subject.

THEN THERE WAS ONE by Eugene Burns. Harcourt, Brace & Co., N. Y. 212 pages photographs. $2.50

Of the seven first-line U. S. carriers when war began, four were sunk in the first year of war, the fifth saw action in non-Pacific waters—and the sixth was out of action at the decisive moment. "Then there was one"—the "Enterprise." This is its story, from Pearl Harbor on through every major action, but one.

MODERN WOOD ADHESIVES, by T. D. Perry. Pitman Publishing Corp., N. Y. 208 pages, illustrations, index. $3.

Handbook of modern wood adhesives in relation to construction and engineering projects in wood. Various types of glues are described and their properties analyzed. Other phases covered are methods of comparing glues, glue mixing and spreading equipment, pressure, adhesion, re-driers, and impregnation and testing each accorded a chapter.

LONG RANGE FLIGHT, by Colin Hugh McIntosh. McGraw-Hill Book Co., N. Y. 177 pages diagrams, flight plans, and graphs. $2.50.

A study of the essential techniques for aircraft operation in long distance flights. This book details the fundamentals that must be understood in order to make use of the charts used by airline operators, also considers long-range flight thought and practice and explains methods of cruising control and preflight planning. Also covered are the principles of efficient engine operation and controlled flight through the use of the 'hawgosh' chart.

INSTITUTE OUR PLANNED PROCEDURE

A Treatment and Control for Industrial Skin Irritations

Cut out this ad and attach to your letterhead. It will bring you a good sized jar of TARBONIS without charge, a complete dispensing Manual and an attractive booklet we can furnish your employees on sanitation and precaution. Why experiment further? . . . TARBONIS is the solution, tested and proven in Industry . . . succeeds where many other methods fail . . . against a long list of irritants encountered.




THE TARBONIS COMPANY
1220 HURON ROAD • CLEVELAND 15, OHIO

When I Need Gages That are "RIGHT on the NOSE"




All gages sold by Republic Gage Co. must pass a rigid inspection of Pitch Diameter, Lead, and Thread Angle. Only when all three are within their proper tolerances are gages released to our customers. That is why inspectors and buyers specify our products when they need gages that are "Right on the Nose."


The result of our "Controlled Accuracy" policy is gages of highest quality. Take advantage of that fact in solving your gaging problems by specifying gages by Republic Gage.



REPUBLIC GAGE CO.
2228 FENKELL AVENUE
DETROIT 21, MICHIGAN
PHONE UNiversity 1-0370


These LINDE METHODS *Reduce Costs of* MAINTENANCE OPERATIONS





OXY-ACETYLENE WELDING

The oxy-acetylene flame makes possible the joining of practically any metals—like or unlike—so that the weld is as strong as the base metal itself. *Welded piping systems* in plants and refineries use less fittings, occupy less space, and remain leakproof indefinitely. *Bronze welding* and resurfacing speed the repair of worn or broken parts. *Hard Facing* with Haynes Stellite alloys makes parts subjected to abrasion, heat, or corrosion last from two to twenty-five times longer.




Straightening

Structural steel, shafts, pipe, plate, and other metal parts and structures that have become bent or warped can often be trued up in the shop or on the job by applying the intense heat of oxy-acetylene flames at the right points.




Hand-Cutting

Flame cutting with manually operated blowpipes is useful for cutting pipe in the fabrication of piping systems. Hand cutting also is used to cut structural steel in construction or alteration work—to reclaim old pipe—and to cut scrap to length.




Gouging

With Oxweld hand-cutting blowpipes equipped with gouging nozzles, surface metal—such as faulty or temporary welds—can be removed quickly leaving a groove without need of grinding or chipping, and without harm to the adjacent areas.



Flame-Priming

This process removes loose scale, rust, and surface moisture from steel prior to painting—making paint go on faster, bond tighter, and last longer.



Heating

Heating for bending, straightening, and forming operations is facilitated by the oxy-acetylene flame. Shown here, a pipe is being wrinkle bent.



Oxygen, Acetylene, Carbide

A booklet describing use of Linde oxygen, Prest-O-Lite acetylene, Union Carbide, and Oxweld apparatus in these and other processes will be sent without charge on request. Ask for Form 5268A.

BUY U. S. WAR BONDS AND STAMPS

THE LINDE AIR PRODUCTS COMPANY

Unit of Union Carbide and Carbon Corporation

30 E. 42nd St., New York 17, N. Y. UCC Offices in Other Principal Cities

In Canada: Dominion Oxygen Company, Limited, Toronto

The words Haynes Stellite, Linde, Oxweld, Prest-O-Lite and Union are trade marks



The U.S. Army's newest weapon in the night skies...designed on battle experience

When skies go dark, air warfare calls for a special kind of combat plane. Pilots discovered this during the Battle of Britain. Thus the "night fighter" was born.


From then till now, night fighters have been made over from models originally planned for other uses.

The Northrop "Black Widow"—built on knowledge hard-won in four years of night combat—is the first airplane created especially for night fighting.

Big, venomous, scarcely-equipped, the "Black Widow" has what it takes to lurk in the darkened skies . . . to keep an "umbrella" over advanced bases, airstrips, beachheads and supply lines.


Equally well, the "Black Widow" can sneak behind enemy lines . . . to cripple transportation, blast airdromes.

For such tasks the P-61 "Black Widow" night fighter has speed to spare. It can also throttle way down, almost hover in the dark. It can land slowly. And it packs terrific fire power.




NORTHROP AIRCRAFT, INC.
NORTHROP FIELD, HAWTHORNE, CALIFORNIA
MEMBER AIRCRAFT WAR PRODUCTION COUNCIL, INC.


GARDEN CITY'S AIRCRAFT PRODUCTS ARE SERVING ON ALL FRONTS . . . .



SOME OF OUR AIRCRAFT PARTS



On every front, equipment made by Garden City can be found — aircraft parts, sub-assemblies and aircraft maintenance devices for the AAF, Navy and leading plane manufacturers. We now have openings for additional press and drop hammer work, skin fabrication and assembly, screw machine work, machine shop production work and tool and die work.



The C-300R clevis and C-200R "starting" lanyard are manufactured by Garden City for America's foremost aircraft producers. The advantages of their holding and gripping characteristics combined with their thumb opening availability are providing new uses for these clevises in the aircraft industry daily. Immediate shipments are now possible. If you desire a sample, clip this to your letter head.

PRODUCTION FACILITIES

Do you need someone to get into production NOW? We make our own Kirksite dies, all our own tools, jigs and fixtures. We have resident AAF and Navy inspection and can have one of our tooling men in your plant tomorrow.

Clip This

GARDEN CITY PLATING & MFG. CO.
(Corner) Ogden Blvd. & Talman Avenue
CHICAGO 8, ILLINOIS

Send Me Sample Quick Opening Clevis

CLIP THIS TO YOUR LETTERHEAD



COURTESY OF DOUGLAS AIRCRAFT CO., INC.

Federal aircraft ball BEARINGS

FEDERAL not only has the experience, but the skill, knowledge and facilities essential to the manufacture of fine ball bearings for aircraft service.

•

At home, or abroad . . . on land, or at sea . . . these QUALITY ball bearings provide dependable, accurate control.




TRADE MARK

THE FEDERAL BEARINGS CO., INC.
Makers of Fine Ball Bearings
POUGHKEEPSIE, N. Y.
REPRESENTATIVES LOCATED AT
Detroit: 2040 Book Tower • Cleveland: 402 Swetland Building
Chicago: 502 S. Wabash Ave. • Los Angeles: 5410 Wilshire Blvd.

TWO RECORD-BREAKERS...

and PACKARD-BUILT ENGINES powered them both!



May 12—Mustang fighter breaks transcontinental speed record

Los Angeles — 2,470 miles, 6 hrs., 31 min., 30 sec. — New York



May 13—Mosquito bomber breaks transatlantic speed record

Labrador — 2,200 miles, 6 hrs., 46 min. — British Isles

Two world speed records shattered, within the space of two days!

And both records were broken by war planes powered by Packard-built Rolls-Royce aircraft engines

An Army Air Forces colonel set the new speed record for transcontinental flight in a North American P-51 "Mustang" fighter.

A ferry pilot of the R.A.F. established the new transatlantic speed record, crossing the ocean in a de-Havilland "Mosquito."

These records were made possible because pilots, planes and powerplants all did their part, functioning perfectly all the way.

We're gratified, naturally, that Packard-built engines took part in these record-breaking flights, and measured up to the high standards set by the pilots and the planes they flew.

But there's a still deeper satisfaction in knowing that *every fighting engine* we build may shorten the war by a week, a day, or an hour!


MUSTANG fighter · WARHAWK fighter · HURRICANE fighter · MOSQUITO fighter-bomber

PACKARD

LANCASTER bomber · NAVY PT boat · ARMY rescue boat

PRECISION BUILT POWER

★ ASK THE MAN WHO OWNS ONE ★



CP HYDRAULIC POWER MACHINE

DEVELOPING pressures up to 100 or more tons, CP Hydraulic Power Machine . . . comprising a self-contained generating plant and a CP Work Unit . . . speeds output and cuts costs in all types of high speed production riveting, piercing, pressing and pulling.

The self-contained CP Power Unit . . . with an electric motor-driven duplex hydraulic pump . . . will handle two, three or four CP Work Units operated one at a time. Or, the CP Power Unit will handle any number of CP Work Units operating simultaneously, up to the capacity of the hydraulic power unit.

Cylinders available in different sizes and capacities can be equipped with a wide variety of yokes. CP Work Units are light and compact for pressures developed. Suspended by a CP Super Safety Balancer and a swivel bail, CP Work Units operate at any angle. Write for complete data on CP Hydraulic Power Machine.

★★★★★★★★★
PNEUMATIC TOOLS
ELECTRIC TOOLS
(Hicycle...Universal)
ROCK DRILLS

CHICAGO PNEUMATIC TOOL COMPANY

General Offices: 8 East 44th Street, New York 17, N. Y.

★★★★★★★★★
AIR COMPRESSORS
VACUUM PUMPS
DIESEL ENGINES
AVIATION ACCESSORIES

Albanene

the Stabilized TRACING PAPER



★STABILIZED to keep its toughness and transparency — that's Albanene Tracing Paper. Because it is treated with crystal-clear Albanite, a new synthetic solid developed in the K&E laboratories—Albanene will not oxidize, become brittle or lose transparency with age. Albanene's improved drawing surface takes ink or pencil fluently, erases with ease . . . Ask your K&E dealer.

TRADE MARK K+E

KEUFFEL & ESSER CO · *Est. 1867*

CHICAGO • NEW YORK • HOBOKEN, N. J. • MONTREAL
ST. LOUIS • SAN FRANCISCO • LOS ANGELES • DETROIT

"PAR" PACKING RINGS

IN STEP WITH THE TIMES



HIGHER PRESSURES— SMALLER HYDRAULIC CYLINDERS . . . *BUT THE SAME POWER—*

Postwar planners, ready to meet the world of tomorrow with new products, or stepping up the performance of present equipment, are really putting hydraulics to work.

The cumbersome, easy-going, "low pressure" systems, familiar to engineer and layman alike, have already been replaced by systems operating at much higher pressures.

These "high pressure" systems utilize smaller cylinders, requiring less oil and make it possible to use smaller pumps. Occupying less space, they operate with less friction . . . more efficiency. All this in line with current design, involving less bulk and more compactly arranged assemblies.

"Par" Packing rings seal positively at these higher hydraulic pressures. Designers of hydraulic equipment in anticipation of postwar demands are invited to avail themselves of our engineering consultation. Sample rings mailed upon request.

NOMOGENOUS

For temperatures from—65° to 200° F. Friction ground to effect a perfect seal under pressure or at zero leads. Designed to meet the exacting standards of military aviation. Applicable to nearly every type of mechanical equipment. Leakproof under all conditions. Impervious to most commercial fluids and gases.



REINFORCED

Temperature range from normal to 750° F. For larger installations. Including giant hydraulic presses. The resilience of proven synthetics reinforced with duck or asbestos laminations, effectively seal against air, steam, water, gear oils, and petroleum solvents.



LINEAR

PACKING AND RUBBER CO.

State Road and Levick St.
TACONY, PHILADELPHIA 35, PA.

PIONEER MANUFACTURER OF SYNTHETIC PACKING RINGS

Over 40 Years Experience in the Design and Application of Mechanical Packings for every Service.

"PAR" PACKINGS

Glass Cloth NOW MAKES PLASTICS

TOUGHER . . .
STRONGER . . .
MORE USEFUL!



It may seem strange to think of glass adding great impact strength to any material. Yet that is just what happens when Fiberglas*—in the form of woven glass fibers—is used to reinforce certain plastics

This combination has resulted in a new kind of structural material with some qualities which excel those of any other material now known!

Besides its surprising ability to absorb shock, this new Fiberglas-plastic material combines great strength (in tension and compression) with very low weight. It also has dimensional stability (neither shrinks nor stretches) and has high fatigue resistance under vibration and other stresses

All these features have combined to provide outstanding advantages for many special applications on military aircraft

Another real value of this glass reinforced plastic is the ease with



which it is fabricated into complex shapes and forms. Expensive dies and great pressure aren't needed Machining is quick, accurate and clean

Admittedly, there is much to learn about this new material. Some authorities have called it a new material of construction. The ingenuity of engineers and designers of the plastics industry will broaden its use.

Manufacturers and design engineers desiring more information regarding this revolutionary development or the reinforcing Fiberglas Textile materials, now available in quantity are invited to write: *Owens-Corning Fiberglas Corporation, 1891 Nicholas Building, Toledo 1, Ohio; in Canada, Fiberglas Canada, Ltd., Oshawa, Ont.*

AN *Opportunity* FOR ENGINEERS AND DESIGNERS



Plastics reinforced with Fiberglas Textiles should be of great interest to designers, engineers and manufacturers seeking a stronger, lighter weight, more durable material We'll gladly help you get acquainted with fabricators now making this amazing new material

FIBERGLAS


*T M Reg U S. Pat. Off

ARMY ★★ NAVY



PAN AMERICAN WORLD AIRWAYS' "DIRECT WIRES"

.... for calling Clippers in any corner of the eorth



Wiring assembly of the Pan American Clipper's communications equipment- It contains hundreds of feet of Belden wire.

Maintenance crew at work on the Clipper between flights

In war ... in peace ... Belden aircraft and radio wires serve the aviation industry Here is an application showing extensive use in Pan American Airways' vital long range communications equipment

Belden aircraft wires are products that only ingenuity, skill, careful control of production, and use of service-tested materials esn build Belden wires have been developed through years of testing, experimenting, and cooperation with aircraft engineers; they offer the plus values to meet the exacting requirements of the aviation industry

Specify Belden

Belden Manufacturing Company
4665 W. Van Buren Street, Chicago 44, Illinois

Awarded the U S Treasury Special Citation of Merit for initiating the War Bond-or Cash Dividend Plan

Belden Aircraft WIRE

Starter, Lighting, and Instrument Cables √ √ √ SPARK PLUG WIRES

FENN PLANTS are set for ACTION



HARTFORD PLANT



NEW BRITAIN PLANT

Building War Products Today
Peace Time Products Tomorrow

Fenn Plants, wholly engaged in war production today, will, when peace comes, continue building special machinery, in which they have majored for three generations. If you are thinking of building new machines or remodeling old ones, it's time to plan Now

Fenn Aircraft
BUILT PARTS FOR FAMOUS PLANES


Fenn Plants are delivering precision parts and sub-assemblies for planes, artillery and other vital war equipment to practically every industrial center

FENN FOR SPECIAL MACHINERY

Fenn designers and engineers have solved many knotty problems in machine design, resulting in efficient, profitable production. Fenn has the men and experience to handle almost any machine design job. Consultation is invited and involves no obligation,

THE FENN MANUFACTURING COMPANY
HARTFORD • CONNECTICUT

AIRCRAFT INSTRUMENTS
by GENERAL ELECTRIC



First in a series showing a few of the many AIRCRAFT INSTRUMENTS that G.E. is now producing

GENERAL ELECTRIC
SCHENECTADY, N.Y.

FINGER-TIP CONTROL for MARTIN TURRETS

A G-E Engineered System That Facilitates Accurate Aiming at 300 Mph

● Enemy fighters buzzing 'round a bomber can make things tough for a turret gunner But one thing now made *easy* for him is the control of his turret—a job that a G-E control system can do electrically

In a Martin turret, the gunner does not have to move the guns themselves He simply turns his control handle—the turret and guns move correspondingly Smoothly, speedily, and without effort, the gunner is able to train and hold his guns on the enemy plane

Exactly what this highly successful system comprises and how the various elements are connected cannot be told But typical components are described at the right

Designing and producing aircraft systems for flight, radio, and power plant control is becoming an increasingly important phase of General Electric engineering. For information regarding available systems, and consultation regarding new projects involving electric control, write to the nearest G-E office. ***General Electric Co., Schenectady, N. Y.***

Testing G-E control system for Martin turrets under firing conditions



G-E TURRETS

The G-E Turret Speed-control System

This typical G-E aircraft system facilitates control of the turret and its guns. While its layout and equipment specifications cannot be revealed, components include the following:

1. TURRET DRIVE MOTOR. Standard G-E 24-volt d-c intermittent-duty unit of rigid construction and light weight. Equipped with steel shell, aluminum or magnesium end shields, and double-shielded ball bearings

2. AIRCRAFT AMPLIDYNE. Provides enormously amplified power (up to 10,000 to 1) from low control-field excitation, and instant response, insuring smooth, dependable performance under rapidly changing conditions.

3. REVERSE-CURRENT RELAY. Automatically connects or disconnects generator from bus Opens main contactor on reverse current of about 15 amp. Will interrupt reverse current several times rating of relay

4. VOLTAGE REGULATOR Controls generator field current and maintains constant voltage under varying generator speed and load Equipped with equalizing coil for equal division of generator load in multi-engined aircraft

5. AIRCRAFT D-C GENERATOR. Supplies electric power for G-E "power packages" and other electric equipment, as well as for turrets. Especially light in weight, with high overload capacity. Special shaft construction withstands vibration and torque pulsations.



PRECISION PRODUCTS AND ENGINEERED SYSTEMS FOR AIRCRAFT

GENERAL ELECTRIC



Our Hats Are In The Ring . . *for Victory and "C" Day*

THIS is a year of campaigns—campaigns for Victory on the War Fronts—campaigns to win the Peace on the Home Front—your own campaign for Post-War Business—with vital issues to be decided now, if you are to meet competition, keep your men at work, yes, even stay in business.

In the Campaign for Victory, "D" Day will ever be remembered. With Victory won, will come still another day no less important to the Campaign for Peace—"C" Day—the day of conversion to peacetime manufacture. This is the day that will keynote the struggle of every American business as it makes its bid for existence in the post-war world. Already many materials are becoming less critical. It's time you looked over the qualifications of likely materials for your post-war products. Many will compete for your vote—glass, plastics, wood, aluminum, new alloys, new steels. The choice won't be easy—for the one you elect must provide your product with the most in durability, efficiency and appearance.

If an improved finish can increase the durability, efficiency and appearance value of your product—then McAleer resourcefulness can be of service to you. For many years McAleer service has been characterized by a probing, restless impatience with ordinary finishing materials and methods. Since America's entrance into the war, our efforts to serve industry have led to developments in wartime finishes so far superior to those produced for pre-war products, the contrast is truly amazing.

McAleer's war record of achievement in producing *quality-controlled* finishing materials with an almost unbelievable versatility of applications can only be excelled by the results we are prepared to produce when new and strategic materials are made available for your post-war product use.

No manufacturer concerned about the present or future can afford to overlook the extra values that an improved finish can give his war or post-war product. *OUR HATS ARE IN THE RING . . . for Victory and "C" Day.* We'd like to present the qualifications of our candidates to meet your particular war and post-war finishing requirements.

McAleer MANUFACTURING CO. ROCHESTER, MICHIGAN

Manufacturers of Quality Controlled Finishing Materials Military Aircraft Sub-assemblies and Pyrotechnics . . .

Making these knives was a Problem

UNTIL GRAPH-MO STEEL WAS USED



A manufacturer of skiving knives used to cut synthetic rubber, truck tread cutting knives, paper knives and slitter knives was faced with an aggravating problem. A substantial amount of stock must be machined away to produce the cutting edge. When made of ordinary tool steel they would warp out of shape so badly after they were hardened that many of them had to be scrapped causing a substantial loss in man hours, machine time, and profit.

Graph-Mo steel proved to be the answer to this problem. Knives made of this performance-proven steel showed practically no movement after hardening. The excellent machinability of Graph-Mo steel permitted the knives to be made faster. Its excellent wear resistance permitted the manufacturer to produce tools possessed of remarkably long service life.

Put Graph-Mo steel to work in your shop. It has been the means of licking a multitude of tough tool and die problems. Steel and Tube Division, The Timken Roller Bearing Company, Canton 6, Ohio.

Write today for your free copy of the 48 page illustrated booklet that is full of good sound information, about the five performance-proven Graphitic Steels Graph-Mo, Graph-Tung, Graph-Al, Graph-Sil and Graph-M.N.S.

TIMKEN TRADE MARK REG. U.S. PAT. OFF.
GRAPHITIC STEELS

FRICTIONAL SAWING



With Tannewitz HIGH SPEED BAND SAWS

Delivers the Goods - IN A HURRY!

BULLETINS Worth Writing for:

SHEET METAL CUTTING BAND SAWS

•

SINGLE AND VARIABLE SPEED BAND SAWS FOR FOUNDRY USE


•

BAND SAWS FOR DI-SAWING, FILING and POLISHING

Everywhere industrialists are discovering the tremendous advantages of cutting sheet steel, non ferrous metals and even heat treated steel up to 1" thick with TANNEWITZ HIGH SPEED BAND SAWS. Millions of teeth per minute generate sufficient frictional heat to make the cutting extremely fast, smooth and convenient. Exceptionally strong, perfectly balanced wheels, bydraulic brakes which are automatically applied in case of sawblade breakage, and many other features designed specifically for high speed operation make these machines vibrationless in operation, perfectly safe and trouble-free. They're mighty well worth getting acquainted with. Write for "HIGH SPEED METAL CUTTING BAND SAW BULLETIN."

THE TANNEWITZ WORKS, GRAND RAPIDS, MICH.

MORRISON Metal Stitching decreases assembly time by 70% at CONVAIR



Flight photo of B-24 Consolidated Vultee Liberator

Another big manufacturer—Consolidated Vultee Aircraft Corporatioo—finds that Morrison Aircraft Metal Stitching saves precious manhours in assembliog parts. Note they say the savings amount to 70% *on many parts.*

If *you* are riveting or spot welding Aluminum, Stainless Steel, Plastics, Cork, Rubber, Asbestos, Wood, or Canvas, it will pay you to investigate Morrison Aircraft Metal Stitchers. Machines are available for immediate shipment. Write for Bulletin No 7-A.



CONSOLIDATED VULTEE AIRCRAFT CORPORATION

December 15, 1943

Mr. W. B. Reich
Harry W. Brintnall Company
746 E. 17th Street
Los Angeles, California

Dear Mr. Reich:

Attached are several pictures showing the use of the Morrison Aircraft Metal Stitching Machine at the Vultee Field Division.

Experience here has shown that Metal Stitching has decreased assembly time by approximately 70% on many parts.


The photographs illustrate the Stitcher in use on B-24 Bomber parts.

Sincerely yours,

CONSOLIDATED VULTEE AIRCRAFT CORPORATION
Vultee Field Division
Nelson Morrison
Methods and Controls Manager

Below: stitching a duct at Vultee.





Another of the many parts being metal stitched

MORRISON

PRODUCTS OF THE SEYROLD DIVISION
HARRIS-SEYROLD-POTTER COMPANY
DAYTON 7, OHIO

STITCHERS



LOOKING FOR TROUBLE

TO keep the Allies' supply lines open, to enable us to dispose men, munitions and food where they are wanted, demands utmost efficiency to the last detail.

Aircraft looking for trouble and ready to destroy the menace that comes from under the sea, ships, guided by men ceaseless in their vigilance, dodging this trouble, all are dependent on the absolute reliability of engines both in aircraft and ships.

The job of work Vokes Filters have to do is to ensure that the air, oil and fuel oil servicing engines is free from impurities so that maximum power and speed and complete dependability can be assured. Vokes Filters, under the severest battle conditions in all areas of fighting on land, sea and in the air, have stood up to demands made on them. Exacting tests in nearly three years of war in all branches of the services has substantiated the claim for Vokes Filters —99.9 per cent. FILTRATION EFFICIENCY UNDER ALL CONDITIONS.



TOP—VOKES OIL FILTER FOR AIRCRAFT CONTINUOUSLY REMOVES ALL IMPURITIES TO 0.00004 IN DIA. RESISTANCE NEGLIGIBLE. NO INTERRUPTION OF OIL CIRCULATING.

BOTTOM—VOKES AIR FILTER FOR AERO ENGINES STANDARD TYPE FOR MOST FIGHTING AIRCRAFT.


VOKES

VOKES LIMITED · FILTRATION EXPERTS

THE ARTHUR S. LEITCH CO. LTD., 1123 BAY STREET, TORONTO, CANADA
E. CANTIN, 101 PARK AVE., NEW YORK

3 WORK-SPEEDING FEATURES

make the "Hornet" tops in portable DC welders



1 SIMPLE 'GLOVE-GRIP' CURRENT CONTROL



All current regulation over the "Hornet's" wide welding range is centralized in one convenient, easy-grip hand wheel. Accurately calibrated dial covers "high" and "low" ranges for infinite current settings.

2 FOOL-PROOF POLARITY CONTROL



Only by flicking this switch can polarity be changed from straight to reversed, or vice versa. Accidental polarity reversal is impossible on the "Hornet".

3 FAST RECOVERY, SELF-CONTAINED EXCITER



Extremely fast recovery time exceeding Navy requirements. Simplest, most efficient means of self-excitation is employed on the "Hornet". This close-up shows rectifier and starter.

FAMOUS FOR ITS *Penetrating "Stinger"*

AND THESE OTHER IMPORTANT FEATURES

Throughout industry many important features of the "Hornet" have made it a widespread choice among operators. With its deep penetrating arc and excellent arc characteristics, it has earned the title—"the machine that makes the arc behave", • It starts easily... quickly • has "split-second" recovery • no sticking or "pop-outs" • and has unusually low spatter loss, • It's streamlined in design and easily portable. • All "live" parts are completely shielded.

The "Hornet" is made in 200, 300, and 400 ampere sizes. For complete details call or write any Air Reduction office, or mail coupon for illustrated catalog.

★ BUY UNITED STATES WAR BONDS ★

Send for Free Catalog




AIR REDUCTION


General Offices: 60 East 42nd Street, New York 17, N. Y.
In Texas: Magnolia Airco Gas Products Co. General Offices: Houston 1, Tex.
Offices in all Principal Cities

Air Reduction
60 E. 42nd Street
New York 17, N.Y.

Please send me a free copy of the Wilson "Hornet" Catalog

Name .....
Company .....
Address .....
City ..... State .....






HOLTZER-CABOT

SPECIAL FRACTIONAL HP MOTORS DESIGNED TO FIT THE APPLICATION

If operating characteristics, speeds, hazards, ambients, etc., were always similar for products... standard "off-the-shelf" motors could be used for most cases. However, experience proves that operating conditions do vary in motor applications — and the only way to meet performance requirements is to use a special motor specifically designed to meet operating conditions such as load cycle, speed stability, speed control, reversal of rotation, atmospheric conditions, quietness, etc.

For over 50 years Holtzer-Cabot has concentrated its facilities in the design and application of special fractional HP motors to meet the exacting performance requirements of such products as instruments, aircraft, machine tools, business machines, etc. And although today all of our energies are being utilized in building motors for military products, our motor development engineers will gladly discuss your peace-product motor problems with you.







THE

HOLTZER-CABOT ELECTRIC COMPANY

Designers and Builders of Special Fractional HP Motors and Electrical Apparatus

125 AMORY STREET, BOSTON 19, MASS.

New York, N. Y. • Chicago, Ill. • Philadelphia, Pa.



New aircraft cleaner prevents scale formation on coils and valves of steam-cleaning equipment

In aviation maintenance bases, steam cleaning equipment quickly clogged up with deposits of lime, magnesium and other minerals present in the water. Turco chemists, called on to apply the results of their research, so compounded Steam-Aero that it would sequester (hold in solution) these scale-forming minerals. This method of forestalling precipitation and deposit has also provided steam cleaning guns with a form of insurance against the kicking and sputtering caused by scale. It has cut down equipment servicing time, saved fuel in the making of steam, prolonged the usefulness of the equipment itself.

This is the same sequestration quality that answers the need for elimination of mineral deposits which etch or injure delicate plane surfaces. Steam-Aero has a rich, neutral foam that cleans aluminum as safely as it cleans it thoroughly. It is scientifically balanced so that it rapidly emulsifies oil and grease, and the surface rinses free. It may be used to clean well-bonded paint safely.

Turco technicians saw the importance of producing a high foam with exceptionally tough bubble walls. Tough bubble walls cling better to vertical surfaces, for longer soaking, and operators, accustomed to judging the strength by the foam and inclined to use more of a compound that is flat than one which lathers richly, are not so apt to waste the compound.

It's simple, it's easy to use. Turco Steam-Aero. Half an ounce per gallon of water (slightly more for hard water) is usually all that is necessary. In any concentration, Steam-Aero retains its perfect balance.

Write for free bulletins.

Other Turco Products for Aircraft Maintenance

Mulsinol — for cold water cleaning of surfaces, engines and parts. Used with water alone, or with petroleum solvents, rinses free.

Plasti-Glyst — the safe, fast cleaner for plastic glass. Approved by makers of Plexi-Glas.

Carbrax — cleans pistons fast and thoroughly, removes carbon, varnish, etc.

Panetrol — emulsifies sludge, removes carbon deposits, strips primers and engine enamel.

Fuzee — cleans aluminum cylinder heads, carburetors, etc.

Turco W. O. No. 1 — Government-approved for weather-resistant bonding of aircraft paints in the field.


TURCO Turco

INDUSTRIAL CHEMICAL COMPOUNDS

TURCO PRODUCTS, INC. • Main Office and Factory: 6135 S. Central Ave., Los Angeles 1 • Offices and Factories: 1606 Henderson St., Houston 10, Texas; 125 West 46th Street, Chicago 9 • Offices and Warehouses: New York City, Atlanta, Kansas City, Seattle, Denver, San Francisco, and all Principal Cities

INCREASE YOUR MAN-POWER BY BETTER SELECTION OF . . .

MACHINE-POWER



American industry has about reached the "bottom of the barrel" for man-power. Any required increase in production, therefore, must come from improved efficiency of present workers and their machines.

Alert manufacturing executives have substantially increased production with marked savings in power, capital investment and operating cost—by using fast, streamlined Walker-Turner Machine Tools on hundreds of jobs where heavier and slower equipment had been employed formerly. A few of these "speeder-uppers" are shown on this page. Send for Catalog.

WALKER-TURNER COMPANY, INC.

walker-Turner
COMPANY, Inc.
PLAINFIELD, N.J.
U.S.A.

MACHINE TOOLS

DRILL PRESSES — HAND AND POWER FEED • RADIAL DRILLS
METAL-CUTTING BAND SAWS • POLISHING LATHES • FLEXIBLE SHAFT MACHINES
RADIAL CUT-OFF MACHINES FOR METAL • MOTORS • BELT & DISC SURFACERS



BE SURE IT'S *Right* ON THE NOSE

THE designers, builders and pilots of most American planes rated under 250 h.p. have given their verdict: "Sensenich propellers are *right* on the nose." It's their judgment and acceptance that has made Sensenich the nation's largest manufacturers of wood aircraft propellers. We're proud of that . . . so proud we want to help users be *sure* that every Sensenich propeller is *always* "right on the nose."

INSPECT YOUR PROPELLER


For even a Sensenich propeller needs care and occasional repair. Frequent and careful propeller inspections will help maintain the maximum efficiency and high safety factor built in at the Sensenich plant. Immediately sand and seal with varnish small nicks or bruises. This prevents moisture penetration which destroys balance and may even cause further trouble. In case of more serious damage—deep abrasions, torn fabric, loose metal edging, etc.—send or bring propeller to an approved Sensenich service station. There, experts will restore it to its original condition. Repair facilities are also available at Sensenich's main plant and West Coast branch.

AIRCRAFT SENSENICH PROPELLERS

SENSENICH BROTHERS, *Dept V, Lancaster, Pa.—adjacent to Lancaster Municipal Airport; West Coast Branch, Glendale, Cal.*

GOT A "PROPELLER TIP"? IT MAY BE WORTH $5. If you have a suggestion for propeller care, send it along to Sensenich. Sensenich pays $5 for "propeller tips" used on this space.

THE LADY AND THE TIGER



TODAY in airframe assembly plants all over the country, patriotic women, who have laid away their kitchen aprons to engage in the serious business of winning the war, are skillfully installing the strong steel nerves that control America's finest fighting planes.

In our aircraft cable plants, too, women are helping produce American TIGER BRAND Control Cables. Here, under the guidance of men who have spent years mastering specialized operations, their nimble fingers have been trained to meet the exacting demands of delicate and intricate jobs. To these ladies we owe our record for holding quality of production consistently at highest levels.

The high-quality American TIGER BRAND Control Cables we offer for your use combine ample strength to handle maximum loads with lightness, minimum stretch, excellent flexibility and superior resistance to fatigue, wear and corrosion. Flawless performance is assured by their Excellay Preformed construction — in which individual wires and strands are helically preformed to the exact shape they will assume in the finished cable.

AMERICAN STEEL & WIRE COMPANY
Cleveland, Chicago and New York
COLUMBIA STEEL COMPANY
San Francisco
United States Steel Export Company, New York


AMERICAN Tiger Brand CONTROL CABLES

UNITED STATES STEEL

the *Stabl-Vis* Test Accuracy Rotameter

eliminates

time-consuming weigh-rigs and burettes in testing Aircraft Accessories!




You can test your volume production equipment in "jig" time with the "Stabl-Vis" rotameter. You just "plop" your fixture into the test line and open the control valves—a glance at the meter gives you the ***accurate*** flow rate through the manufactured part.


Expensive, cumbersome weigh-rigs and burettes with their production-delaying time runs are eliminated by the "Stabl-Vis" meter because of its greater speed and accuracy. By means of its patented float design, the "Stabl-Vis" is the only meter that compensates for variations in fluid viscosity and density. So in spite of temperature changes, evaporation, or normal variations in fluid composition, the calibration of the "Stabl-Vis" rotameter "stays put" and it continues to tell your operator ***accurately*** and ***instantaneously*** whether your equipment is up to standard.

The "Stabl-Vis" Test Accuracy rotameter has been widely accepted by the Aircraft Industry. It is being used to test the great majority of aviation engines and accessories that are being produced today. It works equally well on liquids or gases—just a few of the fluids accurately measured are gasoline, lubricating oils, de-icer fluid, hydraulic oils, oxygen, prestone, water, air, blow-by gases, kerosene, diesel fuel, etc. The "Stabl-Vis" rotameter may be obtained as an indicating meter, or with a remote recording chart which gives you a factual record of the test performance of each unit to send to your customers.

For full information, we suggest that you send for our special catalog sections 98-Y and 63-G. Bulletin 98-Y discusses the interesting story and scientific theory behind the "Stabl-Vis" development. Bulletin 63-G describes the various types of "Stabl-Vis" rotameters made especially for the Aviation Industry and is profusely illustrated with applications of this speedy, high-accuracy meter to aircraft testing. Owing to the paper shortage, kindly request these catalogs on your Company letterhead. They are sent free, without obligation.



Carburetor Test Panel with "Stabl-Vis" Test Accuracy Meters



FISCHER & PORTER CO.
307 COUNTY LINE ROAD, HATBORO, PA.

FLOW RATE INDICATING, RECORDING OR CONTROLLING ROTAMETERS FOR ANY LIQUID OR GAS

QUICK QUIZ FOR AIRCRAFT MEN

One of these Answers May Make You a Fortune!



Q Can you put "M P-T"* into your machines?

A Chances are you can. For instance in one plant, large traveling cranes were stopped 17 minutes each shift for lubrication. Alemite Lubrication Specialists recommended a new combination of lubricants and method of application. Time-outs for lubrication were cut to 3 minutes per crane per shift adding 5 hours "M. P-T"* per week. (Another example of the efficiency of one of the new Alemite Centralized Lubrication Systems.)

* More productive time



Q Are your lubricating methods as safe as they could be?

A Maybe. But listen to this: one lubricating job called for the oiler to cross a cat walk, lean over and reach down to get at remote bearings. Alemite Lubrication Specialists recommended a system where all 58 bearings, accessible or remote, are now lubricated easily and safely from three locations and each bearing gets the right lubricant in the right amounts every time. (Tip! This is one of Alemite's new Centralized Lubrication Systems.)



Q Is it possible to put "M P.T" into any size machine?


A Certainly. In this case a battery of small machines was stopped too long and too often for lubrication. Alemite Lubrication Specialists helped to put 12 hours extra productive time each week into the machines by a simple change in lubricating methods. Fifty two weeks times 12 adds up to 624 hours "M.P.T." per year. Have you checked your lubrication time lately?

Can "LUBRI-*chaos*" Rob You of Money, Machines and Production?

It surely can! And "Lubri-*chaos*" is found in the most modern plants. Today, with wartime schedules of production, "Lubri-*chaos*" has shown how it really can cut into plant efficiency.

Alemite, as pioneer in the handling, distribution and application of lubricants has long crusaded against "Lubri-*chaos*." As a result, the modern Alemite methods are now recognized as the answer to "Lubri-*chaos*" in scores of factories all over America.

The Alemite Method, including the new "Colortoule" system of completely organized lubrication, will play an important part in boosting peacetime production to meet competition. Consult with Alemite Lubrication Specialists about readying your machines now to gain the competitive advantages of the world's most modern lubricating methods. Alemite, 1865 Diversey Parkway, Chicago 14, Illinois, in Canada, Belleville, Ontario.




One of Alemite's Centralized Lubrication Systems—an accurate dependable method of lubricating machine bearings no matter how remote from one location. Alemite Systems are available in a number of types to meet the requirements of any machine. Write for complete information.

American Product of STEWART WARNER

ALEMITE

First in Modern Lubrication

CONSULTATION • EQUIPMENT • LUBRICANTS • MAINTENANCE • ENGINEERING



Want to move 35 Tons?

WE wouldn't tell you how fast America's fighting planes go. That's a military secret.

But we've all read it's well over 300 miles an hour.

We've read too how they hit 700 or 800 miles an hour in dives. And how paint was peeled by the air pressure.

Did you ever stop to think that the plane's flaps and controls have to work surely, smoothly and dependably against pressures like that?

It's done by such mechanisms as you see in the picture.

They are called Lear Actuators.

They are powerful. Some can push up to 75,000 pounds.

They are light. That's a "must" in aircraft.

They are small. They have to fit in available space.

A good many preconceived notions had to go by the board to meet all these requirements. For example, the little electric motor that runs them is full of revolutionary engineering refinements.

Every man and every minute we have now can't make all the motors and actuators that we would like to deliver for Uncle Sam's aircraft.

But the day is coming when they will have different jobs to do. New jobs on peacetime products—perhaps like steering ocean liners, or parking cars, or things we've never thought of.

That is one reason for this advertisement. We want to know who can use an actuator or a motor like these.

Another reason is, we want you to know that there is available the kind of thinking and engineering which have produced these and some 250 other Lear products.

Even this small actuator weighing but 3.3 pounds can move 1200 pounds.

LEAR AVIA INC.
PIQUA • OHIO

SR-4
STRAIN GAGE



Tells you what is happening ... when it happens

It isn't necessary—now—to *over*design to assure adequate safety factors where exact service stresses can't be predicted

A device as small as your little fingernail, cemented in place on any plane or curved surface, can tell you exactly *what* is happening . . . *at the instant it happens.* Check your test requirements against this list of jobs the SR-4 is doing.

1 Testing structures or machines under steady load conditions

The SR-4 accurately measures static strains down to 1 part in 2,000,000, (Equivalent to 15 lb sq in stress in steel) and exhibits perfect linearity, even in the plastic range.

2 High temperature testing under steady load conditions

Standard Phenol-resin bonded gages are serviceable up to 500° F and with small loss in accuracy up to 700° F.

3 Testing structures or machines under varying load conditions

The SR-4 handles frequencies ranging from 0 to 30,000 per second, with no loss of linearity.

4 High temperature testing under varying load conditions

No loss of accuracy or sensitivity is entailed. Measurements in the presence of hot oil have been successfully made.

Tests on the production floor or in the field can be made as easily and accurately as in the laboratory. The SR-4 can solve some worrisome problems for you. The Baldwin Locomotive Works, Baldwin Southwark Division, Philadelphia, Penna., U. S. A.

Bulletins NOW READY!

- **No. 165**—Torquemeter
- **No. 169**—Portable Strain Indicator
- **No. 170**—Strain Recorder
- **No. 171**—Applications
- **No. 172**—Scanning Recording Equipment
- **No. 174**—Applications to Shipyard Problems
- **No. 175**—Bonded Resistance Wire Strain Gage

BALDWIN
SOUTHWARK
TESTING EQUIPMENT



"Just Keep Her Headed North, Dear
—and Wake Me When Home's In Sight"


THERE HE IS, heading home from a weekend spent with his son and his wife . . Or from a dreamed-of vacation spot too far away to visit in two weeks before the war. But, in that plane of tomorrow he'll be taking wings for granted and laughing at long distances.

A man will think nothing of catching a nap in the sky while the wife takes the wheel. For an instrument panel by Stewart-Warner, as simple as the Stewart-Warner panel in the car, will tell her at a glance all that she needs to know.

When the needs of war are filled, the "know-how" that has given our fighting men the finest planes aloft can quickly give us planes that meet the needs of peace equally well. And Stewart-Warner will be ready with the needed instruments . . embodying the rugged simplicity and dependability that put Stewart-Warner instruments into many million pre-war vehicles, and more recently into everything from non-combat planes to PT boats.

With such instruments as their guides, American families will take their post-war wings for granted. This goal of safe, low-cost flight for everyone, toward which the aviation industry has steadily advanced, is just over the horizon in peaceful skies.

INSTRUMENTS BY
STEWART-WARNER CORPORATION
CHICAGO ILLINOIS



Great Pictures of the War . . . made with Fairchild CAMERAS



Official U S Navy photograph

An old story to camera fans is the above famous Pearl Harbor picture. But surprising news to most folks is that it was made not with a standard *still* camera . . . but with a Fairchild precision *aerial* camera!

Action shots on land and sea, as well as from the air, are made with Fairchild cameras Why? Because no matter how swift the action . . . no matter how far from the photographer it may recede . . . the Fairchild camera still gets accurately detailed close-ups

With focal lengths up to 60-inch, Fairchild cameras could make recognizable shots of your living-room furniture from two miles up . . . and do it in the black of night as well as in the light of day.

These are the reasons why many great pictures of the war, on land and sea too, are made with Fairchild precision aerial cameras




Destroying Jap planes in Marianas Islands — a Ziff-Davis Pub Co. photo — one of a series also taken with a Fairchild Aerial Hand Camera

Fairchild CAMERA AND INSTRUMENT CORPORATION

88-06 Van Wyck Boulevard, Jamaica 1, N. Y. • *New York Office:* 475 Tenth Avenue, New York 18, N. Y.

THE STORY OF AERIAL PHOTOGRAPHY IS THE STORY OF FAIRCHILD CAMERAS



PLANES IN FLIGHT

"Out of the West at break of day,
Bringing to Germany fresh dismay,
The affrighted air with a shudder bore
The terrible grumble and rumble and roar,
Telling the battle was on once more."

Out goes the call, "Crush Germany with air power," and thousands of planes take off to obey the command. Through the clouds by day — through the black of night they wing their way—aided by electronic devices powered by Leland high frequency inverters.

Sturdy, dependable Leland DC motors unfailingly lift their landing gear to speed their flight, and as surely lower it to assure a happy landing. Still other Leland equipment helps to furnish power for ground radio and phone communications and for testing of vital aircraft instruments.

Proud, indeed, is Leland to play a part in today's tremendous drama. Equally gratifying will be the privilege of supplying expertly engineered electrical equipment to industry in days to come.

THE LELAND ELECTRIC COMPANY
DAYTON 1, OHIO

Leland ELECTRIC MOTORS

CREATIVE ELECTRICAL ENGINEERING

CHAMBERSBURG CECOSTAMP



THE Cecostamp continues to blaze new trails in the formation of the tough, springy sheets of lightweight, hard-to-form metals used in the production of aircraft and other modern equipment. Having the ability to produce even intricate shapes in sheet metal without tearing, wrinkling or stretching, the Cecostamp opens up new fields in the formation of sheet metal parts for use in the limitless post-war market. New applications are constantly being made by Cecostamp users, many of which have been photographed and described, and are now a part of our files. Perhaps you are working along similar lines. If you would like to see some recent developments, please write us.

CHAMBERSBURG ENGINEERING CO. • CHAMBERSBURG, PA.



DATA ON PHOTOGRAPH


This photograph shows an excellent example of multiple die work, utilizing the full bed area of a 48" x 48" Cecostamp. The die is accurately balanced; and the part, a 24SO Aluminum fairing, is made in two blows. The first blow is a hard one that forms the part without wrinkles. The second blow is a lighter one to combat any effects from air pressure confined in the trapped die. With this dual-impression die, the Cecostamp is actually forming one part per blow. Incidentally, this particular Cecostamp die has eliminated the necessity for a skilled operator and the need for rubber pads in forming this part.




IN HUCK BLIND RIVETS


The Pin Is Secured to the Sleeve by a


Positive MECHANICAL LOCK





Huck Blind Rivets are available in 1/8", 5/32" and 3/16" diameters with AN456 Brazier, 78° Modified Countersunk and 100° Countersunk Heads





One driving operation not only fills the hole and forms the blind rivet head but also automatically extrudes the locking collar to form a conical keystone lock and breaks off the pin at the breaknock groove as illustrated.

RESULTS OF COMPARATIVE TESTS

PERTINENT DATA (HUCK BLIND BRAZIER HEAD RIVETS (AN 456 HEAD-TYPE)

Rivet diameter 5/32" Sheet material . . 24ST Alclad
Hole size . . . No 21 drill (.159) Edge distance 2 x rivet diameter
Single Shear, Single Rivet Specimens

ALLOWABLE DESIGN LOAD BASIS (SOLID CONVENTIONAL RIVETS PROTRUDING HEAD TYPE)

CONVENTIONAL SOLID A17ST RIVET
Shear—30,000 p.s.i.—based on hole area
Bearing value in 24ST Alclad sheets—100,000 p.s.i.

CONVENTIONAL SOLID 17ST RIVET
Shear—34,000 p.s.i.—based on hole area
Bearing value in 24ST Alclad sheets—113,000 p.s.i.

Allowable design loads for solid rivets are based on rivet shear or bearing values, whichever are the lower.

SHEET THICKNESS (Actual)	ALLOWABLE ULTIMATE DESIGN LOAD SOLID CONVENTIONAL RIVETS		ACTUAL ULTIMATE LOAD HUCK BLIND RIVETS				% GAIN DUE SOLELY TO LOCK
			With Lock		Without Lock		
	A17ST	17ST	Ultimate Load-Lbs.	*Type Failure	Ultimate Load-Lbs.	*Type Failure	
.073	596	675	779	R	706	R	10.3
.063	596	675	802	R	689	R	16.4
.051	596	675	757	R	519	T	45.9
.041	596	675	683	R	447	T	52.8
.031	509	575	591	S	362	T	63.3

*Type of Failure R-Rivet in shear T-Rivet in tension, S-Complete shear failure

BECAUSE of a positive mechanical lock between the pin and sleeve, there is never a possibility of the pin of a Huck Blind Rivet working out under any conditions of fatigue loading or vibration. Once driven, a Huck rivet becomes the equivalent of a one-piece solid rivet, with greater ultimate shear strength than conventional A17ST (Type AD) or 17ST (Type D) "icebox" solid rivets in joints normally critical in shear as well as in thinner sheets critical in bearing.

With no lock other than friction, a two-piece blind rivet will, in thin sheets, become critical in tension and fail at loads very substantially lower than the allowable bearing loads of the sheets even though such bearing loads are less than the allowable rivet shear load.

Shown at the right are the results of tests which illustrate the great increase in allowable shear loads in thinner sheets resulting from the increased rivet tensile strength brought about by the Huck positive mechanical lock. Figures shown are the average of five tests.

Huck MANUFACTURING COMPANY
Specialists in Aircraft Riveting Processes
2474 BELLEVUE AVENUE • DETROIT 7, MICHIGAN



"Pillows" of steel tubes make soft landings

Greatest strength with the least weight is the contribution SHELBY Seamless Tubing makes to this bomber landing gear.

WHEN a 12-ton bomber sits down, she needs steel "pillows" to cushion the shock. Tubular steel landing gear has the strength, rigidity, and endurance and is so designed that it absorbs the shock of bumpy landings on any front.

When you say *any* front in this war, you take in a lot of territory. The problems introduced by 50 below zero temperatures in the north, sand storms in the desert, and corrosive atmosphere in the jungles, call for tubes with special properties. The trick is to produce *one* steel that resists heat, cold, abrasion, corrosion, fatigue, shock, vibration and plain wear.

SHELBY Seamless Aircraft Tubing has the necessary physical characteristics. You can obtain it in proper alloys to meet specific conditions. Any size is available in the standard forms.

All types and sizes are made strictly in accord with government specifications for such parts as engine mounts, wing spars, fuselage struts, longerons and vital parts of landing gears. Write for further information.

STEEL NEEDS SCRAP NOW
—SEND IT IN!

NATIONAL TUBE COMPANY
PITTSBURGH, PA.

Columbia Steel Company, San Francisco *Pacific Coast Distributors* United States Steel Export Company, New York

USS

UNITED STATES STEEL



Precipitron KEEPS AIR FROM "SCRATCHING" SUPERFINISHED SURFACES

A NEW PRINCIPLE FOR CLEANING AIR

Dirt, smoke and soot—

passes through an electrostatic field

receives a positive (+) charge

and is drawn to a collection plate of opposite polarity (−)

where it remains until flushed down the drain.

Scratching superfinished surfaces means costly rejects. Air-borne dust and dirt can cancel the productive results of irreplaceable man-hours, increase costs and waste precious materials.

Precipitron* is your protection against this damage. This Westinghouse electronic method of cleaning air is the most efficient yet developed—90% more effective than mechanical methods. Precipitron removes foreign particles as small as 1/250,000 of an inch. Even tobacco smoke, most difficult of all air-borne matter to remove, is effectively captured on Precipitron collector plates.

If protection for your precision work calls for *clean* air be sure to get all the facts about the Precipitron. Full details of its application and low-cost operation can be obtained from your nearest Westinghouse office. Or, write Westinghouse Electric & Manufacturing Co., Dept. 7-N, East Pittsburgh, Pa. J-04007

*Trade-mark registered in U.S.A.


Westinghouse Precipitron *the Electronic Air Cleaner*

PLANTS IN 25 CITIES OFFICES EVERYWHERE

HYCON

REGISTERED TRADE MARK





Hydraulic Units Assemble into 3000 p. s. i. Test Equipment and Benches

3000 p s i. Cylinder Test Bench Manufactured by Accmatool Corp. of New York, N. Y.

PUMPS
ACCUMULATORS
PRESSURE METERING VALVES
4-WAY VALVES
UNLOADING
AND RELIEF VALVES



Specifications and Engineering Data on Request

THE NEW YORK AIR BRAKE COMPANY

Hydraulic Division

420 Lexington Avenue, New York 17, N. Y.

NEW MIRACLE SAW

Cuts Magnesium, Aluminum and Non-Ferrous Metals *Faster!*



● A stumbling block to industry's use of non-ferrous metals during the important war years has been the difficulty of cutting them rapidly.

Now that problem is solved by the new DoALL Buttress Band Sow, developed in the DoALL Research Laboratory to cut Magnesium, Aluminum Zinc, Brass, Copper, Monganese Bronze, Tempaloy Bronze, Gray Cast Iron, Kirksite, Wood, etc.

MAGNESIUM

Approximate size 10 x 12 x 18". Cut at the rate of 100 square inches per minute with this new DoALL Buttress—5 to 7 times faster than with usual metal saws.

ALUMINUM

Riser Rings from Ford Castings, sand-heat treated. Cut at the rate of 90 square inches per minute. The new DoALL Buttress lasted for 108 cuts, a production increase of 400%

SILICON ALUMINUM—30 to 33 square inches per minute.

14 ST ALUMINUM—24 square inches per minute

ALUMINUM ARMOR PLATE 5/16"—25 to 30 lineal feet per minute

ALUMINUM 24 ST 1"—160 square inches per minute



DoALL Buttress
TRADE MARK REG.

The spectacular new band saw that has been tried out recently in a dozen large aircraft and other war plants with unheard-of-before results. Not only does smoother cutting, but does the work in 1/10 to 1/5 the former time. Fits any band sawing machine.

NO SHARPENING REQUIRED

Use the DoALL until worn out, then insert a new saw

IMMEDIATE DELIVERY from all our Supply Points. Write for Literature and Prices.



DoALL

INDUSTRY'S NEW SET OF TOOLS

Send for Illustrated Literature

THE DoALL COMPANY

1232 Thacker St. Des Plaines, Ill.

Sales & Service Offices: Baltimore, Boston, Chicago, Cincinnati, Dayton, Detroit, Erie, Hartford, Indianapolis, Los Angeles, Milwaukee, Minneapolis, New Orleans, New York, Orlando, Philadelphia, Pittsburgh, Rochester, Rockford, St. Louis, San Francisco, Seattle, Toledo, Tulsa, West Hartford

HOW TO MAKE PERMANENT ELECTRICAL CONNECTIONS

permanent

INSERT
STRIPPED CONDUCTOR INTO HYDENT CONNECTOR BARREL

INDENT
CONNECTOR TO WIRE WITH BURNDY HYTOOL

INSTALLED
permanently
RESISTS LOOSENING INDEFINITELY



When you indent a HYDENT connector to a wire, you eliminate all doubt about the strength and permanency of the connection and its ability to resist loosening even under severe vibration. You *know* it's a permanently sound connection, because simple indenting compresses conductor barrel and wire into virtually one strong homogeneous whole. Further, the HYDENT connector is of pure copper one-piece construction, a feature which eliminates all extra contact surfaces, thereby assuring maximum electrical conductivity.


You'll find indenting a real time-saver, too, both for production and maintenance needs. Ask us to send you full details today.



Headquarters for CONNECTORS

Burndy

BURNDY ENGINEERING CO., INC.
107 BRUCKNER BOULEVARD, NEW YORK 54, N. Y.
IN CANADA Canadian Line Materials, Ltd., Toronto 13



Air Force + Airfields = Air Power

With incredible speed America built an air force—in quality the finest ...in number the greatest the world has ever known.

Early in this global war it was painfully apparent that something else was needed to translate air force into air power.

The world's finest air forces flying the world's finest war planes could not carry the battle to Rome, Berlin and Tokyo without speedily installed and highly mobile air bases from which to operate—always within fighting range of the retreating enemy.

In a little more than one month after Pearl Harbor, Butler factories began producing pierced steel landing mat. Shortly thereafter Gen. H. H. Arnold, Head of the Army Air Corps, called it "the year's greatest achievement in aviation."

Since then a hundred thousand tons of steel have streamed into Butler factories to be made into steel landing mat. Sailors and soldiers have laid millions and millions of feet of it into airfield landing strips around the globe.

This is but one reason why Butler Built Steel Products are in short supply. Other thousands of tons of steel are still leaving Butler factories in the shape of combat hangars, truck and trailer tank refueling units, task force steel buildings, machine shops, supply depots, aviation gasoline storage tanks, and other equipment designed to make airfields as mobile as a circus

BUTLER MFG. COMPANY
Kansas City 3, Mo.
Galesburg, Ill. Minneapolis 14, Minn.
Sales Offices—Washington, Chicago, Atlanta, Shreveport

BUTLER BUILT
STEEL BUILDINGS





FREE BOOKLET
HANGARS
Emerging from war production are Butler Steel Hangars for every airport need. Send for this booklet.

BUTLER MANUFACTURING CO.
7406 East 13th St., Kansas City 3, Mo.
906 Sixth Ave., S. E., Minneapolis 14, Minn.

Name_____
Firm _____
Address_____
City_____ State_____



UNITED STATES ELECTRICAL TOOLS

Fine quality is a living tradition with us . . . . . not a bit of wishful reminiscence of the past . . . . . but an ever-present rule of today . . . . . exemplified in every product we make for war or civilian use.

THE U S LINE is the broadest and most complete on the market, backed by a four guarantee, electrically and mechanically correct. All tools are subjected to the most rigorous tests throughout production and before shipment

PORTABLE SCREW DRIVERS AND NUT SETTERS

For production, maintenance, construction. Standard models furnished with positive clutch, normally held in "open" position engaged by pressure on tool and released when screws or nuts are driven up tight. Can be furnished with slip clutch attachment. Bits, locked in place by a spring pressed ball, are equipped with a "slot finder", also with removable blades. Ball bearings.

The Good Mechanics' Choice

Write us . . . some models available for reasonable delivery dates.

The UNITED STATES ELECTRICAL TOOL Co.
CINCINNATI, OHIO

AC CERAMIC AIRCRAFT SPARK PLUGS

FIRED THE FOUR WRIGHT R-3350 ENGINES OF THE "CONSTELLATION" IN ITS RECORD COAST-TO-COAST RUN

April 17 — Burbank, California to Washington, D. C., — 6 hours, 58 minutes)

TWA's huge C-69 "Constellation" broke all transcontinental speed records for transport ships on its April 17 run to the Washington airport. The Wright-powered Lockheed, world's largest land-based transport, averaged 355 miles an hour.

AC ceramic aircraft spark plugs, of a design pioneered by AC and similar to that of the AC plugs widely used by the Army Air Forces, were selected for the run.

Thus, the pioneering in aircraft spark plugs which began when AC was the exclusive builder of ceramic plugs for the Liberty engines of World War I—and which included service with Lindbergh, Maitland, Acosta, Byrd in their record-breaking flights—continues. Back of those "Constellation" plugs, back of the AAF plugs, is 35 years of "know-how" which again proves its value in record-breaking service.



AC

AIRCRAFT SPARK PLUGS

DO MORE THAN BEFORE— BUY WAR BONDS NOW!



ALL THAT'S SOAKED UP IS NOT GRAVY

PETROLEUM products, for example, may be absorbed by the thousands of resilient parts in a plane—oil seals, hose, accumulator bags, packing, gaskets, grommets, diaphragms—just as gravy is absorbed by bread. This absorption either adds dead weight not included in the original design calculations, or swelling of the liners reduces the capacity of hose, accumulator bags or other similar parts.

Hycar synthetic rubber with its light weight and superb resistance to oil to keep it light, provides protection against increased weight and decreased capacity not offered by any other comparable material. Hycar is 15% to 25% lighter than many other synthetic rubbers and retains this important quality throughout its long life. Oil-swell can be controlled closely to insure dimensional stability of parts.

Hycar has an operating range of −65° to +250° F. and abrasion resistance 50% better than natural rubber. Unlike many other oil-resistant synthetic rubbers, Hycar has a minimum tendency to cold flow after taking the initial deformation, even at elevated temperatures.

You need these qualities in resilient materials used in the presence of oil and gasoline. Let our technical service staff help solve your individual problems. *Hycar Chemical Company, Akron 8, Ohio.*

Hycar

Reg. U.S. Pat. Off.

LARGEST PRIVATE PRODUCER OF BUTADIENE TYPE

Synthetic Rubber

IT'S *Fluid Power* THAT OPERATES A TRAIN


On railroads Fluid Power is used for everything from blowing the whistle to stopping the train. And it is only with Fluid Power that all brakes can be controlled from the cab.

Fluid Power is transmitted through tubes. Brake pressure is delivered to every car without shafts, gears, belts or pulleys.

This method of providing force where it is needed has many advantages. With Fluid Power you can move tons or squash a bug on a watch crystal!

Fluid Power is easy to control. Parker Engineered Systems are performing a host of different tasks in a wide variety of industries. Applications of Fluid Power seem almost limitless.

If you need power for drive or control, it will pay you to investigate the advantages of Fluid Power. It may hold your answer to better postwar products. A Parker Engineer will be glad to give you complete details.



INVESTIGATE FLUID POWER

Parker has engineered Fluid Power Systems for the chemical, marine, aircraft, petroleum, machine tool and other industries. New uses are constantly being developed. A Parker Engineer will know how Fluid Power can serve you. Ask him. Or address The Parker Appliance Company, 17325 Euclid Avenue, Cleveland, 12, Ohio

THE PARKER APPLIANCE COMPANY

CLEVELAND LOS ANGELES

FLUID POWER ENGINEERING



HEY! LEAVE THAT "PUTT-PUTT" ALONE


No soldier, you don't have to monkey around with that Homelite Portable Gasoline-engine-driven Generator.

You don't have to check the oil level . . . the oil is mixed with the gasoline and fresh, clean oil sprays over all moving parts at each revolution. For the same reason, there's no need to shut-down the unit to change oil . . . there's no oil sump to collect sludge.

The engine is air cooled . . . so there's no water level to be checked.

No adjustments are required when the load on the generator changes . . . a simple built-in governor automatically keeps the engine at a constant speed.

When it comes to operating electric tools, floodlights, landing field marker lights, or even radio equipment . . . this simplicity of operation has proved an important advantage to all the branches of our armed services. Less time is required to keep the Homelite generators operating . . . more time can be given to the number one job . . . winning the war.




Everything in a bomber or around an airport must go like clock-work. The less time devoted to monkeying around equipment the more time there is for combat. Homelite Engineers always keep this fact in mind and they have done everything possible to give the Air Force gasoline-engine-driven generators that are not only lightweight, easily portable, but *rugged and dependable* . . . units that need no babying, tampering or constant fussing around regardless of working or climate conditions.



HOMELITE CORPORATION
PORT CHESTER, NEW YORK

the black widow carries a deadly sting





A DARK shadow streaks across the night sky. A newcomer enters the battle on the side of Democracy. Bearing a lethal sting, the Black Widow, America's newest night fighter, packs the power to destroy anything that flies. Swift as an arrow, formidable as its famed namesake, this new ship, designed by Northrop, in co-operation with the Army Air Force's Matériel Command, promises a deadlier weapon to the men who are bringing victory to the United Nations.


And in the Pratt & Whitney engines that drive this most powerful of all pursuit planes are Foote Bros Gears—gears that of necessity meet new standards in metallurgical and dimensional perfection.

The Black Widow forecasts a new conception of design for the world of tomorrow—an era where high speed, the demand for greater efficiency, will find new uses for high precision gears. The engineering skill, production technique, manufacturing know-hows that have made possible the mass production of gears of such high precision may suggest applications in the development of machines you are designing for a world at peace.

FOOTE BROS GEAR AND MACHINE CORPORATION • 5225 S. Western Blvd., Chicago 9, Ill.









FOOTE BROS.
Better Power Transmission Through Better Gears



When the winds blow cold Exides always come through

A former Exide employee, now in the Armed Forces, wrote us this letter:

"I am up here on the top of the world where the gales blow and the snows pile high. We are completely isolated from the rest of the world. Our camp is on the shore of a fjord in Greenland. Up here in this sub zero weather, a battery is put to an extreme test and Exides always come through."

☆ ☆ ☆ ☆

Exide AIRCRAFT BATTERIES

EXIDES are not winning the war single-handedly. But we are proud that we are contributing in a small way to final victory.

THE ELECTRIC STORAGE BATTERY COMPANY, Philadelphia 32
Exide Batteries of Canada, Limited, Toronto



O W I's new Export Seal may be used in any shape or size—in any language—alone or combined with your company trademark or nameplate. O W I does not sell this Export Seal. Purchase may be made from a source of the exporter's own choice.

and tell it with MEYERCORD DECALS

Millions of non-lend-lease items exported throughout the world, a basis for incalculable wartime and postwar goodwill—now can be uniformly identified as "made in the U.S.A." — with this new, official red, white and blue Export Seal designed and recommended by the Office of War Information.

Investigate Meyercord Decals for the reproduction of Export Seals or combination Seals and regular trademarks or nameplates. They provide highly legible product identification that last for the life of the product. They save time, cost, weight and metal, and require no screws or rivets for application. They are durable, washable, and can be produced in any size, colors or design . . . for application on rough, smooth or crinkled surfaces of any known commercial material. Billions are used all over the world.

Tell the world "It's from the U.S.A." — and use Meyercord Decals for low-cost reproduction of a multi-language program of product identification. Let us suggest combinations of the Seal with your own trademark. No obligation. Address Dept. 5-7.



The nameplate illustrated demonstrates one of many ways in which the O. W. I. Export Seal may be combined with your own trademark economically with Meyercord decals.

This advertisement is published in cooperation with the Office of War Information. Full information regarding O.W.I.'s Export Seal Program may be obtained by writing to: Special Promotion Division, Office of War Information, 250 W. 57th St., New York (19), N. Y.



the MEYERCORD CO.

5323 WEST LAKE STREET • CHICAGO (44) ILLINOIS

WORLD'S LEADING DECALCOMANIA MANUFACTURER



Photos courtesy of Pan American World Airways

WHITING HANDLING EQUIPMENT AT WORK—

at Pan American World Airways

Whiting wing jacks are used in servicing Clippers and many other planes in the Pan American World Airways hangar at Miami, Florida. For understanding cooperation in the solution of your handling, loading, or maintenance problems, consult Whiting Collateral Engineering Service. Whiting engineers offer you the benefit of over half a century of experience in the development of specialized equipment for the industry.


WHITING
CORPORATION

Main Office and Plant: 15699-0 Lathrop Ave., Harvey, Ill.
Western Offices 1151 S. Broadway, Los Angeles 15, Calif. Canadian Subsidiary Whiting Corporation (Canada) Ltd., Toronto, Ontario
Branches Offices in New York, Chicago, Buffalo, Birmingham, Pittsburgh, Detroit, Cincinnati, St. Louis, and Washington, D. C.

• AVIATION DIVISION •

THE GENERAL TIRE & RUBBER COMPANY OFFERS

Engineered Control of Vibration To Improve Any Moving Product



THE GENERAL SILENTBLOC

Is Used as a Vibration Insulator . . . As a Trouble-Free Torque Bearing . . . As a Bearing Cushion to Correct Misalignment



GENERAL SILENTBLOC is made of three main members—1. Straight or flanged tube 2. Rubber cushion ring. 3. Inner sleeve or solid shaft. Rubber is inserted in tube under high pressure, then sleeve is "shot" through rubber ring with terrific force. Extreme pull of elongated rubber produces indestructible cohesion of parts. Each Silentbloc design is engineered to give needed deflection in all planes.

If your product moves, has working parts or can be harmed by foreign vibration—General Silentbloc can improve its efficiency, lengthen life and lower maintenance.

Silentbloc is not a "piece of rubber" stuck in because it is resilient. These shear-type mountings, bearings and couplings are engineered in shape, size and design to give the exact performance that solves your particular problem.

In its various forms, Silentbloc can do three things:

1. *Damp vibration or insulate against it.*
2. *Give trouble-free torque action.*
3. *Correct for misalignment in bearings or shafts.*

The predictable operation of Silentbloc comes from its patented principle of elongation and confinement of the rubber.



Our skilled engineers can fit Silentbloc to your job by varying its size and design, the elongation, the distortion of inner and outer diameter of the rubber, the type and modulus of the rubber. The stretched rubber stays alive even when not in motion.

Silentbloc has proved its advantages in many fields—war material, automobiles, aircraft, industrial and home machinery, electrical and electronic equipment. It can improve your product. For fuller information, write The General Tire & Rubber Company, Dept. 80, Wabash, Indiana.

THE GENERAL TIRE & RUBBER CO.
Mechanical Goods Division, Wabash, Indiana

The GENERAL SILENTBLOC
MOUNTINGS . . . BEARINGS
COUPLINGS

A THOROUGHLY

ACCIDENT PROOF SAFETY NUT



Pats. Pending

A

The Unbrako Internal Wrenching Lock Nut, Illustration A, is a truly superior safety lock nut for primary connections on aircraft. The locking feature is provided by two vulcanized fibre plugs inserted internally through the body of the nut as shown by Fig. 1. Fig. 2 shows how these plugs contact four threads of the bolt, thereby assuring a lasting and dependable locking grip.

Other features of the Unbrako Internal Wrenching Lock Nuts are their decidedly greater bolt thread length, due to the ingenious manner in which the fibre locking plugs are inserted. The construction of the nut is such that decidedly higher Rockwell hardness can be had, without in any way interfering with the locking means. The nuts have especially long life before the torque falls below the minimum set up by Wright Field.



1

2

B

Reg. U. S. Pat. Off.

UNBRAKO

Illustration B shows our popular "Flextac" Nut, for the aircraft industry. Pats. Pending

INTERNAL and FLUSH HEAD BOLTS

"Unbrako" Internal Wrenching Bolts and 100° Flush Head Close Tolerance Bolts, Illustrations C and D, fully meet the high degree of precision demanded by the aviation industry. They are being manufactured in our largest department where equipment is of the finest and workers are highly skilled and experienced in making precision aircraft engine parts. These bolts have the famous "Unbrako" qualities of strength and accuracy while due to their internal wrenching feature they facilitate compact designs and save thereby material, weight and cost.



C


D


National Aeronautical Standard

STANDARD PRESSED STEEL CO.

JENKINTOWN, PENNA., BOX 568 BRANCHES: BOSTON · DETROIT · INDIANAPOLIS · CHICAGO · ST. LOUIS · SAN FRANCISCO


Electronic Heating Increases Use and Extends Applications of PANELYTE* COMPREG





One of the new high frequency units, used in production of Compreg Propeller Blades and Wing Spars — speeds "curing" time. Prevents heat checking of material by supplying uniform heat throughout.

This popular R.C.A. advertisement featured electronic heating apparatus used in manufacture of Compreg



PANELYTE Compreg Propeller Blades — rotary cut veneer impregnated with phenol-formaldehyde. It possesses extremely high tensile, compressive and flexural strength. Carving is done by Engineering Research, Riverdale, Md.

This laminated resinous plastic with wood veneer base is superior to wood in dimensional stability, strength uniformity and resistance to moisture and decay. Panelyte Compreg is superior to light alloys in weight saving and resistance to fatigue failure, erosion and corrosion.

"Gluing by radio waves" cuts "curing" time from hours to minutes — saving production time and costs.

Compreg is preemiently suited to all structural beam applications, within sizes available in the material. Compreg's early use in circuit breaker rods indicates its adaptability in electrical design. Compreg is also a good heat insulating material, and this, coupled with its high strength, makes it ideal for supports in magazines and cold storage units in ships. It prevents heat conduction from deck plates and bulkheads, which occurred when steel supports were used.

Samples and full technical data immediately available.

*Mass production of sheets, rods, tubes, molded forms and fabricated parts in paper, fabric, wood veneer, fibre glass and asbestos base thermo-setting plastics.

PANELYTE *the structural plastic*

PANELYTE DIVISION
ST. REGIS PAPER COMPANY
230 PARK AVENUE
NEW YORK 17, N. Y.

Sales Offices: Atlanta, Boston, Chicago, Cincinnati, Cleveland, Dallas, Denver, Detroit, Kansas City, Los Angeles, Montreal, New Orleans, St. Louis, St. Paul, San Francisco, Seattle, Syracuse, Toronto, Trenton, Vancouver

* MASS PRODUCTION OF SHEETS, RODS, TUBES, MOLDED FORMS, FABRICATED PARTS

PRIME PARTS MAKER
for Prime Contractors


On battlefronts throughout the world, allied paratroopers' lives depend on parachute buckles made in Arnolt plants. Skilled craftsmen, using the most modern machinery, fabricate these buckles to high standards of precision, and predetermine the strength of each to insure an ample reserve of safety. Recently increased plant facilities have made Arnolt a prime source for a diversified list of parts used in automotive, aviation, and marine equipment. Write for a copy of the Arnolt brochure, "Manufacturing Facilities for the War Program."



Peacetime Builders of SEA-MITE MARINE ENGINES

Back the Attack BUY MORE WAR BONDS

ARNOLT MOTOR COMPANY, Warsaw, Indiana
Associated with
ATLAS STEEL AND TUBE COMPANY • MANCHESTER-ATLAS COMPANY
SOUTH BEND MACHINE WORKS • • PERU ENGINEERING PRODUCTS



Altair POWER BRAKE VALVES —the valves with the "honest feel"—give pilots the same pedal reaction as in manual systems since the braking effect is directly proportional to the force applied. This "feel" of direct pressure application is achieved by elimination of spring resistance, pilot-effort being resisted by hydraulic pressure. Should the pressure fail the pedal will depress with no load, thus giving the pilot immediate pressure-loss warning.

Altair Hydraulic Brake Valves incorporate positive seating poppets which eliminate leakage. They offer the further advantage of being quickly adjustable *externally* by means of the leaf spring lever. The valves carry yellow-dot winterization and seal of weight approval.

Additional production capacity is available on Alrair Brake Valves. Write today for engineering and installation data. Pacific Division, Bendix Aviation Corporation, North Hollywood, California. Sales Engineering Offices in New York City and Dayton.

Pacific Division
Bendix Aviation Corporation




THE BRAKE VALVES WITH *the honest feel!*

SOCIETY OF AERONAUTICAL WEIGHT ENGINEERS, INC. WEIGHT APPROVED

VICTORY BUY WAR BONDS STAMPS

Bendix Aviation Corporation DESIGNERS AND MANUFACTURERS OF RADIO AND HYDRAULIC EQUIPMENT—OUR PART OF THE INVISIBLE CREW

© 1944 Pacific Division Bend • Av



BRIGGS REPORTS

on One Billion Dollars in War Orders

—and how the money is being spent

During peacetime, Briggs Manufacturing Company is the Nation's largest independent automobile body manufacturer. In the war Briggs is devoting its peacetime skill to making bodies and parts for medium tanks and aircraft, also, bomber turrets, droppable gas tanks and non-ferrous castings.

Briggs war orders total approximately $1,000,000,000. This money has been spent or is being spent as indicated in the box shown herewith. Percentages are based on distribution of Briggs 1943 sales dollar.

53.6%	to about 40,000 employees for wages and salaries.
0.2%	for executive salaries.
32.1%	to some 2,000 subcontractors for materials, supplies and assemblies.
1.9%	to stockholders for dividends.
9.2%	for taxes.
1.2%	for depreciation.
1.2%	for reconversion expenses and other costs arising from the war.
0.6%	left in the business

In 1943 Briggs did twice as large a dollar volume of business as it did in an average peacetime year. In 1943 Briggs delivered double the number of tank hulls delivered in 1942. In the same year Briggs delivered to the U. S. Army and Navy more than 22,500,000 pounds of airplane sections, as compared with 7,000,000 the year before. This included almost twice as many bomber fire-power turrets as in the previous year. Total shipments to date of airplane sections by Briggs exceed 45,000,000 pounds.

Earnings by Briggs hourly paid employees in 1943 averaged $3,159.00. On December 31, 1943 there were 39,312 people on the Briggs payroll, of which 21,737 were men and 17,575 women. This is 48% greater than on December 31, 1942 when Briggs payroll was 26,401 people.

In the first five months of 1944, shipments of airframe sections, by Briggs, were at considerably greater monthly rates than during any other months since the war began. Production of tank hulls was almost equal to the 1943 rate. Deliveries of auxiliary gas tanks, for the first five months of this year, were 7 times the total for 1943, and shipments of aircraft fire-power turrets were at a rate almost twice that of last year.


Unless very extraordinary developments take place, Briggs 1944 war business should be equal to, or exceed, its record 1943 year.

During the war, Briggs has shown that experience in manufacturing good automobile bodies, plumbing ware and non-ferrous castings has enabled it to turn out good bodies for bombers, fighters, tanks and other war requirements. Briggs is glad that it has been able to play an important part in the Nation's war effort. All of its facilities and energies will continue to be available to the Armed Forces until Victory has been won.


However, when Victory does come, Briggs is prepared to go about the job of reconversion with the same dispatch and intensity that it applied to the preparation for war, and, if it is allowed to do so, can go back into at least some peacetime production quickly.

W. O. BRIGGS
Chairman of the Board

W. P. BROWN
President



BRIGGS MANUFACTURING COMPANY
DETROIT





. . . and Thread Gages, *too!*




VINCO CORPORATION, 8855 SCHAEFER HIGHWAY, DETROIT 27, MICH.

SALES OFFICES— NEW YORK CLEVELAND CHICAGO

MILLIONTHS OF AN INCH FOR SALE BY VINCO

Semi-Automatic Hydraulic Spline and Gear Grinder • Optical Master Inspection Dividing Head • Involute Checker • Angle Tangent to Radius Dresser • Index Plates • Precision Vises • Sine Bars • Straight-side Spline, Serration Spline, Involute Spline and Helical Spline Plug and Ring Gages • Thread Plugs, Rings and Setting Plug Gages • Spur and Helical Master Gears • Munition Gages • Propeller Hub Gages • Built-up and Special Gages • Gear Rolling Fixtures • Spline and Index Fixtures • Hydraulic Power, Control, Utilization and Distribution Units • Engineering, Design and Development.



Come fast, sit down . . .

"By Aluauna make long walk walk. Bimeby big noise birds come fast, sit down Aluauna . . ."

Pin points on the charts today are bases for feeder lines tomorrow. New air routes will need new landing strips, repair shops, communication systems. And as the airplane turns from war to work . . . Air Associates will be ready to supply whatever it needs, wherever it flies, from control tower equipment to cotter pins, properly priced, promptly shipped. Back on the job it has held since 1927, as prime source of materiél to the industry, Air Associates will be better able to serve government, airlines or the private pilot with new specialties of its own design and manufacture . . . with many exclusive items as well as standard stocks . . .

• *Air Associates' postwar catalog will carry a valuable franchise for future business. Manufacturers are invited to discuss the listing of their lines now.*

• AIR ASSOCIATES, INC.

TETERBORO N. J. — *BRANCHES* CHICAGO, DALLAS, LOS ANGELES —
ENGINEERS & MANUFACTURERS OF AIRCRAFT SPECIALTIES —
SUPPLIERS TO THE INDUSTRY SINCE 1927



Rough sliding means trouble!



Exclusive Crown Zipper tooth construction assures quick, smooth, effortless sliding, even around sharp curves!

Look at a Crown Zipper closely, and what do you see? Each individual tooth is identical on both sides!


This exclusive Crown design permits the sliders on Crown Zippers to move with perfect freedom in both directions along the zipper track

Even on heavy aircraft and truck tractor covers, Crown Zippers operate quickly, smoothly, almost effortlessly—take sharpest curves without sticking or bunching the fabric

This big, basic Crown Zipper advantage is but one of *many* Crown superiorities that will make for better service in postwar aircraft equipment applications

Actually, Crown engineers, working in the field with our armed forces, have developed *five* advancements over old style, conventional zippers (See complete list of Crown Zipper superiorities below.)

When *you* turn to postwar, Crown's great backlog of experience in improving zipper design and in adapting zippers to meet special jobs will be invaluable For our designers will sit down with your own designers to adapt—or, if necessary, *create*—special zipper applications to meet your individual manufacturing needs



ONLY CROWN ZIPPER TEETH ARE IDENTICAL ON BOTH SIDES, TO INSURE SMOOTH SLIDING!

CROWN ZIPPERS are 5 ways better



1. Takes sharp curves



2. Die cast for smoother action—extra strength



3. Provides opening wherever you want it



4. Won't lock open



5. Resists corrosion

Member of the J. & P. Coats • Clark's O·N·T Family

THE SPOOL COTTON COMPANY • *745 Fifth Avenue, New York, N Y (Crown Fastener Division)*



This Versatile MICRO SWITCH HOUSING

Meets Widest Range of Aircraft Uses



Type "H" Aluminum Die Cast Micro Switch Housing with cover removed

Type "H" Housing showing easy access to Micro Switch

The Type "H" Micro Switch Housing has incorporated the ideas of leading aircraft engineers and accurately meets widely varying airplane requirements.

This aluminum die-cast housing is designed to operate with the Type "R31" Micro Switch and provides a wide selection of actuator plungers, conduit connections and mounting accommodations. The housings are supplied in both rights and lefts, with or without ground connections.

The large illustration shows an open view of the Type "H" housing with 3/8" overtravel plunger and mounting ears. These are available with straight or adjustable angle conduit fittings with 1/4"—20 or 11/16"—24 A N threads, or 29/64" hole for open wiring. Overall size is 1" thick, 3 15/16" high, 25/32" wide. Weight, without switch, is .227 pounds.

The smaller illustration shows a right hand Type "H" aluminum die cast housing provided with a sealed 3/8" overtravel plunger and angle conduit fitting. Overall size of this housing is 1" thick, 3" high, 3 11/32" wide. The net weight, without Micro Switch, is .272 pounds.

These are but two examples of the wide range of different ways in which these aluminum die-cast Micro Switch housings can be secured to fit many aircraft requirements. They afford mechanical protection, conduit connection, sealing and radio shielding as conditions may require.

For complete details on other types of metal clad housings and actuators for the use of Micro Switches in aircraft, send for our Catalog No. 70.

FEATURES OF THE TYPE "H" MICRO SWITCH HOUSING

1

Basic Micro Switch Units are easily replaced, since they are carried on a pair of accurately fitting pins.

2

Entire assembly may be sealed against entry of water, dust, oil, etc., by means of a synthetic rubber seal placed on the plunger. See illustration.

3

Gasket and cover are secured with flat head cross slotted screws.

4

A ground connection from the switch to the case may be provided inside of the case. Ample wiring space is provided.

5

Housings and actuators become parts of the planes and require no deviation permit. They are built for ready field replacement.

CHARACTERISTICS OF TYPE "R31" AIRCRAFT MICRO SWITCH

The Type "R31" Micro Switch uses the three bladed beryllium copper spring construction which has proven so successful in the millions of Micro Switches used throughout the aircraft industry.

The Type "R31" Micro Switch incorporates contact separation of .070" which satisfactorily interrupts highly inductive loads under conditions of extreme altitude.

Knurled contact surfaces insure positive operation on extremely small loads and minimize transfer of contact material on D.C. operation.

The Type "R31" Micro Switch has been accepted as standard by the Army Air Corps and the Navy Bureau of Aeronautics and is stocked at all Air Depots.

Type BZ-R31 approved under AN Specification AN3910.

Micro Switch Corporation, Freeport, Illinois

Branches: 43 E. Ohio St., Chicago (11) • 4900 Euclid Ave., Cleveland (3) • 11 Park Pl., New York City (7) • 1709 W. 8th St., Los Angeles (14) • Sales & Engineering Offices: Boston • Hartford • Portland, Ore. • Dallas, Tex.

LET'S ALL BACK THE ATTACK . . . BUY EXTRA WAR BONDS

The trademark MICRO SWITCH is our property and identifies switches made by Micro Switch Corporation

MICRO MS SWITCH

Made Only By Micro Switch Corporation . . . Freeport, Illinois, U.S.A.

the *unusual* in Springs is *not unusual* at Muehlhausen



★ Muehlhausen has provided the answers to many challenging spring problems—provided them at a speed in keeping with war-time demands. Unusual spring requirements have been successfully met with unusual spring designs—made possible by this company's widely varied experience, plus engineering skill and extensive production facilities.

Springs of every shape and size, in quantities large and small, are part of everyday production. Muehlhausen craftsmen are able to produce the correct spring for every requirement—whether a tiny compression spring that will be flexed a hundred times a minute; or a large, hot-formed spring that must withstand extreme operating temperatures.

This ability of Muehlhausen to design and fabricate unusual springs has permitted greater latitude in designing war products now, and will enable engineers to plan, with greater freedom, the products of tomorrow.

MUEHLHAUSEN SPRING CORPORATION
Division of Standard Steel Spring Company
740 Michigan Avenue, Logansport, Indiana



SEE HOW SPRINGS ARE HOT-COILED

SEND FOR NEW FOLDER

New booklet illustrates important steps in hot-coiling large springs. Send for copy today.

MUEHLHAUSEN MS SPRINGS
EVERY TYPE AND SIZE



A Single Cardox System Provides Engineered Extinguishing Coverage for One or a Number of Hazards . . . Large and Small

The swift efficiency of carbon dioxide for fire extinguishment is thoroughly recognized. But, where a few pounds, properly applied, will stop one fire, another may call for tons . . . for example, to provide total flooding of large plant production areas, or for severe outdoor hazards

With the Cardox method of control and engineered application, Cardox CO_2 —supplied instantly *in pounds or tons* —gives new protection scope to this non-damaging, non-contaminating medium for fire extinguishing

Enhanced CO_2 Performance

A Cardox System—engineered for the specific hazards it covers—extinguishes fires by a timed *mass* discharge of Cardox CO_2—stored at 0°F. in a mechanically refrigerated Storage Unit.

Enhanced extinguishing performance is possible because, as controlled and applied—*in pounds or tons*—in Cardox Systems: (1) Cardox CO_2 has uniform extinguishing characteristics regardless of plant or atmospheric temperatures; (2) Applications can be engineered in accordance with the requirements of each specific hazard covered; (3) High CO_2 snow yield provides increased cooling effect (carbon dioxide released at 0°F. yields 45% CO_2 snow); (4) Effective projection through relatively great distance is achieved—even outdoors.

Tough Hazards Have "Engineered" Cardox Systems

It is no coincidence that frequently when hazards are toughest to handle . . . where fire or damage by the extinguishing medium would disrupt carefully planned war goods production schedules . . . engineered protection is provided by Cardox Fire Extinguishing Systems

If you would like more information for use in solving current war plant fire protection problems . . . or in formulating fire protection plans that will prevent dangerous delays in getting post-war production in high gear . . . write on company letterhead for Bulletin 371


CARDOX CORPORATION
BELL BUILDING • CHICAGO 1, ILLINOIS

District Offices in
New York, Boston, Washington, Detroit, Cleveland, Atlanta, Pittsburgh, San Francisco, Los Angeles, Seattle

CARDOX
CO_2 FIRE EXTINGUISHING SYSTEMS

FOR EXAMPLE


These sketches illustrate simply the broad scope of protection that can be provided by a *single* Cardox System. The range of efficient applications between these extremes is practically unlimited.



Outdoor Transformers. Local direct application at very high rate builds area flooding effect outdoors. For hazards such as this a Cardox System stands ready at the first flash of fire with tons of Cardox CO_2, if needed



Cardox Hose Reel provides effective protection for numerous hazards calling for *a few pounds* of Cardox CO_2—*or a few hundred*



Cardox CO_2 is supplied *instantly* in pounds or tons from a single Storage Unit containing 500 pounds to 125 tons at controlled low temperature of 0°F. and 300 p.s.i.

To Fly 1000 BOMBERS...



OUR BOYS can fly these four-engined bombers faster, higher and carry more bombs because they use 100-Octane Aviation Gasoline, the most powerful gasoline in the world.




IN NEWLY COMPLETED, modern refinery units Sinclair produces each day enough 100-Octane gasoline to fly 1000 four-engined bombers on a bombing mission. Today, all of Sinclair's aviation gasoline goes to war. After the war this fine fuel will be available for commercial and private planes.

BUY MORE WAR BONDS AND STAMPS

SINCLAIR

NEW



A Template Following

FARNHAM FORMING ROLL

ONE PASS THRU MACHINE COMPLETELY FORMS LEADING EDGE AND FUSELAGE SKINS

Retains the present advantages of the Farnham Forming Roll, with increased production

6 TO 10 TIMES FASTER

A PARAGON RESEARCH DESIGN

FARNHAM MANUFACTURING CO.
1616 SENECA STREET, BUFFALO 10, NEW YORK



THE MIGHTY HAND OF X-RAY

. . . is breaking inspection bottle-necks and speeding the production of war materials in hundreds of industrial plants today. But for x-ray inspection to operate at maximum efficiency requires swift modern Supermix film-processing chemicals instead of slow conventional powders. Supermix has the following 5 advantages over conventional powders:

MORE SPEED. Supermix develops films in only 3 minutes and clears them in 1. It nearly doubles film output.

SUPERIOR QUALITY FILMS. Supermix brings out in films the utmost contrast, density, and detail visibility. Diagnoses are made more quickly and surely.

LESS WORK. Being 100% liquid, Supermix saves time in mixing new solutions. The concentrates are simply poured into the tanks and water added.

CONSTANT DEVELOPING TIME. Chemical exhaustion of Supermix developing solution is compensated by adding Supermix Refresher periodically instead of by lengthening the developing time. Supermix saves the work of continual recalculation.

LOWER COST. Because Supermix liquid concentrates are 50 to 70% longer-lived than conventional powders, they are at least 15% more economical to use. Also, revitalization of the Developer with Refresher makes the Developer last up to 4 times longer, an additional saving.

For speedier, surer, more economical x-ray inspection, order Supermix liquid concentrates today from your nearby G-E Branch Office.

	Developer	Refresher	Fixer
To make 1 gal.	$1.00	$1.15	$1.00
To make 3 gals	2.75		2.70
To make 5 gals	4.50	5.25	4.25

Ask for quantity prices

Prices f. o. b. U. S. Branches. Prices will be increased by the amount of such sales (or use) tax as may be applicable.

GENERAL ELECTRIC X-RAY CORPORATION
2012 JACKSON BLVD. CHICAGO (12), ILL., U. S. A.

Today's Best Buy — U. S. War Bonds



At No Extra Cost...

CLEVELAND *Top Quality* AIRCRAFT BOLTS

give more than AN requirements

The better fit and extra strength you get in Cleveland Aircraft Bolts are *plus values* that result from Cleveland's long experience and sound precision methods—by expert application of the Kaufman Process (our own plant development), close supervision of manufacture and thorough inspection. Write for prices and discounts.

CLEVELAND *Top Quality* **FASTENERS**

The Cleveland Cap Screw Company

2945 EAST 79TH STREET • CLEVELAND 4, OHIO

ALLOY AND AIRCRAFT PARTS DIVISION

MADE BY THE ORIGINATORS OF THE KAUFMAN PROCESS FOR GREATER STRENGTH AND ACCURACY

"Gulf Cutting Oils

HAVE MATERIALLY INCREASED OUR PRODUCTION AND TOOL LIFE"—

Says this plant Superintendent



Actual photo of a Gulf Service Engineer consulting with Superintendent of aircraft parts plant. This plant has considerably improved machining practice with Gulf Lasupar Cutting Oil and Gulf Cut Aid

"This Gulf Service Engineer

GIVES US THE RIGHT RECOMMENDATION FOR EVERY MACHINE AND TYPE OF WORK"

THIS is one of hundreds of war plants that have secured greater production and longer tool life from the use of the proper Gulf Cutting Oil for every machine and type of work, as recommended by Gulf Service Engineers.

Here's the important reason why Gulf Cutting Oils help improve machining practice: Every Gulf Cutting Oil has specific properties which insure better performance on certain types of cutting jobs! Gulf Lasupar Cutting Oil, for example, is used to advantage by the shop shown above. This oil is manufactured by an exclusive process that secures characteristics uniquely advantageous to many cutting operations.

Call in a Gulf Service Engineer today and ask him to show you how Gulf Cutting Oils can help you improve production and tool life and obtain better finishes. For your copy of the booklet on Gulf Cutting Oils, send the coupon below.

GULF INDUSTRIAL LUBRICATION


Gulf Oil Corporation—Gulf Refining Company A
3800 Gulf Building Pittsburgh 30, Pa.
Please send me, without obligation, a copy of the booklet, "Gulf Cutting Oils," which includes a 48 page Machining Guide.

Company.....

Name.....


Title.....

Address.....



KEEP COUNT OF PRODUCTION

the same way gunners keep count of rounds fired . . .



with VEEDER-ROOT COUNTING DEVICES

Bomber and fighter machine-gunners know *at any moment* where they stand and what they have to work with — just by a quick look at a Veeder-Root Counting Device that tells them how many rounds they have left after each burst of fire.

And on production machines in motor and aircraft plants, Veeder-Root Counting Devices provide the same up-to-the-minute "news service" to operators and production heads — enabling them to *see with certainty* whether a machine is producing up to its capacity and schedule — whether it's in need of mechanical or power adjustments, whether it's approaching close to the time for its routine going-over by the maintenance crew.

On the ground, as in the air, Veeder-Root Devices warn of approaching danger-zones *in time to avoid them* and avoid serious casualties. And on any type of production machine, they are easy to install without interrupting production. Find out exactly what they can do to keep *your* production flying. Write—

The Counting House of Industry

VEEDER-ROOT INC.
Hartford 2, Connecticut

In Canada Veeder-Root of Canada, Ltd., Montreal • *In England* Veeder Root Ltd. (new address on request)

MARCOLITE, A NEW LAMINATED PLASTIC MADE BY CONTINENTAL CAN CO., USED BY ARMY-NAVY

Self-sealing fuel tanks of U. S. combat planes are now backed with Marcolite. This remarkable laminated plastic is also designed for other aircraft uses. Many manufacturers are looking to it for wing tips, antenna shields, tabs, access cover doors, fillets, ducts, ailerons and various size tanks. We urge you to investigate how Marcolite can fill your needs. Our new booklet gives details. Mail coupon below.



B-24 SELF-SEALING FUEL TANKS BACKED WITH MARCOLITE!

Marcolite's unique internal structure makes it the ideal backing for fuel cell installations on the Ford-built B-24 bomber. When penetrated by a bullet or other missile, this tough plastic doesn't "flower" or tear. It permits quick and thorough "healing" of the fuel cell. Also, this light, durable plastic has unexcelled strength for weight, which makes it ideal for other new, practical uses in plane production.



SEND FOR FREE BOOKLET!
Gives information on properties, possible applications, forming, fabricating, etc.

CONTINENTAL CAN COMPANY, INC.

PLASTICS DIVISION

MOLDED PLASTICS
Reynolds Molded Plastics • Cambridge, Ohio

LAMINATED PLASTICS
Continental Can Company, Inc. • Chicago
New York • Los Angeles

LAMINATION • COMPRESSION • INJECTION • EXTRUSION • SHEET FORMING

Continental Can Company
Plastics Division, Dept. AI.
100 E. 42nd Street
New York 17, N. Y.

Please send me your free booklet that tells about Marcolite

Name

Firm Name

Address



Surfaces such as the ailerons and rudder which must move accurately for proper control are subject to greater stress and strain than any other part of the plane. That is why AIRWING AVIATION TAPES are used for binding and strengthening such vital surfaces. From the selection of cotton to the final cutting, these tapes are under the supervision of Airwing experts. Careful testing at each stage of manufacture assures high-strength and light weight — guarantees that they exceed U. S. Government specifications.

AIRWING AVIATION TAPES come in a complete selection — Grade A made from long staple Pima cotton, Lightweight and Utility — pinked edge, sealedge, biased, and pre-doped. The complete Airwing line also includes airplane and glider fabrics, balloon and other aviation cloths.

If stock items of cloths or tapes do not meet your requirements, bring your special problem to Thurston — supplier to the Army and Navy since World War I.

W. HARRIS THURSTON, INC.
Division of Reeves Brothers, Inc.
40 WORTH ST., NEW YORK 13
Factory and Warehouse
17 BEACH ST., NEW YORK

REG. U. S. PAT. OFF.
AIR WING FABRICS

Write us for the name of your nearest AIRWING Distributor

"One Pound Saved Can Earn $180.00 a Year"



Send for Free Boots Weight-Saving Booklet Today—Actual weights of over 250 different self-locking nuts used in aircraft, comprehensively reviewed for the convenience of aircraft designers, engineers, operating and maintenance personnel. Copy will be sent you, free, on request.




Boots Steel Anchor Nut
(W2S #8-32) This all-metal self-locking nut is 60% lighter than a comparable fibre nut

UP TO 60 LBS. PER PLANE SAVED BY BOOTS NUTS

- Being *all* metal, they are TOUGHER and SAFER.
- Can be used over and over again.
- "Outlast the plane."
- Now standard fastenings on every type of military aircraft.
- Will be standard on commercial planes after victory.
- Approved by all government aviation agencies.

BOOTS SELF-LOCKING NUTS
"They Fly With Their Boots On—Lighter"

Boots Aircraft Nut Corporation, General Offices, New Canaan, Conn. Dept. E



• The flyer depends on his instruments—the instruments on a hook-up of fuel, hydraulic and lubrication lines. At every joint and intersection the dependability of Dole Aircraft Valve and Fittings backs up the performance of pilot and plane.

Behind Dole Valves and Fittings stands the experienced Dole engineering and production staff, working for war and planning for the day when they will be called upon to solve YOUR problems.


DOLE

THE DOLE VALVE COMPANY
Established 1906
1901-1941 Carroll Ave., Chicago 12, Illinois
Los Angeles • Detroit • Philadelphia


Freedom is Beyond Price. Buy it on a Profit Sharing Basis with U. S. War Bonds

AIRCRAFT VALVES and FITTINGS

LINCOLN CENTRO-MATIC LUBRICATING SYSTEMS...



THE *Modern* WAY TO LUBRICATE all types of machinery



The Lincoln *modern method* of centralized lubrication, makes it possible for all bearings on one machine, or on a series of machines, to be lubricated from a central source without stopping the machines.

The Lincoln Centro-Matic System consists of a number of Centro-Matic Injectors—one for each bearing—and a hand-operated, or a power-operated Centro-Matic Lubricant Pump. The system is easy to install and will help increase your plant efficiency, not only today, but for years to come.


I WOULD LIKE TO HAVE FREE BULLETIN
On Lincoln Centro-Matic Lubricating Systems

*Name*_____
*Title*_____
*Company*_____
*Address*_____
*City*_____ *State*_____

A-144-7

ARMY E NAVY

LINCOLN ENGINEERING COMPANY
Pioneer Builders of Engineered Lubricating Equipment
5701 NATURAL BRIDGE AVE., ST. LOUIS 20, MO., U. S. A.



As the purchasing agent of Bell Aircraft brings out, the new free book "Purchasing Department—Records and Routines" goes far beyond satisfying the natural interest in seeing how others do things.

It is in fact a practical manual based on the purchasing experience of leading organizations in every branch of industry. Here are real solutions to such timely problems as how to buy in proper volume without the danger of understocking or overstocking, how to know where you can place orders and be certain of delivery when you want it, how to keep stocks of materials and parts in proper balance under today's unsettled conditions.


Nothing is left out. Procedures are described in detail. Clear reproductions of actual records in color show how these objectives are being accomplished effectively and accurately, and how they facilitate the executive planning and coordinating that are so necessary these days.

Ask your nearest Remington Rand office for a copy.

We're waiting to address YDUR free copy of

"Purchasing Department—Records and Routines"

A book of ideas that work when the pressure is on



COPYRIGHT 1944

SYSTEMS DIVISION

REMINGTON RAND

Buffalo 3, New York

The New ROMEC G-9 Power-driven FUEL PUMPS



CAPACITY:—400 gallons per hour at 2500 rpm.

HIGHER PRESSURE RANGE:—6 to 35 lbs. per square inch.

LOWER WEIGHT: — Complete pump weighs only 2¾ lbs


VALVES:— Balanced type relief valve with shaft seals that are dependable through extreme ranges of temperature.

MODEL NO.:— RD 5200, type G-9. This is the ultimate development in its class and is now in production.

ROMEC PUMP COMPANY
ELYRIA, OHIO, U. S. A.

Buy War Bonds

Romec AIRCRAFT PUMPS and ACCESSORIES



Horizontal and vertical stabilizer skins for the Vultee BT-15 Trainer—made to highest standards by the superior and exclusive Evans molding process.

Molded plywood skin used to streamline fuselage of great cargo glider. These huge sections are molded in one form and have great strength.

Abstract molded plywood design shows how intricate shapes can be molded under extreme heat and pressures. Note the interesting arcs and angles.

BUY MORE WAR BONDS

Molded Plywood . . . A "Fledgling" With a Great Future

The development of molded plywood is destined to match the powerful saga of the timber trails. Evans Products Company through a superior molding process is revolutionizing the use of wood. It is playing a vital role in the war program and will exert a major influence in the use of molded plywood products in peacetime.

Evans molded plywood is formed under great pressure, which is partly responsible for an amazing inherent strength. An ingenious method of applying heat makes possible intricate designs, curvatures and angles. Both factors are most important in determining the utility of molded plywood products.

Evans designers and engineers are constantly at work developing new wood products and new uses for Evans molded plywood. After the war it will be used as structural and design material in products ranging from automobiles to homes. Thus, Evans molded plywood is a "fledgling" with a great future.


* * *

Vision to Anticipate the Needs of Tomorrow
Creates New Industries Today

E. L. Evans
PRESIDENT

EVANS PRODUCTS COMPANY
DETROIT

Evans War Products: Machine Gun Mounts • Tank and Automotive Heating and Ventilating Equipment • Evenair Water Heaters • Aircraft Engine Mounts • Airplane Landing Gear Beams • Battery Separators • Prefabricated Houses • Molded Plywood Products • Skyloader • Utility Loader • Auto-Loader • Auto-Roller • Auto-Stop • Stampings • Evenair Domestic Heating Equipment



Curtiss and the country have plenty to be proud of in the new Navy "Helldiver"—latest of the great series of Curtiss dive-bombers. She's a fighting favorite of our pilots—clean, fast, and packing a powerful punch. The "Helldiver" has *earned* the title "Fist of the Fleet"!

The "Helldiver"—officially, the SB2C—is a Curtiss plane, built around a powerful Wright Cyclone engine, equipped with a Curtiss electric propeller—and carrying a famous Curtiss name. Kenyon considers it an honor, therefore, to be called on to supply some of the precision parts that go into a "Helldiver."

Fine precision work is a tradition at Kenyon—and aircraft manufacturers have our pledge that even in wartime, Kenyon will supply the precision parts and instruments they need—*delivered in quantity and on time!* Our engineers and laboratories are qualified to develop and design precision instruments, our shops are equipped to produce them—and Kenyon looks forward to rendering similar service to the industry in days of peace.

When you need precision parts, even if they have never been made before—*call on Kenyon!*

KENYON
INSTRUMENT CO., INC.
HUNTINGTON, L. I. NEW YORK
If It's Kenyon Made It's Precision-Built

Do MORE for the War In '44—BUY MORE WAR BONDS!



Plutarch has recorded Caesar's fateful decision to cross the Rubicon on his historic march to Rome: "The die is cast", he said . . . and gambled all on a blitzkrieg. Caesar won — Hitler didn't!

America has learned from each, and our guiding principle is to work for an early knockout but to prepare to win a long war. That goes for industry as well as for the fighting forces.

The die is cast at Solar to uphold America's principle and Solar workers have taken this decision to heart — adding thereby a priceless quality to brawn and skill. The tangible results are seen in new and revolutionary die-castings, constantly improving the quality of Solar airplane exhaust systems made of stainless steel. Production is at high peak, although stainless steel — perfect for the finished job — is tough on forming dies. Solar people do first things first, but prepare for the long haul . . . even looking ahead to brighter days and postwar stainless steel products, bearing the Solar trademark.

ARMY E NAVY

SOLAR

STAINLESS STEEL PRODUCTS

SOLAR

SOLAR AIRCRAFT COMPANY ★ SAN DIEGO 12, CALIF. ★ DES MOINES 5, IA.

Proof of a Better Finish





Surface Analyzer Tape Proves you Get a Better Finish with Chicago Wheels

These results were obtained at a rate of 100 pieces per hour in an aircraft parts plant. Material, X 13-15, Rockwell 60 to 57, grinds out .006 to .007 stock. Chicago Wheel used, ½x½x⅛", Grain 180, Grade L Arcite FV Bond. Spindle Speed 40,000 r.p.m., Lapping and super finishing eliminated on this job.

Can you match that finish? Sounds phenomenal, but you can do it with Chicago Wheels. And, the secret of their superiority lies in the new FV Bond, developed exclusively for Chicago Wheels, after 50 years' experience making wheels for the most accurate and precise applications.

Here's What FV Bond Will Do for You


- Reduce your wheel costs
- Produce a better finish without sacrifice of production time—a finish so smooth that you can measure it in micro inches

TRIAL WHEEL FREE

Write or send the coupon today for a Chicago Wheel, made with this remarkable new FV Bond. Tell us grinder you use, size wheel and kind of material on which you will make your test.

For the duration with full WPB approval we are specializing on small sizes—anything up to 3" in diameter.

Write for Catalog and one of the new Engineering Survey Forms, a step in the direction of better finishing.



ARMY E NAVY

MOUNTED WHEELS

SMALL GRINDING WHEELS

Half a Century of Specialization has Established our Reputation as the Small Wheel People of the Industry

CHICAGO WHEEL & MFG. CO.

America's Headquarters for Mounted Wheels and Small Grinding Wheels

1101 W. Monroe St., Dept. Av. Chicago, Ill.

Send Catalog and Survey Form. Interested in
( ) Mounted Wheels ( ) Grinding Wheels
( ) Send Test Wheel Size

Name .....

Address .....

Notiz!



North American P-51 Mustang Fighter

Ein Tiefdeckerflugel Eindecker mit langer Nase, langem, schlankem Rumpf, großem bauchwärtigem Kühler, Einzelflosse und Seitenleitwerk. Schwanzen- Vierblatt-Propeller. In den Tragflächen montiert: Sechs 50-kalibrige Maschinengewehre Gilt als das schnellste Flugzeug der [illegible] der Vereinigten

ATTENTION LUFTWAFFE! Keep away from this plane. Expect to see it on the farthest trip American bombers make. Expect to see it up high—40,000 feet—but don't expect to see it for long, because the Mustang travels at over 425 m.p.h.

And you can expect to see more and more Mustangs, too. The men and women at North American are stepping up production every month. So when you see this high fighting, far flying Mustang, look out, Luftwaffe. Get out of there quick!

North American P-51 Mustang Fighter



ATTENTION AMERICANS! 00000 bought these planes. WASTE FATS helped arm them. WASTE PAPER helped ship them. GASOLINE flies them. Will YOU help to deliver the next squadron?

FULL-VISION "TEARDROP" COCKPIT ENCLOSURE — DROPABLE WING GAS TANKS FOR INCREASED RANGE — SIX .50 CALIBER MACHINE GUNS

North American Aviation *Sets the Pace*

WE MAKE PLANES THAT MAKE HEADLINES . . . *the B-25 Mitchell bomber, AT-6 Texan combat trainer, P-51 Mustang fighter (A-36 fighter-bomber), and the B-24 Liberator bomber. North American Aviation, Inc. Member, Aircraft War Production Council, Inc.*



SOME OF THE MANY USES:

Propeller Pitch and Governor • Throttle • Carburetor Air and Filter • Supercharger • Remote Valve Control • Mixture • De-Icer • Cargo Door

YEARS of leadership in the field, an outstanding record of performance, continued modernization of design . . . these are the reasons why Simmonds-Corsey Push Pull Controls are the choice of leading aircraft manufacturers. With more than a decade of operating experience, these precision-built controls were the first to gain the Yellow Dot . . . of acceptance in the U. S. Army Air Force Winterization Program, attesting to high performance under Arctic conditions.

More than 500,000 Simmonds controls have been installed on aircraft of the United Nations. A new design innovation is the Radian Unit (illustrated) to provide rotary action from basic push-pull operation. Because of their rugged precision-built qualities, these controls are fast finding new applications in the automotive and ordnance fields as well as in aviation.

Strategically located Simmonds branch offices make possible the utmost in customer service. Let us help you with your control problems. Your inquiries are invited. Write for free descriptive literature.

SIMMONDS AEROCESSORIES INC.

30 Rockefeller Plaza, New York 20, N. Y.

Branch Offices

Dayton • Washington • Hollywood • Montreal

Manufacturing Plants: New York • Vermont • California



quality and quantity

METAL STAMPINGS



Whether the quantity is large or small, Metal Specialty assures you quality stampings. The Metal Specialty Co. is also completely equipped to give you efficient service in Rolling, Coining, Forming, Drawing and Annealing in all Metals. Specialists in Hydraulic cold drawing and embossing in all metals including stainless steel. Deep drawing and embossing up to 850 tons capacity. Shells drawn up to 20" in depth. Assembling including Flash and Resistance Seam Welding. Pressed metal products to specification.






The
METAL SPECIALTY Co.
MAIN OFFICE AND PLANT • ESTE AVENUE • CINCINNATI, OHIO



This is the twelfth of a series of statements by aviation's leaders on THE SHAPE OF FLYING TO COME.



says Colonel Edward S. Evans, PRESIDENT OF EVANS PRODUCTS COMPANY

"TODAY WE ARE only beginning to develop air transport. I look forward to a Tomorrow when jet propulsion planes will fly in the substratosphere at 550 miles or more per hour, and the Flying Wing will carry much greater cargoes at hardly less speed.

"But these by themselves are not enough to usher in the age of freight-by-air.

"We must also build a locomotive of the air designed to draw a train of gliders. The glider train will fill a gap in air transportation because a glider can take smaller loads than a plane; and, by adding or subtracting gliders to the train, adjustments can be made to cargo demands with greater economy.

"Then, we should have well-equipped cargo airports, separate from passenger airports, in all postwar commercial centers; and landing strips for emergency landings at all major crossroads.

"The freight-plane will never drive the train or the ship out of business. But it will become a vital part of distribution. Never bet in America that a thing can't be done."

• • •

YES, COLONEL EVANS—and after all these things are off the blueprints into production—the *idea* of freight-by-air must still be *sold!*

And first place to sell it is to the "test-pilot market"—the people who (in business or in private living) are habitually first to accept any change for the better.


***This is the market aviation thinks of when it thinks of the more than a million TIME-reading families*—whose incomes are twice that of the average family—who are America's best prospects for planes and air travel—whose influence and positions in business make them the natural vanguard for any programs aviation may set up.**

Believing that the ideas of aviation's leaders are always of interest to the aviation industry, TIME here gives them wider circulation in the name of

AVIATION'S SILENT PARTNERS — TIME — THE READERS OF TIME

The man is mad!

Brunelleschi, the Florentine architect, was called insane when he declared, "I propose to raise a cupola without a center column and without any framework whatever. It must be turned in the manner of the pointed arch and must be double . . . the building must be strengthened by the dove-tailing of the stones . . . the walls must be girt around by strong beams of oak." Brunelleschi's daring plan won a few followers. The architect died, but his design was carried out and the exquisite dome of Santa Maria del Fiore rose majestically over the city. It is Brunelleschi's most famous work.



Drawing pencils are tools which transform daring ideas into tangible designs. Typhonite Eldorado pencils are master tools. Whatever the point—needle or chisel—Typhonite Eldorado is the easy, pleasant-to-use pencil that makes the line or figure crisp, sharp, firm, clean. Result? The job is better and the day made brighter for all hands.

Write for Your Complimentary Copy
"I Shall Arise"—a portfolio of Typhonite Eldorado pencil reproductions by Samuel Chamberlain. Subjects are buildings of art and historical importance bombed by the Luftwaffe

TYPHONITE
ELDORADO
PENCIL SALES DEPARTMENT 61-J7
JOSEPH DIXON CRUCIBLE COMPANY JERSEY CITY 3 N. J.



IRVIN AirChute "SINGLE-RELEASE" Harness

UNITED NATIONS' FLYERS *are using it for* SAFER LANDINGS

A one-hand turn and a tap on the single frontal disk instantly releases the harness . . . leaving the flyer entirely free. Accidental release is impossible before disk is "set" for action.

All United Nations' Air Forces for years have used IRVIN as standard equipment . . . and now the Irvin "Single-Release" harness is acknowledged as superior for all landings. IRVIN, as always, leads in Safety.



Tap after "set" for release

•

Harness Falls Away



IRVING AIR CHUTE CO., Inc.
Main Office: 1670 Jefferson Ave., Buffalo 8, N. Y.
Factories at other points in the United States, Canada and England
All Serving the United Nations' Air Forces

BUY MORE BONDS IN THE 5TH WAR LOAN


HOLO-KROME INTERNAL HEX WRENCHING BOLTS



Saves Weight Space & Time

THE STANDARD of the AIRCRAFT INDUSTRY

NASC SPECIFICATIONS



INTERNAL WRENCHING
QUICK and POSITIVE!

The entire Holo-Krome facilities are devoted exclusively to the production of precision made Internal Wrenching Products. Rigid inspection to meet the Holo-Krome standards of quality guarantees every bolt to give Unfailing Performance - to do the job for which it was intended. The experience and knowledge of Holo-Krome Fastening Engineers are available to Aircraft Design Engineers. Specify "Holo-Krome"

GUARANTEED *Unfailing* PERFORMANCE

AIRCRAFT CATALOG - GLADLY SENT

AIRCRAFT DIVISION

THE HOLO-KROME SCREW CORPORATION
MAIN OFFICE & PLANT
HARTFORD 10, CONNECTICUT U.S.A.

Grimes NIGHT CAP Indicator Light



Here's a new number in the family of Grimes aircraft lights that has met with instant approval. This panel indicator light is designed for quick change from maximum daylight visibility to minimum pin point indication at night. The hinged "Night Cap" allows the rays to diffuse through the tiny jewel making it readily visible at night, yet reducing the output so that it does not interfere with the pilot's vision.

The housing of this light is made of insulating plastic. Two types facilitate mounting on any style of instrument panel. Lamps are readily replaced by removing the jewel holder. All colors are available.

The Grimes indicator light is an approved Army Air Forces type and is recommended for all installations where good day and night indication is required.

Grimes type A-3035 (Army 44A18782) is completely interchangeable with the Army prior type 4283593.



GRIMES INDICATOR LIGHT NO. A-3035

GRIMES PART NO.	ARMY AIR FORCES PART NO.	COLOR
A-3035-1	44A18782-1	White
A-3035-2	44A18782-2	Red
A-3035-3	44A18782-3	Green
A-3035-4	44A18782-4	Blue
A-3035-5		Amber



GRIMES INDICATOR LIGHT NO. A-3010

GRIMES PART NO.	ARMY AIR FORCES PART NO.	COLOR
A-3010-1	44A9439-1	White
A-3010-2	44A9439-2	Red
A-3010-3	44A9439-3	Green
A-3810 4	44A9439-4	Blue
A-3010-5		Amber

Better Lighting...

GRIMES

Designs and Makes it!

GRIMES MANUFACTURING CO.
URBANA, OHIO

Heavier "fire power" licks this enemy, too



Fanned to fury by the terrific slipstream, a motor fire was the toughest foe a flyer could meet. Now it's been conquered—by the fire *killing* power of the Kidde Built-in Extinguishing System.


Here's how it works: At the first sign of fire, pilot pulls a handle, sends carbon dioxide gas from Kidde cylinders to flood the engine compartment and snuff out the blaze. Elapsed time: about three seconds!

Gases-under-pressure, stored in lightweight Kidde cylinders, are doing many jobs that will hasten the arrival of the Age of Flight. If you have a problem in this field, our Research and Development Department may have the solution. Drop us a line!



WALTER KIDDE & COMPANY, INC., 140 CEDAR STREET, NEW YORK 6, N. Y.

FLYING POWER STATION



ROTOL

AUXILIARY GENERATING PLANT

ELECTRIC SUPPLY FOR ALL AIRCRAFT SERVICES

30 kw AC 110 VOLTS • 5 kw DC 28 VOLTS

ROTOL LIMITED, ENGLAND • *Canadian Representatives* BRITISH AEROPLANE ENGINES LIMITED · MONTREAL

NATIONAL (TRADE MARK) CARBIDE




Rates "TOPS" with Industry

for these 3 important reasons


1. NATION-WIDE LOCAL DISTRIBUTION

Prompt deliveries in large or small quantities from more than 250 warehouses located in or near all major manufacturing centers. Also supplied by local dealers and distributors.




2. HIGH ACETYLENE YIELD ASSURED

Hourly testing and the use of exceptionally fine quality materials and strictly-controlled manufacturing procedures, produce a carbide practically free from impurities.



3. DUST-FREE IN THE DRUM


Because National Carbide is screened with extreme care. It is carefully packaged under strict supervision in air-tight drums in order to prevent contamination and deterioration.



You can depend on National Carbide—the famous "carbide in the red drum". More than a quarter century of widespread use has established the economy, uniformity and productivity of this quality carbide.

National Carbide is available in all sizes for generator use—packed in standard size drums. For the address of your nearest National warehouse or distributor, write to Air Reduction's New York office, Dept. A.

BUY U.S. WAR BONDS



AIRCO ACETYLENE GENERATORS

Ideal Team-mates for National Carbide

For dependable volume production of acetylene, use National Carbide in Airco Acetylene Generators. Five sizes to choose from—15 lb., 30 lb., 50 lb., 300 lb. and 500 lb. single or double rated. The first three sizes are portable types and the latter two are stationary. These generators are listed by the Underwriters Laboratories, Inc. Write to Air Reduction's New York office for descriptive folder ADC 619, Dept. A.

AIRCO WILSON


AIR REDUCTION

General Offices: 60 EAST 42nd STREET, NEW YORK 17, N. Y.

In Texas: MAGNOLIA AIRCO GAS PRODUCTS CO • General Offices: HOUSTON 1, TEXAS

Offices in all Principal Cities

INESCAPABLE INDICATIONS



. . . Glowing Beacons
Keep Defective Parts from
Assembly in Planes

MAGNAFLUX RESEARCH

Since the pioneering stage of the original Magnaflux Method for steel, our engineers have sought to extend the benefits of rapid non-destructive inspection techniques in every field. For the important foundry industry special portable equipment and new procedures for more sensitive results were developed.

MAGNAFLUX CORPORATION

• Weaknesses that threaten to develop in American armaments are discovered at home, in the factory, and not by the enemy shooting down crippled planes over the battlefield. This is a powerfull factor in our military strength.

Magnaflux* Inspection of aircraft castings like the above, on a 100% basis, at production-line speeds, contributes significantly to the splendid performance record of American aviation.

The cast aluminum fitting shown here, when inspected under black light by the Magnaflux Corporation's Zyglo*Method glowed with fluorescent indications of serious shrinkage cracks. To catch such defects in the foundry before passing them along offers huge savings. Not the least of these is reputation.

The Zyglo Method is being effectively used on all metals, nonmagnetic, and magnetic—particularly on aluminum and magnesium. Write for fully descriptive Zyglo Bulletin

*Magnaflux and Zyglo—the Trade Marks of the Magnaflux Corporation applied to its equipment, materials and inspection methods.

MAGNAFLUX CORPORATION
5906 Northwest Highway, Chicago 31, Illinois
New York • Detroit • Dallas • Los Angeles • Cleveland • Birmingham

Brand New
MERIAM MICROMANOMETER

★ An Outstanding DEVELOPMENT In the Field of MEASUREMENT!

Nothing like it on the MARKET



FOR ca… …ing … … and other devices. • As a co… …nand … … ing pressures and vacuums. • High … …nsiti… … Micromanometer permits readings to plus or minu… … pressure. • Most rugged, and unequalled in simplicity. • Not t… least complicated or mysterious, it can be handled successfully by the average operator. • *Ask for Bulletin 25.*

THE MERIAM Instrument CO.
10920 MADISON AVE. • CLEVELAND 2, OHIO
Representatives in Principal Cities

• MANOMETERS, METERS AND GAUGES FOR THE ACCURATE …



BOMBER PROTECTION

with a special kind of fighter

Without protection against dust and dirt, even the mightiest bomber is hopelessly handicapped. Close-fitting parts of its hydraulic system are soon damaged by gritty abrasives. Wing flaps and landing gear get out of commission, due to the sticking and clogging of valves.

To overcome this danger, Purolator has developed a series of hydraulic filters with special micronic elements that meet every requirement of the Army and Navy. The elements are small in size, light in weight and completely impervious to weather conditions. So effective are they in isolating dirt, that even the smallest foreign particles are trapped and eliminated.

In addition to hydraulic oil filters, Purolator also manufactures highly efficient air filters for vacuum operated aircraft instruments, and a complete line of lubricating oil filters. Write for Purolator's "Aviation" Catalog. Purolator Products, Inc., Founder and Leader of the Oil Filter Industry.



Home Office . . . . . Newark 5 N. J.
Detroit Office . . . . . 609 Fisher Bldg.
Calif. Office . . . 1401 S. Hope St., Los Angeles

KEEP IT CLEAN with PUROLATOR

BUY MORE WAR BONDS AND STAMPS NOW!

91⅔% Savings in Mounting Time

—DILL LOKSKRU



THE FASTER FASTENING THAT HOLDS FAST


1 Drill ONE Hole

2 Insert LOK-SKRU


(Types with flat, flush, countersunk or spacer head. Sizes as required for metal thickness and hole diameter.)



3 Riveted securely by drawing sleeve against inner side of metal with special power or hand tool.



4 Attachment fastened by screw locked in anchor nut.



Disassembled LOK-SKRU with screw for attachments



Write for Folder

Handy information on the many uses and application of Lok-Skrus in airplane construction with data on types and sizes.

THE DILL MANUFACTURING CO.

FACTORY	BRANCH
700 East 82nd St.	1101 S. Flower St.
CLEVELAND, OHIO	LOS ANGELES, CALIF.

THE AVIATION STANDARD FOR SCREW-LOCKING ANCHOR NUT USES AND METAL TO METAL RIVETING

DILL *Lok-Skru* FASTENERS

NAME YOUR SPEED!



...one of the many vital questions on the "BELLANCA AIRCRAFT QUIZ"

AFTER the war, when America settles down to the business of peace and "the pursuit of happiness" in a liberated world, you'll see more sportsmen's air races. You'll see more air travel, too. And wherever flying people meet you'll hear talk of speed!

There's a big difference of opinion about speed. Our Aircraft Quiz has brought that out from hundreds of the flying enthusiasts who've sent in their Quiz returns. Some believe in "speed at any price"—others prefer to compromise a little on speed for the sake of greater efficiency, added safety, more range. How do *you* vote?

Speed is only one of the vital questions raised in our Aircraft Quiz. It *is* a vital question, too. Bellanca is going to build the *right* speed into the post-war planes which many are already trying to buy. Wait until we've finished our war work, *all* of our war work, and you'll see a Bellanca post-war plane that will give private owners exactly what they want. Its speed will be to the taste of the majority.

But that isn't all. Many other Bellanca features will be in line with popular demand. Engines, landing gear, range, seating, construction, capacity and other essential factors that are covered in our Aircraft Quiz are now being voted on, *Yes* or *No*, by men and women all over America—by many in far-distant places, serving with the Armed Forces—who are checking off their answers on this popular Quiz. In this helpful way, you can let us know what *you* want *us* to build for your post-war flying.

Why don't you send for this Quiz today? Just give us your name and address—we'll mail you the Quiz, and later you'll receive our report on all returns, so you can compare your answers with thousands of others. Write us now! ...Bellanca Aircraft Corporation, Dept. S-3, New Castle, Delaware.

Keep on Buying U. S. WAR BONDS

BELLANCA

Because Oil is Ammunition . . .



Wherever men and planes and ships go — oil must go with them. Oil must fight on every front, on every sea. And to get it there — and keep it there — calls for the surest safeguards that can be put on drums.

Tri-Sure Closures answer that demand — with a *seal*, *plug* and *flange* that form *three* lines of defense against every hazard, a *triple* safeguard that keeps every drop of oil inside a drum and every drop of water *out*.

Look at the cross-section view of a Tri-Sure Closure shown above. There you will see the fortress of safety that this *triple* protection forms. And you will see why, on battlefronts thousands of miles away, oil is arriving "as shipped" — in Tri-Sure fitted drums.

Tri-Sure
CLOSURES

AMERICAN FLANGE & MANUFACTURING CO. INC., 30 ROCKEFELLER PLAZA, NEW YORK 20, N. Y.
TRI-SURE PRODUCTS LIMITED, ST. CATHARINES, ONTARIO, CANADA

New LEUBRO
HYDRAULIC OIL VARIABLE DISPLACEMENT PUMP



COMPLETELY *Eliminates* UNLOADING VALVE CIRCUIT

This new Piston-Type Wobble Plate Pump saves an estimated thirty (30) pounds of weight in a Hydraulic system, by completely eliminating Unloading Valve Circuit It also eliminates the damaging shock that is produced by the Unloading Valve. Top performance is assured in actuating Landing Gear, Turrets, Flap Controls, Surface Controls, and Bomb Bay Doors, by use of this Variable Volume Pump. This pump designed for continued rugged use on all hydraulic systems up to and including 3,000 P.S.I.

LONG LIFE

All LEUBRO PUMPS are constructed for maximum dependability and endurance under all conditions of service. Oversize matched bearings, coupled with Nitroloy pistons guided full length in a hardened alloy steel block insures long life and dependable performance.

•

This Pump also available in Constant Displacement Model.

•

Complete information and engineering service available. Write for details

•

CONFORMS TO ARMY-NAVY PUMP STANDARDS

Precision Built — Compact, 6⅞" long . . . . Light Weight, 9 pounds . . . . Efficient — All parts are interchangeable

LEUTHESSER BROTHERS
21 NORTH LOOMIS STREET · CHICAGO 7, ILLINOIS

NEED A CONVEYOR that You can

Wheel to the Job ?



Photos Courtesy Air Cargo Development Section — Pennsylvania Central Airlines

Ask STANDARD CONVEYOR about their

HANDIBELT PILERS!

PORTABLE, inclined pilers like the one illustrated above save a lot of time and effort — handling and stacking packages, bales, bundles, boxes — in the plant or warehouse, at the airport, around the shipping platform, unloading and loading cars, trucks, boats, transport planes

Handibelt Pilers are available in a wide variety of sizes and styles as required by various commodities. The unit illustrated has an adjustable boom which is easily extended over piles or into car or truck, the boom is clear of all supporting obstructions and is adjustable up to 7½, 8½ and 9½ feet. It handles individual items up to 100 lbs. Other Standard Pilers elevate and stack up to 30 feet. Individual horizontal conveyor sections can also be furnished, these are particularly useful for shipside loading and unloading

Standard Conveyor makes an unusually wide variety of handling equipment including power and gravity conveyors in belt, roller, chain and slat types, spiral chutes, tiering and lifting machines, pneumatic tube systems Whether commodities have to be moved in a straight line, a curve, up, down, or across, there is Standard equipment to handle the job, developed in more than forty years of conveyor engineering and manufacture. Write for complete information on Portable Pilers and valuable reference catalog No. A-74 "Conveyors by Standard."

STANDARD CONVEYOR COMPANY

General Offices: North St. Paul, Minn.

Sales and Service in Principal Cities

STANDARD

Quality—Power

CONVEYORS



TIERING AND LIFTING MACHINES



PORTABLE PILERS




SPIRAL CHUTES



PNEUMATIC TUBE SYSTEMS

TORTURED to LIFE!



Here's consolidated living hell for electrical equipment. It's a "torture-chamber" that reproduces the toughest possible conditions of temperature, humidity, atmospheric pressure. It is one of the many "torture devices" at Electronic Laboratories for testing E•L products.

THE HARDEST PART of an *E•L* Power Supply's life is being born. Because then it must survive tests that make its actual service-life a bed of roses by comparison.

E•L Power Supplies have to prove their guts in temperatures more extreme than Siberia's cold or Sahara's heat . . . at altitudes higher than the Himalayas and lower than the Dead Sea . . . in dust storms . . . in salt spray . . . in humidity worse than a Solomons swamp! Severe operating conditions all, yet intentionally exaggerated in tests at Electronic so that *E•L* Power Supplies may live longer in actual service.

If you have power supply needs of converting low voltage to high voltage, obtaining a precisely regulated power output from a varying power input, or anything else, however tough—let Electronic's engineers help you find the answer.

Your problem may be radio . . . motors . . . lighting *E•L* engineers are familiar with them all . . . and many other applications as well! They are at your service for consultation!

Only *E•L* VIBRATOR POWER SUPPLIES Offer All These Advantages:

1. CONVERSION—DC to AC; DC to DC; AC to DC; AC to AC.
2. CAPACITIES—Up to 1,500 Watts.
3. VARIABLE FREQUENCIES—A power supply may be designed to furnish any frequency from 20 to 280 cycles, or a controlled variable output within a 5% range of the output frequency
4. MULTIPLE INPUTS—For example one E•L Power Supply, in quantity production today operates from 6 12, 24 110 volts DC or 110 volts AC, and 220 volts AC with a single stable output of 6 volts DC.
5. MULTIPLE OUTPUTS—Any number of output voltages may be secured from one power supply to suit individual needs
6. WAVE FORMS—A vibrator power supply can be designed to provide any wave form needed for the equipment to be operated.
7. FLEXIBLE IN SHAPE, SIZE AND WEIGHT—The component parts of a vibrator power supply lend themselves to a variety of assembly arrangements which makes them most flexible in meeting space and weight limitations.
8. HIGHEST EFFICIENCY—E•L Vibrator Power Supplies provide the highest degree of efficiency available in any type power supply
9. COMPLETELY RELIABLE—Use on aircraft, tanks, PT boats, "Walkie-Talkies," jeeps peeps and other military equipment under toughest operating conditions has demonstrated that E•L units have what it takes!
10. MINIMUM MAINTENANCE—There are no brushes, armatures or bearings requiring lubrication or replacement because of wear. The entire unit may be sealed against dust or moisture


Electronic LABORATORIES, INC.

INDIANAPOLIS


E L ELECTRICAL PRODUCTS—Vibrator Power Supplies for Communications Lighting, Electric Motor Operation Electric, Electronic and other Equipment—Installed, Sea or in the Air



FLOCKED WIRE MEDIA



This microphotograph of a small section of Air-Maze aircraft filter media shows some of the millions of tiny wicks that continually feed adhesive to the surface and maintain dust-arresting efficiency.



This media, developed by Air-Maze, made possible the high velocity low-resistance filtration of today's aircraft filters.

★

Typical Air-Maze Aircraft Filter—Send for Bulletin No. 113.

One of the six measurements of aircraft engine air filters

★ Aircraft engineers are used to working both ends against the middle. This ability is spot-lighted in designing both high efficiency and low restriction into aircraft engine air filters.

For 100% efficiency, you could block the intake with a solid plate . . . having, unfortunately, 100% restriction. On the other hand, you can get zero restriction—and zero efficiency, too—by leaving the filter out.

Between the two extremes, you'll find that Air-Maze engineers, working closely with the aircraft industry for more than 17 years, have found the answer.

Air-Maze air filters today combine the highest efficiency in their history with the low restriction so vital to maximum engine performance under all conditions.

Our engineers will be glad to work with you in balancing all the factors on our "yardstick" to meet your particular needs.

AIR-MAZE CORPORATION ▲ *Engineers and Manufacturers* ▲ **CLEVELAND 5, OHIO**

Representatives in Principal Cities • *In Canada:* Williams & Wilson, Ltd., Montreal, Quebec, Toronto, Windsor; Flack Bros., Ltd., Vancouver, B. C.

ARMY E NAVY

AIR-MAZE


SPECIALISTS IN AIR FILTRATION



Adapted to carry either paratroops or cargo such as jeeps, light artillery, spare engines, etc.—and quickly convertible to a hospital craft—the Curtiss "Commando" is serving on all the fighting fronts. At critical points in plane and equipment "where the bearings MUST NOT fail", NORMA-HOFFMANN PRECISION BEARINGS are employed—contributing their own reliable service toward the fine over-all performance of this transport.

NORMA-HOFFMANN—identified with the aircraft industry since the earliest days of aviation—pioneered many of the aircraft bearing types now standard. And today there is a NORMA-HOFFMANN PRECISION BEARING for every load, speed and duty in aviation service. Practically every American-built plane—whether for fighter, bomber, transport, patrol, escort or training service—embodies NORMA-HOFFMANN BEARINGS at vital points where friction must be eliminated.

Write for the Catalog. Let our engineers work with you.



NORMA-HOFFMANN BEARINGS CORP'N, STAMFORD, CONN. • FOUNDED 1911

PRECISION BALL, ROLLER AND THRUST BEARINGS

TO WIN THE WAR: WORK—FIGHT—BUY WAR SAVINGS BONDS!

FOR POST-WAR UNIFORMS THAT SPELL SERVICE

REEVES ARMY TWILL

"FROM COTTON TO CUTTER"



Leading bus companies are typical of the many customers for Reeves Army Twill. Whatever the industry, if uniforms are needed, this top-quality fabric tailors smartly and gives superb service. Over 80 million yards of it have already been used to help equip America's fighting men, and it is proving itself under the toughest climatic and combat conditions of global war. This fabric, Sanforized Shrunk* and color-fast to sun, water and perspiration, will meet *your* post-war uniform needs. When the time comes to order them, choose from a wide range of popular colors — for long-lasting good looks insist on Reeves Army Twill.

*Residual shrinkage less than 1%

THE REEVES FABRIC GROUP INCLUDES: *Reeves Army Twill • Glengarrie Poplin • Reeveking Gabardine • Byrd Cloth • Martine Herringbone • Reeves Sateen • Warrior Twill*

Mills: Mill No. 1, Greenville, S. C. and Woodruff, S. C. Fairforest Finishing Co., Spartanburg, S. C.

REEVES BROTHERS, INC.

54 WORTH STREET • NEW YORK 13, N. Y.

Representatives in Atlanta • Boston • Chicago • Dallas • Los Angeles • Philadelphia • St. Louis • Montreal • Toronto

Dependability **PRE-PROVEN!**



A-P *Built*

HYDRAULIC LANDING FLAP ACTUATING CYCLINDER

This long, narrow cylinder is built to extreme measures of accuracy for positive, trouble-free operation.

Every day, on A-P designed test racks, specially trained men and women put A-P Hydraulic Aircraft Controls through combat conditions and lifetime tests. These tests *pre prove the dependability* of A-P Aircraft Controls for field and operations use.

Originated at A-P, these test methods are so successful in guaranteeing the quality of A-P Aircraft Controls, that other manufacturers are adopting them and for the same reasons.

Automatic Products Company, with its proven ability to control Freon in refrigeration valves, finds the control of oil in hydraulic valves a familiar subject. As a result, with control manufacturing techniques successfully established, A-P produces Hydraulic Aircraft Controls of superlative quality—accurate and dependable.

This knowledge, manufacturing skill, and production capacity can be put to work for your advantage too! Write us about any control or production problems that you have. Perhaps we can help you solve it economically.

Check the coupon for YOUR copy of new Aircraft Control catalog.

AUTOMATIC PRODUCTS COMPANY
2484 North Thirty Second Street
Milwaukee 10, Wisconsin

Gentlemen: Send me copy of your "Aircraft Control Devices" catalog.

Firm Name_____

Address_____

City_____ State_____


Individual_____

AUTOMATIC PRODUCTS COMPANY

2484 North Thirty-Second Street • Milwaukee 10, Wisconsin

an aircraft . . .

FORGING



Deck Landing Hook Forging requires special die design with close heating and processing control to form it.

Absolute Reliability in this Deck Landing Hook Forging

is obtained by forging this unit so that the metal is uniformly distributed throughout the entire thin sections of the hook, and by concentration of fiber flow lines where the greatest shock and stress occur in service. This required maintaining close forge temperature control and several quick blows in the hammer to assure uniformity in the thin sections and to avoid cold working the metal. The how of obtaining strength and toughness in unusual forgings may be discovered through the broad experience of our engineers. It has been our privilege throughout 31 years of technical production effort to bring the utmost IMPROVEMENT OF METALS BY FORGING to hundreds of manufacturers of operating mechanisms. A talk with one of our forging engineers may reveal the units of your production which can be improved by using forgings to meet new peacetime conditions.

DROP FORGINGS

THE STEEL IMPROVEMENT & FORGE CO.

960 East 64th Street CLEVELAND, OHIO

Compounds and Equipment for Metal Finishing



REMEMBER: Metex *Aero* Compounds have been specifically developed for faster, — positive cleaning of all metals used in modern aircraft and engine production.

WRITE FOR *Free* DATA SHEETS

MAC DERMID

INCORPORATED

WATERBURY 88, CONNECTICUT

WRITE ONE OF THESE SERVICE ORGANIZATIONS FOR FREE DEMONSTRATION

NEW YORK	DETROIT	CHICAGO	CLEVELAND	ST LOUIS	TORONTO—CAN
Udylite Corp. (L I City)	Udylite Corp Wagner Bros	Udylite Corp. Geo A Stutz Mfg Co.	Udylite Corp McGean Chem. Co	LaSalco, Incorporated	Clark Industrial Supplies Co

hi-g
Remote Valve Controls
that reduce weight



General Controls' **hi-g** Electro-magnetic valves control important aircraft functions, such as propeller feathering, wing flap, landing gear, anti-icing and temperature controls.

hi-g valves are fast-acting, compact, light in weight **hi-g** indicates their positive ability to operate in any position, regardless of vibration, acceleration or change of motion

Designed for continuous or intermittent duty, **hi-g** valves are available in more than a score of types for handling aromatic or domestic gasolines, vapors, air, steam, water, hydraulic and lubricating oils, and anti-icing fluids under pressures up to 3000 lbs. or more. They are supplied in a wide range of AN pipe sizes or tubing connections, and AN electrical connectors. Normally open, normally closed, single seated, pilot piston operated and 3 or 4-way selector valve types.

Write or wire today for complete engineering data and descriptive bulletin

A LIGHTWEIGHT CHAMPION

General Controls' type AV-1, pictured above weighs only 8½ ounces. This valve is designed for cabin heating, oil dilution and anti-icing applications. Packless, two-wire, current failure, normally closed, direct current, magnetic valve



VIBRATION RESISTANT hi-g valves can be engine-mounted. On trucks, tractors, locomotives, tanks, ships, graders and other moving equipment, they simplify plumbing—save materials, space, weight, time and money


hi-g
GENERAL CONTROLS

Wartime Manufacturers of Electro-Magnetic and Temperature Controls for Aircraft

Peacetime Manufacturers of Automatic Pressure, Temperature, and Flow Controls

901 ALLEN AVENUE, GLENDALE 1, CALIFORNIA

BOSTON • NEW YORK • PHILADELPHIA • DETROIT • CHICAGO
CLEVELAND • DALLAS • DENVER • SAN FRANCISCO • ATLANTA



FIGHTING STARS OVER BERLIN

There they go again . . . American bombers over Berlin. Guided by star American pilots . . . manned by star American crews . . . powered by star American engines . . . produced by star American workers.

For these fighting planes over Europe and other theatres of war, Lawson workers have contributed many types of precision aircraft engine parts. Lawson employees, star workers in the battle for victory, are again being honored for their long record of war production.

This new fighting star which adorns our "E" pennant marks the third citation received for meritorious war service in a highly specialized field. Lawson workers dedicate themselves anew to the task of producing star war materiel to bring the day of victory closer.

FIRST "E" AWARD April 29, 1943 — SECOND "E" AWARD October 30, 1943 — THIRD "E" AWARD May 17, 1944

LAWSON

Established 1933

Machine and Tool Company

MALDEN, MASS.

MANUFACTURERS OF PRECISION MACHINE TOOLS AND AIRCRAFT ENGINE PARTS

FROM ALL ANGLES



. . . the superiority of FLIGHTEX is apparent. It's lighter, stronger, smoother fabric that surpasses U.S. Army and Navy specifications. No wonder each year more manufacturers buy more FLIGHTEX than any other airplane fabric.

World's Premier Airplane Fabric — FLIGHTEX FABRIC

FLIGHTEX


TEXTRON, INCORPORATED • FLIGHTEX FABRICS DIVISION
350 Fifth Avenue New York 1, N. Y.
Leading Manufacturers of Fabric and Tapes for the Aircraft Industry
Export Representative—Aviquipo, Inc. 25 Beaver St., N. Y. Cable Address—"Aviquipo"

RESALE DISTRIBUTORS

AERONAUTICAL TRADING CO. Jamaica, N. Y.
AIR TRANSPORT EQUIPMENT INC. Garden City, N. Y.
AVIATION SUPPLY CORP. Hapeville, Ga., Orlando, Fla., Charlotte, N. C., Nashville, Tenn.
BOB TRAUBA AERO SUPPLY, Pittsburgh, Pa.
INTER CITY AVIATION INC. East Boston, Mass.
KARL OTT, York, Pa.
LEAVENS BROS. AIR SERVICE, LTD. Toronto, Canada.
PACIFIC AIRMOTIVE, Burbank, Cal., Oakland, Cal.
SNYDER AIRCRAFT CORP. Chicago, Ill., Columbus, Ohio
SUPPLY DIVISION INC. Robertson, Mo., Memphis, Tenn.
THE AIRCRAFT STEEL & SUPPLY CO., Wichita & Kansas City, Kansas, Dallas, Texas.
VAN DUSEN AIRCRAFT SUPPLIES, Minneapolis, Minn., Waterloo, Iowa

Landing Fields Overseas—or "Terminals" in your Own Plant

'Phone your Transportation Advisor for help in Planning Truck Systems to Speed your War and Peace Materials Safely— at Reduced Cost



A manufacturer of airport landing mat wanted better "terminal facilities" for handling his materials. He found them when he consulted the E-P Man. Together they developed the Truck System illustrated above, for transporting formed steel units in volume between press, paint and shipping departments. Note only half the load is supported by the Truck.

With Elwell-Parker equipment he has increased his output—reduced his costs materially—cleared his aisles—established higher safety records.

You can project *your* load-transportation program with equal confidence of new savings ahead. The Elwell-Parker Field Engineer—your Transportation Advisor—will help you plan a Truck System to handle engines, parts and assemblies in modern Unit Loads—to speed your processes, reduce costs, assure employees' safety.

His experience—plus ours covering more than 35 years—is at your call.

The Elwell-Parker Electric Company, 4125 St. Clair Avenue, Cleveland 14, Ohio.




DIAL THE E-P MAN TODAY!

Albany 2-4095	Columbus ... AD 4824	Kansas City ... VA 7021	New Orleans, MA 6316-C
Birmingham ... 3-3323	Denver ... GE 5500	Los Angeles ... PR 5911	Philadelphia ... LO 3710
Boston ... COM 5522	Detroit ... MA 2233	Memphis ... 8-1648	Pittsburgh ... AT 6734
Buffalo ... GR 7664	Ft. Worth ... 4-6184	Milwaukee ... MA 7817	St. Louis ... LA 4545
Charlotte ... 5026	Greenville ... 534	Minneapolis ... GE 3247	San Antonio ... TR 3653
Chicago ... SUP 7420	Indianapolis ... LI 3131	Montreal ... HA 7191	San Francisco ... GA 1827
Cincinnati ... MA 0650	Jacksonville ... 5-1384	New York ... CO 7-0797	Seattle ... EL 5722
Cleveland ... MA 8915			Syracuse ... 2-9596
			Toronto ... WA 1478

ELWELL-PARKER

POWER INDUSTRIAL TRUCKS





Stay at Your Battle Stations!

MANAGEMENT
LABOR

—the 5th War Loan Drive is still on.

July 29th is the last pay day in the Drive.

The U. S. Treasury has set the overall goal at $16,000,000,000 —$6,000,000,000 from individuals alone. This is the biggest sum ever asked of the American people—*and it must be raised!*

Keep fighting. The 5th War Loan is a crucial home front battle of tremendous importance to the total war effort.

Tighten up your 5th War Loan Drive organization. Step up your solicitation tempo. Drive! Drive!! Drive!!! Hit your Plant Quota's 100% mark with a bang that'll proclaim to all the world that the U. S. Home Front is solidly in back of the Fighting Front.

Need help? Need ideas? Call on the Chairman of your War Finance Committee. He's standing by.

Here's the Quota Plan:

1. Plant quotas are to be established on the basis of an *average* $100 *cash* (not maturity value) purchase per employee.
2. Regular Payroll Savings deductions made during the drive accounting period will be credited toward the plant quota.
3. Employees are expected to contribute toward raising the cash quota by buying extra 5th War Loan Bonds. 1—Outright by cash. 2—By extra installment deductions. 3—By extra installment deductions plus cash.

Example—JOHN DOE MFG. CO.—1,000 Employees

1,000 Employees x $100 . . $100,000 Cash Quota

Regular payroll deductions during the eight weekly payroll accounting periods of June and July. 30,000

$70,000 (to be raised by sales of extra Bonds)

5TH WAR LOAN

BACK THE ATTACK—SELL MORE THAN BEFORE

The Treasury Department acknowledges with appreciation the publication of this message by

AVIATION

★ ★ *This is an official U. S. Treasury advertisement—prepared under the auspices of Treasury Department and War Advertising Council.* ★ ★



Success or failure in metal fabrication and finishing depends on chemical cleanness. Paint and other finishes will temporarily cover an unclean surface but unless rust and rust producers, scale, grease and oil are eradicated, the finish breaks down prematurely leaving the metal unprotected.

A recognition of this fact has led to much research and development of new and better materials and methods for cleaning and protecting metal surfaces. The American Chemical Paint Company has, for over a quarter of a century, devoted its research facilities to this particular chemical field, originating and developing products which have eliminated many problems of the metal-working industries.

These developments found ready acceptance in the automotive industry in pre-war days and, more recently, in the field of aeronautical construction, are affording material assistance in speeding and benefiting war production.

DEOXIDINE—By reason of its ability to eradicate rust and produce a steel surface clean chemically as well as mechanically Deoxidine overcame one of the more serious difficulties of the automotive industry in its early days. Today in aircraft production Deoxidine is used to clean and condition metal surfaces for painting and also to clean and prepare aluminum surfaces to receive a uniform "Alrok coating.

KEMICK—*A Heat Resisting Paint*—In the pioneer automobile days, Kemick provided a means for durably coating exhaust manifolds and exhaust lines that attained temperatures too hot for ordinary paints—eliminating the costly and more fragile coatings of vitreous enamel. Today it provides protection for aircraft exhaust stacks and rings as well as for automotive exhaust lines.

RODINE—*Pickle Bath Control*—Rodine made possible substantial savings in pickling acid, reduced the dissolution of metal and improved pickling conditions to an extent that pickling became a scientifically-controlled operation.

DEOXYLYTE—Early in the automobile age, Deoxylyte was developed as a means of controlling rinse baths in the metal cleaning process at the proper pH so necessary to durable finish coats.

PEROLINE—Developed for the auto-body builder as a means of preventing rust and thus reducing the amount of Deoxidine required to clean bodies and sheet metal parts in preparing them properly for painting. Peroline is a combined cleaning chemical and oil which removes blushes of rust, destroys rusters on the material and preserves the clean surface.

CUPRODINE—Steel surfaces are treated and coated with copper without the use of current. Cuprodine provided a new type of lubricant which was rapidly adopted by the steel industry in the drawing of wire, and by others to facilitate difficult drawing of steel shell cases and machine parts.

OTHER PRODUCTS—The above are but a few developments of ACP research. Other products none the less important include:

Pickle Bath Toner—Improves pickling of oily work
Cuprotek—Copper Coating Protection
Flexol—Soldering Fluxes
Rideline—Alkaline Cleaners
Ridosol—Improves detergent properties of Alkali Cleaners
Solvent No. 3—Speeds paint and enamel removal
Litheform—Makes paint adhere to zinc surfaces
Metal Stripping Solution No. 2—Provides a rapid and efficient method of removing coatings of copper, lead zinc, cadmium and magnesium.

These are typical of the many chemical products which have been developed by the American Chemical Paint Company for use in cleaning, pickling, and the fabrication of metals. American Chemical Paint Company solicits an opportunity to assist you.

AMERICAN CHEMICAL PAINT CO.

ACP

CHEMICALS ACP PROCESSES


Please send me general Technical Service Data Sheets on

Name *Title* ☐ CUPRODINE

Company ☐ CUPROTEK


Address

AMERICAN CHEMICAL PAINT CO., Ambler, Pa.



Below—Duplicating turret top shape from a plaster model.

Above—166 483 square feet devoted to die production exclusively



Above—Small lamination for electric motor

ALLIED PRODUCES DIES FOR THE "Stamp of Approval"

Buy More War Bonds

Long before the war, precision dies produced by Allied Products Corporation enjoyed the automotive industry's "stamp of appcoval". Today, Allied is engaged 100% in the production of dies and parts for manufacturers of war material. But the moment the shooting stops—or before, if the war production board desires—Allied will be ready to start producing again for the makers of cars and trucks and their suppliers.

Dies of all types and sizes up to the largest, including those where extreme accuracy is required, are an Allied specialty. Modern equipment from Swiss Jig Borers to a 23-foot Ingersoll Milling Machine, speeds the operations of experienced craftsmen. Additional equipment, including electric cranes with a handling capacity of 50 tons, expedites the flow of finished dies and parts. Bring your stamping die problems to Allied for sure solution!

"IT'S AN ALLIED PRODUCT!" Allied Products Corporation and its divisions, Richard Brothers and Victor-Pressmaster, in Detroit and Hillsdale, Michigan, also make The original patented R B Interchangeable Punch and Die, plastic molds, jigs and fixtures, precision hardened and ground parts and other special products.

ALLIED PRODUCTS CORPORATION

Executive Offices: 4646 Lawton Ave., Detroit 8, Mich.

All their plants have now added a star to their Army-Navy "E" pennants

HIGH TEMPERATURES

...as they affect the properties and usefulness of metals

A metal's fitness for high temperature use is usually measured by two yardsticks

1. *Its resistance to oxidation*
2. *Its strength and hardness*

at the temperatures it must undergo.

Getting a good rating on one of the two counts isn't enough. A thoroughly satisfactory metal for most heat-resisting use must get a high mark on both.

Resistance to oxidation is measured in terms of freedom from scaling and intercrystalline attack. High strength won't matter for long if a metal oxidizes and scales, thus reducing in cross-section, or if intercrystalline change saps its vitality. Also, in many applications, the scale that flakes off is one more complicating factor.


On the other hand, an oxidation-resistant metal that is too soft or weak to support its required load in the high temperature range is out from the start.

Strength for heat-resisting service is measured by a series of tests, the most important of which is the creep strength of the material.

In this test, the metal is subjected to known stress under controlled temperature and atmosphere conditions. The results are reported as pounds of stress necessary to produce an elongation over a prolonged period of time.

Along with this basic test for high temperature usefulness are others which determine the endurance limit, impact strength, short time tensile strength, and hot hardness . . . all of which help give a "yes" or "no" to the metal's selection for high temperature use.

The results of these tests in the chart below show the reasons for the remarkable high-temperature service life of the nickel chromium alloy Inconel.



For most purposes . . . and especially for applications where mechanical stress is involved . . . Inconel is outstanding even among the heat-resisting INCO Nickel Alloys for service at the highest temperatures. Inconel fights off progressive oxidation. It is little affected by thermal shock, or sudden, wide swings in temperature. It holds up well under both suddenly applied and constant load and it is a workable material which can be formed into complicated shapes and welded to produce ductile joints that endure constant vibration without cracking.

An aeronautical use that points up some of the properties of Inconel is the collector tube on the fuel-air mixture indicator for bombers and fighters. Continuously exposed as it is to the direct blast of corrosive exhaust gases at 1400°F., the tube must combine freedom from oxidation with strength at high temperatures. No other material has been found which does this particular job as well as Inconel.

The many heat-resisting properties of Inconel are demonstrated, perhaps even more graphically, by the exhaust manifolds used on Pan American Clippers.



A collector ring for a Pan American Clipper must be able to withstand temperatures ranging from a normal 1500°F. up to white heat on take-off—far above the temperatures where most metals would weaken, warp and scale away. The hot strength of Inconel is its chief value as a material for exhaust manifolds

Here, the same red-hot blast of exhaust gas is encountered as in the collector tube. Intense vibration and exceedingly quick temperature changes are piled on top of the corrosive and strength sapping attack of the hot gas. Despite these destructive factors . . . and the very light gauge of the sheet used . . . many of the Inconel manifolds have seen more than 5000 hours of flying service *without repair.*



Continuously exposed to aircraft exhaust flames at around 1400°F., this collector tube for a fuel mixture indicator is made of strong heat-resistant Inconel. Tube is product of Cambridge Instrument Co., New York, N. Y.

For further information regarding the properties and working of INCO Nickel Alloys, write for a copy of the new booklet "INCO Nickel Alloys for the Aircraft Industry." A copy is yours for the asking.

THE INTERNATIONAL NICKEL COMPANY, INC.
67 WALL STREET NEW YORK 6, N. Y.



A LEADING COSMETICS MANUFACTURER REPORTS:

"We cut down the size of our gift boxes and standard packages to effect an over-all saving of approximately 25% of the paper and cardboard, standardized our window displays and eliminated all die-cuts, as well as steps, shelves and secondary planes. We also folded all displays in half to save more than 50% of the paper and paperboard normally used."

A BIG PLATE GLASS COMPANY REPORTS:

"Our 1944 Color Book was reduced in size and quantity, resulting in a paper saving of 136,000 pounds. Our Color Cards, of which four or five million are used annually, were reduced in size at an approximate reduction of 50% in paper tonnage. We have eliminated our Dealer Sales Portfolio. Our Color Book has become a 'self mailer,' eliminating need for envelopes."

Mr. Manufacturer,

CAN YOU TOP THESE?

The quotations used in this advertisement are from responses to the A. N. A. Committee of Paper Saving

ONE OF THE TOP LIFE INSURANCE COMPANIES REPORTS:

"In 1944 we will continue to specify lighter weights of paper wherever possible and take all possible steps further to reduce paper tonnage. We are instructing our field offices to scrutinize carefully all requests for printed material and to disapprove all requests for quantities that appear excessive."



A FAMOUS ADDING MACHINE COMPANY REPORTS:

"In advertising and promotion we are using about 30% of the amount of printing and paper used in 1941 — that represents about 2/3 saving. However, further savings will be effected whenever possible this year as last."

Remember—

PAPER IS WAR POWER




USE LESS—SAVE ALL WASTE PAPER!

This advertisement contributed by this publication and prepared by the War Advertising Council in cooperation with the War Production Board and the Office of War Information.

HARNESS to Keep 1200 Horses Going Strong

...yet electronically QUIETED!



Titeflex radio shielded harness No. C26980 for Wright Cyclone Engines which power Flying Fortresses. Sleeves are Natvar extruded vinylite tubing, and identification markers are Natvar

Titeflex harnesses physically protect high tension ignition systems from magneto to plugs and, at the same time, shield vital lines of communication from the principal source of interference—the ignition system itself.

A tremendous job, when you stop to consider that these Titeflex harnesses perform in a wind stream of over 300 mph—with or without rain and ice, but always subject to vibration. And at temperatures ranging from 50°F. below zero up to 300°F. at the spark plug end!

We are proud of the fact that Natvar extruded vinylite tubings and identification markers are contributing to this performance.

What about *your* requirements? Write, wire, or phone us for deliveries either from nearby wholesaler's stock, or from our own.

Natvar

- Wire and cable identification markers
- Extruded plastic tubings
- Extruded plastic cordage
- Varnished tubings and sleeving
- Lacquered tubings and sleeving
- Varnished cambric—straight cut and bias
- Varnished cable tape
- Varnished canvas and duck
- Varnished cellulose acetate
- Varnished fiberglas cloth
- Varnished papers


Write for bulletins

THE NATIONAL VARNISHED PRODUCTS Corporation

TELEPHONE RAHWAY 7-2171 — CABLE ADDRESS NATVAR RAHWAY, N. J.

229 RANDOLPH AVENUE ★ WOODBRIDGE NEW JERSEY


7 NVP 1



EXTRACTOR POSTS

WITH WELDED ANTI-VIBRATION SIDE TERMINALS

NOW UNDERWRITERS' APPROVED



Extractor Post No 341001 (Tool-operated type), for 3 A G Fuses Welded side terminals Knob and body black bakelite Positive fuse grip Full visual shock-proof inspection Spring-actuated cup Specially designed grip prevents fuse from dropping out



No 342001 (Finger-operated type)

Resistance to extremes of shock, vibration and temperatures is provided by Littelfuse Extractor Posts with electrically welded side terminals By Littelfuse process, terminals are made integral with inside metal shell. Maximum conductivity is insured. Other Littelfuse improvements for dependability, durability, and convenience make these extractor posts outstanding examples of Littelfuse *complete circuit protection.*

SEND for B/P and ENGINEERING DATA. Ask for Samples

Littelfuse will be glad to counsel with you on safeguarding new equipment, or irreplaceable *present* equipment. Fuses, Fuse Clips, Fuse Panels, Circuit Breakers, Thermocouples, Fine Wire Products, Indicators, etc.

LITTELFUSE INCORPORATED

4757 Ravenswood Avenue, Chicago 40, Illinois
200 Ong Street, El Monte, California




---She's Not So Dumb

FIRST PRIZE for speeding production goes to SPEEDI-DRI—the quick-acting oil- and grease-absorbent that puts a sure, slip-proof footing under employees who have to work around machines that drip oil and grease onto the floor. Sure-footed workers move faster when the danger of slipping is eliminated by SPEEDI-DRI. Application of this light-reflecting, granular material will not only absorb the daily oil deposits but will soon draw the old accumulations of oil and grease from the floors. SPEEDI-DRI also retards fire, saves shoes from oil-rot, helps prevent industrial skin-diseases, reduces porter-labor, improves morale, brightens the plant, cuts insurance costs. Write for literature and FREE SAMPLE.

SUPPLIERS East—Refiners Lubricating Co., New York 1, New York.
Midwest & South—Waverly Petroleum Products Co., Philadelphia 6, Pa.
West—Waverly Petroleum Products Co., Russ Bldg., San Francisco 4, Calif.

SPEEDI-DRI
OIL AND GREASE ABSORBENT



Something new in pressure sealing tapes. Filmonize printed tape in a complete color range, one, two or three colors *on one roll*—now used in war plants for identification because the colors won't fade and the printing can't rub off—for labeling and sealing in one operation because that saves time and production cost—in place of decals because Filmonize goes on ten times faster than decals and lasts forever. Place a trial order with your distributor and let your experience prove, *you've never had as good a tape.*

Filmonize Sets New Standards

- Easy to use—strips cleanly off the roll.
- No "curl-back"... no tangle... no waste
- Fade-proof colors... protected sealed in.
- Widths from ½" to 18" throughout the Filmonize line

Filmonize
SELF-SEALING TAPES

INTERNATIONAL PLASTIC CORPORATION MORRISTOWN, N. J.

No Oil "Absenteeism"

IN BEARINGS SEALED WITH

American Bearing FELTS!

To keep lubricants *in*—and to keep *out* dust, grit, moisture and other saboteurs of non-stop bearing performance—use fine quality American Bearing Felts. These special Felts, made from white, fine fibre new wool, meet the most exacting requirements for all types of ball and roller bearings.

Frictionless contact is the secret of Felt's admitted superiority. Felt Retainers alone fit snugly to the shaft—supplying lubrication *when* and *as* needed—yet set up no friction to slacken speeds. By selecting Bearing Felts of the correct density, lubricants of any viscosity can be employed for high or low shaft speeds.

Product engineers are available to explain the latest techniques in bearing lubrication—or to advise on any other Felt application.

American Felt Company

TRADE MARK

General Offices: GLENVILLE, CONN.


Sales Offices at: New York; Boston; Chicago; Detroit; Philadelphia; Cleveland, St. Louis, San Francisco; Dallas, Seattle; Los Angeles

PRODUCERS OF FINEST QUALITY FELT PARTS FOR OIL RETAINERS, WICKS, GREASE RETAINERS, DUST EXCLUDERS, GASKETS, PACKING, VIBRATION ISOLATION, INSULATION AND SOUND ABSORPTION FELTS

G-M TYPE 27 RELAY

SMALL — COMPACT

SENSITIVE — POWERFUL



A MULTI-POLE RELAY FOR AIRCRAFT AND MOBILE EQUIPMENT

The G-M Type 27 relay is designed for permanence of adjustment. Exceeds usual aircraft specifications for temperature, humidity, elevation, salt spray, requirements. The following are actual examples of type 27 characteristics:


1. Type 27, specification 12700, single pole single throw relay—contact pressure 50 grams minimum—acceleration 10g—coil power 90 milliwatts at 25° C ambient, contact gap .010 inch, weight 5¼ ounces.
2. Type 27, specification 12746, three pole relay with two double throw contacts and one single pole normally open contact—contact pressure, 30 grams minimum; acceleration, 10g; pick up 3.75 milliamperes maximum with 10,550 ohm coil (148 milliwatts), contact gap .010 inch, weight 5½ ounces.

Comparable relays with a variety of contact forms and coil resistances can be supplied. We invite your inquiries.

G-M LABORATORIES INC. Buy WAR BONDS & STAMPS

4319 NORTH KNOX AVENUE, CHICAGO 41, ILL.

DILLON PRECISION DYNAMOMETER



for STATIC TESTING

for TENSILE TESTING

PROMINENTLY USED BY

Consolidated Aircraft	Lockheed Aircraft
Union Steel Products	Gar Wood Industries
Goodyear Tire	Union Pacific R R.
E. I. DuPont	Fisher Body Co.
Chrysler Corp.	Hamilton Propellers

and thousands of others!

ACCURATE and light weight. Only 8 lbs. 4 oz. Measures just 8¼"x6¼"x3". Capacities from 0-500 lbs. up to 0-10,000 lbs. Hundreds of uses in lab. or shop. Priced low. Delivery from stock.

WRITE FOR ILLUSTRATED FOLDER


W. C. DILLON & CO., INC. 5416 W. HARRISON STREET CHICAGO, ILLINOIS

BACK OF THE BREN GUN



Below:—Finishing and removing burrs on Bren Gun port piston






Above—Close-up of finishing on extension post

Brightboy

The Bren Gun is precision-made. On many of its parts where close tolerance work is a "must," Brightboy's resilient rubber and abrasive combination has materially speeded production and improved the finish.



Brightboy is back of the Bren Gun and hundreds of other implements of war contributing an entirely new conception of precision-quality finishing. On the basis of its war production record, Brightboy will continue to bridge the gap between the grind and the buff in peacetime production applications.

A wide variety of Brightboy shapes and sizes give like effectiveness both to machine and manual production. Your dealer will furnish you with Applications Data and Brightboy prices. Our Service Department will cooperate to show you how you can save time—improve quality—with rubber-cushioned Brightboy.

BRIGHTBOY INDUSTRIAL DIVISION

WELDON ROBERTS RUBBER CO.

Newark 7, N. J.

WELDON ROBERTS

Brightboy

Make sure of your Engine Mechanic's License!

Prepare for your CAA exam with this practical Question and Answer book.

Here are hundreds of CAA examination questions and their correct answers designed to test your knowledge and provide the practice you need in actual examination procedure. The questions cover all the necessary material for a CAA airplane engine license—the answers are clear, up-to-date, accurate, the kind of information you will be expected to give on the exam. Use this book to check up on your weak points, to acquaint yourself with the type and scope of the examination, to insure yourself in advance of a better grade.



Just Published!

Airplane Engine Mechanics Questions and Answers

By BALLA NUSBAUM
Instructor, Flight Engineer School, Pan American Airways; Instructor in N.Y.C. Board of Education War Industries Training Program; Licensed Airplane and Engine Mechanic; Ground Instructor and Pilot

and AUGUSTIN AILWORTH
Inspector, American Export Airlines; Consulting Editor of Aviation Handbook; Formerly Instructor in Manhattan Trade School of Aviation Trades; Licensed Airplane and Engine Mechanic and Ground Instructor

McGraw-Hill-Whittlesey Practical Manual

206 pages, 7¼ x 4¾, 7 illustrations, $3.00

A practical manual to help you prepare for licensing by the Civil Aeronautics Administration. The full scope of the engine mechanic's work is covered in nine big sections dealing with power plant principles, engine operation and test, maintenance and procedure, and the various airplane systems. Each section starts with a brief outline of fundamentals to help you review essential background material. Then from 50 to 200 questions on the subject are given, including both multiple choice and essay types, followed by the correct answers.

Read this list of chapters

CAA Regulations and Preparations for Licensing Engine Mechanics
Power Plants in General
Lubrication and Oiling Systems
Fuels, Induction and Fuel Systems, and Carburetion
Ignition and Electrical Systems
Engine Instruments
Engine Operation and Test
Cooling Systems
Propellers

McGRAW-HILL ON-APPROVAL COUPON

McGRAW-HILL BOOK CO., Inc., 330 W. 42nd St., New York 18, N.Y.

Send me Hobbard and Dilworth's Airplane Engine Mechanics Questions and Answers for 10 days' examination on approval. In 10 days I will send $3.00 plus few cents postage, or return book postpaid. (Postage paid on cash orders.)

Name .....

Address .....

City and State .....

Position .....

Company .....

Av. 7 44

(Books sent on approval in U.S. and Canada only.)

Here's Your Post-War Model Now




...the New Scott

Automatic, Steerable and Full-Swivel

Tail Wheel Assembly

(MODEL 3-24)



● You have long had the need. Three years ago Scott Engineers began to design, build and test automatic steerable and full swivel tail wheel assemblies to meet that need. Today—the new Scott "3-24" Tail Wheel Assembly is a perfected and practical reality—ready for service on nearly all makes of light aircraft.

Providing the inherent safety and maneuverability in taxiing of the steerable type, including more effective control in strong cross-winds, this new model also provides the advantages of the full swivel assemblies, easier ground handling — sharper taxiing turns — protection against damage to parts from severe usage.

Thoroughly tested for field service, the Scott "3-24" stands out as an outstanding development embodying the greatest number of potential service hours ever built into a tail wheel assembly!

1 Rugged Universal Osterstroml Bracket fits both 1½" and 1¼" spring leaves

2 Patented Automatic Mechanism—dependable longwearing pro—tected by streamlined steel cap.

3 Large area Hard Bronze Swivel Bushing grooved for lubrication easily replaced, sealed with metal dust cap

4 Single Arm fork of drop forged chrome alloy gives maximum freedom from mud and ice accumulation.

5 Wheel: High strength aluminum alloy castings rigidly locked with three AN bolts. Large Timken Roller Bearings grease packed for long life. Felt grease seals and light dust caps.

6 Tire: 6 x 2 solid cushion with steel wire bead. Can't come off.

Available from authorized Scott Distributors or from Scott Chartered Dealers

Get Details! Here's post-war thinking too—a practical, profitable dealer program for post-war selling. Full explanation on request.

Scott

AVIATION CORPORATION

Lancaster, N. Y., U. S. A.

SCOTT AVIATION CORPORATION

214 Erie Street Lancaster, N. Y.

As the semaphore cautions **DANGER**...



...the Lisle plug gives

ADVANCE WARNING of aircraft engine wear!

When ferrous metal particles appear in the aircraft engine lubricant they give *advance warning* of undue wear. LISLE MAGNETIC DRAIN PLUGS promptly detect this condition. The powerful magnet in each LISLE plug draws the metal particles from the circulating lubricant, gives prompt indication of the danger before serious damage can occur. Low cost — long life — invaluable security. For an extra margin of safety, specify LISLE plugs instead of ordinary drain plugs. • ENGINE DESIGNERS: Write for data and samples, no cost or obligation.

LISLE CORPORATION

Box Clarinda, Iowa

Lisle Magnetic DRAIN PLUGS

1919's VISION

IS 1944's REALITY



A DREAM COME TRUE—a completely coordinated and integrated air-rail express service!

Ever since the fast, safe, personalized handling of shipments we know as Express Service was developed in 1839, it has been distinguished by adapting new techniques.

From the moment the airplane was proved capable of sustained flight, alert Railway Express began to plan how this new transportation vehicle could be made to serve the needs of industry and the public.

Step by step the way was proved. *1919* saw the first chartered flight for Air Express on a definite route, New York to Chicago. *1927* was a real milestone year. It saw the establishment of the nation's first Air Express network serving 26 airport cities coast-to-coast, and the formation of Air Express Division of the Express company: the essential step toward providing a responsible, co-ordinated air-rail express service. *1944*—Air Express directly serves 350 airport cities at 3-mile-a-minute speed, and 23,000 Railway Express offices the nation over through integrated Air-Rail service. International Air Express to over 60 foreign countries.

From 5 160 shipments in four months of 1927 to over 1,500,000 in 1943—that's the record of Air Express Serving the war effort today spectacularly and successfully. Air Express coordinated with Railway Express will serve you well tomorrow.

RAILWAY EXPRESS AGENCY AIR EXPRESS

NATION-WIDE AIR RAIL SERVICE

Just Published!



The essential techniques of aircraft operation for long-distance flight

A highly practical book for flight crews and operators of long-distance aircraft, combat and transport alike—who want to know how to achieve maximum utility from aircraft they fly. Entirely devoted to how-to-do-it material, the book explains principles of efficient engine operation, principles and use of airplane cruising charts, methods of cruising control, pre-flight planning, and controlled flight through use of the "howgozit" chart.

LONG-RANGE FLIGHT

By Colin Hugh McIntosh

Chief Navigator, American Airlines, Inc.

177 pages, 5½ x 8½, 40 illustrations, $2.50

This basic and nonmechanical explanation of long-range flight operation not only tells you clearly exactly what to do but also *why* to do it. The book explains engine performance and shows how to use the power control chart, the power calculator and tells how to achieve best economy with the fuel-air mixture.

The book will show you.—

—the various factors governing cruise performance.
—the four methods of cruise control
—how a constant-power cruise control is planned from the cruise log chart
—what method of cruise control to use in order to achieve maximum efficiency for long-range flight.
—the advantages and disadvantages of the different maximum-range cruise control charts.
—how to operate in case of engine failure

Two chapters are devoted to the detailed and practical explanation of the planned flight. These chapters will show you how to make out a flight analysis form for the different types of cruise control, including constant-instrument-air-speed flight analysis and maximum-range flight analysis; how to select and make out the flight plan, how to calculate engine-failure analysis, and finally, how to plot and use the graph of actual flight performance.

McGRAW-HILL ON-APPROVAL COUPON

McGraw-Hill Book Co., Inc., 330 W. 42nd St., New York 18, N. Y.

Send me McIntosh's LONG-RANGE FLIGHT for 10 days' examination on approval. In 10 days I will send $2.50 plus few cents postage, or return book postpaid. (Postage paid on cash orders.)

Name .....


Address .....

City and State .....

Position .....

Company ..... Av 7 44

(Books sent on approval in U. S. and Canada only.)



You Can Get . . . the RIGHT SPRING —from RELIABLE

Springs are something which can't be trademarked—you can't tell by looking at one, who made it. But if the springs in your product are RELIABLE Springs, you can be sure that they are reliable in every sense of the word. Once your demands are determined, Reliable is equipped to observe them within close limits.

Reliable Springs conform to exacting standards of accuracy in size and shape. All factors, such as toughness, uniform resiliency, perfect seating, high resistance to fatigue and corrosion, are carefully considered in every instance. Reliable uses the most modern methods of forming, finishing, tempering and heat-treating. Our springs are used for many aircraft purposes and for sensitive instruments and electrical apparatus.

Reliable Springs of almost every type have of course been furnished for all the mechanism of war. When you convert to peacetime production, Reliable can provide springs or light stampings that will enhance the serviceability of your product.


Let us quote on your requirements. Catalog 44 will be mailed on request.

THE RELIABLE SPRING & WIRE FORMS CO.
3167 Fulton Road Cleveland 9, Ohio

Representatives in Principal Cities

YOU CAN RELY ON
Reliable Springs
ROUND AND FLAT WIRE SPRINGS · COILS · HOOKS · BENDS · LIGHT STAMPINGS

MORGANITE BRUSHES



When a machine constructor chooses a grade of brush for a given motor or generator, he wants to know that the material is uniform and can be uniformly reproduced over a period of years.

In service also, operating and maintenance men want brushes that give identical results when replacements are required.

Through the years, Morganite brushes have remained uniform within close limits. Because constructors and operators know they can depend on Morganite brushes, you will find them on many heavy duty machines.


When a brush problem arises, communicate with Morganite and obtain an honest helpful answer.

MORGANITE BRUSH COMPANY, Inc.
Long Island City 1, New York

TRADE MARK

5 In a Series of Factors Essential to Maximum Brush Efficiency

. . . uniformity of material necessary for continued brush satisfaction



Actual Size

CAT-HEADS

Laminated Plastics have been used for more than fifty years. The automotive and aviation industries grew up with them. The present war has uncovered many new uses for Phenol Fibre and Vulcanized Fibre.

In the post-war world, as at present, Taylor intends to maintain leadership on the strength of two qualities—(1) the ingenuity of Taylor engineering and (2) the Taylor Verifibre Process in which *all* raw materials are controlled by Taylor and checked and verified at every manufacturing step.

As an example of Taylor ingenuity, consider the "Cat's Head" illustrated above. The core is made of Phenol Fibre—to eliminate moisture absorption and provide high dielectric strength. But because an electric arc will not carbonize Vulcanized Fibre, the front and back of the "Cat's Head" are made of Vulcanized Fibre.

It is not too soon to discuss with our engineers the advantages of Laminated Plastics in the products you are planning. Write today.

Salute to
PENNSYLVANIA-CENTRAL AIRLINES
ON ITS EIGHTEEN YEARS OF SERVICE TO THE NATION

TAYLOR FIBRE COMPANY
LAMINATED PLASTICS. PHENOL FIBRE · VULCANIZED FIBRE
Sheets, Rods, Tubes, and Fabricated Parts
Norristown, Pennsylvania • Offices in Principal Cities
Pacific Coast Headquarters 544 S. San Pedro Street, Los Angeles

★ ★ ★ ★ ★ ★ ★ ★ ★ ★ ★

Now Ready

FLIGHT PREPARATION TRAINING SERIES

Published under the Supervision of the Training Division, Bureau of Aeronautics, U. S. Navy

THIS outstanding series of short texts has been produced under the supervision of the Training Division, Bureau of Aeronautics, U. S. Navy, to meet the special needs of intensified training courses for pilots in war time. The texts embody enough theory and background to provide the reader with an intelligent understanding of science and navigational principles but omit all duplicating and nonessential matter. The Series as a whole represents what is probably the first carefully planned and thoroughly integrated set of texts that has been available for preflight training based on Service standards.

MATHEMATICS FOR PILOTS
157 pages, 4¼ x 7⅛ 75¢

PHYSICS MANUAL FOR PILOTS
229 pages, 4½ x 7⅛ 90¢

PRINCIPLES OF FLYING
338 pages, 4½ x 7⅛ $1.50

OPERATION OF AIRCRAFT ENGINES
206 pages, 4¼ x 7⅛ 90¢

AIR NAVIGATION. PART I. Introduction to Earth
79 pages, 8¼ x 11, $1.00

AIR NAVIGATION. PART II. Introduction to Navigation
81 pages, 8¼ x 11, $1.00

AIR NAVIGATION. PART III. Dead Reckoning and Lines of Position
80 pages, 8¼ x 11, $1.00

AIR NAVIGATION. PART IV. Navigation Instruments
147 pages, 8¼ x 11, $1.50

AIR NAVIGATION. PART V. Relative Movement
118 pages, 8¼ x 11, $1.25

Examine them FREE

McGraw-Hill Book Co., 330 W. 42 St., N.Y.C., 18

Send me the books checked below for 10 days examination on approval. In 10 days I will pay for the books, plus few cents postage, or return them postpaid. (Postage paid on cash orders.)

Flight Preparation Training Series

- ☐ Mathematics for Pilots, 75c
- ☐ Physics Manual for Pilots, 90c
- ☐ Principles of Flying, $1.50
- ☐ Operation of Aircraft Engines, 90c
- ☐ Air Navigation, Part I, $1.00
- ☐ Air Navigation, Part II, $1.00
- ☐ Air Navigation, Part III, $1.00
- ☐ Air Navigation, Part IV, $1.50
- ☐ Air Navigation, Part V, $1.25

Name .....
Address .....
City and State .....
Position .....
Company .....

AV 7-44

How to fly *safely*

Practical rules for any pilot who wants to become a "million miler"



Here is a brand new approach to the problem of safety in flight—it analyzes the danger periods which all pilots go through, explains why and when they come, and shows you *that they can be avoided*. It tells you how to acquire the right mental attitude, correct technique, and the knowledge of what to expect—the three things that make up the formula for safe flying. This is a "must" book for all pilots—a book that will help you to learn by the mistakes of others—not by your own.

Just Published!

SAFETY AFTER SOLO

By JOHN R. HOYT

Lt. Comdr., USNR (Naval Aviator), formerly Superintendent of Aviation Training, U.S. Naval Air Station, Grosse Ile, Michigan; Inspector, General Inspection Division, Civil Aeronautics Division

336 pages, 5¾ x 8¼, 51 illustrations, 6 tables, $3.00

This is a clearly written, simple explanation of the facts every pilot must know to fly safely. It covers recent advances in aeronautics, both in practical flying and in the psychology of flight, giving you up-to-date, accurate information on methods and techniques for cross-country flying, essential facts about turns and landing, practical pointers on passing the CAA examination, important information on night flying, avoiding dizziness in turns, use of oxygen, etc., etc.

Read this list of chapter headings

PART I Flying for Fun
1 The Right Mental Attitude
2 Recognizing Weather: Thunderstorms
3 Recognizing Weather: Fog
4 Recognizing Weather: Icing
5 Compass Courses
6 What to Do in a Forced Landing
7 Planning and Making a Cross-country Flight

PART II Avoiding the Danger Period
8 Sharpening the Senses
9 What Every Pilot Should Know about Turns
10 How to Check Your Plane

PART III Getting That CAA Certificate
11 How to Fly Sixty Minutes an Hour
12 Five Difficult Maneuvers Made Easy
13 Good Morning, Inspector!

PART IV For Every Pilot
14 How to Use the Eyes at Night
15 Night Flying
16 Avoiding Dizziness in Turns
17 If You're a New Instructor
18 How High Can You Fly?
19 The Best Pilots Become Scared
20 How to Get 10,000 Hours

McGRAW-HILL ON-APPROVAL COUPON

McGRAW-HILL BOOK CO., Inc., 330 W. 42nd St., New York 18, N. Y.

Send me Hoyt's Safety After Solo for 10 days' examination on approval. In 10 days I will send $3.00, plus few cents postage, or return book postpaid. (Postage paid on cash orders.)

Name .....

Address .....


City and State .....

Position .....

Company ..... AV 7 44

(Books sent on approval in U. S. and Canada only.)

Callite Tungsten Electrodes



Welding Curtiss-Wright Steel Propeller Blade, with C-T Tungsten Electrodes

For Atomic-Hydrogen, Helium and Argon Arc Welding

Callite Tungsten Electrodes provide the accurate control and concentration of heat at the point of work, necessary for the welding of lighter metals and other delicate work.

Of 99% pure tungsten—their uniform high purity resists the intense heat of the arc. C-T Electrodes retain their stiffness, keeps the arc properly spaced and are consumed slowly. Deposits are strong, dense, clean and smooth—free from spatter and scale, greatly reducing grinding and finishing.

Send for Bulletin No. 154 for details. Our engineers will cooperate with you on problems involving the use of tungsten. Callite Tungsten Corporation, 545 Thirty-ninth St., Union City, N. J. Branch Offices, Chicago, Cleveland.

Callite TUNGSTEN ELECTRODES

Standard—or special polished, clean and black. 7 standard diameters; 12-inch lengths, random lengths and other diameters on special order.

MADE BY PIONEERS IN TUNGSTEN METALLURGY

WORLD-WIDE PROVING GROUND



For precision-built TUTHILL PUMPS

Hundreds of thousands of Tuthill Small Pumps in service throughout the world today provide the best evidence of dependable pump performance. Precision manufacture makes these internal gear rotary pumps outstanding for small pump requirements. Sizes from 1 to 200 g.p.m. and pressures up to 400 p.s.i. Available for coolant, lubrication, hydraulic fuel delivery and liquid transfer service. Write for General Catalog.

★

TUTHILL

SERVING ARMY · NAVY · AIR FORCE · MERCHANT MARINE

TUTHILL PUMP COMPANY

939 E. 95th ST. • CHICAGO 19, ILLINOIS



Machining to Infinitesimal Tolerance Limits


AIRCRAFT engines and other instruments of war would not be the precision mechanisms that they are today, were it not for the machining of vital parts to tolerance limits that closely approach the infinitesimal.

As specialists in this exacting field, we shall be glad to serve you as soon as war-work permits if you are developing a postwar product that requires machining or experimental work of a highly delicate character.

• *Write Us Concerning Your Requirements!*

THE GOVRO-NELSON COMPANY

1931 Antoinette Detroit 8, Mich.



Whether you need the tiny, vest-pocket Penlight . . . the 3-cell, hand-fitting, safety Service Light . . . the strong, hand-freeing Safety Headlight . . . or the powerful, night piercing Safety Lantern, you're bound to find the right kind of light in the Justrite line.

Justrite Lanterns are designed to meet specific requirements for the work they have to do . . . the amount of light needed . . . and the safety that's required on the job. Each Justrite Lantern is built to give years of dependable service even under the most rigorous circumstances.



THE JUSTRITE PENLIGHT

Here's the handiest little package of light most of our boys in the skies have seen. It fits snugly in a vest or shirt pocket or clips to almost anything . . . always ready for instant, sure-fire light. Red beam is made by pushing red, built-in, plastic slide over the white bulb.

Right now, the Penlight is reserved for Military Aircraft only.

Write today for complete details of these and other Justrite Safety Products

JUSTRITE MANUFACTURING COMPANY

2063 N. Southport Avenue, Dept. E-1, Chicago 14, Ill.

JUSTRITE *Safety Products*

SAFETY CANS · FILLING CANS · OILY WASTE CANS
APPROVED SAFETY ELECTRIC LANTERNS



ARTER

EXACT PARALLELISM

Pre-requisite on this exacting railroad piston ring grinding job by ARTER. There are many reasons why shopmen are enthusiastic about ARTER ROTARY SURFACE GRINDERS. Versatility, accuracy, simplification of operation, are among them. For more than a quarter of a century, ARTERS have advanced progressively. Three models now available—"A", "B" and "C" with chuck diametrical capacities for 8" to 40".

ARTER GRINDING MACHINE COMPANY

WORCESTER, MASSACHUSETTS • U. S. A.

MANHATTAN

RUBBER PRODUCTS

protect men and equipment on world-wide airways

Engine Mounts, Hose, Radio Shielding Tubing, Connections for Push-rod Cover Seals, Air Intake Connections, Engine Baffle Seals, Molded Rubber Parts and many other MANHATTAN Rubber Products protect men and equipment. Natural and synthetic rubber products, specially engineered to meet specific applications, isolate vibration, resist action of aromatic fuel, oil, alcohol and low temperatures.

MANHATTAN Technicians are available for consultation with aircraft engineers. Write for information.

MANHATTAN PRODUCTS USED IN FABRICATION

51st Year


Air Hose	Conveyor Belt
Paint Spray Hose	Other rubber products for plant maintenance
Welding Hose	
Abrasive Wheels	
Transmission Belt	Plane Fueling Hose

Keep ahead with MANHATTAN

THE MANHATTAN RUBBER MFG. DIVISION
OF RAYBESTOS-MANHATTAN, INC.
Executive Offices — Passaic, New Jersey

WEIDENHOFF MAGNESCOPE

FOR MAGNETO TESTING



HERE for the first time is a scope for viewing magneto contact point action and setting. The new Weidenhoff Model 341 Magnescope checks closure time, E-gap, primary output, coming-in speed and all other vital performance factors. A great step forward in magneto maintenance . . . For the armed forces now. For commercial airplanes when Victory is won.

KEEP BUYING WAR BONDS

Joseph Weidenhoff, Inc. Chicago 26, Illinois



The Airman



High Accuracy — *Available Today*

Hand-carved solid walnut and beautifully hand-rubbed finish make the AIRMAN a clock of distinction for either your mantel or your desk. Truly an air man's clock, this distinguished time-piece is entirely worthy of its name. And accuracy is assured by its 7-jewel 8-day precision Swiss movement. The Airman is 15" wide 4½" high with luminous dial of 2" diameter. See this clock at your dealer's. It's $60.00 including excise tax. Write us if your dealer cannot supply you.

HERMAN MILLER CLOCK COMPANY • ZEELAND, MICHIGAN

FITZGERALD GASKETS

FOR AIRCRAFT ENGINES

GASKET CRAFTSMEN FOR 38 YEARS


Write for information

THE FITZGERALD MANUFACTURING COMPANY
TORRINGTON, CONN.


BRANCHES CHICAGO AND LOS ANGELES
CANADIAN FITZGERALD, LTD., TORONTO

FITZGERALD GASKETS

THE COMPLETE LINE THAT COMPLETELY SATISFIES



"Aero-Seal" HOSE CLAMPS



Distinctive worm gear tightening action provides powerful belt-like pull-up. Uniform pressure all around prevents leaks. Can be put on or taken off hose in place on pipe. Can be re-used. No loose parts. Compact design. Extremely long take-up. Made in sizes from ½" up. *Write for circular.*

AIRCRAFT Standard PARTS CO.

Proved outstandingly reliable in severe service on aircraft fuel, oil, and coolant lines.

Aircraft Standard Parts Co.
1715G NINETEENTH AVE., ROCKFORD, ILL.



--AND THIS IS INVASION YEAR!


It is necessary now more than ever for war plants to maintain full production time. To terminate this war in the shortest possible time will require many skilled hands, from those that pull a trigger to those that run a machine. This means looking ahead constantly.

At present, Peck facilities are being employed to the utmost in producing springs and screw machine products. We want to keep them that way. Won't you, therefore, please let us know as far ahead as possible what your future needs are liable to be? Rest assured we will schedule them for the earliest possible delivery.

PECK SPRINGS & SCREW MACHINE PRODUCTS

The Peck Spring Company 30 Summitt St., Plainville, Conn., U.S.A.

PRECISION TESTING



Dillon TENSILE TESTER

FOR LABORATORY, PRODUCTION LINE OR FIELD TESTING

A HIGHLY PORTABLE UNIT IN A LOW PRICE RANGE


CAPACITIES UP TO 10,000 LBS.

Tests spot welded specimens aluminum, steel, magnesium, plastics, wire etc. Quick action jaws—easy to operate. Readily adaptable to compression or transverse testing. Fully portable, light weight, easily motorized. Seven capacities ranging from 250 lbs. up to 10,000 lbs. Finest workmanship—handsomely finished. In use by leading concerns everywhere. Extremely accurate, low in cost, good delivery.

WRITE TO DEPT.

W. C. DILLON & CO., INC. 5410 W. HARRISON STREET CHICAGO, ILLINOIS

UTICA TOOLS for More Tool Mileage



UTICA Tools are always in demand by the best mechanics. Correctly designed and smooth in operation, they lighten effort and give longer wear. Sold through our distributors who are the outstanding hardware and mill supply houses.

Send for Aviation Bulletin No. 41

★ Buy More War Bonds Today! ★

No. 41—4". 5"-6" Electricians' Diagonal Pliers

UTICA DROP FORGE AND TOOL CORPORATION UTICA, NEW YORK

SAVE 50% Empire BLACK

"TOP HONOR" BLACK OXIDE FINISH FOR STEEL

YES 50% right from the start with EMPIRE BLACK, the superior black oxide finish for steel, PLUS THE FOLLOWING ROYALTAGES, TOO:

EMPIRE BLACK has a 40 degree operating range! Works perfectly at low at 260° F., up to 300° F.

EMPIRE BLACK requires but one bath—generates uniformly on cast or hard steels—rust and wear resistant—does not change dimensions.

EMPIRE BLACK will not crack, chip or peel—perfect base for lacquer or paint.

EMPIRE BLACK TAKES LESS OF EVERYTHING! Less cost—less time—less labor—less fuel.

Produces permanent attractive, blue black color

FREE! TEST IT! OUR EXPENSE



5 Lbs. Empire Salts

Prove the merits of EMPIRE BLACK for yourself on steel gages, tools, machine and production parts. DON'T DELAY—SEND FOR SAMPLE TODAY! No obligation.

Protective Coatings, Inc. DETROIT 27, MICH.

DANLY Knurled



SOCKET-HEAD CAP SCREWS
HOLLOW SET SCREWS

All Die Makers' Supplies
Danly Commercial Sets
Danly Special Sets

DANLY MACHINE SPECIALTIES, INC.
2100 South 52nd Avenue, Chicago, Illinois
MILWAUKEE • LONG ISLAND CITY, N. Y.
DAYTON • DETROIT • ROCHESTER
CLEVELAND • PHILADELPHIA
BUCKMAN METALS & SUPPLY CO.
Los Angeles • San Francisco

DANLY PRECISION DIE SETS

FOR AVIATION MATERIALS-HANDLING

KRANE KAR Mobile Swing Boom Crane



USERS
Curtiss-Wright, Boeing, Bell, Republic, Consolidated, Lockheed, Douglas, etc.

Used in production of airplanes — handling jig sections in erection and handling steel for these jig sections; unloading equipment from freight cars; loading aircraft assemblies and spare parts on cars; lifting, moving and rearranging production equipment, raw materials, etc., for building maintenance and repair.

Send for Literature
2½, 5, and 10 Ton Cap.

Krane kar
SILENT HOIST WINCH & CRANE CO.
46 63rd ST. BROOKLYN, N.Y.

Change your Address?

Let us know
so that we can keep copies of
AVIATION
coming promptly.


TO: Circulation Dept.,
AVIATION, 330 West 42nd Street, New York 18, N. Y.

Name

Old Address

New Address

Company



SCREWS

All kinds, sizes and shapes, standard and special designs. Contract and engineered screw specialties, precision made, economically produced.

NEW ENGLAND SCREW CO.
KEENE, NEW HAMPSHIRE

SHEET METAL SCREWS
MACHINE SCREW NUTS
MACHINE SCREWS
PLASTIC INSERTS
HOLDING PINS
SPECIAL RIVETS
ALL TYPES OF HEADS AND THREADS



BROWNSKIN GRIZZLYBEAR Scores Again!

A colorful folder showing how the Chrysler Corporation of Canada Ltd., protects their engines for export shipping has now been prepared. It tells the story of their use of A-19 Brownskin Grizzlybear to lick the problem of corrosion on overseas shipments.

Write today for your free copy of Folder BAV

ANGIER CORPORATION
CORROSION PREVENTIVE AND WATERPROOF PAPERS
FRAMINGHAM, MASSACHUSETTS

Angier



Air Tamer

Easy as pointing your finger . . . *this* blowgun gives the air *where* you want it, *as* you want it. A breeze or a blast! LIGHT and handy but built for tough service. Write C. A. Norgren Co., 220 Santa Fe Dr., Denver 9, Colorado

Norgren

B-H

MANUFACTURERS OF SHEET METAL AND TUBULAR ACCESSORIES

B-H

ALUMINUM TANKS

CONTRACTORS TO ALL LEADING ENGINE AND PROPELLER MANUFACTURERS

B-H AIRCRAFT CO., Inc.
LONG ISLAND CITY 1, N. Y.

"It's For Victory!"




5TH WAR LOAN

Back the Attack...
BUY MORE THAN BEFORE!

HOME OF THE Hotel Hawaiian Room Lexington

CHARLES E. ROCHESTER Vice Pres. and Mng. Dir.
LEXINGTON AVE. AT 48th ST., N.Y.C. 17

KEEP THE WORK AT THEIR FINGERTIPS!




Gold Medal
Portable Work Stands

Light and strong, of welded tubular construction, these Gold Medal Portable Work stands promote safety and efficiency. They are ideal for aircraft assembly and maintenance work. *Write for Bulletin illustrating many types.*

Gold Medal
Safe Ladders and Scaffolding for Every Purpose
Originators of the Gold Medal Safety Line
THE PATENT SCAFFOLDING CO., INC.
155th DAYTON ST., CHICAGO 22, ILLINOIS
3821 12th St., Long Island City, N. Y. — 6168 Eastmar Ave., St. Louis, Mo
424-428 Commercial St., Los Angeles, Calif.
44 Hoyees St., N.W. Atlanta, Ga — 2835 Bridge St., Philadelphia, Pa

AIRCRAFT STUDS
CLASS 3 FIT



Send your requirements to
J. W. PITT, INC.
BATH, NEW YORK

The Tubular MICROMETER
FEATHER TOUCH

Modern, Light Weight, Perfectly Balanced, Hollow Steel Frame. Designed for critical inspection.



Engineered to Perfection. A New Standard of Accuracy.

TUBULAR MICROMETER CO.
St. James, Minn.

AIRCRAFT TURNBUCKLES
to meet
"AN" STANDARDS

Precision made by new production methods, resulting in substantial savings in critical material and machine time.

Available in a range of sizes

RELIABLE ELECTRIC COMPANY
3145 Carroll Avenue
Chicago 12, Illinois



MERCURY AIRCRAFT



NAF 47089 Oil Separator

• Many makers of Navy aircraft look to Mercury for these separators, secure that their schedules will be met, whatever the quantity.

MERCURY AIRCRAFT INC.
AIRCRAFT SURFACES • FUEL TANKS
PARTS • ACCESSORIES
At The Cradle of Aviation
HAMMONDSPORT • NEW YORK



PRECISION
DIE MAKING MACHINERY

Two companion machines that far outrange in versatility and ease of operation any combination unit. The Grob Band Saw and the Grob File embody exclusive principles of design and construction not found in any other single machine. Write us for details which prove their place in your plant.

GROB BROTHERS GRAFTON, WISCONSIN

WASHERS
Over 40 years experience Write for literature.
WHITEHEAD STAMPING CO.
EST. 1903
1665 W. Lafayette Blvd. Detroit 16, Michigan

DYKEM STEEL BLUE
STOPS LOSSES
making dies & templates



simply brush on right at the bench; ready for the layout in a few minutes. The dark blue background makes the scribed layout lines show up in sharp relief, and at the same time prevents metal glare. Increases efficiency and accuracy

Write for full information
THE DYKEM COMPANY, 2303 A North 11th St., St. Louis 6, Mo.
In Canada: 444 Pacific Ave., Toronto, Ont.

WILLIAMS
DROP-FORGINGS
ANY SHAPE—ANY MATERIAL
COMPLETE FACILITIES
Write today for helpful Forgings Data Folder
J. H. WILLIAMS & CO. "The Drop Forging People" Buffalo, N.Y.

OLDSMOLOY
—a unique, white bronze possessing great strength, corrosive resisting qualities, machinability and which will take and retain a high polish.

PHYSICAL CHARACTERISTICS
Tensile Strength—psi 70,000 to 76,000
Elongation on 2"—% 15 to 20%
Reduction in area—% 21 70
Proportional Elastic Limit with Berry Strain Gauge—psi 25,150

Oldsmoloy is a chrome nickel molybdenum bronze, non magnetic and non-carbonizing. It welds readily with the oxy-acetylene torch. Oldsmoloy is successfully used for gears, bearings, and parts in food machinery and pump fittings for corrosive chemicals.

Write for Bulletin
giving specifications and applications for Oldsmoloy.

OLDS ALLOYS Company D-3
8686 Rheem Ave. Southgate, Calif.
Suburb of Los Angeles

GRUEN
MANUFACTURING COMPANY
★
AIRCRAFT PARTS
PRECISION MACHINE WORK
SCREW MACHINE PRODUCTS
STAMPINGS
TOOLS DIES
★
GRUEN MANUFACTURING CO.
318 EAST 65TH STREET, NEW YORK, N. Y.

WHERE TO BUY

NEW EQUIPMENT — ACCESSORIES — MATERIALS — SUPPLIES

ALLEN
Specializes in Soders, Fluxes, Welding Brazing Compounds
SILVER SODERS & FLUXES
L. B. ALLEN CO., INC.
6753 Grye Newr Ave. Chicago 31, Illinois



PLASTICLEAR CLEANER
cleans and polishes all types of clear plastics such as Plexiglass, Lucite, acetate—nitrates removes grease, dirt bugs and prevents new foreign matter from adhering to the plastic surface. Aleo cleans, polishes and protects all types of chrome and painted surfaces (such as varnished surfaces of propellers) removing rust, stains, and restoring original brilliance. Clearer vision or safer vision.

PLASTICLEAR SUPER-HARD WAX
seals and protects any plastic or painted surface. Easy to use—just apply it, wipe it and it's done. Leaves a high melting-point anti-roeeptic super hard transparent film that prevents sun e rays from injuring plastic thus preserving the clarity. Protection is afforded by perfect bonding of the film to the cleaned surface. Can be applied to all types of painted surfaces. The film is impervious to gasoline, oil and salt water. Write on your letterhead for a generous sample



L. W. FERRINAND & CO. INC., Newton Lower Falls 62, Mass.

STANDARD AIRCRAFT FINISHES
Since 1913
TITANINE
TITANINE INC. UNION, N. J.

WHEN you are in need of some product, equipment or service to speed and improve operation, or save money . . . you may find it here—in the Where To Buy Section. Have you noticed these specialties in recent issues? . .

Aircraft Designings, Developing
Aircraft Finishes
Brass Fixtures
Cable Splicers
Engraving Acid Etching
Electric Marking
Custom Aircraft Fabrication
Sinzee
Light Weight Skis
Mechanical Rigete
Soders
Wire Stippers

GOULD
STORAGE BATTERY CORP.
DEPEW, N. Y.
A MAJOR SUPPLIER OF AIRCRAFT BATTERIES TO THE AMERICAN ARMED FORCES

A CENTERED EYE IN 1 OPERATION
Precision CENTERED EYE Bending
With DI-ACRO BENDERS

The DI ACRO Bender makes perfectly centered eyes from rod or strip stock at high hourly production rates. Both eyes and centering bend are formed with one operation. Any size eye may be formed within capacity of bender and ductile limits of material.



Send for Catalog
DIE LESS DUPLICATING showing many kinds of "die less" duplicating produced with DI ACRO Benders, Brakes and Shears.



DI-ACRO Precision Bending is accurate to .001" for duplicated parts. DI ACRO Benders bend angle, channel rod, tubing, wire, moulding, strip stock, etc. Machines are easily adjustable for simple, compound and reverse bends of varying radii

O'NEIL-IRWIN MFG. CO.
358 EIGHTH AVE. SO., MINNEAPOLIS 15, MINN

BALDOR
BALL BEARING GRINDERS
HEAVY DUTY



ASK FOR BULLETINS
ON COMPLETE LINE

BALDOR Grinder No. 191—built for the heavier production jobs. 1½ hp., ball-bearing motor; 1725 r.p.m., 220, 3-phase, 60-cycle. 10"x1" Alexite wheels, exhaust type guards and adjustable tool rests

BALDOR ELECTRIC COMPANY
4390 Duncan Ave. St. Louis 10, Mo.

Manufacturers of
Electric Motors
Electric Motor Generators
Battery Chargers
Arc Welding Stingers
Welding Transformers

Easy Acting . . . Up And Down
Helmet-Goggle



Designed for acetylene welders who prefer goggles, yet need the convenient raising and lowering feature of a helmet for inspection of their work. It is made to fit close around the eyes to exclude the light. Has an adjustable headband, with padded sweat band for added comfort. Comes with the popular Sellstrom Type A lens holder and a choice of lenses in regular acetylene shades.

Sellstrom
Write for CATALOG
MANUFACTURING CO.
663-7 N. Aberdeen St., Chicago 22, Ill.

Senior Mechanical Engineers

Junior Mechanical Engineers

Mechanical Draftsmen

needed for new aircraft engine programs by an aircraft engine company in the eastern area.

Aircraft engine experience preferred but not necessary if mechanical background is satisfactory.

Proper clearance with the War Manpower Commission necessary.

To arrange for an interview, please send your qualifications to

P-849, Aviation
330 W. 42d St., New York 18, N. Y.

WANTED

GRADUATE MECHANICAL ELECTRICAL ENGINEERS AND STRESS ANALYSTS

Excellent immediate and post war opportunity for qualified engineers having experience on small electro mechanical devices. Apply by letter only giving experience and training resume and draft status

Must comply with W. M. C. Regulations.

LEAR, INC.
PIQUA, OHIO

R. J. Elgin Special Representative

WANTED

HELICOPTER PROJECT ENGINEER

No helicopter experience required but must have executive record in the successful project management of Army-Navy airplane projects and certificate of availability. Pennsylvania aircraft manufacturer. Write

P-850, Aviation
330 West 42nd St. New York 18 N. Y.

HELP WANTED

Inspector-Instructor

Knowledge of tool room practices and assembly methods of major aircraft fixtures required.

Write or Wire

The OHIO AIRCRAFT FIXTURE Co.
4413 Train Ave. Cleveland 13 Ohio
Phone: Wrednine 5811
Statement of availability required.

WANTED

PRODUCT DESIGN ENGINEERS

by a long established manufacturer of electrical equipment — electro-magnetic relays — solenoids — switches. Located in small midwestern city, convenient to Chicago.

Relays, solenoids, switches, and related items to be designed, are primarily for

Automotive
Farm
Radio
Aircraft and
Industrial Control Equipment

Write, giving complete resumé of past experience, salary desired etc. to

P-861, Aviation
520 North Michigan Ave., Chicago 11, Ill.

POSITION VACANT

ENGINEERS to register as Consultants. Excellent opportunity to supplement present income, prepare for profitable postwar future with check engineering group. Write Engineering Specialists Box 1858—A Los Angeles 25 Calif.

REBUILDING

AIRCRAFT BATTERIES rebuilt. New Plates and separators. Your case cover and seals. Let us quote. Bowers Battery Mfg. Co. Inc. Reading Pa.

POSITIONS WANTED

AVIATION MAINTENANCE executive. Retired Marine Corps Officer desires civilian employment. Thoroughly capable of assuming full charge of all maintenances. Fiscal Spanish. PW-854 Aviation 330 W. 42nd St. New York 18 N. Y.

PILOT—EXECUTIVE. Grand experience in airline and manufacturing. Current instrument and instrumental rating 3300 hours. PW-855 Aviation 520 N. Michigan Ave. Chicago 11 Ill.

AERONAUTICAL ENGINEER and designer with 15½ years of aircraft designer experience on military and commercial projects. Thoroughly familiar with all phases of experimental and production designer techniques. Desires executive engineering position. Available. PW-858 Aviation, 330 W. 42nd St., New York 18, N. Y.

AERONAUTICAL ENGINEER, university graduate, four years experience including two years aerodynamics and averacas experience in India and Australia, desires connection as survey engineer or technical representative. Now employed single, 3A. PW-857 Aviation 68 Post Street San Francisco 4, Cal.

PROSPECTIVE REPAIR station or feeder line executives, Army officer desires position on management or maintenance manager. Married, college degree licensed 7 years varied aviation maintenance and instructing experience. PW-848 Aviation, 520 N. Michigan Ave., Chicago 11 Ill.

REPRESENTATIVE WANTED

MANUFACTURERS REPRESENTATIVE wanted by a midwestern manufacturer of metal stampings in small lots. Some very desirable territory still open on a protected commission basis. Die stamping knowledge an advantage. Reply Room 228 549 Washington Boulevard Chicago Illinois

REPRESENTATIVE AVAILABLE

AVIATION INDUSTRIAL, commercial. Retired senior Royal Canadian air force equipment officer, wide experience, excellent connections, available as Canadian representative. Present location Ottawa. RA 853 Aviation 330 W. 42nd St. New York 18 N. Y.

FOR SALE

FOR SALE—Irvin and Pioneer parachutes A. & candidian. Write Oklahoma Air College P. O. Box 1948 Oklahoma City 3 Oklahoma.

PARACHUTES FOR SALE. All types new and used. Jos. Crane & Company 39 Main Street, Mineola L. I. New York Garden City 5378.

NEW TIRES 8.00x4, 8.00x6, 7.00x4, two-ply $9.75 four $11.75. Tubes $3.25. We wholesale and carry large stocks. Propellers, spark plugs, batteries, fullwheel assemblies, windshield, synthin, Gab Trader, Acre Supply, Municipal Airport, Pittsburgh, Pa.

BOOKS

AIRCRAFT HYDRAULIC SYSTEMS by E. W. McDonough. Design Theory Operation. A specialized branch of aeronautics for students, mechanics, engineers, draftsmen. Training schools. Testing and maintenance of commercial and military hydraulic installations. Illustrated fully. $2.00. Aircraft Specialties, 121 So. Waller Ave. Chicago 44 Illinois.

WANTED

ANYTHING within reason that is wanted in the field served by Aviation can be quickly located through bringing it to the attention of thousands of men whose interest is assured because this is the business paper they read.

(Additional Employment Ads on Opposite Page)

WANTED

SALES MANAGER

Long established mid-western manufacturer of electrical equipment—electro-magnetic relays — solenoids—switches—selling principally to manufacturers in the following industries:

Automotive
Farm Equipment
Radio
Aircraft
Industrial Controls

Man selected for this position must have sufficient engineering knowledge of our products and their uses to be able to discuss them intelligently with engineers; to visualize potential markets, to suggest new products, and developments.

Write, giving complete resumé of past experience, salary desired etc. to

SW-862, Aviation, 520 North Michigan Ave., Chicago 11, Ill.

AIRCRAFT DESIGNING

Our two plants are furnishing the following Engineering services to many companies throughout the United States.

LOFTING
TOOL PROCESSING
AIRCRAFT DESIGNING
TOOL DESIGNING & DETAILING
MACHINE DESIGNING & DETAILING
SHEET METAL LAYOUT FOR AIRCRAFT

TOOL PROCUREMENT
GENERAL DRAFTING
ELECTRICAL LAYOUT
GENERAL PLANT LAYOUT
PIPING & STRUCTURAL LAYOUT
VENTILATION & AIR CONDITIONING
PRODUCT DESIGNING and DEVELOPMENT

Let us help you in your Engineering problems.

H. L. YOH COMPANY
740 Sossom St. Philadelphia, Pa.
Lombard 8855

REPRESENTATIVE WANTED

Nationally known manufacturer of precision tensile testing machines will appoint experienced sales representatives and jobbers in some territories. Write giving complete record of products now handled, qualifications and other details. This is a widely advertised line and offers permanent connection to the right parties. Replies held confidential.

RW-850 Aviation
520 N. Michigan Ave., Chicago 11, Ill.

WANTED

SALES ENGINEERS

A leading manufacturer of Hydraulic Equipment has openings for men with mechanical engineering training and an understanding of basic hydraulic principles.

The growing importance and acceptance of Hydraulic Controls have so greatly increased the sales opportunities of this already established company, that additional men are required to contact both new and old customers.

High caliber men are desired—capable of meeting and counseling with executives and aggressively presenting a sales program.

These are permanent positions with increasing opportunities for advancement.

Please write giving all details of your educational background experience physical characteristics and ambitions.

SW-860 Aviation
330 W. 42nd St. New York 18 N. Y.

INVENTORS!

We seek specialized equipment, preferably patented, in Aircraft, Automotive, and Building Trade Fields, also established U. S. products for development and production by the associated companies of the Simmonds Group throughout the world.

SIMMONDS AEROCESSORIES, INC.
30 Rockefeller Plaza, New York 20, N.Y.

AVIATION SCHOOLS

AERONAUTICAL ENGINEERING

DEGREE IN 27 MONTHS

Qualify in Aeronautical Engineering at Indiana Tech. B. S. degree in 27 months. Completed instruction through intensive practical program. New, modern Wind Tunnel. Prop. tests with our own engine. Government approved Ground School Courses. Aeronautical industry rapidly expanding. Companies need engineers. Attractive appointments for Graduates. Enter Sept. 5, Dec. 5, March and June. Tuition and living costs low. Self-help opportunities. Also B. S. degree courses in 27 months in Chemical, Civil, Electrical, Mechanical and Radio Engineering. Catalog and list of successful graduates on request.

INDIANA TECHNICAL COLLEGE
107 E. East Washington Blvd. Fort Wayne 2, Ind.

PROFESSIONAL SERVICES

LANCASTER, ALLWINE & ROMMEL
Registered Patent Attorneys
Booklet — "General Information Concerning Inventions & Patents" and "Fee Schedule" sent without obligation.
Patents—Copyrights—Trade-Marks
Suite 422 815—15th St., N.W. Washington 5, D.C.

SEE US FOR

INSTRUMENTS

NEW — USED — ALL TYPES — SALES — REPAIR — INSTALLATION — COMPLETE STOCK

STANDARD AIRCRAFT EQUIPMENT COMPANY

Approved Repair Station 169

Hangar "D," Roosevelt Field, Mineola, L. I., N. Y. Garden City 8753

NEW ... AUTNENTIC OUTSTANDING AUTHORITATIVE



AVIATION DICTIONARY

By Charles A Zweng

Member, Institute of Aeronautical Sciences. Author of Radio & Instrument Flying etc.

A new Encyclopædic Aviation Dictionary by the well known author—bristling with new aviation terms—for instance can you define:

Sinking rate	Sensible horizon
Libroscope	Hour angle
Resonant frequency	False cone of silence ?
S B R A	Relative bearing

These, and thousands of other words defined in ZWENG'S AVIATION DICTIONARY. The publishers congratulate the author for this his latest contribution to aviation. This splendid volume is bound in maroon leatherette with gold lettering.

Price only $6.00 postpaid or C.O.D.

New Dead Reckoning Equipment

For Defense of Land, Sea and Air

RADIO and INSTRUMENT FLYING. By Charles A. Zweng Instructor U S Air Corps. New 4th Edition covering new important material. Written especially to prepare the pilot for government examination for instrument rating. Radio-Telephone Permit for student with Meteorology, Radio-Orientation, let downs, etc. Only $4 00 postpaid.

CELESTIAL NAVIGATION—complete equipment consisting of Air Navigation Note Book and Navigation Plotter. Simplified Celestial Navigation, Air Almanac, Line of Position Book, and Hydrous Star Chart. All 6 items only $11 75 postpaid or C O D

AERONAUTICAL TRAINING Just off the press. New enlarged edition. For the first time shows separate sections containing Typical Private Pilot and Commercial Pilot Multiple Choice Examinations. $3 00 postpaid or C O D

GROUND INSTRUCTOR Written for the student preparing for "Ground Instructor Rating." Excellent for class work. Covers Navigation, Meteorology, Aircraft and Theory of Flight, Engines and Civil Air Regulations. $3 00 postpaid or C O D

GROUND INSTRUCTOR RATING Just published. Contains Typical Multiple Choice examinations on Navigation, Meteorology, Aircraft and Theory of Flight, Engines and CAR. Nomenclature and aviation dictionary in back of book. It's new and different. Something you cannot afford to be without. $3 00 postpaid. Or it may be purchased in combination with "Ground Instructor" for $5 00

AIRPLANE and ENGINE MECHANICS Examinations. New authentic Quiz Book now covers the new Typical Multiple Choice examinations fully illustrated with necessary diagrams. Used by Lockheed, Boeing, Northrop, Ryan and outstanding schools. Why fail? Only $3 00 for both examinations and CAR.

Instrument Flying by Weems & Zweng	4 00
ASTRONOMY by Baker	3 75
MARINE NAVIGATION (Weems)	3 00
WEEMS NAVIGATION PLOTTER	2 50
DALTON MK VII NAVIGATION COMPUTER	7 50
COX & STEVENS COMPUTER	35.10

Celestial Aid Navigation Training

Prepare now for this important phase of Air Defense. Our students are now air navigators and instructors in various quarters of the world.

Write for information



AIR NAVIGATOR'S LOG BOOK $2 00

Pilot's Log Book with fabric cover gold letters $1 00

New Army Type E-6B Navigation Computer (white face with black letters) not shown in cut $10 00

AIRLINE TRANSPORT PILOT RATING By Zweng. A new and timely book for men preparing for the Air line government examination ... $4 00

PAN-AMERICAN NAVIGATION SERVICE, Dept. M

12021 VENTURA BOULEVARD NORTH HOLLYWOOD, CALIFORNIA

WANTED

SELL YOUR SURPLUS EQUIPMENT



IT IS NEEDED TO SPEED THE WAR'S END

DSP INC. ORGANIZATIONS

We have a demand for your surplus and idle equipment—a single item or a complete plant. Send us your list of such equipment—and put it to work where it is needed most.

WE PURCHASE ON A CASH BASIS

DULIEN STEEL PRODUCTS, INC.

of Washington	of California	of New York
200 NATIONAL BLDG. SEATTLE 4, WASH	11611 SO. ALAMEDA LOS ANGELES 2, CALIF	2280 WOOLWORTH BLDG NEW YORK 7, N Y

A. R. S. NO. 294 "THAT'S US"



"Uncle Sam might criticize our grammar, but he fully approves the quality and technical competence of our repair work. That's why Snyder's other name is APPROVED REPAIR STATION No 294. Mail and phone orders receive prompt and careful consideration

SNYDER AIRCRAFT CORPORATION

MUNICIPAL AIRPORT Chicago 38, Illinois	SULLIVANT AVE. AIRPORT Columbus 4, Ohio

AERO TRADES COMPANY

Roosevelt Field, L. I.

EXPERIMENTAL WORK MODIFICATIONS

Specialists in Wood & Metal — Manufacturers of Airplane Parts

Government Approved Station 115

ANODIZING OF ALUMINUM NARD CNROMIUM PLATING

Philadelphia Rust-Proof Co.

3317 Frankford Ave. Phila., Pa.

FOR SALE—AIRCRAFT STEELS

SAE 1019

Item No		
111	1" Hex	607 lbs

SAE C-1019

103	½" x ¼"	312 lbs.
101	11/16" dia	104 lbs
102	1½" dia	28 lbs

SAE 1020

106	¾" rd.	413 lbs.
119	3½" dia.	12300 lbs. (HR)
108	1" x 1¼"	2800 lbs.
108-A	3½" rd 2. 1 33	104800 lbs

SAE 1112

121	⅝" sq	127 lbs.
125	2½" dia	5136 lbs.

SAE 2330

133	5/16" HRA	3370 lbs.
134	⅜" CDN	4687 lbs
138	⅜" CDHT	18 lbs
136	⅜" CDA	2290 lbs
137	5/16" Hex CDN	3494 lbs.
138	5/16" CDN or ANN	2381 lbs
138-A	5/16" HRA	840 lbs.
A139	⅜" CDN	2383 lbs.
A140	⅜" CDA	2095 lbs.
141	7/16" CDA	1871 lbs
142	7/16" Hex. CDA	31423 lbs
143	7/16" Hex CDN	11225 lbs.
144	½" Hex CDN	6010 lbs.
146	9/16" Hex CDA	3385 lbs.
147	9/16" Hex CDN	91856 lbs.
150	⅝" dia CDN	57 lbs
151	11/16" CDN	4000 lbs
153	¾" CDN	9850 lbs
155	¾" rd CDHT	85 lbs
A156	13/16" Hex. HRA	1710 lbs
A157	⅞" CDHT	5642 lbs
158	⅞" Hex CDA	6200 lbs
159	⅞" Hex CDN	12543 lbs
A160	15/16" CDN	166 lbs
A161	15/16" CDHT	8220 lbs
163	1" CDHT	5090 lbs
A166	1 5/16" CDN	1885 lbs
A167	1⅜" GR	5580 lbs.
168	1⅜" CDN Hex	450 lbs
171	1½" rd CDN	150 lbs
A172	1 9/16" CDN	250 lbs
173	2" Hex CDN	1750 lbs
173-B	⅝" dia. HRA	2350 lbs.

SAE 4130

175	7/16" Hex CDA	1400 lbs
A177	½" x ¾" CDHT	110 lbs
A178	½" CDN	237 lbs
A179	½" x 1" CDA	262 lbs
180	½" x 7/16" HRA	105 lbs
181	½" CDHT	637 lbs
A182	5/16" x 4" HRA	18000 lbs
183	5/16" HRA	32 lbs
184	5/16" CDN	3000 lbs.
185	⅝" x 1" HRA	605 lbs.
186	⅝" hx CDA	1535 lbs.
187	⅝" HRA	444 lbs.
188	⅝" CDHT	48 lbs.
188-A	⅝" sq HRN	288 lbs.
189	⅝" x 11/16" CDHT	16 lbs.
190	⅝" square HRA	100 lbs.
A191	9/16" x ⅜" HRA	1064 lbs
192	9/16" CDHT	4067 lbs
194	⅝" CDN	11253 lbs
195	⅝" HRA	206 lbs.
197	⅝" x ⅝" HRA	1027 lbs.
198	⅝ x 2½" HRA	985 lbs.

Item No		
199	11/16" Hex. CDN	290 lbs
A200	¾" x 1½" HRA	4580 lbs
201	¾" x 2" HRA	440 lbs
202	¾" Hex HRA	58 lbs
203	¾" x 1½" HRA	10235 lbs
A204	13/16" dia. CD 12,000 pcl	15981 lbs
205	13/16" rd CDA	2572 lbs
A206	⅞" x 1½" HRA	14874 lbs
A207	⅞" x 1 5/16" HRA	1070 lbs
A208	⅞" x 1 7/16" HRA	16500 lbs
213	15/16" CDN	1796 lbs
A214	1" x 1½" CDHT	326 lbs
216	1" x 1½" HRA	154 lbs
217	1" hx HRA	53 lbs
218	1 1/16" HRA	1331 lbs
219	1 1/16" CGN	4000 lbs
220	1 1/16" x 1½" HRA	665 lbs
A221	1⅛" x 1⅜" HRA	8230 lbs.
A222	1⅛" x 1 11/16" HRA	6280 lbs
224	1⅛" x 1 5/16" HRA	861 lbs.
225	1⅛" x 2¼" HRA	38819 lbs
227	1⅛" CGN	3437 lbs
230	1¼" CGN	4000 lbs
A231	1 5/16" dia. HRA	4415 lbs
232-A	1⅜" square HRA	5741 lbs.
A233	1⅜" HRA sq	565 lbs.
237	1½" rd HRA	841 lbs
239	1 7/16" HR	2223 lbs
240	1½" x 1½" HRA	3744 lbs
241	1 9/16" HRA	142 lbs
242	1½" sq HRA	210 lbs
244	2" CDA	300 lbs
245	3½ rd HRA	135 lbs
247	2⅜" CDN	143 lbs
A248	2½" RCS HRA	10262 lbs.
249-A	13/16" CDN	2460 lbs
249-B	½" HB	1600 lbs
A250	3½" hx RCs HRA	1470 lbs
A251	4" HRA	82838 lbs.
251-A	4" HRA dia.	5740 lbs
251-B	1" HRA dia. Not Ann	35000 lbs

SAE 4140

251-C	3/16" dia. CDN	1627 lbs
252	5/16" dia. HRA	3900 lbs.
253	⅜" CDN	135 lbs
254	½" dia. CDN	2062 lbs
255	⅝" Hex CDN	475 lbs.
256	⅝" rd. HRA	28 lbs.
257	5/16" CDN	667 lbs.
258	⅝" dia CDN	930 lbs.
260	⅝" rd. CDHT	143 lbs.
261	9/16" rd. HRA	13 lbs.
262	⅝" x 2½" HRA	15648 lbs.
A263	⅝" dia. CDN	10907 lbs.
264	⅝" x 1½" HRA	70 lbs.
265	⅞" rd. HRA	35 lbs.
A268	13/16" x 1½" HRA	10207 lbs
A269	15/16" dia. CDN	18055 lbs.
270	15/16" rd HRA	110 lbs.
A271	1" x 1⅝" HRA	30770 lbs.
A272	1" x 1⅝" HRA	3432 lbs.
273	1" dia. CDN	33095 lbs.
274	1" rd. HRA	2282 lbs.
275	1 1/16" rd. HRA	7 lbs.
A276	1⅛" x 2⅛" HRA	9680 lbs.
277	1⅛" x 1 4/16" HRA	690 lbs.
278	1⅛" rd. HRA	200 lbs.
279	1 6/16" dia. CDHT	1720 lbs
280	1 5/16" dia. HRA	4520 lbs
282	1 3/16" CDN	2110 lbs
283	1⅛" x 3½" HRA	1370 lbs.
284	1⅜" round CDHT	667 lbs.
A286	1 11/16" dia. HRA	91480 lbs.
A287	1 11/16" dia. CDA	142000 lbs
289	2" x 2⅜" HRA	673 lbs
A290	2½" dia. HRA	23665 lbs.
A292	2½" x 4" HRA	218 lbs.

Item No		
293	2½" x 3" HRA	900 lbs
A294	2½" x 7½" HRA	146 lbs
295	2" sq HRA	11441 lbs
296	3½" rd HRA	284 lbs.
297	3½" x 5½" HRA	158 lbs
298	4" rd HRA	5477 lbs
299	5" x 6" HRA	191 lbs
299-A	2½" dia. 1 DHT	270 lbs
299-B	1⅛" x 5½" HRA	20338 lbs
299-C	5 1/32" x 2 7/16" HRA	973 lbs.
A861	½" x 1½" CDA	7600 lbs.
A302	⅜" x 1½" HRA	7713 lbs.
303	1 25/32" x 6 9/16" HRA	48375 lbs
303-A	1½" x 3½" HRA	7247 lbs

SAE-X-4340

304	11/16" x 4" HRA	11064 lbs.
305	1" Hex. CDN	3130 lbs
A306	1⅛" dia. HRA	415 lbs.
A307	1 7/16" Hex. CDN	9752 lbs
308	1 7/16" Hex. CD	11301 lbs.
309	1 11/16" Hex. CDA	11713 lbs.
310	2½" dia CDN	1390 lbs.

NE 9740 BARS

312	2½" dia CD	17080 lbs.

CHROME NICKEL BELGIAN STEEL (4% Nickel)

314	5/16" 3200 CN Bar	853 lbs.
315	5/16" 3200 CN Bar	465 lbs.
316	4055 CN Bar	8440 lbs
317	1 378 CN Bar	2351 lbs
318	1 496 CN Bar	2217 lbs.
319	1 575 CN Bar	479 lbs.
320	2" dia CN Bar	3197 lbs
321	2 3/16" dia. CN Air Hard Bar	1687 lbs.
322	2⅜" dia CN Bar	356 lbs
323	2⅝" dia. CN Bar	240 lbs
324	4 72" dia. CN Bar	3060 lbs.
325	4 92" dia. CN Bar	1524 lbs
326	6⅜" dia. CN Bar	2244 lbs.
327	6" dia. CN Bar	2114 lbs.
328	6½" dia. CN Bar	1607 lbs.

STEEL BILLETS & BARS

330	5/16" dia. SAE 1040	215 lbs.
A331	7/16" dia. SAE 3245	1009 lbs.
332	9/16" dia SAE	230 lbs
333	½" Hex SAE 2330	866 lbs
334	1" dia. Nickel Steel Spec 46S-23	161 lbs
335	1 1/16" dia. SAE 1315	800 lbs
336	1¼" dia. C 1119	9069 lbs.
A337	1½" dia. SAE 1314	588 lbs
338	1 7/16" dia. SAE 3115	1180 lbs
339	1½" dia. SAE 3312	421 lbs
340	⅝" dia. CMV	10678 lbs.
341	Steel Ingots SAE 6135	480 lbs.
342	7/16" Hex. CMO Billets	5370 lbs.
343	⅝" dia NS Bar	2845 lbs
344	¾" Hex NS Bar	1010 lbs.
345	⅝" Hex. CMS Billets	9307 lbs
346	1" Hex. CMO Billets	1867 lbs
347	1 1/16" Hex NS Bar	441 lbs
348	1 1/16" Hex. CMO Billets	7906 lbs.
349	1⅜" dia. NS Bar	3014 lbs.
350	1 7/16" Hex. NS Bar	3014 lbs
351	1⅝" Hex CMO Billets	3271 lbs

AIRCRAFT QUALITY STEEL SHEETS

A353	.072" x 18" x 72" x 4130 O.H	351 piece
A355	.072" x 18" x 72" x 4130 E.F	3167 piece
A355	.083" x 18" x 72" x 4130 O.H.	936 piece
A356	.083" x 18" x 72" x 4130 E.F	400 piece

STAINLESS STEEL TUBING

Item No			
A374	⅛" x .049 Seamless Type 347	2078 feet
375	⅜" x .093 Seamless 347	1175 feet
376	½" x .092 Seamless 347	1410 feet
377	1" x .015 Welded 347	2412 feet
378	2" x .037 Welded 347	3376 feet
379	2½" x .049 Seamless 347	2465 feet
380	2½" x .049 Seamless 347	17093 feet

NE-8630 STEEL TUBING SEAMLESS (All Cold Drawn—Normalized)

A382	7/16" x .065	1877 feet
A383	⅝" x half	6615 feet
A385	⅝" x half	5337 feet
386	⅝" x .065	2100 feet

NE-8630 STEEL TUBING

A388	⅝" o.d x .083	6575 feet
A389	1⅛" o.d x .072	6719 feet
A390	1⅛" o.d x .058	4848 feet
A391	1⅜" o.d x .166	2153 feet
A395	1⅜" x .250	1358 feet

SAE X 4130 CHROME MOLY STEEL TUBING

A399	⅜" x .028	1300 feet
A403	⅜" x .078	429 feet
406	⅝" x .120	630 feet
A404	7/16" x .385	3600 feet
A406	½" x .072	764 feet
408	½" hx x .028	3554 feet
A409	½" x .065	617 feet
A411	11/16" x .065	51 feet
A412	11/16" x .083	4260 feet
413	¾" x .058	16646 feet
414	¾" x .125	14 feet
A415	¾" sq x .065	4145 feet
A416	⅞" x .385	3201 feet
417	⅞" x .095	433 feet
A418	⅞" x .083	933 feet
A419	9/16" x .049	3197 feet
A420	1" x .065	169 feet
A421	1" x .148	83 feet
A422	1" x .072	4692 feet
A423	1" sq x .072	5734 feet
425	1 1/16" x .013	1860 feet
A426	1⅛" x .072	528 feet
A427	1⅛" x .065	7341 feet
A428	1¼" x .035	1263 feet
429	1⅜" x .058	780 feet
A431	1½" sq x .065	5634 feet
A432	1⅝" x .106	29 feet
A433	1¼" x .313	97 feet
A434	1 5/16" x .035	322 feet
A435	1⅜" x .058	519 feet
A436	1⅜" x .058	12750 feet
A437	1⅜" x .095	8278 feet
A438	1⅜" x .166	354 feet
A439	1⅜" x .120	2500 feet
A441	1⅜" x .219	992 feet
A443	1⅜" x .313 x .035	2575 feet
444	1⅜" x .109	136 feet
A445	1⅜" x .156	10830 feet
446	1 13/16" x .035	35 feet
447	2" x .035	1150 feet
448	2" x .125	326 feet
A449	2" x .250	492 feet
450	2" x .006	20 feet
451	2⅛" x .134	196 feet
A453	2⅛" x .183	900 feet
A454	2⅜" x .281	236 feet
455	2⅜" x .035	128 feet
456	2⅜" x .049	934 feet
A458	3⅛" x .049	235 feet
A461	3⅝" x .006	88 feet
461-A	1" x .095	554 feet
461-B	1⅛" x .065	4000 feet

For immediate shipment from New York stock.

NORTHEASTERN STEEL COMPANY

352 GROVE STREET BROOKLYN 27, N. Y.

Tel. No. — Gleemore 2-6352,3,4 — Write, telephone or telegraph

ADVERTISERS IN THIS ISSUE

A C Spark Plug 328
Adel Precision Products Corp 106
Aero Products Insert 211
Aeroquip Corp 202
Air Associates Inc. 345
Aircraft Fitting Co. The 22
Airfall Nut Corp 246
Airfall Standard Parts Co 412
Aircooled Mfg Co 14
Air Maze Corp 396
Alemite 514
Air Reduction 387 377
Albertson & Co., Inc 36
Allen Mfg Co The 242
Allen Co Inc, L B 410
Allied Products Corp 380
Allis Co The Louis Insrrt 247-248
Allison Engineering 64
Aluminum Co of America 101
American Broach & Machine Co 234
American Chain and Cable Co Inc 21
American Chemical Paint Co 397
American Flange & Mfg Co Inc 382
American Hammered Piston Ring 31
American Machine & Metals Inc 251
American Magnesium Corp 100
American Pail Co 404
American Phenolic Corp 95
American Screw Co 105-426
American Screw Products 218
American Steel and Wire Co 312
Ampere Metals, Inc 256
Angier Corp 416
Anchor Post Fence Co 102 103
Apex Machine & Tool Co The Insert 212
Arnolt Motor Co 240
Arter Grinding Machine Co 412
Atkins & Co, E C 204
Automotive Electric Sales Corp 73
Automotive Products Co 389
Automotive & Aircraft Div of American Chain & Cable Co Inc. 21

B G Corp The 268
Baldot Electric Co. 419
Baldwin Southwark Division—Baldwin Locomotive Works The 316
Bahr Manning 241
Baldrn Mfg Co 267
Brilliance Aircraft Corp 381
Bell Aircraft Corp Insert 104
Bendix Aviation Corp 4 106
Back Covrr
Brndix Aviation Pacific Div 341
Bendix Radio Back Cover
Bendix-Scintilla 4
Bendix Stromberg 166
Berry Brothers 47
B H Aircraft Co Inr 416
Blackhawk Mfg Co 58
Bliss Co E W 12
Bolton Mfg Corp 75
Booth Frit Company 251
Boole Aircraft Net Corp 350
Borg-Warner Corp 200
Bower Rolles Bearing Co Insert 50
Brooks Corp., Inc Insert 259
Briggs Mfg Co 342
Briggs Stratton Corp 273
Bristol Co The 345 426
Bryant Chucking Grinder Co 74
Burndy Engineering Co Inr 326
Bush Mfg Co, The 30
Butler Mfg Co 327

Callite Tungsten Corp 410
Cannon Electric Development Co 263
Carborundum Company The 63
Cardea Corp 350
Carnegie-Illinois Steel Corp 85
Carpenter Steel Co. 255
Celanese Corp of Aomrica 224
Central Screw Co 426
Chamberlain Engineering Co 220
Champion Spark Plug Co Insrrt 60
Chandler Evans Corp 24
Chandler Products Corp 426
Cherry Rivet Co 34
Chicago Pneumatic Tool Co 263

Chicago Wheel and Mfg Co 367
Clarostat Mfg Co., Inr 262
Cleveland Cap Screw Co Thr 354
Cleveland Pneumatic Tool Co The 81
Climax Molybdenum Co 250
Columbia Steel Co 85 312
Conr Automatic Machine Co Inc 50
Continental Can Co., Ier 257
Continental Screw Corp 426
Cook Electric Co 237
Corbin Screw Corp Thr 426
Crescent Co The 275
Crescent Truck Co. 244
Curtiss Airplane Co Insert 103
Curtiss Propeller Insert 226
Curtiss Wright Corp Insert 193 229

Danly Machine Specialties Inr 415
Darnell Corp Ltd 271
Dearborn Gage Co 270
Dratsch Co The 218
DeVilbiss Co The 28
Dill Mfg Co. 290
Dillon and Co Inr W C 404 414
Dixon Crucible Co Joseph 372
Dohr Valve Co 350
DoAll Company The 325
Douglass Aircraft Co Inr 44
Dow Chemical Co The 32-32
Third Covrr
Du Pont de Nemours & Co E I 16
Dykem Co. Thr 416
Drox Fastener Co Inr 170

Eberhard Faber Pencil Co 260
E A Laboratories Inr 55
Eclo Aircraft Corp 15
Electric Auto-Lite Co Thr 43
Electric Sherrge Battery Co The 324
Electronic Laboratories Inr 285
Elwell-Parker Electric Co 304
Emerson Electric Mfg Co The 57
Eutectic Welding Alloys Co 270
Evans Products Co 364

Fairchild Camera & Instrument Corp 210
Fairchild Engine and Airplane Corp 86
Farnham Mfg Co 252
Federal Bearings Co Inr The 291
Federal Telephone & Radio Corp 37
Fenn Mfg Co The 290
Firestone Tire and Rubber Co Thr 54
Fisher and Porter Co 313
Fitzgerald Mfg Co The 412
Fletcher Aviation Corp 78
Flexo Tubr Co The 48
Flightlex Division Textron Inr 395
Foote Bros Gear and Machine Corp 335
Fulton Sylphon Co, The 23

Gardea City Plating & Mfg Co 290
General Controls 302
General Electric Co 70-99 209 300 381 353
General Screw Mfg Co., 426
General Tire and Rubber Co, The 337
G M Laboratories Inc. 404
Goodrich Co., The B F Insert 157-160
Goodyear Tire and Rubber Co Inr The 8-9 10-11
Gould Storage Battery Corp 418
Gouvo Nilson Co Thr 411
Graybar Electric Co, Inc 243
Grimes Mfg Co. 374
Grub Brothers 410
Greenfield Tap and Die Corp 49
Gruen Mfg Co. 418
Gulf Oil Cop 355

H & A Mfg Co Inr 28
Hall Mfg Co 18
Halbrafters Co Thr 65
Hansen Mfg Co 90
Harper Co The H M 426
Harris Seybold Potter Co 30
Hartwell Aviation Supply Co 222
Heinemann Circuit Breaker Co 52
Hein-Krause Screw Corp Thr 373
Hemelite Corp 332
Hotel Lexington 416
Hoffner Cabot Electric Co 395
Hork Mfg Co 321
Hycar Chemical Co 330

Ingersoll-Rand Co. 64
International Nirbel Co Inr Thr 104-389
International Electric Corp. 403
International Screw Co 426
Interstate Aircraft & Engineering Corp 91
Irving Air Chute Co Inr 372

Jones and Lamson Machine Co 29
Jessrita Mfg Co 411

Kaynar Mfg Co., The 395
Schaefer Son, A 42
Scott Aviation Corp 406
Seaville Mfg Co 426
Searchlight Section 420 421-422-423
Sedgwick Machine Works 250
Sellstrom Mfg Co 410
Sensenich Brothers 311
Severeair Tool Industries Ier 84
Shakeproof, Ier 426
Sheffield Corp, The 60
Silent Hoist Winch and Crane Co 415
Similar Refining Co. Ier 351
Simmonds Aerocessories, Inr 369
Sunmaco Mfg Co 253
Small Motors, Inc 273
Snap On Tools Corp 66
Sperry Vornum Oil Co—Inr Insrrt 69-72
Solar Aircraft Co 360
South Bend Lathr Works 52
Southington Hardware Mfg Co 426
Spencer Thermostat Co. 87
Sperry Gyroscope Co. Ioc 226
Spool Cotton Co The 346
Square D Co.—Kollsmoos Instrument Div 6
Standard Coorvyor Co 384
Stoodard Pressed Steel Co 338
Steel Improvement & Forge Co., The 360
Stewart Warner Corp 40 41 317
Studebaker Corp The 12
Sunnen Products Co 88
Superior Tubr Co 276
Swen Engineering Co 264
Switlik Parachute Co 60

Tennewta Werke The 304
Terbeats Co. Thr 287
Taylor Fibre Co 400
Thornton Ier, W Harris 258
Timm Ier 371
Timken Roller Bearing Co Thr 126-393
Tinnerman Products, Inc- Second Cover
Titanium, Inc. 418
Tohr Dortschmeen Corp 232
Torrington Co The 46
Tubr Turns, Inc. Insert 265-266

Tubular Micrometer Co. 417
Turco Products, Inr 309
Tuthill Pump Co. 411

Union Carbide & Carbon Corp 268
Union Oil Co 31
United States Elrc. Tool Co. The 328
United States Steel Corp.. Subsidiaries
85 312 322
United States Steel Export Co 85 312
Utica Drop Forge & Tool Corp 414

Vredrr Root Inr 256
Vickers, Inr. 280
Vanre Corp. 344
Vokes Ltd 208

Waldes Koh-I-Noor Inr 51
Walker-Turner Co Inr 310
Walter Motor Trnrk Co 347
War Savings Bonds 306
Waverly Petroleum Products Co 403
Weatherhead Co. The 97
Weldon Tool Co. 257
Weidenhoff Inc Joseph 412
Westinghouse Electric and Mfg Co
10 53 65-222
Where To Buy 418
Whitaker Cable Corp 220
Whitehead Stamping Co 418
Whitr Rodgers Electric Co 256
Whiting Corp Aviation Division 336
Williams and Co, J H 418
Wittak Mfg Co 262
Wolfe's Head Oil Rrfining Co 25
Wolverine Belt Co 426
Wynnen Gordon 240

Young Radiator Co 274

Zephyr Mfg Co 277

★ ★ ★

SCHOOLS

Indiana Technical College 421

AVIATION'S MARKET PLACE

(CLASSIFIED DISPLAY ADVERTISING)

BOOKS 426 422
BUSINESS OPPORTUNITIES 421
EMPLOYMENT (Positions Wanted and Vacant) 420-421
FOR SALE 421 427 423

PROFESSIONAL SERVICES 421
SPECIAL SERVICES 421

(CLASSIFIED DISPLAY ADVERTISERS)

Aero Trades Co 422
Ouion Steel Products Inc 422
Lancaster Alfwlos & Cement 421
Leer Inc 420
Northeastern Steel Co. 423
Ohio Aircraft Fixtnre Co 428
Pan American Navigation Service 422
Philadelphia Gust Proof Co. 422
Simmonds Aerocessories Inc 471
Snyder Aircraft Corp 422
Standard Aircraft Equipment Co 471
Yoh Co, H. L. 424

IT'S LIKE GIVING YOUR ASSEMBLY LINE A SHOT IN THE ARM TO SWITCH TO THE SCREWS WITH THE ENGINEERED RECESS THAT SPEEDS UP ASSEMBLY AS MUCH AS 50%



IT'S PHILLIPS



Manufacturers in every industry can tell you that switching to Phillips Recessed Head Screws acts like a tonic to assembly lines.

To start with, you get faster—*much faster*—screw driving. Comparisons made in scores of plants prove that Phillips Screws step up fastening speed as much as 50%.

Next, Phillips Recessed Head Screws save precious man hours. The scientifically Engineered Recess utilizes the worker's full turning power and skill. Time and muscle are not wasted on wobbly starts, slantwise drives and dangerous driver skids—nor on correcting sloppy work.

Finally, with all this increased speed, you get vastly better workmanship. Phillips Recessed Head Screws make driving so simple, so steady that the most inexperienced operator soon becomes master of the trickiest fastening jobs!

If these are the kind of results you'd like, but aren't getting from slotted and other type screws, you owe it to yourself and to your workers to switch to Phillips—the screws with the *Scientifically Engineered Recess*. They cost *less to use* . . . because they help you *produce much more*. Any one of the 23 manufacturers below will enable you to prove it in your own plant.



PHILLIPS *Recessed Head* SCREWS

WOOD SCREWS · MACHINE SCREWS · SELF TAPPING SCREWS · STOVE BOLTS

TO MAKE WARTIME QUOTAS AND PEACETIME PROFITS



IDENTIFY IT!

Faster Starting: Driver point automatically centers in the Phillips Recess . . . fits snugly. Fumbling, wobbly starts, slant driving are eliminated. Work is made trouble-proof for green hands.

Faster Driving: Spiral and power driving are made practical. Driver won't slip from recess to spoil material or injure worker. (Average time saving is 50%.)



Center corners of Phillips Recess are rounded NOT square

Easier Driving: Turning power is fully utilized. Workers maintain speed without tiring.

Better Fastening: Screws are set-up uniformly tight, without burring or breaking of screw heads. The job is stronger, and the ornamental recess adds to appearance.



Bottom of Phillips Recess is nearly flat NOT tapered to a sharp point

23 SOURCES


American Screw Co., Providence, R. I.
The Bristol Co., Waterbury, Conn.
Central Screw Co., Chicago, Ill.
Chandler Products Corp., Cleveland, Ohio
Continental Screw Co., New Bedford, Mass.
The Corbin Screw Corp., New Britain, Conn.
General Screw Mfg. Co., Chicago, Ill.
The H. M. Harper Co., Chicago, Ill.
International Screw Co., Detroit, Mich.
The Lamson & Sessions Co., Cleveland, Ohio
Manufacturers Screw Products, Chicago, Ill.
Milford Rivet and Machine Co., Milford, Conn.
The National Screw & Mfg. Co., Cleveland, Ohio
New England Screw Co., Keene, N. H.
Parker-Kalon Corp., New York, N. Y.
Pawtucket Screw Co., Pawtucket, R. I.
Pheoll Manufacturing Co., Chicago, Ill.
Reading Screw Co., Norristown, Pa.
Russell, Burdsall & Ward Bolt & Nut Co., Port Chester, N. Y.
Scovill Manufacturing Co., Waterbury, Conn.
Shakeproof Inc., Chicago, Ill.
The Southington Hardware Mfg. Co., Southington, Conn.
Wolverine Bolt Co., Detroit, Mich.



IN THE C-47

Magnesium floor beams—25% stronger yet 5% lighter!

The *weight* of a metal is no longer considered a measure of its *strength*. To reduce weight and at the same time retain strength has become a commonplace accomplishment.



Now, through the utilization of Dowmetal Magnesium Alloys, it is possible to combine lighter weight with increased strength.

This new "team"—light weight and strength—goes to work in the Dowmetal floor beam installation of the Douglas C-47 "Skytrain," the Air Transport and Troop Carrier Commands' "Workhorse of the Air." Here Dowmetal extruded I-beams have proved 25% stronger yet 5% lighter than the best of all other metals tested—and the cost is 30% less.

Magnesium, the lightest of all structural metals, logically finds its place in industry wherever metal is put in motion, whether by hand or by power: in portable and manual tools, in the reciprocating and moving parts of machinery, in the various fields of transportation. Dowmetal Magnesium Alloys have been developed to fulfill a broad range of requirements: sand, permanent mold and die casting, forging, extrusion, forming, welding, riveting. Dow shops and foundries are equipped to fabricate Dowmetal in quantity, and in small or experimental lots. As the pioneer and major producer of magnesium, Dow offers the knowledge and experience gained during 28 years of research.

DOWMETAL *magnesium*

THE METAL OF MOTION

DOWMETAL

MAGNESIUM DIVISION · THE DOW CHEMICAL COMPANY
MIDLAND, MICHIGAN

New York · Boston · Philadelphia · Washington · Cleveland · Detroit · Chicago · St. Louis · Houston · San Francisco · Los Angeles · Seattle

Working Hand-in-Glove



Behind the scenes in Precision Aircraft Rodio Monufacture . . . One of a series, photogroph by BR Photo

"CALLING D FOR DORIS. CALLING D FOR DORIS . . ." Somewhere up in the stratosphere, a flier's gloved hand flicks on a Bendix* Aircraft Radio and the voice of the squadron leader comes in clear and crisp, unblurred by the biting cold. The operating frequency is correct . . . set by means of a frequency standard which a girl's gloved hand tested here in the Bendix "cold box," where 40-below temperatures duplicate conditions of altitude flying.

Bendix Radio employees thus literally work hand-in-glove with our fliers . . . testing aircraft radio equipment for its ability to function not only in the bleak cold of the upper air, but in the blistering heat of the tropics . . . in desert dryness and jungle humidity . . . for its ability to stand up under combat strains and landing shock. Bendix engineers have devised more than a thousand such tests and inspections covering every stage of production, from single parts and sub-assemblies to the compact, finished radio.

Maintenance of the highest standards of quality and precision in manufacture, plus exhaustive pre-flight testing, assure dependable performance even under the most extreme conditions . . . have earned for Bendix Radio equipment the deserved confidence of our fliers in the armed forces, and the pilots of our commercial airlines.

THE INVISIBLE CREW
Precision Equipment by
Bendix Aviation Corporation

*Trade Mark of Bendix Aviation Corporation

BENDIX RADIO

BENDIX RADIO DIVISION OF THE BENDIX AVIATION CORPORATION

BALTIMORE, MARYLAND — NORTH HOLLYWOOD, CALIFORNIA